

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES
2. AMENDMENT/MODIFICATION NO. <div style="text-align: center;">2</div>	3. EFFECTIVE DATE <div style="text-align: center;">12-Feb-2003</div>	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. <i>(If applicable)</i>	
6. ISSUED BY <div style="text-align: center;">US Army Corps of Engineers, Kansas City District 760 Federal Building, 601 East 12th Street Kansas City, Missouri 64106-2896</div>		7. ADMINISTERED BY <i>(If other than item 6)</i>		
8. NAME AND ADDRESS OF CONTRACTOR <i>(No., street, county, State and ZIP Code)</i>			(x) 9a. AMENDMENT OF SOLICITATION NO. <div style="text-align: center;">DACA41-02-B-0003</div>	
			9b. DATED <i>(SEE ITEM 11)</i> <div style="text-align: center;">1/16/2003</div>	
			10a. MODIFICATION OF CONTRACT/ORDER NO.	
			10b. DATED <i>(SEE ITEM 13)</i>	
CODE			FACILITY CODE	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS				
<input checked="" type="checkbox"/> The above number solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning ____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegraph which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.				
12. ACCOUNTING AND APPROPRIATION DATA <i>(If required)</i>				

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS,
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

(x)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: <i>(Specify authority)</i> THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.	
	B. THE ABOVE NUMBER CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES <i>(such as changes in paying office, appropriation date, etc.)</i> SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF:	
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:	
	D. OTHER <i>(Specify type of modification and authority)</i>	
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.		

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

Barracks - 1st BDE, FY03 - PN 10538, Fort Riley, Kansas
The Solicitation is amended in accordance with the attached pages.

**BID OPENING IS DELAYED UNTIL 2:00 PM, LOCAL TIME, 5 MARCH 2003, IN ROOM 748
FEDERAL BUILDING, 601 E. 12TH STREET, KCMO 64106-2896.**

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER <i>(Type or print)</i>	16A. NAME AND TITLE OF CONTRACTING OFFICER <i>(Type or print)</i>
15B. CONTRACTOR/OFFEROR	16B. UNITED STATES OF AMERICA
15C. DATE SIGNED	16C. DATE SIGNED
_____ <i>(Signature of person authorized to sign)</i>	BY _____ <i>(Signature of Contracting Officer)</i>

The SOLICITATION is amended as follows:

1. SPECIFICATIONS:

- a. **SPECIAL PHASING SCHEDULE:** See phasing notes on Sheet C3.5 Volume 2A for work associated with the construction of the chiller modifications to the existing Dining Facility. All work associated with the construction of the Trooper-Apennines Traffic Roundabout shall be deferred to the spring of 2004 and completed within 90 calendar days after commencement of the site work. See phasing notes on Sheet D-1 Volume 2A for demolition of existing buildings, parking lots and utilities.
- b. **Revised Sections:** The following sections are deleted and replaced with revised sections of the same numbers. For convenience, changes have been emphasized by underlining text changed from the previous issue or indication of text deleted. However, all portions of the revised specification pages shall apply whether or not changes have been indicated. Copies of the revised sections are attached.

Bidding Schedule: pages 3 and 4 of 131

Page 126 of 131

01100: entire section replaced

01130: paragraph titled "Investigation Costs"

01130: paragraph titled "As-Built Drawings"

01330: paragraph titled "Procedures"

01451: paragraph titled "Capability Recheck"

01451: paragraph titled "Additional Requirements"

01500: entire section replaced

02510: paragraph titled "Casing Pipe"

02531: paragraph titled "Roads, Railroads and Airfields"

02712A: paragraph titled "Job Description"

02714A: after paragraph titled "Gradation Requirements"

04220A: paragraph titled "Clay or Shale Brick"

04220A: paragraph titled "Exterior Sheathing"

06100A: paragraph titled "Sheathing"

07311A: paragraph titled "Shingles"

08120: Shop Drawing submittal "Doors and Frames" reviewer

08810A: after Shop Drawing submittal "Installation"

09250: paragraph titled "Glass Mat Covered or Reinforced Gypsum Sheathing"

09250: paragraph titled "Glass Mat Covered or Reinforced Gypsum Sheathing Sealant"

09250: paragraph titled "Exterior Application"

09250: paragraph titled "Glass Mat Covered or Fiber Reinforced Gypsum Sheathing"

09650A: paragraph titled "Rubber Tile (RFT)(BRKS)"

10430A: Product Data submittal reviewers

10500: paragraph titled "Lockers"

10500: new paragraph 2.1.4 titled "Locker Base (BHQ Only)"

10500: paragraph titled "TA-50 Gear Lockers (Type LK-2)"

10500: new paragraph 2.3 titled "Locker Bench (COF)"

10500: paragraph titled "Installation"

Revised Sections (Continued):

10520: paragraph titled "Fire Extinguisher Cabinet"
 10605N: entire section replaced
 13851A: paragraph titled "Alarm Functions", subparagraph (a)
 13851A: paragraph titled "Addressable Manual Fire Alarm Stations"
 13851A: paragraph titled "Wiring"
 15400A: new paragraph 1.7 titled "Battalion Headquarters and Company Operations Facilities (2-COF and 4-COF)"
 15400A: new paragraph 1.8 titled "Condensate Drain Lines For Fan-Coils (FCU-1A, FCU-2A, and FCU-1B), Heating and Ventilating Units (HVV-1A, 2A, 3A, 4A, 1B, & 2B), and Blower Coils (BC-1A, BC-2A, and BC-1B) Located In Company Operation Facilities (2-COF and 4-COF)"
 15895A: new paragraph 1.5 titled "Battalion Headquarters"
 15951A: paragraph titled "Weather Dependent Test Procedures"
 16415A: new paragraph 3.11.3 titled "Motor 3-Phase Failure Relay"

c. New Section: Section 01312A Quality Control Systems (QCS) is a new section and is added to the Specification.

2. DRAWINGS: The following sheets have been revised, replaced or added. Copies are included.

VOLUME 1

E0001
 AE201
 AE501
 AE601
 BE101
 BE103
 BE105
 BE107
 BE201
 BE202
 BE203
 BE204
 BE205
 BE206
 BE501
 BE801
 BE802
 C1001
 C1003
 C1004

VOLUME 1 (Continued)

E601
E903
B0101
B0201
B0202
B0203
B0204
B0205
B0206
C4.5
C5.1
C6.16
A8.1
AA8.5
BA7.2
BA12.1
BA8.3
BA1.9
BA1.10
BA1.11
BA3.8
AM1.1
BM1.6
BM2.1
BM5.8
BM7.1
BM7.2
BM7.3
M3.1
M9.1
M9.2
M10.1
M11.1
M11.3
M11.4
M11.5
M11.7

VOLUME 2A

C1001
C1002
C1004
DE101
B0101
B0201
B202
A9.1
AA1.2
AA8.1
AA8.2
BA8.1
BA9.1
C2.3
C2.4
C3.5
DM7.1

VOLUME 2B

E0001
AE201
AE202
AE501
AE603
AE604
BE201
BE501
E903
T1.2
AA1.1
AA1.2
AA1.3
AA2.1
AA3.1
AA5.1
AA5.2
AA6.1
AA8.1
AA8.2
BA1.2
BA1.3
BA3.1

VOLUME 2B (Continued)

BA5.1
BA6.1
BA8.1
BA8.2
BA9.1
A3.3
A3.4
A3.5
A9.1
AM5.1
AM5.2
AM7.1
AM7.2
AM11.2
AM11.7
BM5.1
BM7.1
BM11.2
BM11.7
M10.1
M11.4
M11.5

New Sheet

BA5.2

VOLUME 2C

CE0001
CE201
CE301
CE501
CE801
CE903
CA1.2
CA3.2
A3.4
A3.5
A6.3
CA7.1
CA8.2
CA8.8
CA8.10
CA9.3
CM10.1
CM11.2
CM11.4
CM11.5

3. DRAWINGS: The following sheet is a new drawing and added. A copy is included.

Volume 2A sheet C1.0

4. Bidders are required to acknowledge receipt of this amendment on the Bidding Form, in the space provided, or by separate letter or telegram prior to opening of bids. Failure to acknowledge all amendments may cause rejection of the bid.

5. Bids will be received until **2:00 p.m., local time, 5 March 2003**, in Room 748 Federal Building, 601 E. 12th Street, Kansas City, Missouri 64106-2896. and at that time publicly opened.

DELETE AND REPLACE THE FOLLOWING BID SCHEDULE PAGES.

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0001	Barracks	1	Lump Sum		
0002	Soldier Community Building	1	Lump Sum		
0003	2 Company Operation Facility Buildings	1	Lump Sum		
0004	4 Company Operation Facility Buildings	1	Lump Sum		
0005	Battalion Headquarters	1	Lump Sum		
0006	Site Work To include all work outside 1.8 meters of the barracks, Soldier Community Building, 2 Company Operation Facility, 4 Company Operation Facility, and Battalion Headquarters.	1	Lump Sum		
0007	Demolition Buildings 7044, 7046, 7047, and 7048 to include removal of paving, sidewalks, utilities, etc as shown on drawings.	1	Lump Sum		
TOTAL BASE SCHEDULE					
0008	NOT USED				
0009	NOT USED				
0010 OPTION	New Barracks Parking Lot Pave with Portland Cement Concrete and base course as shown on Drawings as option 1. NOTE: The lump sum amount is the difference between the cost of asphalt and concrete.	1	Lump Sum		

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0011		1	Lump Sum		
OPTION	Existing Asphalt Parking Lot located west of 2-COF site - Remove existing asphalt pavement and replace with new Portland Cement Concrete and Base as shown on drawings as option 2.				

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0012		1	Lump Sum		
OPTION	New Battalion Headquarters Parking Lot Pave with Portland Cement Concrete and base course as shown on Drawings as option 3. NOTE: The lump sum amount is the difference between the cost of asphalt and concrete. NET AMT				

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0013		1	Lump Sum		
OPTION	Existing Asphalt Parking Lot located west of 4-COF site - Remove existing asphalt pavement and replace with new Portland Cement Concrete and base course as shown on drawings as option 4.				

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0014		1	Lump Sum		
OPTION	Demolish Building #7230 to include removal of paving, sidewalks, utilities, etc. as shown on drawings as option 5.				

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0015		1	Lump Sum		
OPTION	Demolish Buildings #7028 and #7031 to include removal of sidewalks and utilities within 1.8 meters of the buildings as shown on drawings as option 6.				

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0016		1	Lump Sum		
OPTION	Extension of Design Submittal for Trooper-Apennines Traffic Roundabout as shown on drawings as option 7.				
	Design	1 lump sum			
	Construction	1 lump sum			

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0017		1	Lump Sum		
OPTION	Pedestrian Underpasses Add Pedestrian Underpasses for Trooper-Apennines Roundabout as described in scope of work and drawings.				
	Design	1 lump sum			
	Construction	1 lump sum			

TOTAL OPTIONS _____

TOTAL BASE SCHEDULE AND OPTIONS _____

Section 00800 - Special Contract Requirements
CLAUSES INCORPORATED BY FULL TEXT

52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984)

The Contractor shall be required to (a) commence work under this contract within 10 calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than 900 days after the Contractor receives Notice to Proceed. The time stated for completion shall include final cleanup of the premises.

(End of clause)

52.211-12 LIQUIDATED DAMAGES--CONSTRUCTION (SEP 2000)

(a) If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of \$835.00 for each calendar day of delay until the work is completed or accepted.

(b) If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

(c) Exception to liquidated damage: In case the Contracting Officer determines that seeding is not feasible during the stated completion time, seeding will be exempted from liquidated damages.

(End of clause)

52.231-5000 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE
MAR 1995)--EFARS

(a) This clause does not apply to terminations. See 52.249-5000, Basis for Settlement of Proposals and FAR Part 49.

(b) Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for which the Government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule, Region __5__. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.

(c) Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.

(d) When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet.

(End of clause)

SECTION 01100

GENERAL

PART 1 GENERAL

1.1 INQUIRIES

Pursuant to SECTION 00100 paragraph titled "Explanation to Prospective Bidders", any inquiries regarding this Invitation, before bids are opened, should be addressed to the District Engineer, Kansas City District, Corps of Engineers, 700 Federal Building, Kansas City, Missouri 64106, ATTN: Mr. Robert Smith. Inquiries for which oral explanation or advice on the plans and specifications will suffice may be referred to Mr. Smith by calling Area Code 816-983-3277. Telephone calls concerning the mailing of plans and specifications should be made to Contracting Division at Area Code 816-983-3975. Collect telephone calls will not be accepted. (KCDO APR 84)

1.2 SUPERINTENDENCE OF SUBCONTRACTORS

(a) The Contractor shall be required to furnish the following:

(1) If more than 50% and less than 70% of the value of the contract work is subcontracted, one superintendent shall be provided at the site and on the Contractor's payroll to be responsible for coordinating, directing, inspecting and expediting the subcontract work.

(2) If 70% or more of the value of the work is subcontracted, the Contractor shall be required to furnish two such superintendents to be responsible for coordinating, directing, inspecting and expediting the subcontract work.

(b) If the Contracting Officer, at any time after 50% of the subcontracted work has been completed, finds that satisfactory progress is being made, he may waive all or part of the above requirement for additional superintendence subject to the right of the Contracting Officer to reinstate such requirement if at any time during the progress of the remaining work he finds that satisfactory progress is not being made.

1.3 IDENTIFICATION OF EMPLOYEES

The Contractor shall be responsible for furnishing to each employee and for requiring each employee engaged on the work to display identification as may be approved and directed by the Contracting Office. All prescribed identification shall immediately be delivered to the Contracting Officer, for cancellation upon the release of any employee. When required by the Contracting Officer the Contractor shall obtain and submit fingerprints of all persons employed or to be employed on the project.

1.4 FORT RILEY ACCESS CONTROL

Fort Riley is implementing physical security measures in the form of access control. These measures will apply to all contractors and their employees.

Fort Riley will require each vehicle to have either a temporary or

permanent identification marker attached. It shall be the Contractor's responsibility to monitor and control all company and employee identification markers and comply with Fort Riley's requirements for issuing and returning these markers.

1.4.1 Minimum Requirements

a. Contractor

- (1) Current Lists of all employees.
- (2) Current Lists of all subcontractors and employees.
- (3) Company identification visibly marked on all vehicles.
- (4) Current state vehicle registrations.
- (5) Proof of liability insurance.
- (6) Valid state drivers license.
- (7) Picture identification.

b. Each Employee

- (1) Contractor-provided picture identification.
- (2) Written verification of employment.
- (3) If the employee drives a personally owned vehicle to the job site: valid state drivers license, current state vehicle registration, and proof of liability insurance.

1.4.2 ID Cards

Picture identification cards shall be visibly worn at all times while on the installation.

1.4.3 Responsibility for Compliance

The Contractor shall be responsible for complying with all security conditions as determined by Fort Riley and shall be responsible for any additional requirements that may be implemented.

1.5 APPLICATION OF WAGE RATES

The inclusion of the Davis-Bacon Act General Wage Decision or the Service Contract Act Wage Determination in the solicitation is a statutory requirement. It is not a representation by the U.S. Army Corps of Engineers that any specific work task can be performed by any specific trade. Which work tasks can be performed by what trades depends on and is determined by the prevailing area practice for the local area where the contract is being performed. It is the sole responsibility of the bidder to determine and comply with the prevailing area practice. Inquiries regarding a prevailing area practice should be directed to the Corps of Engineers, Contractor Industrial Relations Specialist (telephone number 816-983-3723) or to the Department of Labor Regional Wage and Hour Division.

Application of wage rates and fringe benefits: For the application of the wage rates and fringe benefits contained in the Decisions of the Secretary of Labor, attached to and a part of this contract, all work required within 5 feet outside building lines shall be considered Building Construction.

Highway Construction rates apply to the construction, alteration or repair of roads, streets, highways, runways, taxiways, alleys, trails, paths, parking areas, and other similar projects.

All other construction not defined herein as Building Construction or Highway Construction shall be considered Heavy Construction.

1.6 PAYMENTS TO SUBCONTRACTORS

The Contractor's attention is directed to CONTRACT CLAUSE titled "Payment Under Fixed-Price Construction Contracts." In addition to the requirements set forth in the referenced paragraph, the Government will reimburse the Contractor, upon request, for amount of premiums paid by the subcontractors for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor furnishes evidence of full payment to the surety.

1.7 PAYMENTS TO CONTRACTOR (KCD MAY 90 - FORMERLY FAR 52.2/9101(a))

The following is an example of a Contractor's release of claims clauses required to comply with the provisions of paragraph (h) of the CONTRACT CLAUSE titled "Payments Under Fixed-Price Construction Contracts":

RELEASE OF CLAIMS

The undersigned Contractor under contract dated _____, 2000, between the United States of America and said Contractor for the _____ located at _____, in accordance with paragraph (h) of the CONTRACT CLAUSE titled "Payments Under Fixed-Price Construction Contracts" of said contract, hereby releases the United States, its officers, agents, and employees from any and all claims arising under or by virtue of said contract or any modification or change thereof except with respect to those claims, if any, listed below:

(Here itemize claims and amounts due.)

1.8 PARTNERING

The Government intends to encourage the foundation of a cohesive partnership with the Contractor and its subcontractor. This partnership will be structured to draw on the strengths of each organization to identify and achieve mutual goals with the intent to complete the Contract within budget, on schedule and in accordance with plans and specifications. This partnership will be bilateral in makeup, and participation will be totally voluntary. Any cost associated with implementing this partnership will be agreed to by the Contractor and the Government, and will be shared equally with no change in Contract price. To implement this partnership initiative, it is anticipated that thirty (30) days after Notice to Proceed, a team building workshop will be conducted. Follow-up workshops will be held periodically throughout the duration of the Contract as agreed to by the Contractor and the Government.

1.9 PROSPECTIVE CONTRACTOR RESPONSIBILITY

Each bidder shall furnish, within 3 calendar days after receipt of request therefor, data which will show the bidder's ability to perform the work or services required by this Invitation for Bids. Such data shall include as a minimum: Bank certification of financial capability, or a financial statement not over 60 days old, which will be treated as confidential (if over 60 days old, a certificate shall be attached thereto stating that the financial condition is substantially the same or, if not the same, the changes that have taken place); names of commercial and financial reporting agencies from whom credit reports may be obtained; trade creditors; name and address of bonding company; business and construction experience; past record of performance of Government contracts; and construction plant and equipment available for this job, with resume of work in progress or other data that will assure that the bidder is in a position to perform the work within the time specified.

In addition, if the bid exceeds \$1,000,000, the bidder shall furnish upon request, a certified statement listing:

- (a) Each contract awarded to him within the preceding three-month period exceeding \$1,000,000 in value with brief description of the contract.
- (b) Each contract awarded to him within the preceding three-year period not already physically completed and exceeding \$5,000,000 in value with brief description of the contract.
- (c) If the prospective Contractor is a joint venture, each joint venture member will be required to submit the above defined certification. There shall also be furnished any other available information which will serve to substantiate the bidder's qualifications as a responsible prospective Contractor. (KCD APR 84)

1.10 PERFORMANCE OF WORK BY CONTRACTOR

Bidder's attention is directed to SPECIAL CLAUSE titled "Performance of Work by Contractor." The successful bidder will be required to furnish the Contracting Officer, a description of the work which he will perform with his own organization (e.g., earthwork, paving, etc.), the percentage of the total work this represents, and the estimated cost thereof. Such description of work to be performed by the Contractor's own organization shall be furnished to the Contracting Officer within 10 days after award of the contract.

1.11 LABORATORY AND TESTING FACILITIES

The Contractor shall provide and maintain all measuring and testing devices, laboratory equipment, instruments, transportation, and supplies necessary to accomplish the required testing. All measuring and testing devices shall be calibrated at established intervals against certified standards. The Contractor's measuring and testing equipment shall be made available for use by the Government for verification of their accuracy and condition as well as for any inspection or test desired pursuant to the CONTRACT CLAUSE titled "Inspection of Construction." The location of the laboratory shall be convenient to the site such that test results are

available prior to proceeding with the next sequential phase of the work.
(KCD)

1.12 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER

(a) This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance with the CONTRACT CLAUSE titled "Default: (Fixed Price Construction)." In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied:

(1) The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.

(2) The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the Contractor.

(b) The following schedule of monthly anticipated adverse weather delays is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the project location and will constitute the base line for monthly weather time evaluations. The Contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent activities.

MONTHLY ANTICIPATED ADVERSE WEATHER DELAY

WORK DAYS BASED ON (5) DAY WORK WEEK

Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
(9)	(5)	(3)	(3)	(4)	(5)	(4)	(3)	(5)	(3)	(3)	(6)

(c) Upon acknowledgment of the Notice to Proceed (NTP) and continuing throughout the contract, the Contractor will record on the daily CQC report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the Contractor's scheduled work day. The number of actual adverse weather delay days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph b, above, the Contracting Officer will convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the CONTRACT CLAUSE titled "Default (Fixed Price Construction)." (ER 415-1-15)

1.13 REQUIRED INSURANCE SCHEDULE

In accordance with CONTRACT CLAUSE titled "Insurance - Work On A Government Installation," the Contractor shall procure and maintain during the entire period of his performance under this contract the following minimum

insurance.

Type	Amount
Workmen's Compensation State Statute	coverage complying with applicable
Employers' Liability	minimum amount of \$100,000.00
General Liability on Comprehensive Form of Policy	minimum limits of \$500,000 per occurrence for bodily injury which includes, but is not limited to, insurance for all work required herein
Comprehensive Automobile Liability	minimum limits of \$200,000 per person and \$500,000 per occurrence for bodily injury, and \$20,000 per occurrence for property damage

1.14 CONTRACTOR-FURNISHED EQUIPMENT DATA

At or before 30 days prior to final inspection and acceptance of the work, the Contractor shall submit the data mentioned in the following subclauses.

(1) Equipment List. An itemized equipment list showing unit retail value and nameplate data including serial number, model number, size, manufacturer, etc., for all Contractor-furnished items of mechanical equipment, electrical equipment, and fire protection systems installed under this contract.

(2) Guarantees. A list of all equipment items which are specified to be guaranteed accompanied by a copy of each specific guarantee therefor. For each specific guaranteed item, a name, address, and telephone number shall be shown on the list for subcontractor who installed equipment, equipment supplier or distributor and equipment manufacturer. The completion date of the guarantee period shall correspond to the applicable specification requirements for each guaranteed item.

(3) Warranty Service Calls. The Contractor shall furnish to the Contracting Officer the names of local service representatives and/or Contractors that are available for warranty service calls and who will respond to a call within the time periods as follows: 4 hours for heating, air-conditioning, refrigeration, air supply and distribution, and critical electrical service systems and food service equipment, and 24 hours for all other systems. The names, addresses, and telephone numbers for day, night, weekend, and holiday service responses shall be furnished to the Contracting Officer and also posted at a conspicuous location in each mechanical and electrical room or close to the unit.

1.15 DATE OF SAFETY AND HEALTH REQUIREMENTS MANUAL (EM 385-1-1)

(a) The date of the U.S. Army Corps of Engineers Safety and Health Requirements Manual in effect on the date of this solicitation is

3 September 1996. See Section 00700, Contract Clause titled "Accident Prevention."

(b) Section 06.I of EM 385-1-1 is deleted. Job hazard analysis for confined space entry procedures is still required, as per 01.A.09 of EM 385-1-1. OSHA Standards 29 CFR 1910.146 or 29 CFR 1926 shall apply.

(c) Before initiation of work at the job site, an accident prevention plan, written by the prime contractor for the specific work and hazards of the contract and implementing in detail the pertinent requirements of EM 385-1-1, will be reviewed and found acceptable by designated Government personnel.

1.16 COMPLIANCE WITH OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)

The Contractor shall comply with OSHA standards as well as the most current edition of the Corps of Engineers General Safety Requirements Manual (EM 385-1-1). The OSHA standards are subject to change and such changes may affect the Contractor in his performance under the contract. It is the Contractor's responsibility to know such changes and effective dates of changes.

1.17 CONSTRUCTION EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE

Whenever a modification or equitable adjustment of contract price is required, the Contractor's cost proposal for equipment ownership and operating expenses shall be as set forth in SPECIAL CLAUSE titled "Equipment Ownership and Operating Expense Schedule." A copy of EP 1110-1-8 "Construction Equipment Ownership and Operating Expense Schedule" dated August 1995 can be ordered from the Government Printing Office (GPO) by calling Telephone No. 202-512-1800.

1.18 SHOP DRAWINGS

The Contractor's attention is directed to clause "Specifications and Drawings for Construction" of the Contract Clauses.

1.19 SUBMITTALS

(a) Submittal Procedures. See Division One SECTION: SUBMITTAL PROCEDURES.

(b) Shop Drawings shall be submitted in ample time to secure approval prior to the time the items covered thereby are to be delivered to the site. ENG Form 4025 and 4026 shall be used for the transmittal of shop drawings. Unless otherwise specified, shop drawings shall be submitted not less than 30 days before commencement of fabrication of fabricated items and not less than 15 days before delivery of standard stock manufactured items. Where materials are stock with the manufacturer, catalog data, including specifications and full descriptive matter, may be submitted as shop drawings. When catalog includes nonapplicable data, the applicable data shall be clearly designated and identified by item number, item name, and name of manufacturer. Shop drawings submitted (including initial and final submittals) shall be reproductions on high quality paper with clear and legible print. Drawings shall generally be bordered a minimum of one inch

and trimmed to neat lines and unless otherwise specified, the minimum scale shall be 3/8-inch to the foot. Shop drawings quality will be subject to approval. Each shop drawing, including catalog data, shall be identified with a title block including the name of Contractor, contract number, name and location of project, and name of item of work or structure to which the shop drawing applies. Material fabricated or delivered to the site before approved shop drawings have been returned to the Contractor will be subject to rejection. NO CONSTRUCTION OR INSTALLATION SHALL BE DONE FOR ANY ITEM REQUIRING SHOP DRAWINGS, UNTIL ALL SHOP DRAWINGS FOR THAT ITEM HAVE BEEN APPROVED.

(c) As-Built Shop Drawings: Upon completion of the work under this contract, the Contractor shall furnish five complete sets of prints or one complete set of reproducibles of all shop drawings as finally approved. These drawings shall show all changes and revisions made up to the time the equipment is completed and accepted. The quality of the reproducibles and prints is subject to approval.

(d) As-Built Drawings: The Contractor shall maintain three separate sets of red-lined, full scale, as-built construction drawings marked up to fully indicate as-built conditions. These drawings shall be maintained in a current condition at all times until completion of the work, and shall be available for review by Government personnel at all times. All variations from the contract drawings, for whatever reason, including those occasioned by modifications, optional materials, and the required coordination between trades, shall be indicated. These variations shall be shown in the same general detail utilized in the contract drawings. In addition, the Contractor shall indicate on the As-Built Drawings, the brand-name, description, location, and quantity of any and all materials used which contain asbestos. The Contractor shall also be responsible for updating the Government-furnished CADD files to reflect the current as-built conditions throughout the duration of the project. The updated CADD design files shall be maintained in the Intergraph Microstation format consistent with the graphic standards established in the CADD contract drawings provided by the Government. The Contractor will be provided a copy of the Tri-Service CADD standards to facilitate his efforts in the maintenance of design files. The updated CADD files shall be reviewed by the Government on a monthly basis during the progress payment evaluation. The Contractor shall be prepared to demonstrate the status of the updated CADD files in his on-site office. The as-built utility drawings shall show locations and elevations of all underground new utilities and existing utilities encountered, including dimensions from permanent structures and/or survey locations. The submittal requirements for as-built utility drawings shall be shown as separate activities on the Contractor-prepared network analysis. Upon completion of the work, the marked-up drawings and the updated CADD files shall be furnished to the Contracting Officer on CD. In multiphased construction where portions of a system are to be turned over to the user prior to completion of the project, the marked-up drawings for that portion shall be furnished to the Contracting Officer at that time. (MRD ltr 30 Oct 70 and KCD 8 Apr 91)

(e) CADD Files: The Government will provide to the Contractor, within 30 calendar days after Notice of Award, copies of the CADD computer files of the contract drawings for the production of as-built drawings. These files

will be in Intergraph Microstation format. The Government provides no warranty, expressed or implied, of the CADD computer files. The Contractor shall assume all responsibility to verify the CADD drawing files. The Contractor will not utilize the CADD drawing computer files to resolve dimensional or other discrepancies. The Government will not guarantee the measurable accuracy of the CADD drawing computer files.

(b) Purchase Orders: Each purchase order issued by the Contractor or his subcontractors for materials and equipment to be incorporated into the project, shall be maintained on file at the Contractor's field office for inspection and review by Government representatives. Each purchase order shall (1) be clearly identified with applicable DA contract number, (2) carry an identifying number, (3) be in sufficient detail to identify the material being purchased, (4) indicate a definite delivery date, and (5) display the DMS priority rating. At the option of the Contractor, the copies of the purchase orders may or may not indicate the price of the articles purchased. (MRD Ltr 22 Oct 74)

(f) Color Boards:

1. The Contractor shall submit a minimum of three (3) complete sets of color boards within 120 calendar days of receipt of Notice to Proceed. Construction color boards shall be submitted in a 3-ring notebook binder with all materials securely mounted on rigid 8-1/2 by 11-inch presentation (mat) board, with a maximum spread of 25-1/2 by 33 inches for foldouts, clearly coded regarding location of materials in the facility.

2. An index shall be provided listing pertinent contract specifications and drawings for each sample and any proposed substitutions or variances shall be so designated. The Contractor shall also certify, in writing, that all submittal items technically comply with the project specifications.

3. Color boards shall reflect all actual finish textures, patterns, and colors required for this contract as specified on the Interior Room Finish Schedule, the Exterior Finish Schedule and Interior Finish Materials Legend located in the Contract Drawings, and the sample requirements of the submittal registers. All materials must be labeled with the manufacturer's name, pattern and color reference. Patterned material samples (i.e., carpet) must be of sufficient size to enable evaluation of the pattern. Samples shall be keyed or coded to match any key or code system in the Contract Drawings.

4. The Contractor shall express mail a minimum of three (3) copies of the color boards to the Contracting Officer. The Contracting Officer will forward one copy of the colorboards to CENWK-EC-D for review and concurrence. Concurrence or comments will be provided not later than 45 calendar days after receipt of the submittal. This paragraph does not cover the quality of finishing materials. The quality, physical requirements, and method of installation shall be submitted with the appropriate shop drawings. The Contractor shall not submit any of the above requirements with the color boards. Specific locations where the various materials are required are shown on the drawings.

1.20 SPECIAL REFERENCES

(a) Shop Drawings. Bidder's attention is directed to SPECIAL CLAUSE titled "Shop Drawings." The basic requirements for Shop Drawings are set forth in the CONTRACT CLAUSES and SPECIAL CLAUSES.

(b) Approved Equal. Bidder's attention is directed to SPECIAL CLAUSE titled "Approved Equal."

(c) Payment to Subcontractors. Bidder's attention is directed to SPECIAL CLAUSE titled "Payments to Subcontractors."

1.21 DIFFERENCES IN DRAWINGS

In addition to the provisions of CONTRACT CLAUSE paragraph "Specifications and Drawings for Construction," the structural drawings shall govern in cases where they differ from the architectural drawings.

1.22 DAMAGE TO WORK (1966 MAR OCE)

The responsibility for damage to any part of the permanent work shall be as set forth in the CONTRACT CLAUSE titled "Permits and Responsibilities." However, if, in the judgment of the Contracting Officer, any part of the permanent work performed by the Contractor is damaged by flood or earthquake, which damage is not due to the failure of the Contractor to take reasonable precautions or to exercise sound engineering and construction practices in the conduct of the work, the Contractor will make the repairs as ordered by the Contracting Officer and full compensation for such repairs will be made at the applicable contract unit or lump sum prices as fixed and established in the contract. If, in the opinion of the Contracting Officer, there are no contract unit or lump sum prices applicable to any part of such work an equitable adjustment pursuant to CONTRACT CLAUSE titled, "Changes," of the contract, will be made as full compensation for the repairs of that part of the permanent work for which there are no applicable contract unit or lump sum prices. Except as herein provided, damage to all work (including temporary construction), utilities, materials, equipment and plant shall be repaired to the satisfaction of the Contracting Officer at the Contractor's expense, regardless of the cause of such damage.

1.23 WORK ADJACENT TO ROADS AND HIGHWAYS

Where the construction work is on or adjacent to, or involves hauling over public or private roads, streets, or highways, all herein referred to as "roads," the said roads shall, except as otherwise specified or directed, be kept open for traffic at all times during the construction period. Further, the Contractor shall, during said construction, provide, erect and maintain warning signs, lanterns or torches or other safety devices and, when necessary, provide flagmen for protection of traffic to the satisfaction of the Contracting Officer and local authorities. The Contractor shall keep the right-of-way of the roads free of debris that might be caused to accumulate thereon by his operations, and upon completion of the work, shall clean up the said roads and repair any damage to the roads occasioned by his operations under this contract to the satisfaction of the Contracting Officer and local authorities having jurisdiction. The drainage from the roads shall not be obstructed by the

construction work. The Contractor shall be responsible for obtaining and paying for all permits required for operation on all roads.

1.24 APPROVED EQUAL

The drawings and the TECHNICAL PROVISIONS of these specifications may, in some instances, refer to certain items of equipment, material, or article by trade name. References of this type shall not be construed as limiting competition, but shall be regarded as establishing a standard of quality. In this respect, the Contractor's attention is directed to CONTRACT CLAUSE titled "Material and Workmanship."

1.25 SCHEDULE OF WORK

The Contractor's attention is directed to CONTRACT CLAUSE titled "Schedule for Construction Contracts," wherein if, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer.

1.26 UPKEEP OF ROADWAY AREAS WITHIN A MILITARY INSTALLATION WHICH THE CONTRACTOR USES

In addition to the requirements in CONTRACT CLAUSE titled "Operations and Storage Areas," the Contractor shall comply with the following requirements: Where the construction work is on or adjacent to, or involves hauling over public roads, streets, or highways located on a military installation, all herein referred to as "roads," the said roads shall except as otherwise specified or directed, be kept open for traffic at all times during the construction period. The Contractor shall keep the roads including adjacent construction site free of debris including litter, waste construction material, mud etc., that might be caused to accumulate thereon by his operations, and upon completion of the work, shall clean up the said roads and construction site and repair any damage occasioned with his operations under this contract to the satisfaction of the Contracting Officer. The drainage from the roads shall not be obstructed by the construction work.

1.27 PROTECTION OF UTILITY LINES

(a) It shall be the Contractor's responsibility to protect all existing utility lines from damage during excavation for utilities systems. Any damage resulting to existing utility systems shall be repaired by the Contractor, to the satisfaction of the contracting officer, at no additional cost to the Government.

(b) All requests for access and/or locations must be made through the Contracting Officer's Representative (COR) or Resident Engineer. The Director of Public Works will work directly with the Resident Engineer to provide timely information to the Contractor.

(c) Not less than 3 or more than 10 workdays prior to the actual day of excavation on each site, the Contractor shall contact Kansas One-Call System, Inc., Toll Free 1-800-344-7233 and obtain a Kansas Dig-Safe Ticket

Number. Immediately after obtaining a Kansas Dig-Safe Number the Contractor shall contact Fort Riley Dig-Safe Coordinator at Public Works, Building 337, Telephone 1-785-239-8187, FAX 1-785-239-8188, and accomplish the items listed below. No exceptions to this policy will be tolerated. The Contractor will be held liable for all costs incurred by various underground utility owners for repairs to damaged underground utilities resulting from failure to comply with this procedure.

- (1) Provide Kansas One-Call System Ticket Number.
- (2) Provide company name, name and telephone number of point of contact.
- (3) Provide a site drawing with measurements from nearest building showing depth and nature of work:
- (4) Mark the area to be dug with white paint.

1.28 MODIFICATIONS PRIOR TO DATE SET FOR OPENING BIDS

The right is reserved, as the interest of the Government may require, to revise or amend the specifications or drawings or both prior to the date set for opening bids. Such revisions and amendments, if any, will be announced by an amendment or amendments to this Invitation for Bids. If the revisions and amendments are of a nature which requires material changes in quantities or prices bid or both, the date set for opening bids may be postponed by such number of days as in the opinion of the issuing officer will enable bidders to revise their bids. In such cases, the amendment will include an announcement of the new date for opening bids. (KCD APR 84)

1.29 EXPEDITING NOTICE TO PROCEED

Notwithstanding the requirements of Block 12 on page 00010-1 of SECTION 00010 and SECTION 00100 paragraph titled "Late Submissions, Modifications, and Withdrawals of Bids," in order to expedite award of contract and issuance of NOTICE TO PROCEED, it is requested that an officer of the company or corporation determined to be the successful bidder shall appear in the office of the Commander, Kansas City District, Corps of Engineers, 757 Federal Building, 601 East 12th Street, Kansas City, Missouri, for signing contract documents. Therefore, upon written acceptance of this bid, mailed or otherwise furnished within 60 calendar days after the date of opening of bids, it is requested that the successful bidder shall within 48 hours after receipt of notification appear in the office of the Commander and execute Notice to Proceed documents, and give performance and payment bonds on Government Standard forms 25 and 25A with good and sufficient surety. It is also requested that the successful bidder furnish insurance certificates required in SPECIAL CLAUSE titled "Required Insurance Schedule" at this time.

1.30 UNEXPECTED HAZARDOUS SUBSTANCES

In the event that suspected hazardous substances are revealed during construction activities, all such construction activities in the immediate area shall be immediately suspended. Hazardous substances for purposes of

this specification only, shall be defined as CERCLA hazardous substances, infectious or radioactive wastes, asbestos or oil. The Contractor shall leave the materials undisturbed and shall immediately report the find to the Contracting Officer's Representative (COR) so that proper authorities can be notified. The Contractor shall not resume construction activities in the vicinity of the suspected hazardous substances until written clearance is received from the COR. Identification and removal of any such materials will be conducted in accordance with all Federal, state and local environmental laws and regulations according to the CONTRACT CLAUSE titled "Differing Site Conditions."

1.31 TIMBER DISPOSAL

(a) Any and all hardwood trees, stems and limbs three (3) inches in diameter or greater that must be removed as a result of construction be stockpiled by the Contractor in the area designated, i.e. 2d and K Street, Camp Funston. Excluded from this requirement are cedar, pine and cottonwood trees, stems and limbs.

(b) All cedar, pine and cottonwood trees, stems and limbs; all trees, stems and limbs less than three (3) inches in diameter; and all stumps and roots will be taken to the construction and demolition debris landfill for disposal. This landfill is located in the vicinity of the corner of E and 4th Streets in Camp Whitside.

1.32 FORT RILEY CONSTRUCTION DEMOLITION DEBRIS (C/D) LANDFILL OPERATIONS

The Fort Riley Construction Demolition Debris (CD) landfill is located on Campbell Hill Road approximately one mile north of Camp Funston. There is no charge for using the landfill. Delivery vehicles shall be identified with contractor signs on both sides of the vehicle and must provide the contract number. The CD landfill will have an attendant on duty and be open for normal operations (excluding Federal Holidays) Monday-Friday, 0730-1600. Only construction demolition debris materials will be accepted.

Acceptable materials are posted on a board at the entrance. Asbestos materials deliveries require a call for an appointment 24 hours in advance of delivery. Telephone (785) 761-5002. All transformers and light ballasts shall be turned in to Building 339 within the PW maintenance yard on Main Post. Light ballasts shall have all wires cut off. POC is Don Wainwright, telephone (785) 239-3832. Any salvageable items shall be turned in to the Directorate of Environment and Safety (DES) Recycle Center, Building 1980, in Camp Funston. POC is the Solid Waste Program Manager, DES, telephone (785) 239-2860.

1.33 KANSAS SALES AND USE TAX

In accordance with FAR clause 52.229-3, notice is given that the contract price excludes the Kansas sales tax and compensating (use) tax on all sales of tangible personal property and materials purchased by the Contractor or subcontractors for the construction of projects, including repairing or remodeling facilities, for the United States. In accordance with Kan. Stats. Anno., sec. 79-3606(e), the Contracting Officer will obtain from the State and furnish to the Contractor an exemption certificate for this project for use by the Contractor and subcontractors in the purchase of

materials for incorporation in the project and of services. The Contractor and the subcontractors shall furnish the number of such certificate to all suppliers from whom such purchases are made, and the suppliers shall execute invoices covering the same bearing the number of such certificate. Pursuant to a 1977 Amendment to K.S.A., 1976 Supp., 79-3606(e), effective 1 July 1977, the Contractor is required to retain all invoices for a period of five (5) years during which time these invoices are subject to audit by the Kansas Director of Taxation. Upon completion of the project, the Contractor shall complete the Project Completion Certification (Form STD 77, Rev. 6/77) in duplicate returning one copy to the Contracting Officer, and forwarding the other to the Kansas Director of Taxation. (KCD)

1.34 WORKING HOURS

Working hours for this project will be limited to Monday through Friday, 7:30 a.m. to 4:30 p.m., except as follows: Work will not be permitted on weekends and Federal holidays. In unusual circumstances, such as when utility turn-off is required for an extended period of time, authorization for weekend or holiday work may be requested from the Contracting Officer; these instances must be coordinated well in advance, in writing. Likewise, utility turn-off of short duration or work which will disrupt normal operations or traffic flow must be scheduled at least 3 working days in advance and may require schedule changes to ensure that safety is maintained.

1.35 LIMITS OF RIGHT-OF-WAY

Limits of right-of-way within private property shall be established as soon as practicable and at least 30 days prior to commencing work in the immediate vicinity, to allow time for relocation of fences by owners of property adjacent to the location of the work.

1.36 INTERRUPTIONS TO UTILITY SERVICES

A schedule showing the approximate times of interruptions of utility services and roads shall be submitted approximately 30 days in advance of interrupting services to make connections. Where it is necessary to interrupt services to make connections and the period of interruption will last more than 2 hours, the connections shall be performed on Saturday or Sunday, unless otherwise approved by the Contracting Officer. Final arrangements shall be made with the Contracting Officer at least 72 hours in advance of the scheduled times of interruptions.

1.37 COORDINATION BETWEEN CONTRACTORS

(See CONTRACT CLAUSE titled "Other Contracts.") Construction work on another contract is underway concurrently with this Contract. The obligations of the Contractor under this Contract will include jointly planning and scheduling the work, on a cooperative basis, with the other Contractor involved in order to minimize delays and interferences. Alterations to systems installed under the other contract, including connections to sewer, waterlines, and bituminous pavement shown as existing, may not be in place.

1.38 PROTECTION OF UTILITY LINES

(a) It shall be the Contractor's responsibility to protect all existing utility lines from damage during excavation for utilities systems. Any damage resulting to existing utility systems shall be repaired by the Contractor, to the satisfaction of the contracting officer, at no additional cost to the Government.

(b) All requests for access and/or locations must be made through the Contracting Officer's Representative (COR) or Resident Engineer. The Director of Public Works will work directly with the Resident Engineer to provide timely information to the Contractor.

(c) Not less than 3 or more than 10 workdays prior to the actual day of excavation on each site, the Contractor shall contact Kansas One-Call System, Inc., Toll Free 1-800-344-7233 and obtain a Kansas Dig-Safe Ticket Number. Immediately after obtaining a Kansas Dig-Safe Number the Contractor shall contact Fort Riley Dig-Safe Coordinator at Public Works, Building 337, Telephone 1-785-239-8187, FAX 1-785-239-8188, and accomplish the items listed below. No exceptions to this policy will be tolerated. The Contractor will be held liable for all costs incurred by various underground utility owners for repairs to damaged underground utilities resulting from failure to comply with this procedure.

- (1) Provide Kansas One-Call System Ticket Number.
- (2) Provide company name, name and telephone number of point of contact.
- (3) Provide a site drawing with measurements from nearest building showing depth and nature of work.
- (4) Mark the area to be dug with white paint.

1.39 CLOSEOUT OF CONTRACTS (KCD JULY 1990)

The closing out of various features of the contract shall be done before or on the Government contract construction completion date. The Contractor's specific submittals and items required for closeout include, but are not limited to, Operation and Maintenance Manuals (O&M), training, spare parts, equipment list, guarantees, as-built shop drawings and contract drawings.

The Contractor shall review the contract documents and prepare a plan for closeout no later than 90 days after the notice to proceed date for approval by the Contracting Officer Representative (COR). The closeout plan shall also include the Specification Volume No., specification reference section and building name on each closeout item. A summary of the type of closeout information required for each of the items shall be prepared by the Contractor for the closeout plan. The closeout data base shall be updated as required by the Contracting Officer to ensure adequate tracking of the items noted.

The following is a general list of the various types of closeout materials and the data required for each. (* indicates data required on initial submittal)

(a) O&M Manuals:

Descriptions*, Specification Paragraph*, Date Due*, No. Copies Due*, Date Submit Action Code, Resubmit Date, Approved, Date to User

(b) Training Requirements:

Description*, Specification Paragraph*, Length Required*, Date Scheduled, Plan Submitted, Plan Approved, Date Training Held

(c) Spare Parts Required:

Description*, Specification Paragraph*, Quantity Required*, Date Turned Over to User

(d) Salvaged Material:

Description*, Specification-Plan Requirement*, Quantity*, Turn In Document Received

(e) Government-Furnished Equipment:

Description*, Specification-Plan Requirement*, GFCI-GFGI*, Number Required*, Date Equipment Data Required*, Date Equipment Required*, Turnover Document Provided

(f) Utilities Provided or Relocated by Others:

Description*, Relocate or Provide*, Specification-Plan Note*, Date Required*

1.40 LARGE VOLUME OF FORT RILEY CONSTRUCTION

Bidders are advised that a number of construction projects will be in progress at Fort Riley during the performance of this contract. Each individual Contractor shall be responsible for coordinating and scheduling the work such that the work shall be accomplished to minimize delays and interference.

1.41 UNEXPLODED ORDNANCE

The Contractor shall anticipate the possibility of finding several types of expended and dud ammunition on the construction site. The Contracting Officer and the Range personnel will brief the Contractor, (and the Contractor's employees) on the types of ammunition that may be encountered. The Contractor shall establish and follow appropriate procedures to ensure the safety of all personnel on the worksite. If the Contractor encounters suspect ammunition, all work in that area shall be halted, the location of the suspect ammunition marked, and the Contracting Officer notified. The Contractor shall continue work in other areas until Fort Riley Ordnance

Disposal Personnel "identify" and (if necessary) "dispose-of" the suspect ammunition.

1.42 SCHEDULE OF WORK IN RANGE AREAS

The Contractor shall be responsible for preparing a project schedule for all work within the Range Areas in accordance with Section 01320A PROJECT SCHEDULE. The Contractor's work plan and operations in the Range Areas shall be coordinated with the Contracting Officer and Range Control Manager prior to the construction start date. The Contractor may, at the direction of the Contracting Officer, be required to phase their construction activities around military operations.

1.43 CHECKPOINTS

The Contractor shall access the jobsite only through designated checkpoints and shall allow extra time for security clearing. The Contractor-designated checkpoint for material delivery is restricted to the 12th Street Control Point, unless otherwise directed by the Contracting Officer. The Contractor's employees may access the jobsite through any designated checkpoint.

1.44 AGGREGATE SOURCES (1965 MAY OCE)

a. Concrete aggregates may be furnished from any source designated by the Contractor and approved by the Contracting Officer, subject to the conditions hereinafter stated.

b. Aggregate Sources: Reference the Kansas Department of Transportation, Bureau of Materials and Research, Aggregate Source Report "B" Listing, Class 2 Aggregate, dated June 21, 2002 or later. All aggregates shall be tested for compliance with specified requirements. The Contractor shall be responsible for aggregate testing.

c. After the award of the contract, the Contractor shall designate in writing only one source or combination of sources from which he proposes to furnish aggregates. Laboratory test reports for acceptance testing shall be provided as required by Sections 02714A, 02721A, 02722A, 02741A, 02754A, and 03300 of the Technical Provisions. If an aggregate source is not approved for use by the Contracting Officer, the Contractor shall submit new sources for approval at no additional cost to the Government.

1.45 SPECIAL SCHEDULING

See phasing notes on Sheet C3.5 Volume 2A for work associated with the construction of the chiller modifications to the existing Dining Facility. All work associated with the construction of the Trooper-Apennines Traffic Roundabout shall be deferred to the spring of 2004 and completed within 90 calendar days after commencement of the site work. See phasing notes on Sheet D-1 Volume 2A for demolition of existing buildings, parking lots and utilities.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

* * * * *

SECTION 01130

DELIVERIES OR PERFORMANCE
FOR
TROOPER-APENNINES TRAFFIC ROUNDABOUT
01/03

PART 1 GENERAL

1.1 DESIGN SCHEDULE AND GENERAL CONTRACT PROCEDURES

After the award of the Contract option the Contractor shall execute the work in accordance with the following: Construction shall not commence until the Government has reviewed and approved the applicable design documents. The Government reviews the Contractor's design documents for compliance with the Contract and conformance with the technical requirements, as defined in the Scope of Work (Attachment to this section). The Contractor is totally and solely responsible for the design, coordination, compatibility, completeness, and compliance with the contract requirements. Prior to start of construction, there will be a meeting to discuss the Contractor's Quality Control Plan for this option. See Section 01451A Contractor Quality Control for details. After notice to proceed with the Contract option, the contractor shall schedule a pre-design conference or use a charette process to start the design to be held at the Corps of Engineers, Fort Riley Area Engineer Office, Building 322 Marshall Drive, Fort Riley, Kansas, or other location designated by the Contracting Officer, to acquaint the Contractor with the general plan of contract administration and requirements under which the design is to proceed.

1.1.1 Design Preparation

The design of the Trooper-Apennines Traffic Roundabout shall follow the Scope of Work (See Attachment to this section. The Contractor is responsible for acquiring the services of one or more Licensed Civil Engineers, registered in the State of Kansas, with demonstrated geotechnical engineering and roundabout design engineering expertise (minimum 2 comparable projects), to prepare and stamp the Geotechnical Investigation Report, design plans and Design Analysis (P.E. stamp and signature required).

1.1.2 Basis for Design

b. After the Contractor completes the engineering, geo-technical subsurface investigations, and topographic survey, and construction and Traffic Management Plan. Contractor shall submit those designs including soils report, drawings, specifications and design analysis for approval by the Contracting Officer.

1.2 SUBMITTALS

1.2.1 Design Submittals

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES. All design submittals including the 50%, 100%, and 100% Back-Check shall include design of the Trooper-Apennines Traffic Roundabout as follows (See paragraph titled "Design Review Distribution" below):

SD-01 Preconstruction Submittals

50 Percent Design Submittal; G, RE.

The 50 percent design submittal shall be complete with construction work plan, traffic roundabout designs, site surveys, geo-technical subsurface investigations, site design including plan and profile sheets, utilities, relocations of utilities, demolition, site grading, drainage slopes, traffic signage, roadways, etc. The 50% shall be completed within 90 calendar days after the Notice to Proceed and include a design analysis with calculations, drawings, and specifications referenced in ER 1110-345-700, Design Analysis, Drawings, and Specifications. The Contractor shall acquire a copy of the ER from the following Army based Web Site:
<http://www.usace.army.mil/inet/usace-docs/eng-regis/er1110-345-700/toc.htm>.

100 Percent Design Submittal; G, RE.

The 100 percent design submittal shall incorporate all review comments from the 50 percent design review and be completed within 60 calendar days after the Contractor receives the letter of approval of the 50 percent design from the Fort Riley Area Engineer.

100 Percent Back-Check Submittal; G, RE.

The 100 percent back-check design submittal shall be complete within 15 calendar days after the Contractor receives the letter of approval of the 100 percent design from the Fort Riley Area Engineer.

SD-02 Shop Drawings

Construction Drawings, Specifications and Design Analysis; G, RE.

See subparagraph titled "Design Documents" below.

As-Built Drawings; G, RE.

See paragraph titled "As-Built Drawings" below.

SD-07 Certificates

Certification of Compliance; G, RE.

See subparagraph titled "Certification of Compliance" below.

Verification of Site Conditions; G, RE.

See subparagraph titled "Verification of Site Conditions" below.

1.2.2 Additional Submittals

Additional submittals and back check reviews may be required until the Government is assured that all review comments have been satisfactorily addressed. The Government review does not constitute approval or acceptance of any variations from the IFB or acceptance of the Contractor's design unless such variations have been specifically requested in writing and approved by the Contracting Officer. The responsibility for a total design in accordance with the Contract and all applicable laws and regulations shall remain with the Contractor and any interim notice to proceed with construction by the Contracting Officer after the approval of the 50% design submittal will in no way mitigate that responsibility.

1.2.3 Design and Reviews

The Government review period for the 50 percent and 100 percent submittals shall be 20 calendar days each. The Government review period for the back check submittal shall be 15 calendar days. The time stated for completion of design for review is incorporated into the overall completion time for the project stated in Section 00800.

1.2.4 Review Comments

All review comments shall be managed and documented in electronic format utilizing the internet-based Dr Checks software program, available at website <http://65.204.17.188/projnet/home/version1/index.cfm/> at no cost to the Contractor. The Kansas City District Project Manager, through the Contracting Officer, will coordinate with the Contractor to provide access to the DrChecks system and passwords.

1.2.5 Identification of Submittals

Each design submittal shall be appropriately stamped, i.e., "For Review Only". Each sheet of the drawings shall be stamped. The back-check design submittal after the Government review of the 100% completed design shall be stamped "For Back-Check Review Only--100%", accordingly; each sheet of the drawings shall be stamped.

1.3 SUBMISSION OF CONSTRUCTION DRAWINGS, SPECIFICATIONS AND DESIGN ANALYSIS

1.3.1 Title Blocks

For the final project drawings, the Contractor shall incorporate Government format title blocks on his own sheets.

1.3.2 Design Documents

Design documents shall include Construction Drawings, Specifications and Design Analysis for categories such as, but not limited to, architectural, structural, mechanical, electrical, grading, drainage, paving, and outside

utility services in accordance with ER 1110-345-700. If changes to the project specifications are required, or additional specification sections are required, the specifications shall be in sufficient detail to fully describe and demonstrate the quality of materials, the installation and performance of equipment, and the quality of workmanship. Detailing and installation of all equipment and materials shall comply with the manufacturers' recommendations. The design analysis shall be for each discipline of work and shall include all features with the necessary design calculations, tables, methods and sources used in determining equipment and material sizes and capacities, and shall provide sufficient information to support the design.

1.3.3 Review Meetings

All review meetings will be held at the U.S. Army Corps of Engineers Area Engineer Office, 322 Marshall Drive, Fort Riley, Kansas or other building at Fort Riley designated by the Contracting Officer.

1.3.4 Certification of Compliance

The Contractor shall certify that all items submitted in the design documents comply with the contract documents. The criteria specified in the IFB are binding contract criteria and in case of any conflict after award of the option between the IFB criteria and Contractor's submittals, the IFB criteria will govern unless there is a written and a signed agreement between the Contracting Officer and the Contractor waiving a specific requirement. This certification shall be included on each sheet of working drawings.

1.3.5 Verification of Site Conditions

The Contractor is solely responsible to verify all existing site conditions including underground utilities which are significant to design and construction of the Trooper-Apennines Traffic Roundabout including field inspections, topographic surveys, utility information, subsurface investigations, testing and Geotechnical Report, researching and obtaining all necessary as-built drawings and reproducing them for his own use as necessary, and discussing status with knowledgeable personnel. The information shall be reflected in the design documents.

1.3.6 Investigation Costs

Topographic surveys and geo-technical subsurface and soils testing information, TEXT DELETED, permits, etc required by the Contractor for design and construction after award of the contract option shall be procured and paid for by the Contractor.

1.4 MATERIAL REQUIRED FOR 50 PERCENT DESIGN SUBMITTAL

1.4.1 ER 1110-345-700 Requirements

a. Material submitted for the 50 Percent Design Submittal shall comply with ER 1110-345-700 including all design documents for the Trooper-Apennines Traffic Roundabout. The 50 Percent Design Submittal

shall include drawings, design analysis, proposed changes to contract specifications and any additional specification sections not included in the contract. The design shall use Hard Metric units.

1.4.2 Site Work

Portions of the site work need to be at a higher percentage of design in order to receive NTP with final design after the 50% design review and approval by the contracting officer.

1.4.3 Surveys and Soils Reports

All topographic surveys and subsurface geo-technical investigations including the soils report must be complete.

1.4.4 Site Layouts

Site layouts at 50% design must include road layouts, pavement designs, site grading and drainage, location of all existing utilities including those to be relocated, design layout for street lighting, electrical distribution and traffic signs.

1.4.5 Design Analysis and Calculations

The Design Analysis, including calculations required to support the grading, site drainage, pavement design, sidewalks, utilities, roadway lighting, traffic signage, etc., designs shall be submitted.

1.4.6 Quality Control Documents

Quality Control documents or certification that the approved QC Plan has been followed shall be submitted.

1.5 MATERIAL REQUIRED FOR 100 PERCENT DESIGN SUBMITTAL

1.5.1 General Requirements

For general requirements, Contractor shall see ER 1110-345-700.

1.5.2 100 Percent Design Submittal Documents

All drawings, including site design, specifications, and Design Analysis calculations at 100% design complete, including certification of compliance with the approved QC Plan, shall be submitted.

1.5.3 Design Analysis

All design and calculations shall be reviewed and stamped by a licensed professional engineer and traffic engineer,. The design analysis shall be a separate bound assembly, in one or more volumes, of all the functional and engineering criteria, design information and calculations applicable to the project design as noted in ER 1110-345-700. The analysis shall be organized in a format appropriate for review, approval and record purposes.

The design calculations shall be presented in a clear and legible form,

with all methods and references identified and all assumptions and conclusions explained. Calculations submitted shall include all of those required to support design of the scope of the Trooper-Apennines Traffic Roundabout Scope of Work. The design analysis shall cover each discipline of work and shall include all features. The design analysis shall include complete site designs, design calculations for pavement sections, road layouts, storm drainage electrical distribution, communication lines, street lighting, traffic signage, etc. If applicable, electrical design calculations shall include lighting and load calculations, cathodic protection, lightning protection, secondary power and data distribution systems.

1.5.4 Equipment Schedule

Based on the results of calculations, provide a complete list of the materials and equipment proposed with the manufacturer's published catalogued product installation specifications and roughing-in data. Data shall include the manufacturer's wiring diagrams, installation specifications, ARI certification, and the standard warranty for the equipment.

1.5.5 Specific Design Requirements

1.5.5.1 Site Utilities

Information on existing lines shall be provided where existing utilities are involved with new construction. Additional detail drawings shall be provided where required. Specifications shall be provided for valves, pipes, etc. Materials and construction of all mains and appurtenances shall be indicated.

1.5.5.2 Grading

Information on general site grading, storm drainage and contour lines with an interval of not more than .25-meter shall be provided.

1.5.5.3 Site Grading Plans

Site grading plans and designs of entrance roads and parking including road profiles, pavement section profiles, ditches, drainage structures, etc., shall be provided.

1.5.5.4 Site Demolition Plans

Site demolition plans of existing buildings to be demolished, utilities, and other site appurtenances shall be provided.

1.6 DESIGN REVIEW DISTRIBUTION

1.6.1 Distribution of Documents

a. The Contractor shall transmit the 50 percent, 100 percent, and 100 percent back check submittals to the Government agencies and in the quantities indicated below. All documents shall contain an index of

contents. The Contractor shall enclose a letter of transmittal with the contract number of each submittal package indicating the type of submittal (e.g., 50 percent design, 100 percent design, 100 percent back check, etc.), the project name and number and the date written comments are due at the Office of the Contracting Officer. Provide copies to the following distribution:

Six (6) copies of all transmittals shall be sent to the U.S Army Corps of Engineers, Kansas City District, ATTN: CENWK-PM-MM (Robert Smith), 601 E. 12th Street, 700 Federal Building, Kansas City, Missouri 64106-2896

Three (3) copies to the U.S. Army Corps of Engineers, Fort Riley Area Engineer Office, ATTN: FMRI (Mike Istas), Building 322 Marshall Drive, Fort Riley, Kansas 66442-6016

Six (6) copies to Fort Riley Public Works, ATTN: AFZN-PW-R (Jon Cranmer), Building 330 Dickman Avenue, Fort Riley, Kansas 66442-6016

All submittals shall be transmitted by overnight express mail. One (1) copy of each submittal includes the following: one copy of the half-size set of drawings, one set of specifications, and one design analysis.

1.6.2 Review Time Extension

If for any reason the Government requires more time than stated for review of submittals, the Contractor will be granted an extension of time equal to the number of calendar days of delay.

1.6.3 Design Review Meetings

Design review meetings at 50% and 100% design shall be held at Fort Riley Area Engineer Office or room at Fort Riley designated by the Contracting Officer not later than 25 days after receipt of submittal.

1.6.4 Meeting Requirements

The Contractor and his representatives involved in the design shall attend the review conferences. Government personnel will present review comments for discussion and resolution. All comments shall be annotated in COE Dr Check's database with comment action agreed on within 10 calendar days from the conference date. Unresolved problems will be resolved by immediate follow-up action at the end of meetings. In addition to the comment actions in Dr Check's the Contractor shall submit copies of a memorandum of the design review meetings, summarizing major decision points and issues, which require resolution and the action office. On receipt of final corrected designs, subsequent to completion of the back check reviews, the Kansas City District will provide formal Government approval necessary to initiate construction. The Government, however, reserves the right to disapprove design document submittals. In this case, every effort shall be made during follow-up action between the Contractor and the Kansas City District to resolve conflicts and problems so that design documents can be approved. However, if the final submittal is incomplete or deficient, requiring correction by the Contractor and re-submittal for review beyond;

the first back check review, the cost of handling and re-reviewing will be deducted from payment due the Contractor at the rate of \$500 per submittal.

1.6.5 Government Review

The Contractor shall submit complete design documents in the same quantity to the same office described in paragraph 5.a, for each additional Back check submittal until the Government is satisfied that all review comments have been addressed and resolved. Following government approval of the last back check submittal, the Contractor shall submit 2 copies of the electronic CADD .dgn files within seven (7) calendar days, including three (3) complete sets of full size copies and six (6) half scale copies of the drawings and nine (9) copies of the specifications to Fort Riley Area Engineer Office, six (6) complete sets of half size drawings and specifications to the Fort Riley Public Works, and six (6) complete sets of half size drawings and specifications to the Kansas City District Office. The Contractor shall properly sign, stamp or seal the final dated drawings.

1.7 APPROVALS PRIOR TO CONSTRUCTION

Acceptance of the final plans and specifications shall be obtained from the Contracting Officer prior to the start of construction. However, the Army may accept a design submission for site development, and if found satisfactory, allow the contractor to proceed with earthwork and other elements of site development while final plans and specifications for total work being completed. The responsibility for a totally integrated design in accordance with the contract will remain with the contractor and this interim NOTICE TO PROCEED will in no way mitigate against that responsibility.

1.8 SUBMITTAL REGISTERS

On receipt of approval to start construction, the Contractor shall submit copies of ENG Form 4288, Submittal Register, in accordance with Section 01330: Submittal Procedures, paragraph: Submittal Register.

1.9 DESIGN DRAWINGS

See Section 01100. Provide final As-Built Drawings in CADD using Micro station format. Design criteria and referenced drawings furnished by the Government are intended to serve as minimum standard in the preparation of acceptable working drawings and specifications. Applicable details of these drawings shall be incorporated into the working drawings and specifications without reference to their source. Incorporation by reference only is not acceptable. Plan sheet size preferred is "D" size (24 by 36 inches)(full size). Sheet size "E" (28 by 40 inches) is acceptable. Construction drawings shall be provided in both original hard copy and on a CD-ROM compact disk and produced in a Bentley Micro Station 95 CADD format.

1.9.1 Cover Sheet

A cover sheet for the drawings shall be provided by the Contractor and the cover sheet shall include, as a minimum, the project number and title,

project location, installation map, contract number, and execution year.

1.9.2 Format

Drawings shall be produced in a Bentley MicroStation 95 CADD format and compatible without conversion with the CADD system hardware and software in use at Fort Riley PW.

1.9.3 CADD Files

CADD files must display as plotted and vice versa (WYSIWYG). Formatting and layering in CADD drawing design files shall be in accordance with the Tri-Service Architectural/Engineering/Construction Computer-Aided Design and Drafting (CADD) standards. Half-scale drawings shall be exact half-scale reproductions of the full-scale drawings.

1.9.4 CADD Design Files

Design files shall be fully compatible with Bentley MicroStation 95 version or earlier version. Plotted files shall provide final deliverable CADD files that display all design file features correctly when plotted on the current Public Works plotters. Currently Public Works plotters are HP 650c plotters. CADD reference files shall be merged when used to create drawings and cover sheets.

1.10 CONFLICTING DOCUMENTS

In cases of conflicts between the IFB and contractor's design, the IFB (Scope of Work, including applicable laws and regulations) shall govern. Other conflicts that arise shall be referred to the Contracting Officer for determination.

1.11 SCHEDULE AFTER AWARD OF CONTRACT

The Contractor shall provide a detailed schedule, which shall include a phasing plan, utility disruptions, demolition/asbestos abatement plan, erosion control plan, and any other activities that would affect existing construction, on or off the project site.

1.12 CONSTRUCTION REQUIREMENTS

After the Contractor has completed the applicable project design documents the Government will issue to the Contractor a notice to proceed with construction. Prior to commencement of construction a Pre-construction Conference will be held to acquaint the Contractor with the general plan of contract administration and requirements under which the construction operation is to proceed. This conference will also inform the Contractor of the obligations concerning equal opportunity and Federal wage rates reporting system.

1.13 CONTRACT CLOSEOUT

Completion, acceptance, and contract settlement are accomplished when final punch list items (see Contract Clause Inspection of Construction) have been

completed and approved, as-built drawings are complete, and warranty provisions and dates are established.

1.14 CRITERIA

The design criteria referenced in this section is intended to serve as a minimum standard for the Contractor to prepare designs. Additional criteria are available to the Contractor at the TECHINFO web site. Technical manuals and other DOD criteria shall not be referenced in the specifications. The project requirements shall be abstracted and incorporated into the specifications. Hard copies will not be provided to the Contractor. Criteria is available electronically at the following web sites:

- a. TECHINFO: <http://w2.hnd.usace.army.mil/techinfo/>
- b. Publications of HQUSACE: <http://www.usace.army.mil/inet/usace-docs/>
- c. Construction Criteria Base: <http://www.ccb.org/html/home.html>
(use CE0688 for the user identification and the password for access)
- d. Army Regulations and Pamphlets (AR's, AP's):
<http://books.army.mil/cgi-bin/bookmgr/Shelves>
- e. Standards. The drawing standards used shall comply with the Tri-Service A/E/C CADD Standards. The manual is available at <http://tsc.wes.army.mil>
- f. Specifications: The Contractor shall prepare specifications using Unified Facilities Guide Specifications in SPECSINTACT. If the Contractor needs to prepare specifications for items of work not covered by guide specifications, the format of the new specifications shall match the guide specifications.
- g. Fort Riley Installation Standard Design Guide.

1.15 SITE SURVEY

All topographic survey data needed to complete the design of Trooper-Apennines Traffic Roundabout shall be accomplished by the Contractor.

1.15.1 Maps

Topographic (including site features), limits of construction and existing utility lines must be adequately described by means of maps. Scale of maps will vary depending on size of the site and intricacy of detail to be shown. In general, maps should be drawn at a scale of not less than 1:1000. It is desirable to base the maps on a coordinate system and to show the coordinate lines. All features will be shown accurately to scale.

The Contracting Officer will furnish base map .DGN files following award of this option. The base coordinate system can be obtained from the KCD survey section. The topographic map will show site boundaries and the following additional information.

1.15.1.1 Benchmarks and Monuments

Sufficient benchmarks and monuments to serve during preparation of the site plan and during actual construction shall be shown.

1.15.1.2 Contours

Shape of the ground by contour lines and by spot elevations at all significant points shall be shown. Contour interval will be 0.25 meters . Spot elevations on which contours are based will also be indicated on the map.

1.15.1.3 Elevations

Elevations of streets and curbs by spot elevations at all significant points shall be shown.

1.15.1.4 Existing Facilities

Existing site facilities, such as buildings, parking areas, roads, walks, fences, and retaining walls shall be shown.

1.15.1.5 Water Courses

Water courses, ponds, etc., and the elevation of high water if possible shall be shown.

1.15.1.6 Rock Outcrops

Rock outcrops by accurate outlines and by enough points of elevation to indicate their shape shall be shown.

1.15.1.7 Existing Trees

Data on existing trees shall be provided, including location, identification by common name, diameter of trunk (four feet above the ground), approximate spread of branches, and average ground elevation at the base of isolated trees six inches or more in caliper, principal trees on property lines, and along margins of woods, the largest and best trees within woods at the rate of not less than 16 per acre, and foliage outlines for edges of woods and for masses of shrubby vegetation.

1.15.1.8 Utility Map

This map will show all utility easements or rights-of-way, location, size and invert elevations of existing sanitary sewers, storm drains or open drainage channels, drain inlets and manholes, location and size of existing water, gas and steam mains and underground conduits, location of existing overhead electric power, street lighting, and telephone lines, including pole locations, location of rail lines and rights-of-way, location of fire alarm call boxes and similar appurtenances.

1.15.1.9 Verification of As-Built

The AE shall be responsible for verifying as-built information as needed for the design.

1.15.2 Environmental Recommendations

The intent of the Government is to design within environmental requirements currently in effect. Every effort will be made to comply with the environmental recommendations provided by the Installation. If in the opinion of the AE compliance with the requirements cannot be accomplished due to engineering problems, the AE will immediately notify the Contracting Officer in writing with recommendations.

1.16 SUBSURFACE INVESTIGATIONS

Borings, testing and field logs are the responsibility of the Contractor. A Pavement Design, completed in strict accordance with the Scope of Work, and based on information developed as a result of the subsurface investigation, is required. Boring logs and basic soils design assumptions shall be placed on the drawings.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

INDEX

EXTENSION OF DESIGN SCOPE OF WORK: FORT RILEY, KANSAS TROOPER-APENNINES TRAFFIC ROUNDABOUT

Extension of Design Scope of Work

Enclosures:

1. Site Design and Utility Relocation Design Requirements
2. Survey Requirements
3. Geotechnical Requirements
4. Pavement Design Requirements

Sheets:

1. Option 16 Site Plan
2. Option 17 Site Plan
3. Option 16 Boring Location Plan
4. Option 16 typical Sections
5. Option 16 Pavement Profiles
6. Option 16 Miscellaneous Details
7. Option 16 Conceptual Traffic Plan

Exhibits: Utility Maps

1. Electric
2. Gas
3. Water
4. Sewer
5. Storm Drainage
6. Cable TV
7. Telephone and data (fiber optic)
8. Survey Control Points

**EXTENSION OF DESIGN SCOPE OF WORK:
FORT RILEY, KANSAS
TROOPER-APPENNINES TRAFFIC ROUNDABOUT**

1. SCOPE (Options 16 and 17)

Option 16 to the Contract consists of (1) completing the design of the Trooper-Appennines Roundabout; and (2) constructing the project in accordance with the Contract.

Option 17 includes the design and construction activities associated with adding 3 pedestrian underpasses to the Trooper-Appennines Roundabout project.

1.1 Design

The design has been partially completed: A traffic study was conducted and computer simulation modeling was utilized to identify and prepare the concept design. The enclosed "Option 16 Site Plan" (Sheet 1) shows the overall layout including proposed horizontal geometrics. Contract specifications shall apply, however, if determined necessary during design, Contractor may propose changes and develop additional specifications.

Also enclosed are "Option 17 Site Plan" (Sheet 2), "Option 16 Boring Location Plan" (Sheet 3), "Option 16 Typical Sections" (Sheet 4), "Option 16 Pavement Profiles" (Sheet 5), "Option 16 Miscellaneous Details" (Sheet 6), and "Option 16 Conceptual Traffic Plan" (Sheet 7) to be used by the Contractor in completing the Roundabout Design. The successful Contractor will be provided the design files included with this document in MicroStation format.

1.2 Qualification

The lead designer is required to have demonstrated roundabout design experience (responsible charge of a minimum of 3 comparable projects). The engineer responsible for the design of traffic control systems, roadway signing and pavement markings must be a registered Professional Traffic Operations Engineer (PTOE). Prior to commencing design work, the Contractor shall submit for Government approval, documentation of PTOE registration and comparable project design experience, including client references (names and telephone numbers).

2. GENERAL DESIGN REQUIREMENTS

2.1 Surveying

Survey requirements are described in Enclosure 2. Exhibits 1 through 8 provide approximate extent and locations of existing utilities in the project area, however, additional utilities may be present. Exhibit 9 provides approximate control point locations. Survey control point data (coordinates, elevation, datum shift, etc.) will be provided following Contract award.

2.2 Geotechnical Investigation

Contractor shall complete a geotechnical investigation, with minimum requirements being as shown in the "Option 16 Boring Location Plan" (Sheet 3) and in Enclosure 3. The boring locations, depths and lab tests shown are the minimum required. Contractor will be required to coordinate with the Contracting Officer: hours during which drilling is allowed may be limited. Prior to drilling the Contractor shall obtain Environmental Clearance from the Contracting Officer.

3. DESIGN COMPLETION

3.1 Design Submittals

Design submittals are explained in the Contract (Section 01130). Design guidance is explained in Enclosure 1.

3.2 Design Plans

Using the survey, geotechnical report and the documents included with this scope of work design the pavement section and geometrics (both vertical and horizontal) to complete the Roundabout Design Plans.

3.3 Pavement Design Requirements

Pavement design requirements and criteria are listed Enclosure 4. The pavement design will consist of concrete curb and gutter and a minimum of 200 mm of asphalt pavement over a drained granular base (Contractor is required to complete the design analysis for the pavement as part of the design). The horizontal geometrics are provided (curve radii, number of lanes and approximate alignments), but the alignments, which are based on planimetrics, shall be adjusted as needed by the Contractor to fit the survey. Longitudinal grades for the roadways shall be a maximum of 5 percent.

3.4 Storm Drainage

The storm drainage on the project shall be accommodated through the use of curb inlets. The pipes from the inlets shall discharge into the existing roadway ditch system.

3.5 Sidewalks

The existing sidewalks in the area will be reconnected to the new roadway pavements using wheelchair ramps at the curbs. Sidewalks shall be concrete and shall match existing sidewalk widths and shall be a minimum of 6 inches in depth.

3.6 Street Lighting

Street lighting shall be provided and designed in accordance with FHWA Roadway Lighting Manual (use urban collector as a minimum design requirement). Street light units will be placed

at all roadway project crosswalks. Existing street lights shall be salvaged and delivered to an on-post location designated by the Contracting Officer.

3.7 Landscaping

Landscaping shall at a minimum restore all areas disturbed by construction to a grass covered condition. The contractor shall provide whatever measures are necessary to prevent erosion.

3.8 Permitting

The contractor is referred to the Contract Specifications for all permit requirements.

3.9 Utility Relocations

Any utility relocations required by the final design shall be designed by the Contractor and relocated by the Contractor as part of this project.

3.10 Traffic Management

Traffic Management is a critical aspect of this project. A Traffic Management Plan shall be submitted for Government approval. Overnight closures (1900 to 0500) will be allowed, but access across Trooper Drive shall be provided at all times. Daytime traffic restrictions will be allowed (0500 to 1900), however, road closures will not be allowed 0500 to 1900 hours. During the peak traffic times (0530 to 0630, 0715 to 0815, 1130 to 1230 and 1630 to 1730), only limited traffic restrictions will be allowed. A flagman may be used during off-peak times.

Contractor may elect to construct a temporary detour road around the south side of the PX as shown on Sheets 1 and 2. The temporary detour road shall be at least 7.315 meters wide with 3 meter wide unpaved shoulders. The minimum pavement section for this detour road will be least 100 mm of asphalt concrete over 150 mm of graded crushed aggregate base course. This road will require a culvert, sized to pass the 10-year storm, in the existing drainage ditch. Drainage calculations developed for culvert sizing must be included in the Design Analysis Report. Contractors may leave the detour road in place at the conclusion of the project.

3.11 Signal Removal

The existing traffic signals at the Apennines-Warren Drive intersection will be removed (salvaged) and delivered to an on-post location designated by the Contracting Officer.

3.12 Traffic Signing

A Traffic Signing plan shall be completed by the Contractor for review and approval by the Government. **The traffic signs shown on the attached plan sheets are for informational purposes only and are not representative of the required traffic signs for the roadway project. Prior to submittal of the 50 percent design plans, the traffic signing plan shall be coordinated with the**

Contracting Officer. All traffic signs used on this project shall be Standard size signs or larger and comply with the Manual on Uniform Traffic Control Devices (MUTCD).

Yield and stop signs shall be placed at the approaches shown in Sheet 7.

"Keep Right" signs (MUTCD R4-7) shall be placed at median noses that separate traffic entering and exiting the circulating roadway (separating head to head traffic).

"Wrong Way" signs (MUTCD R5-1a) shall be placed on the circulating roadway upstream from entry points. The signs will also be placed on entry and exit roads that vehicles could incorrectly turn onto. At each location, the signs will be placed on both sides of the roadway. "Do Not Enter" signs (MUTCD R5-1) may be used in place of the wrong way signs at the direction of the Contractor's design engineer and with the approval of the Contracting Officer.

A "One Way" sign (MUTCD R6-1) will be placed across from the Warren Drive entry point to indicate the direction of flow on the circulating roadway.

Street name signs shall be placed at each intersection. Way finding signs shall be placed along the circulating roadway and on adjacent roads as needed to clearly identify downstream roadway connections.

3.13 Pavement Markings

All pavement markings shall be thermoplastic. Pavement markings shall comply with the MUTCD.

A Pavement Marking plan shall be completed by the Contractor for review and approval by the Government. The pavement markings shown on Sheets 1, 2 and 3 are for information only and may not be representative of the required markings for the roadway project. Prior to submittal of the 50 percent design plans, the pavement marking plan shall be coordinated with the Contracting Officer.

Turn arrows shall be placed on exclusive turn lanes and exclusive lanes shall include "only" markings. Turn arrow and "only" markings shall be placed in advance of and at intersections. Spacing shall be coordinated with the Contracting Officer. Shared through/turn lanes shall be marked with shared through/turn lane arrows in advance of and at intersections. Median approaches will require markings as described in section 3.15. Stop bar markings shall be installed at each stop sign location. Arrows shall be placed on the circulating roadway to indicate direction of travel upstream of entry points to communicate direction of flow to the drivers.

3.14 Crosswalks

Required crosswalk locations are shown on the "Option 16 Site Plan (Sheet 1). Details of the crosswalk markings are shown on the "Option 16 Miscellaneous Details" (Sheet 6). Crosswalk markings shall be thermoplastic.

3.15 Medians

All median islands shown on the “Option 16 Site Plan” (Sheet1) shall be raised islands with 6 inch curb unless otherwise noted. The median islands shown in black shall be paved with a minimum of 6 inches of concrete unless otherwise noted.

All island noses facing approaching traffic shall have a paved ramp nose similar to the detail shown on “Option 16 Miscellaneous Details” (Sheet 6). The ramp portion of these noses shall be covered with yellow thermoplastic.

3.16 Trooper-Desert Storm Intersection

The limits of construction are shown on Sheet 1. The south, east and west legs of the intersection will be constructed by others, however, pavement markings will exceed the limits of construction, as shown.

Traffic control shall consist of stop signs on Desert Storm Drive (eastbound and westbound approaches) along with time-of-day restricted turning movements described as follows: During peak traffic periods as defined by the Contracting Officer, left-turns will be restricted on Trooper Drive (northbound and southbound approaches) and the left-turn and through movements on Desert Storm Drive (eastbound and westbound approaches) will be restricted. These lane movement restrictions shall be communicated to motorists using both conventional ground mount signs in advance of the intersection and with overhead fiber optic or LED signs. As part of this contract, traffic signal pole assemblies and equipment at the Trooper-Apennines intersection shall be relocated to the Trooper-Desert Storm intersection and shall provide timer-activated lane control signage. Any equipment not needed for the Trooper-Desert Storm installation will be salvaged and delivered to a location designated by the Contracting Officer. The fiber optic or LED signs will be mounted over and centered on the lanes being restricted.

The Trooper Drive signs will display a no left-turn diagram (MUTCD R3-2) when that movement is restricted. The arrow will be white with the circle/slash red. The Desert Storm signs will be similar to the Trooper Drive signs except they will show shared through-left arrows instead of a left-turn arrow. They will be on only when the movements are restricted. The signs will be off or blank at all other times of the day. The advanced conventional signs will show the restricted movements and include a placard noting the times of day the restrictions are in place. Specifications for and design of the signal control installation will be completed by the Contractor and provided to the Government for review and approval.

4. OPTION 17

4.1 Pedestrian Underpass

Option 17 consists of (1) designing three pedestrian underpasses and the associated connecting sidewalks, stairs and ramps together with the necessary drainage, grading and security/safety

lighting to the design of the Trooper-Apennines Roundabout (Option 16); and (2) constructing these additions to the Option 16 project in accordance with the Contract.

4.2 Geotechnical Investigation

The Contractor shall incorporate into the geotechnical investigation, required for Option 16, three additional borings, one each at the locations of the Pedestrian Underpasses as described in Enclosure 3.

4.3 Design Plans

The general layout of the three pedestrian underpasses and the sidewalk/stair/ramp access system is shown on the enclosed "Option 17 Site Plan" (Sheet 2). The design shall endeavor to layout the sidewalks, grading and underpass structure locations in such a manner that the majority (if not all) of the areas are visible from the surrounding roadways and/or parking areas. The minimum design for the sidewalks in this option shall be 4 feet wide and 6 inches thick concrete. Through the underpasses the sidewalks shall be 6 foot wide. The sidewalks shall have a maximum grade of 5 percent. Where it is necessary to exceed 5 percent, due to space limitations, the sidewalk shall be classified as a ramp and be designed to handicapped standards (ADA).

The underpasses shall have minimum clearances of 6 foot wide and 8 foot high. The underpasses shall have minimum cover of 2 feet in roadway and sidewalk areas and 1 foot in landscape areas. All lighting associated with the pedestrian underpasses shall have incandescent fixtures suitable for wet locations with guarded, shatterproof globes. All exposed surfaces of the underpasses shall be covered with a material to provide a graffiti-resistant surface. Guardrail shall be provided on both sides of the roads at the pedestrian underpass locations.

END

ENCLOSURE 1: SITE DESIGN

1. SCOPE. The Design Requirements include all the requirements for the location and layout of a construction project.

2. PURPOSE

3. REFERENCES.

TECHINFO: [Techinfo Home Page](http://www.hnd.usace.army.mil/techinfo/)

<http://www.hnd.usace.army.mil/techinfo/>

Publications of HQUSACE:

<http://www.usace.army.mil/inet/usace-docs/>

4. PLANS REQUIRED. Any or all of the following plans may be required to show the complete design requirements:

4.1 Concept Plans.

Typical Pavement Sections

Site Plan

Pavement Profiles

4.2 Final Plans.

Typical Pavement Sections

Site Plan

Removal Plan

Pavement Profiles

Erosion Control Plan

Utility Plan

Grading and Storm Drainage Plan

Miscellaneous Details

5. DESCRIPTION OF PLANS.

5.1 Typical Pavement Sections. Required typical pavement sections showing the various lane configurations and pavement design components.

5.2 Site Plan. The Site Layout Plan shall show all the site design and layout information necessary to field locate the drives, walks, roads, and all other appurtenances to be constructed on the project. The information shall be complete to the extent that dimensions or coordinates will locate every constructed item above and below the ground. Site Plans shall be a scale of 1:250 metric. The Site Plan, prior to adding the dimensions, should serve as the base sheet to provide reproducible drawings for the Utilities Plan, and the Grading and Drainage Plan. The Site Plan shall show all existing physical features and utilities within and adjacent to the work site that will remain after the proposed construction has been completed. Whenever the Site Plan occupies more than one sheet of drawings, a Key Plan shall be included. Landscaping shall be shown on the Site Plan. Landscaping shall show or designate the limits of seeding and/or sodding (all unsurfaced ground areas disturbed by construction within the project limits shall be seeded and/or sodded).

5.3 Removal Plan. The removal plan will show the existing physical condition of the site before construction. The physical features usually include field survey information such as the above and below ground utilities; buildings, drives, roads and parking areas, walks, trees and tree sizes, shrubs, and other vegetation; and such facilities as retaining walls, etc. Each physical feature to be removed shall be as indicated on the standard legend sheet and properly noted to be removed, to remain, or to be relocated.

5.4 Erosion Control Plan. An erosion control plan and specification shall be prepared by the Contractor showing berms and dikes, retention or detention ponds, silt fences

and temporary seeded areas if determined to be necessary for the specific project.

5.5 Site Grading and Storm Drain Plan. The site grading and storm drain plan shall be at a scale of 1:250, using the basic site plan layout (without siting notes and dimensions) showing the following:

Existing utilities to remain.

Existing grading contours.

Uniform grades shall be labeled using slope arrows.

Proposed new culverts, storm drains, and subdrains with tentative sizes.

Location of borings.

5.6 Pavement Profiles. Pavement profiles for all new roads and streets, with vertical curve information. Profiles shall show all underground utilities existing and new.

6. SURVEY REQUIREMENTS.

6.1 A Field Survey for the design of the project shall be furnished by the District or by the A-E as directed by the scope of work. The Survey requirements are as follows:

6.2 Contractor furnished Surveys.

6.2.1 General. The Contractor shall perform all engineering and topographic surveys for this project. The original Surveys, field notes, and digital data are District property and shall be furnished to the Contracting Officer. Electronic drawings and data shall be furnished in a Micro-Station compatible format. Meta Data shall be provided as required by EM 1110-1-2909. See Enclosure 2 for additional survey requirements and information.

7. WASTE AND BORROW AREAS.

7.1 See the Project Specifications for Waste and Borrow Area availability and requirements.

8. CONTRACTOR'S STAGING AREA AND PARKING.

8.1 Show areas for Contractor storage, temporary fencing, sheds, and parking for subcontractors and their employees if this information is available during design.

9. WORK BY OTHERS.

9.1 Any work, be it construction, relocation, and/or removal, shown on the drawings, which is not existing but to be performed by others shall be identified on the Site Plan, Site Preparation, Utilities and/or Grading and Drainage Plans as "N.I.C." (For "Not in Contract"). Note on each drawing that there is information on the drawings for work, which is not in the contract.

10. FINAL DESIGN. In general, the final design documents must include sufficient information for construction of the project. Specific requirements for plans, are given below.

10.1 Drawings. Generally, the corrected concept plans may be used as the basis for the final plans; however, all details necessary to complete construction must be included. The following information is required in addition to the previously stated requirements for concept plans.

New grading contours shall be provided on the site grading plan.

Profiles of all new storm drains, subdrains, and culverts showing new and existing grades, pipe diameters and lengths, pipe slopes, invert elevations, top of grade elevations, top of man hole elevations, etc. Class and gage of all storm drain pipes should be provided.

Details of all storm drain and subdrain structures.

Storm drain and subdrain structure schedules.

Traffic Signing and Striping Details.

A grading plan with finished contours and a plan and profile with complete horizontal and vertical curve data. Plan and profile drawing shall also show existing contours for bidding earthwork quantities.

11. GRADING. Positive drainage shall be provided for all areas and existing drainage ways shall be utilized to the extent possible. Required excavation and embankment quantities shall be balanced to the extent possible without compromising the design. Ice on walks should be a safety consideration for all areas.

11.1 Design Criteria.

Department of the Army and Air Force Technical Manuals.

TM 5-822-2 - General Provisions and Geometric Design for Roads, Streets,
88-7, Chap 5 - Walks, Open Storage Areas (July 87)

Handicapped Standards.

Uniform Federal Accessibility Standards (1984)

11.2 Additional Criteria Limits.

11.2.1 Gutter Grades:

Desirable minimum of 0.8 percent.

Absolute minimum of 0.5 percent.

11.2.2 Longitudinal Walk Grades:

Maximum of 5 percent.

11.2.3 Overlot Grades:

Minimum 1 percent for cohesionless sandy soils.

Minimum 2 percent for cohesive soils or turfed areas.

Minimum grade of 0.3 percent for channelized flow.

12. DRAINAGE.

12.1 Design Criteria.

12.1.1 Department of the Army and Air Force Technical Manuals.

TM 5-820-1 - Surface Drainage Facilities for Airfields and Heliports (Aug 87)
88-5, Chap 1

TM 5-820-4 - Drainage for Areas Other Than Airfields (Oct 83)
88-5, Chap 4

12.1.2 Department of the Army Technical Manuals.

TM 5-820-3 - Drainage and Erosion Control, Structures for Airfields and Heliports (Jan 78)

12.1.3 Engineer Manuals.

EM 1110-2-2902 - Conduits, Culverts, and Pipes (Mar 69)

12.2 Storm Run-off. Determination of storm run-off shall be in accordance with the method presented in TM 5-820-1/AFM 88-5, Chapter 1 or TM 5-820-4/AFM 88-5, Chapter 4. Sizing of storm drainage systems for developed portions of military installations such as administrative, industrial, and housing areas as well as roadway culverts shall be based on rainfall of 10-year frequency. Protection of military installations against flood flow originating from areas exterior to the installation will normally be based on 25-year or greater rainfall, depending on operational requirements, cost-benefit considerations, and nature and consequences of flood damage resulting from the failure of protective works.

12.3 Storm Drainage System Layout. The storm drainage system shall be designed so as to minimize the number of drainage structures required. Structures shall be located at all changes in direction of storm drain line, at the intersection of two or more storm drain lines, and where required to intercept rainfall runoff. The distance between drainage structures will be not more than approximately 100m for conduits with a minimum dimension smaller than 760mm. Storm drain lines shall be located outside of paved areas to the extent possible. Curb inlets shall be spaced along two-lane roads so that the width of flooded areas does not exceed half the lane width. Where storm drain pipes are of different diameters, the pipe crowns shall be matched at the centerline of drainage structures.

13. TRAFFIC SIGNAGE DESIGN CRITERIA. Traffic signage shall be provided for all new roads. The Contractor shall address traffic signage with the facility user. American National Standards Institute (ANSI) Standards:

D6. 1-1988 - Manual on Uniform Traffic Control Devices for Streets and Highways.

UTILITY RELOCATIONS

1. SCOPE. Items covered in this section include water supply and distribution systems, outside fire protection, sanitary sewage systems.

2. REFERENCES.

TECHINFO: [Techinfo Home Page](http://www.hnd.usace.army.mil/techinfo/)
<http://www.hnd.usace.army.mil/techinfo/>

3. PRELIMINARY DESIGN.

3.1 Drawings. Drawings shall contain, as a minimum, the following:

Using the basic site plan layout show the following:

3.1.1 All Existing Utilities.

3.1.2 Water Supply, Sewer, Gas, Power, and Communication lines (Relocations)

Develop separate layout sheet showing:

Proposed routing and tentative sizes.

Existing utilities and aboveground features, which could affect construction.

Show proposed locations for manholes, relief valves, blowoffs, isolation valves, etc.

Proposed valves (including PIVs), lift station and manhole locations.

Proposed fire hydrant locations.

Lighting

4. FINAL DESIGN. In general, the final design documents must include sufficient information for construction of the project. Specific requirements for plans and design analysis are given below.

4.1 Drawings. Generally, the corrected and approved concept plans may be used as the basis for the final plans; however, all details necessary for complete construction must be included. The following information is required in addition to the previously stated requirements for concept plans.

4.1.1 Water Distribution , Sewage Collection Systems and Gas Distribution (Relocations)

Profiles of all gravity sewers, waterlines and sewage force mains. Profiles may be omitted for short waterlines unless necessary to assure adequate cover or avoid interference with other underground facilities.

Indicate existing pipe material where new lines connect. Indicate type of connection and elevation.

Location of all valves, fire hydrants and similar appurtenances.

Appropriate water and sewer details.

For pavement cuts, show type of pavement to be removed and replaced.

4.1.2 Water Supply Lines, Outfall Sewers, Long Force Mains.

Include survey ties and/or bearings.

Include stationing in both plan and profile.

ENCLOSURE 2: SURVEYING REQUIREMENTS

1. Survey. The project scope includes performing an engineering and topographic survey on which to base the design. The following are minimum survey requirements for this project.

1.1. Surveyor shall be responsible for contacting 1-800-344-7233 and Ft. Riley Public Works (Building 337, 913-239-8187) for utility flagging.

1.2. Record and confirm the locations of any permanent benchmarks located inside and outside the project limits. Survey shall have at least three monument points.

1.3. The levels on which items are placed shall be done in accordance with Tri-Service CADD standards:

1.3.1. Table 1 in the Tri-Service CADD standards lists the level attributes.

1.3.2. Table 2 in the Tri-Service CADD standards lists the north arrow, scale marker, existing legend to be used.

1.3.3. Scale shall be 1:250 metric.

1.3.4. Text size shall be 0.6 meters high at 1:250 scale.

1.3.5. Font shall be 1.

1.4. The survey shall be provided in metric units with a 0.3 - meter contour interval. Provide spot elevations at high and low points and abrupt changes in grade along centerline and at top of bank of drainage courses, at structures, physical appurtenances, roadways and adjacent walkways if any exist. The survey shall show all natural and manmade features to include all utilities above and below ground indicating types, sizes, depths, invert elevations, etc. Show all trees by species, diameter, and location. Show all infrastructure at a level of detail appropriate for the mapping scale and accuracy. Plot all ground shots to the nearest (.003 meter) and all hardened surfaces to the nearest (.003 meter). Show all bench marks and other control points with elevations. Also, establish and show coordinate locations for key permanent points, i.e., streets intersections and corners of structures, and the control traverse of the survey.

1.5. Provide ground spot elevations on obvious eroded surfaces (i.e., eroding drainage paths from downspout outlets, culvert outlets, etc.).

1.6. Locate all existing street centerlines, edges of pavement, type of pavement, sidewalks, retaining walls, fences, buildings, piers, abutments, structures, curbs, utilities, etc.

1.7. Identify the major trees (100 mm) and indicate trunk size at a height of 1 M above the existing ground line at the base of the tree and the type of tree. Locate shrubbery and indicate accordingly.

1.8. Water Lines: Locate all valves, standpipes, regulators, etc. Locate all fire hydrants. Provide an elevation on top of valve case and top of valve. Provide size of pipe, material, and distance above ground for standpipes.

1.9. Sanitary Sewers: Locate all manholes/cleanouts and provide type of manhole (i.e., concrete, brick), manhole diameter, and top of rim elevation along with invert elevation of all pipes connected to the manhole. Identify type, size, and direction of each pipe. Locate and identify force mains, lift stations, gate structures, etc.

1.10. Storm Drainage: Locate manholes and all other storm drainage structures such as culverts, pipe outfalls, headwalls, catch basins, gate structures and cleanouts. Provide type of manhole (i.e. concrete, brick, etc.), manhole diameter, top of manhole or top of catch basin elevation along with an invert elevation of all pipes connected to a manhole or catch basin. Identify type, size, and direction of each pipe. Provide type, size, and invert elevations for all culverts. Provide information on existing pipe closures (i.e. flap gates, sluice gates, etc.) such as: size, type of material, controls, etc.

1.11. Electrical: Locate all power poles, guy wires, vaults, manholes, meters, transformers, electrical boxes, and substations. Obtain type and height of poles, number and size of transformers, number of cross arms, number of wires (electrical and communication), direction and low wire elevation at each pole. Identify the number and anchor points of any guy wires. Provide top of rim or top of vault elevation, top of wire or conduit elevation, direction and bottom elevation of manholes and vaults. Provide size for all electrical vaults and boxes.

1.12. Gas: Locate all valves, meters, and gas line markers. Provide elevation on top valve case and on top of valve.

1.13. Telephone: Locate all poles, manholes, boxes, etc. Provide top of rim elevation, top of wire or conduit elevation, direction and bottom of manhole elevation. Obtain type and height of poles; number of cross arms; number of wires and low wire elevation at each pole.

1.14. Street Light: Locate all poles and provide type and height of poles. Identify number and type of lights on poles. If connected by wires, show direction and low wire elevation.

1.15. Equipment and Use. Vertical control shall be established with spirit or self-leveling instruments. Trigonometric leveling or "total stations" shall not be used in setting vertical control or in determining the elevation of critical items such as floors, foundations, runways or taxiway, drainage structures, and utility lines. Horizontal control shall be established with equipment capable of producing the accuracies specified below.

1.16. Accuracy. The project Survey shall meet or exceed the horizontal and vertical accuracy as specified in EM 1110-1-1004 and EM 1110-1-1005.

1.17. Horizontal and Vertical Control. Field Surveys shall incorporate existing horizontal and vertical control. Horizontal control shall be referenced to the North American Datum of 1983. Vertical control shall be referenced to the North American Vertical Datum of 1988. Projects shall be referenced to the State Plane Coordinate System (include combined factor used to convert to horizontal) unless other wise specified in the scope of work. The use of these control points and benchmarks shall be fully documented on the Survey and in the field notes. All project specific horizontal and vertical control shall be described fully in the field notes and shown on the map.

1.18. Final product shall be a Bentley Microstation 3d file. The survey file shall have the following data included:

- 1.18.1. Control point descriptions
- 1.18.2. Survey crew names
- 1.18.3. Date of survey
- 1.18.4. Combination factor used in the reduction to state plane system
- 1.18.5. The file shall have north arrow, bar scale, state plan coordinate system grid (with coordinate labels).
- 1.18.6. Provide a table of Sanitary Sewer information.
- 1.18.7. Provide a table of Storm Sewer information.
- 1.18.8. Provide a table of survey control and TBM information.
- 1.18.9. Provide a 100 M x 100 M grid with coordinate values

ENCLOSURE 3: GEOTECHNICAL REQUIREMENTS

1. GENERAL. This Enclosure describes minimum requirements for the Geotechnical Investigation.

2. SUBSURFACE EXPLORATIONS. The Contractor shall obtain a minimum of ten (10) borings near the locations shown on the “Option 16 Boring Location Plan” (Sheet 3). These borings shall be to a minimum depth of 1.5 meters. If Option 17 is selected, the Contractor shall obtain an additional three (3) borings (one each at the location of each Pedestrian Underpass) to a minimum depth of 4.6 meters.

3. BORROW MATERIAL CHARACTERIZATION. If required, borrow soils are available on post. The Contractor shall perform sufficient sampling and testing borrow materials to confirm the material meets the suitability requirements. Recommendations for material suitability shall be supported by laboratory data.

4. GEOTECHNICAL REPORT is required. Contractor shall use relevant criterion (see below. Photographs of any rock core obtained during drilling shall be included in the Geotechnical Report. The Geotechnical Report shall address the following:

- The pavement design shall be justified by inclusion of all design computations and/or references;
- Material parameters and subsurface soils characterization;
- Engineering instructions for the construction contractor/construction inspectors.

4.1 Material requirements. The designers develop a summary of the type of materials to be used on the project. This summary be provided in the Geotechnical Report.

4.1.1 Borrow Areas. Borrow material needs shall be identified in the Geotechnical Report to include the quantity and types of materials required by the project. Coordinate with the Contracting Officer to identify suitable existing borrow sources located on Government property. A summary of the borrow material parameters shall be included in the Geotechnical Report along with laboratory results to support the material’s suitability for use in project applications.

4.1.2 Special Material Requirements. Special material requirements shall be identified in the Geotechnical Report: For example, sensitive soils that are subject to volume changes with changing soil moisture content. Contractor shall provide mitigation measure recommendations to safeguard the project from the detrimental effects of these materials (special compaction requirements, special moisture conditioning, etc.).

5. DRAWINGS. The geotechnical report include the following drawings.

5.1 Borings locations (surveyed).

5.2 Boring Logs. Copies of the boring strip logs shall also be included in the construction drawings.

5.3 Boring Log Legend.

6. PAVEMENT DESIGN. Contractor shall provide the following:

6.1 Design Calculations, Sections, and Requirements. Design calculations, sections, and requirements based on the design data, current criterion, results of the geotechnical investigation and relevant materials design requirements. Design calculations, sections, and requirements shall be included in the Design Analysis. Additional pavement design requirements and information is included in Enclosure 4.

6.2 Pavement Design Specifications. Pavement and materials requirements are provided in the project specifications. Contract specifications for aggregates, bituminous materials, Portland cement concrete, and joint sealants shall be reviewed to ensure applicability and Contractor shall prepare any specifications for Government approval, which are not included in the Contract.

6.3 Pavement Design Drawings. Typical pavement sections shall be provided showing the various lane configurations. Details showing interface between new and existing pavements, new pavements of different sections, joint sealant details, and other relevant design details shall be provided.

7. QUALITY CONTROL: Contractor's Quality Control Plan shall address and apply to the Geotechnical investigation and report.

8. CRITERIA: Any conflicts between criteria listed below shall be documented and submitted to the Contracting Officer for resolution before proceeding with subsurface investigations.

Engineer Manual 1110-1-1804, "Geotechnical Investigations", dated 29 February 1984, Department of the Army, U.S. Army Corps of Engineers.

- TM 5-822-2 General Provisions and Geometric Design for Roads, Streets,
88-7, Chap 5 Walks, and Open Storage Areas (July 87)
- TM 5-822-5 Pavements Design for Roads, Streets, Walks, and Open Storage
88-7, Chap 3 Areas (Jun 92)
- TM 5-822-7 Standard Practice for Concrete Pavements (Aug 87)
88-6, Chap 8
- TM 5-822-8 Bituminous Pavement, Standard Practice (Jul 87)

The documents listed may be obtained at www.hnd.usace.army.mil/techinfo/index.asp.

Commercially Available Design Guidance: The following list represents other Kansas City District Corps endorsed relevant geotechnical design guides for proper foundation design:

“Introductory Soil Mechanics and Foundations”, 3rd Edition, George B. Sowers and George F. Sowers, MacMillan Co., 1970.

“Standards and Specifications for the Foundation Drilling Industry”, Revised 1995, Incorporating ACI 336.1 94.

ENCLOSURE 4: PAVEMENT DESIGN REQUIREMENTS

Pavement Design Analysis: A flexible pavement section shall be designed and detailed using criteria presented in TM 5-822-5, Pavement Design for Roads, Streets, Walks, and Open Storage Areas. The pavement should be designed for seasonal frost conditions in accordance with TM 5-822-5 Chapter 18 using "Reduced Subgrade Strength" method.

In no case shall the asphaltic concrete portion of the pavement section be less than 200 mm (8").

PRELIMINARY PAVEMENT DESIGN

Fort Riley, KS Trooper-Apennines Traffic Roundabout
Preliminary Pavement Design

By : John Raleigh (HDR Engineering)

Design considerations : Ft Riley is in an area where frost design criteria are applicable in accordance with TM 5-822-5. Lime-modification of pavement subgrade soils is used at this installation to reduce moisture sensitivity of the plastic soils and reduce expansive soil characteristics. Lime modified subgrade provides a stable working platform for subsequent construction. The construction activity related to the use of lime-modified subgrade may contribute to subgrade uniformity as required in TM 5-822-5 paragraph 18-17. In order to be considered for use in satisfying part of the frost design section requirements, lime-modified subgrade soils should be evaluated for freeze-thaw durability in accordance with paragraph 18-14b. Lime-modified subgrade soil mix design should conform to TM 5-822-4. These requirements were not used in previous phases of the Ft Riley Barracks Renewal projects. To remain consistent with the previous phases of the project the lime-modified subgrade will not be used to satisfy pavement section requirements, but will be incorporated into the pavement section being built.

Traffic based on the Fort Riley Traffic Study Trooper Drive dated January 2003.

Traffic Evaluation:

Group 1	=	9200
Group 2	=	1380
Group 3	=	<u>920</u>
		11,500

Type terrain: Rolling

Pavement Type: Street

Category IV (TM 5-822-5, paragraph 3-2,a.).

DHV = 1380 (based on 12 percent of the effective ADT).

Class A (TM 5-822-2, Table 1-2).

Design Index, D I = 5 (TM 5-822-5, Table 3-1).

Design Conditions:

Normal period subgrade design CBR = 5 (based on previous evaluation).

Subgrade soil, Frost Design Soil Classification = F3-F4 (TM 5-822-5, Table 18-2).

The Frost - Area Soil Support Index = 3.5 (TM 5-822-5, Table 18-3).

Base Course = 80 CBR (TM 5-822-5, paragraph 6-4)

Pavement Drainage Layer thickness: H=100 mm (ETL 1110-3-435).

Pavement Separation Layer thickness: H=100 mm (ETL 1110-3-435).

The normal period design section thickness is 470 mm based on a subgrade design CBR = 5 (TM 5-822-5, Table 8-1). The frost design section thickness by the Reduced Strength (RSS) Method is 584 mm (TM 5-822-5, paragraph 18-7.a.).

The minimum pavement and base course design requirement is 63.5 mm of asphalt concrete pavement on 100 mm of 80 CBR aggregate base course. (TM 5-822-5, Table 6-1).

On previous projects at Ft. Riley Trooper Drive pavement sections used a 50 mm asphalt concrete (AC) surface course on a 75 mm asphalt concrete intermediate course with drainage and separation layers. Ft. Riley DPW has used 200 mm AC over a drainage layer on Apenniness Drive repairs and requested we use this design section. Equivalency factors for the use of asphalt stabilized soil layers is 2.3 to 1. (TM 5-822-5, Table 8-1).


The minimum design section (RSS Method):

- 63.5 mm asphalt concrete (AC) surface course
- 100 mm graded crushed aggregate base course (GCA)
- 100 mm graded aggregate drainage layer
- 100 mm graded aggregate separation layer
- 220 mm graded aggregate subbase course
- 150 mm Lime-Modified subgrade


Using the equivalency factors for stabilized layers, the minimum design AC pavement for Ft. Riley Trooper - Apennines Traffic Roundabout is 200 mm AC. Subtracting the minimum required thickness of 63.5 mm AC results in 136.5 mm AC more than the minimum requirement. $136.5 \text{ mm} \times 2.3 \text{ equivalency factor} = 314 \text{ mm}$ of sub base. Therefore, using 200 mm of AC surface and intermediate course would reduce the required sub base course from 220 mm to a negative 94 mm.


The minimum pavement design section required (RSS Method);

- 50 mm asphalt concrete (AC) surface course
- 150 mm AC intermediate course (minimum 2 Lifts)
- 100 mm graded crushed aggregate base course (GCA)
- 100 mm graded aggregate drainage layer
- 100 mm graded aggregate separation layer
- 150 mm Lime- Modified Subgrade




HORIZONTAL CURVE DATA									
①	Δ = 12° 34' 10" Left	④	Δ = 173° 13' 27" Left	⑦	Δ = 5° 21' 22" Left				
R = 152.00	R = 48.75	R = 150.00	L = 14.02	L = 14.02	L = 14.02				
T = 33.35	T = 16.74	T = 7.02	PC STA. 23+16.97	PT STA. 24+64.36	PC STA. 30+26.00				
PT STA. 0+45.99	PT STA. 0+12.64	PT STA. 24+64.36	PT STA. 24+64.36	PT STA. 30+40.02	PT STA. 30+40.02				
②	Δ = 67° 17' 25" Right	⑤	Δ = 40° 45' 17" Right	⑧	Δ = 21° 14' 14" Left				
R = 110.00	R = 430.00	R = 430.00	L = 305.86	L = 227.96	L = 615.00				
L = 129.19	L = 73.21	L = 159.72	PC STA. 0+49.54	PT STA. 1+78.73	PC STA. 30+93.41				
PT STA. 1+78.73	PT STA. 1+78.73	PT STA. 29+22.92	PT STA. 29+22.92	PT STA. 33+21.36	PT STA. 33+21.36				
③	Δ = 17° 26' 11" Right	⑥	Δ = 3° 18' 06" Right	⑨	Δ = 2° 32' 37" Right				
R = 310.00	R = 865.00	R = 865.00	L = 49.85	L = 32.62	L = 870.00				
L = 94.34	L = 24.93	L = 24.93	PC STA. 20+91.72	PT STA. 29+31.87	PC STA. 33+98.90				
T = 47.54	T = 19.32	T = 19.32	PT STA. 20+91.72	PT STA. 29+81.72	PT STA. 34+37.52				






TYPICAL SECTION
NEW CONSTRUCTION


	T	B	CURB/GUTTER
THREE LANE	10.974	3.0	0.61
TWO LANE	7.316	3.0	0.61
FOUR LANE	14.632	3.0	0.61




TYPICAL CONSTRUCTION
BITUMINOUS PAVEMENT WIDENING




SECTION A



SECTION D



SECTION C



SECTION B







Exhibit 2

GAS 1" = 250'



WATER 1"=250'

Exhibit 3




SEWAGE 1" = 250'

Exhibit 4



STORM DRAINS 1" = 250'

Exhibit 5



Survey Control Points @ Trooper Traffic Circle



0 500 1,000 1,500
Feet

42

SECTION 01312A

QUALITY CONTROL SYSTEM (QCS)

08/01

PART 1 GENERAL

1.1 GENERAL

The Government will use the Resident Management System for Windows (RMS) to assist in its monitoring and administration of this contract. The Contractor shall use the Government-furnished Construction Contractor Module of RMS, referred to as QCS, to record, maintain, and submit various information throughout the contract period. This joint Government-Contractor use of RMS and QCS will facilitate electronic exchange of information and overall management of the contract. QCS provides the means for the Contractor to input, track, and electronically share information with the Government in the following areas:

- Administration
- Finances
- Quality Control
- Submittal Monitoring
- Scheduling
- Import/Export of Data

1.1.1 Correspondence and Electronic Communications

For ease and speed of communications, both Government and Contractor will, to the maximum extent feasible, exchange correspondence and other documents in electronic format. Correspondence, pay requests and other documents comprising the official contract record shall also be provided in paper format, with signatures and dates where necessary. Paper documents will govern, in the event of discrepancy with the electronic version.

1.1.2 Other Factors

Particular attention is directed to Contract Clause, "Schedules for Construction Contracts", Contract Clause, "Payments", Section 01320A, PROJECT SCHEDULE, Section 01330, SUBMITTAL PROCEDURES, and Section 01451A, CONTRACTOR QUALITY CONTROL, which have a direct relationship to the reporting to be accomplished through QCS. Also, there is no separate payment for establishing and maintaining the QCS database; all costs associated therewith shall be included in the contract pricing for the work.

1.1.3 Contract Requirements for Quality Control

Notice: The requirements of this section are applicable to each contract awarded under this Solicitation.

1.2 QCS SOFTWARE

QCS is a Windows-based program that can be run on a stand-alone personal computer or on a network. The Government will make available the QCS software to the Contractor after award of the construction contract. Prior to the Pre-Construction Conference, the Contractor shall be responsible to download, install and use the latest version of the QCS software from the Government's RMS Internet Website. Upon specific justification and request by the Contractor, the Government can provide QCS on high-density diskettes or CD-ROM. Any program updates of QCS will be made available to the Contractor via the Government RMS Website as they become available.

1.3 SYSTEM REQUIREMENTS

The following listed hardware and software is the minimum system configuration that the Contractor shall have to run QCS:

Hardware

IBM-compatible PC with 200 MHz Pentium or higher processor

32+ MB RAM

4 GB hard drive disk space for sole use by the QCS system

3 1/2 inch high-density floppy drive

Compact disk (CD) Reader

Color monitor

Laser printer compatible with HP LaserJet III or better, with minimum 4 MB installed memory.

Connection to the Internet, minimum 28 BPS

Software

Microsoft (MS) Access 97 or newer version database software

MS Windows 95 or newer version operating system (MS Windows NT 4.0 or newer is recommended)

Word Processing software compatible with MS Word 97 or newer

Internet browser

The Contractor's computer system shall be protected by virus protection software that is regularly upgraded with all issued manufacturer's updates throughout the life of the contract.

Electronic mail (E-mail) compatible with MS Outlook

1.4 RELATED INFORMATION

1.4.1 QCS User Guide

After contract award, the Contractor shall download instructions for the installation and use of QCS from the Government RMS Internet Website; the Contractor can obtain the current address from the Government. In case of justifiable difficulties, the Government will provide the Contractor with a CD-ROM containing these instructions.

1.4.2 Contractor Quality Control(CQC) Training

The use of QCS will be discussed with the Contractor's QC System Manager during the mandatory CQC Training class.

1.5 CONTRACT DATABASE

Prior to the pre-construction conference, the Government shall provide the Contractor with basic contract award data to use for QCS. The Government will provide data updates to the Contractor as needed, generally by files attached to E-mail. These updates will generally consist of submittal reviews, correspondence status, QA comments, and other administrative and QA data.

1.6 DATABASE MAINTENANCE

The Contractor shall establish, maintain, and update data for the contract in the QCS database throughout the duration of the contract. The Contractor shall establish and maintain the QCS database at the Contractor's site office. Data updates to the Government shall be submitted by E-mail with file attachments, e.g., daily reports, schedule updates, payment requests. If permitted by the Contracting Officer, a data diskette or CD-ROM may be used instead of E-mail (see Paragraph DATA SUBMISSION VIA COMPUTER DISKETTE OR CD-ROM). The QCS database typically shall include current data on the following items:

1.6.1 Administration

1.6.1.1 Contractor Information

The database shall contain the Contractor's name, address, telephone numbers, management staff, and other required items. Within 14 calendar days of receipt of QCS software from the Government, the Contractor shall deliver Contractor administrative data in electronic format via E-mail.

1.6.1.2 Subcontractor Information

The database shall contain the name, trade, address, phone numbers, and other required information for all subcontractors. A subcontractor must be listed separately for each trade to be performed. Each subcontractor/trade shall be assigned a unique Responsibility Code, provided in QCS. Within 14 calendar days of receipt of QCS software from the Government, the Contractor shall deliver subcontractor administrative data in electronic format via E-mail.

1.6.1.3 Correspondence

All Contractor correspondence to the Government shall be identified with a serial number. Correspondence initiated by the Contractor's site office shall be prefixed with "S". Letters initiated by the Contractor's home (main) office shall be prefixed with "H". Letters shall be numbered starting from 0001. (e.g., H-0001 or S-0001). The Government's letters to the Contractor will be prefixed with "C".

1.6.1.4 Equipment

The Contractor's QCS database shall contain a current list of equipment planned for use or being used on the jobsite, including the most recent and planned equipment inspection dates.

1.6.1.5 Management Reporting

QCS includes a number of reports that Contractor management can use to track the status of the project. The value of these reports is reflective of the quality of the data input, and is maintained in the various sections of QCS. Among these reports are: Progress Payment Request worksheet, QA/QC comments, Submittal Register Status, Three-Phase Inspection checklists.

1.6.2 Finances

1.6.2.1 Pay Activity Data

The QCS database shall include a list of pay activities that the Contractor shall develop in conjunction with the construction schedule. The sum of all pay activities shall be equal to the total contract amount, including modifications. Pay activities shall be grouped by Contract Line Item Number (CLIN), and the sum of the activities shall equal the amount of each CLIN. The total of all CLINs equals the Contract Amount.

1.6.2.2 Payment Requests

All progress payment requests shall be prepared using QCS. The Contractor shall complete the payment request worksheet and include it with the payment request. The work completed under the contract, measured as percent or as specific quantities, shall be updated at least monthly. After the update, the Contractor shall generate a payment request report using QCS. The Contractor shall submit the payment requests with supporting data by E-mail with file attachment(s). If permitted by the Contracting Officer, a data diskette may be used instead of E-mail. A signed paper copy of the approved payment request is also required, which shall govern in the event of discrepancy with the electronic version.

1.6.3 Quality Control (QC)

QCS provides a means to track implementation of the 3-phase QC Control System, prepare daily reports, identify and track deficiencies, document progress of work, and support other contractor QC requirements. The Contractor shall maintain this data on a daily basis. Entered data will automatically output to the QCS generated daily report. The Contractor shall provide the Government a Contractor Quality Control (CQC) Plan within

the time required in Section 01451A, CONTRACTOR QUALITY CONTROL. Within seven calendar days of Government acceptance, the Contractor shall submit a data diskette or CD-ROM reflecting the information contained in the accepted CQC Plan: schedule, pay activities, features of work, submittal register, QC requirements, and equipment list.

1.6.3.1 Daily Contractor Quality Control (CQC) Reports.

QCS includes the means to produce the Daily CQC Report. The Contractor may use other formats to record basic QC data. However, the Daily CQC Report generated by QCS shall be the Contractor's official report. Data from any supplemental reports by the Contractor shall be summarized and consolidated onto the QCS-generated Daily CQC Report. Daily CQC Reports shall be submitted as required by Section 01451A, CONTRACTOR QUALITY CONTROL. Reports shall be submitted electronically to the Government using E-mail or diskette within 24 hours after the date covered by the report. Use of either mode of submittal shall be coordinated with the Government representative. The Contractor shall also provide the Government a signed, printed copy of the daily CQC report.

1.6.3.2 Deficiency Tracking.

The Contractor shall use QCS to track deficiencies. Deficiencies identified by the Contractor will be numerically tracked using QC punch list items. The Contractor shall maintain a current log of its QC punch list items in the QCS database. The Government will log the deficiencies it has identified using its QA punch list items. The Government's QA punch list items will be included in its export file to the Contractor. The Contractor shall regularly update the correction status of both QC and QA punch list items.

1.6.3.3 Three-Phase Control Meetings

The Contractor shall maintain scheduled and actual dates and times of preparatory and initial control meetings in QCS.

1.6.3.4 Accident/Safety Tracking.

The Government will issue safety comments, directions, or guidance whenever safety deficiencies are observed. The Government's safety comments will be included in its export file to the Contractor. The Contractor shall regularly update the correction status of the safety comments. In addition, the Contractor shall utilize QCS to advise the Government of any accidents occurring on the jobsite. This brief supplemental entry is not to be considered as a substitute for completion of mandatory reports, e.g., ENG Form 3394 and OSHA Form 200.

1.6.3.5 Features of Work

The Contractor shall include a complete list of the features of work in the QCS database. A feature of work may be associated with multiple pay activities. However, each pay activity (see subparagraph "Pay Activity Data" of paragraph "Finances") will only be linked to a single feature of work.

1.6.3.6 QC Requirements

The Contractor shall develop and maintain a complete list of QC testing, transferred and installed property, and user training requirements in QCS. The Contractor shall update all data on these QC requirements as work progresses, and shall promptly provide this information to the Government via QCS.

1.6.4 Submittal Management

The Government will provide the initial submittal register, ENG Form 4288, SUBMITTAL REGISTER, in electronic format. Thereafter, the Contractor shall maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file to the Contractor. The Contractor shall use QCS to track and transmit all submittals. ENG Form 4025, submittal transmittal form, and the submittal register update, ENG Form 4288, shall be produced using QCS. RMS will be used to update, store and exchange submittal registers and transmittals, but will not be used for storage of actual submittals.

1.6.5 Schedule

The Contractor shall develop a construction schedule consisting of pay activities, in accordance with Contract Clause "Schedules for Construction Contracts", or Section 01320A, PROJECT SCHEDULE, as applicable. This schedule shall be input and maintained in the QCS database either manually or by using the Standard Data Exchange Format (SDEF) (see Section 01320A PROJECT SCHEDULE). The updated schedule data shall be included with each pay request submitted by the Contractor.

1.6.6 Import/Export of Data

QCS includes the ability to export Contractor data to the Government and to import submittal register and other Government-provided data, and schedule data using SDEF.

1.7 IMPLEMENTATION

Contractor use of QCS as described in the preceding paragraphs is mandatory. The Contractor shall ensure that sufficient resources are available to maintain its QCS database, and to provide the Government with regular database updates. QCS shall be an integral part of the Contractor's management of quality control.

1.8 DATA SUBMISSION VIA COMPUTER DISKETTE OR CD-ROM

The Government-preferred method for Contractor's submission of updates, payment requests, correspondence and other data is by E-mail with file attachment(s). For locations where this is not feasible, the Contracting Officer may permit use of computer diskettes or CD-ROM for data transfer. Data on the disks or CDs shall be exported using the QCS built-in export function. If used, diskettes and CD-ROMs will be submitted in accordance

with the following:

1.8.1 File Medium

The Contractor shall submit required data on 3-1/2 inch double-sided high-density diskettes formatted to hold 1.44 MB of data, capable of running under Microsoft Windows 95 or newer. Alternatively, CD-ROMs may be used. They shall conform to industry standards used in the United States. All data shall be provided in English.

1.8.2 Disk or CD-ROM Labels

The Contractor shall affix a permanent exterior label to each diskette and CD-ROM submitted. The label shall indicate in English, the QCS file name, full contract number, contract name, project location, data date, name and telephone number of person responsible for the data.

1.8.3 File Names

The Government will provide the file names to be used by the Contractor with the QCS software.

1.9 MONTHLY COORDINATION MEETING

The Contractor shall update the QCS database each workday. At least monthly, the Contractor shall generate and submit an export file to the Government with schedule update and progress payment request. As required in Contract Clause "Payments", at least one week prior to submittal, the Contractor shall meet with the Government representative to review the planned progress payment data submission for errors and omissions. The Contractor shall make all required corrections prior to Government acceptance of the export file and progress payment request. Payment requests accompanied by incomplete or incorrect data submittals will be returned. The Government will not process progress payments until an acceptable QCS export file is received.

1.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the requirements of this specification. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification.

-- End of Section --

SECTION 01330

SUBMITTAL PROCEDURES
09/00

PART 1 GENERAL

1.1 SUBMITTAL IDENTIFICATION

Submittals required are identified by SD numbers and titles as follows:

- SD-01 Preconstruction Submittals
- SD-02 Shop Drawings
- SD-03 Product Data
- SD-04 Samples
- SD-05 Design Data
- SD-06 Test Reports
- SD-07 Certificates
- SD-08 Manufacturer's Instructions
- SD-09 Manufacturer's Field Reports
- SD-10 Operation and Maintenance Data
- SD-11 Closeout Submittals

1.2 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.2.1 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

1.2.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.3 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. **Caution:** The Contractor is cautioned that for each Contractor's resubmittal required beyond the initial submittal and one resubmittal for corrections required by the Contracting Officer, the Contracting Officer will assess Administrative Deduction in the amount of \$500.00 from the progress payments due the Contractor. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

1.5 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

PART 2 PRODUCTS (Not used)

PART 3 EXECUTION

3.1 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) System Manager and each item shall be stamped, signed, and dated by the CQC System Manager indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list);

certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

3.2 SUBMITTAL REGISTER

At the end of this section is a submittal register showing items of equipment and materials for which submittals are required by the specifications; this list may not be all inclusive and additional submittals may be required. The Contractor shall complete and submit the forms to the Contracting Officer for approval within twenty (20) calendar days after the Notice to Proceed. The Contractor shall maintain a submittal register for the project in accordance with Section 01312 QUALITY CONTROL SYSTEM (QCS).

3.3 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of thirty (30) calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals.

3.4 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. These forms are included in the RMS-QC software that the Contractor is required to use for this contract. This form shall be properly completed by filling out all the heading blank spaces and identifying each item submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.

3.5 SUBMITTAL PROCEDURE

Submittals shall be made as follows:

3.5.1 Procedures

The Contractor shall submit for approval five (5) copies of all submittals. For information only submittals, the Contractor shall submit two (2) copies of each submittal. For all Military projects an additional copy of all submittals (for information only) related to fire protection/detection systems shall be submitted to the Public Works Office for review by the Fire Chief. The mailing address for these submittals shall be obtained at the preconstruction conference. Items not to be submitted in quintuplicate, such as samples and test cylinders, shall be submitted

accompanied by five (5) copies of ENG Form 4025. Items to be sent to the Engineering and Construction Division (EC) shall be sent to EC-DS or EC-GL, addressed as follows:

US Army Engineering District, Kansas City
ATTN: CENWK-EC-D
Federal Building, 601 East 12th Street
Kansas City, Missouri 64106-2896

3.5.2 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

3.6 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

3.7 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and dated. Four (4) copies of the submittal will be retained by the Contracting Officer and one (1) copy of the submittal will be returned to the Contractor.

3.8 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

3.9 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

<p>CONTRACTOR</p> <p>(Firm Name)</p> <p>_____ Approved</p> <p>_____ Approved with corrections as noted on submittal data and/or attached sheets(s).</p> <p>SIGNATURE: _____</p> <p>TITLE: _____</p> <p>DATE: _____</p>
--

-- End of Section --

SECTION 01451A

CONTRACTOR QUALITY CONTROL
07/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740	(2001) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E 329	(2000b) Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable

to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

3.2 QUALITY CONTROL PLAN

The Contractor shall furnish for review by the Government, not later than 30 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, tests, records, and forms to be used. The Government will consider an interim plan for the first 14 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

3.2.1 Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project superintendent.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.
- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. (Laboratory facilities will be approved by the Contracting Officer.)

- f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

3.2.2 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.3 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted for review a minimum of 7 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the

Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure safety and contract compliance. The Safety and Health Manager shall receive direction and authority from the CQC System Manager and shall serve as a member of the CQC staff. Personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly will also be included as part of the CQC organization. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, show drawing submittals, schedules and all other project documentation shall be promptly furnished to the CQC organization by the Contractor. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a graduate engineer, graduate architect, or a graduate of construction management, with a minimum of 5 years construction experience on construction similar to this contract. This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned no other duties. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

3.4.3 CQC Personnel

In addition to CQC personnel specified elsewhere in the contract, the Contractor shall provide as part of the CQC organization specialized personnel to assist the CQC System Manager for the following areas: electrical and mechanical. These individuals shall be directly employed by the prime Contractor and may not be employed by a supplier or sub-contractor on this project; be responsible to the CQC System Manager; be physically present at the construction site during work on their areas of responsibility; have the necessary education and/or experience in accordance with the experience matrix listed herein. These individuals shall have no other duties other than quality control.

Experience Matrix

	Area	Qualifications
a.	Mechanical	Graduate Mechanical Engineer with 2 yrs experience or person with 5 yrs related experience
b.	Electrical	Graduate Electrical Engineer with 2 yrs related experience or person with 5 yrs related experience

3.4.4 Additional Requirement

In addition to the above experience and/or educational requirements, the CQC System Manager shall have completed the course entitled "Construction Quality Management for Contractors" within the past five years and shall be in possession of a valid certificate of instruction. If the individual designated as CQC System Manager does not currently meet this training requirement, it is mandatory that the training be successfully completed within ninety calendar days of appointment to the position of CQC System Manager. The Contractor's CQC System Manager may be appointed and serve fully in that capacity pending certification, providing all other qualifications are met. If the CQC System Manager fails to successfully complete the training, the Contractor shall promptly appoint a new CQC System Manager who shall then attend the next available course if he/she does not have a current course certification. The certification is valid for five years at which time retraining is required. If the Contractor needs this training, it will be provided by Government personnel after award of the contract. The cost for the training course shall be borne by the Contractor and will not exceed one hundred dollars (\$100.00) per course, per person. Payment shall be by check in advance of the training. The Contractor shall contact the Contracting Officer upon award of the contract to arrange for course participation.

3.4.5 Organizational Changes

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

3.5 SUBMITTALS AND DELIVERABLES

Submittals, if needed, shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements. The submittals required by Sections 15951A DIRECT

DIGITAL CONTROL FOR HVAC; 15990A TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS; or 15995A COMMISSIONING OF HVAC SYSTEMS shall be coordinated with Section 01330 SUBMITTAL PROCEDURES to ensure adequate time is allowed for each type of submittal required.

3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.
- b. A review of the contract drawings.
- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.

- j. Discussion of the initial control phase.
- k. The Government shall be notified at least 24 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 24 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

3.7 TESTS

3.7.1 Testing Procedure

The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements. Upon request, the Contractor shall furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site. The Contractor shall perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.
- d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.
- e. Results of all tests taken, both passing and failing tests, shall be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test shall be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an offsite or commercial test facility shall be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.

3.7.2 Testing Laboratories

3.7.2.1 Capability Check

The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing

procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329.

3.7.2.2 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will be assessed a charge of \$3,800 to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the contract amount due the Contractor.

3.7.3 Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests, and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

3.7.4 Furnishing or Transportation of Samples for Testing

Costs incidental to the transportation of samples or materials shall be borne by the Contractor. Samples of materials for test verification and acceptance testing by the Government shall be delivered to the Corps of Engineers Division Laboratory, f.o.b., at the following address:

For delivery by mail:

USACE Research and Development Center
ATTN: Joe Tom, CEERD-SC-E
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

For other deliveries: Same as above.

Coordination for each specific test, exact delivery location, and dates will be made through the Area Office.

3.8 COMPLETION INSPECTION

3.8.1 Punch-Out Inspection

Near the end of the work, or any increment of the work established by a time stated in the Special Clause, "Commencement, Prosecution, and Completion of Work", or by the specifications, the CQC Manager shall conduct an inspection of the work. A punch list of items which do not conform to the approved drawings and specifications shall be prepared and included in the CQC documentation, as required by paragraph DOCUMENTATION. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected.

Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.8.2 Pre-Final Inspection

The Government will perform the pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates.

3.8.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at the final acceptance inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups, and major commands may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List

of deficiencies noted, along with corrective action.

- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Offsite surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

-- End of Section --

SECTION 01500A

TEMPORARY CONSTRUCTION FACILITIES

02/97

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS

The items furnished under this section shall be maintained in good condition throughout the construction period. The items furnished shall remain the property of the Contractor and shall be removed from the site upon completion of the work.

1.1.1 Site Plan

The Contractor shall prepare a site plan indicating the proposed location and dimensions of any area to be fenced and used by the Contractor, the number of trailers to be used, avenues of ingress/egress to the fenced area and details of the fence installation. Any areas which may have to be graveled to prevent the tracking of mud shall also be identified. The Contractor shall also indicate if the use of a supplemental or other staging area is desired. The site plan shall include drawings and details of all temporary utilities work.

1.1.2 Identification of Employees

The Contractor shall be responsible for furnishing to each employee, and for requiring each employee engaged on the work to display, identification as approved and directed by the Contracting Officer. Prescribed identification shall immediately be delivered to the Contracting Officer for cancellation upon release of any employee. When required, the Contractor shall obtain and provide fingerprints of persons employed on the project. Contractor and subcontractor personnel shall wear identifying markings on hard hats clearly identifying the company for whom the employee works.

1.1.3 Employee Parking

Contractor employees shall park privately owned vehicles in an area designated by the Contracting Officer. This area will be within reasonable walking distance of the construction site. Contractor employee parking shall not interfere with existing and established parking requirements of the military installation.

1.2 AVAILABILITY AND USE OF UTILITY SERVICES

1.2.1 Payment for Utility Services

The Government will make all reasonably required utilities available to the Contractor from existing outlets and supplies, as specified in the

contract. Unless otherwise provided in the contract, the amount of each utility service consumed shall be charged to or paid for by the Contractor at prevailing rates charged to the Government or, where the utility is produced by the Government, at reasonable rates determined by the Contracting Officer. The Contractor shall carefully conserve any utilities furnished without charge.

1.2.2 Meters and Temporary Connections

The Contractor, at its expense and in a manner satisfactory to the Contracting Officer, shall provide and maintain necessary temporary connections, distribution lines, meter bases, and meters required to measure the amount of each utility used for the purpose of determining charges. The Contractor shall make arrangements with the post utilities officer before final electrical connection is desired so that a utilities contract can be established. The Contractor will provide a meter and make the final hot connection after inspection and approval of the Contractor's temporary wiring installation. The temporary plan shall be submitted for approval in accordance with EM 385-1-1.

1.2.3 Final Meter Reading

Before completion of the work and final acceptance of the work by the Government, the Contractor shall notify the Contracting Officer, in writing, 5 working days before termination is desired. The Government will take a final meter reading, and then the Contractor shall disconnect service, and remove the meters. The Contractor shall then remove all the temporary distribution lines, meter bases, and associated paraphernalia. The Contractor shall pay all outstanding utility bills before final acceptance of the work by the Government.

1.2.4 Sanitation

The Contractor shall provide and maintain within the construction area minimum field-type sanitary facilities approved by the Contracting Officer. Government toilet facilities will not be available to Contractor's personnel.

1.3 BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN

1.3.1 Bulletin Board

Immediately upon beginning of work, the Contractor shall provide a weatherproof glass-covered bulletin board not less than 915 by 1220 mm in size for displaying the Equal Employment Opportunity poster, a copy of the wage decision contained in the contract, Wage Rate Information poster, and other information approved by the Contracting Officer. The bulletin board shall be located at the project site in a conspicuous place easily accessible to all employees, as approved by the Contracting Officer. Legible copies of the aforementioned data shall be displayed until work is completed. Upon completion of work the bulletin board shall be removed by and remain the property of the Contractor.

1.3.2 Project and Safety Signs

The requirements for the signs, their content, and location shall be as shown on the drawings. The signs shall be erected within 15 days after receipt of the notice to proceed. The data required by the safety sign shall be corrected daily, with light colored metallic or non-metallic numerals. Upon completion of the project, the signs shall be removed from the site.

1.4 PROTECTION AND MAINTENANCE OF TRAFFIC

During construction the Contractor shall provide access and temporary relocated roads as necessary to maintain traffic. The Contractor shall maintain and protect traffic on all affected roads during the construction period except as otherwise specifically directed by the Contracting Officer. Measures for the protection and diversion of traffic, including the provision of watchmen and flagmen, erection of barricades, placing of lights around and in front of equipment and the work, and the erection and maintenance of adequate warning, danger, and direction signs, shall be as required by the State and local authorities having jurisdiction. The traveling public shall be protected from damage to person and property. The Contractor's traffic on roads selected for hauling material to and from the site shall interfere as little as possible with public traffic. The Contractor shall investigate the adequacy of existing roads and the allowable load limit on these roads. The Contractor shall be responsible for the repair of any damage to roads caused by construction operations.

1.4.1 Haul Roads

The Contractor shall, at its own expense, construct access and haul roads necessary for proper prosecution of the work under this contract. Haul roads shall be constructed with suitable grades and widths; sharp curves, blind corners, and dangerous cross traffic shall be avoided. The Contractor shall provide necessary lighting, signs, barricades, and distinctive markings for the safe movement of traffic. The method of dust control, although optional, shall be adequate to ensure safe operation at all times. Location, grade, width, and alignment of construction and hauling roads shall be subject to approval by the Contracting Officer. Lighting shall be adequate to assure full and clear visibility for full width of haul road and work areas during any night work operations. Upon completion of the work, haul roads designated by the Contracting Officer shall be removed.

1.4.2 Barricades

The Contractor shall erect and maintain temporary barricades to limit public access to hazardous areas. Such barricades shall be required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Barricades shall be securely placed, clearly visible with adequate illumination to provide sufficient visual warning of the hazard during both day and night.

1.4.3 Custer Hill Access

There will be no access to the job site/Custer Hill during PT hours nor will there be any motor vehicle traffic allowed. The PT hours currently are 4:00 PM to 5:00 PM and maybe changed.

1.5 CONTRACTOR'S TEMPORARY FACILITIES

1.5.1 Administrative Field Offices

The Contractor shall provide and maintain administrative field office facilities within the construction area at the designated site. Government office and warehouse facilities will not be available to the Contractor's personnel.

1.5.2 Appearance of Trailers

Trailers utilized by the Contractor for administrative or material storage purposes shall present a clean and neat exterior appearance and shall be in a state of good repair. Trailers which, in the opinion of the Contracting Officer, require exterior painting or maintenance will not be allowed on the military property.

Trailers utilized for the Government inspectors office shall present a clean and neat interior and exterior appearance and shall be in a state of good repair at all times during the duration of the project. Trailers which, in the opinion of the Contracting Officer, require exterior painting or interior or exterior maintenance will not be allowed on the military property.

1.5.3 Maintenance of the Construction Area Including the Storage Area

Fencing shall be kept in a state of good repair and proper alignment. Should the Contractor elect to traverse, with construction equipment or other vehicles, grassed or unpaved areas which are not established roadways, such areas shall be covered with a layer of gravel as necessary to prevent rutting and the tracking of mud onto paved or established roadways; gravel gradation shall be at the Contractor's discretion. Grass located within the boundaries of the construction site shall be mowed for the duration of the project. Grass and vegetation along fences, buildings, under trailers, and in areas not accessible to mowers shall be edged or trimmed neatly. At no time shall the height of the grass exceed 4-inches. Weeds shall be controlled and shall not exceed grass height.

1.5.4 Security Provisions

Adequate outside security lighting shall be provided at the Contractor's temporary facilities. The Contractor shall be responsible for the security of its own equipment; in addition, the Contractor shall notify the appropriate law enforcement agency requesting periodic security checks of the temporary project field office.

1.6 GOVERNMENT FIELD OFFICE

1.6.1 Accommodations for Government Inspectors

The Contractor shall furnish a temporary office facility approximately 4 meters by 20 meters with a minimum of 80 square meters of floor space. It shall be located where directed and shall be reserved for Government personnel only. Gravel parking area for a minimum of four vehicles will be provided and reserved for the sole use of the Government. Access from the parking area to the office shall be by elevated walkway or concrete sidewalks. The steps and landings at the doors shall be substantial.

The Contractor shall furnish bottled drinking water with cooler, thermostatically controlled space heat, ventilation and air conditioning, electric light (suitable for an office environment), sufficient power, and toilet facilities consisting of one lavatory, one water closet. The toilet shall be complete with hot and cold running potable water, sewer, and powered bathroom ventilation.

Utilities shall be connected and disconnected by the Contractor in accordance with local codes and to the satisfaction of the Contracting Officer. The facility shall be laid out and furnished as follows:

There shall be two private offices, one at each end furnished with two desks each, two office chairs each, two four drawer legal size file cabinets each, two telephone instrument each. In addition one office will be supplied with a laptop computer and one printer. The center area between the offices shall be a conference area furnished with a conference table and chairs for ten persons, three four drawer legal-size file cabinets a table for the fax machine, a digital plain paper fax machine, a copying machine that is 11 X 17 inch capable, a mobile plan rack, and a moveable plan table large enough to accommodate full scale drawings. The required phone lines shall be extended to both offices (phone and data) and one corner location (phone, data, and fax) in the conference room. Five telephone instruments shall be provided. The four in the offices shall be desk or wall mounted. The instrument in the conference room shall be cordless.

The minimum configuration for the laptop computer is:

Base Unit: Latitude C810, 1.13GHz, Pentium III, 15.0, USGA, English (220-8834)
 Memory: 512 MB, 2DIMMS, SDRAM for Dell Latitude C810/C610/C400 Notebooks, Factory Install (311-2035)
 Video Memory: 32MB, Double Data Rate, Nvidia, Video Card for Dell Latitude C810 Notebooks, Factory Install (320-9556)
 Hard Drive: 20GB Hard Drive, 9.5MM for Dell Latitude C800/C810 Notebooks, Factory Install (340-6334)
 Operating System: Windows 2000, SP1, English for Dell Latitude C810 Notebooks, Factory Install (420-5720)
 Modem: Internal 3CON Mini-PCI NIC/Modem Combo for Dell Latitude C600/C800/C500/C810 Notebooks, Factory Install(313-7108)
 CD-ROM or DVD-ROM Drive: Internal 8-8-8-24X DVD with Software/CD Read-Write Combo for Dell Latitude C800/C810 Notebooks, Factory Install (313-2576)
 Sound Card: Integrated Sound Blaster Compatible AC97 Sound, OptiPlex (313-8170)
 Additional Software: Microsoft Office XP Professional, Norton Utilities Professional 2002 version, Norton Antivirus 2002 version

Service: Type 3 Contract - Next Business Day Parts & Labor On-Site Response
Initial Year (900-1020)

Service: Type 3 Contract - Next Business Day Parts & Labor On-Site Response
2 YR Extended (900-1732)

Or approved equal.

The minimum printer configuration is: Hewlett Packard 1200se or approved equal, the printer shall be compatible with the laptop.

Used furniture and equipment (except computer, printer and fax), in good condition, will be acceptable subject to approval of the Contracting Officer. Computer, printer and fax shall be new.

The main entrance shall be into the conference room. The second egress shall be a door in either of the offices. Entrance and egress doors shall be equipped with substantial locks.

The Contractor shall provide janitorial service and janitorial consumables, fuel for the heating facilities, electricity, telephone, unlimited internet access, copier, fax and printer consumables including but not limited to toner cartridges and paper, hot and cold running domestic water, and bottled water all at no cost to the Government. The Contractor will not be liable for Government placed long distance telephone calls.

The entire facility including the furniture and equipment will remain the property of the Contractor and shall be removed from the site at the completion of the work.

1.6.2 Trailer-Type Mobile Office

The Contractor may, at its option, furnish and maintain a trailer-type mobile office acceptable to the Contracting Officer and providing as a minimum the facilities specified above. The trailer shall be securely anchored to the ground at all four corners to guard against movement during high winds in accordance with the regulations of the State of Kansas for mobile homes.

1.7 PLANT COMMUNICATION

The Contractor shall furnish three phone lines (telephone, fax, and data) to the Corps of Engineers Site Office. The telephone line shall be "full service" including long distance capabilities. The fax line shall be "full service" including long distance capabilities. The data line shall be data quality and capable of data transmission in excess of 50K. Unlimited internet access shall be provided on the data lines in all three locations within the site office.

1.8 CLEANUP

Construction debris, waste materials, packaging material and the like shall be removed from the work site daily. Any dirt or mud that is tracked onto paved or surfaced roadways shall be cleaned away as soon as it is

deposited. Materials resulting from demolition activities that are salvageable shall be stored within the fenced area described above or at the supplemental storage area. Stored material not in trailers, whether new or salvaged, shall be neatly stacked when stored, elevated from the ground contact on cribbing, and protected from the weather.

1.9 RESTORATION OF STORAGE AREA

Upon completion of the project and after removal of trailers, materials, and equipment from within the fenced area, the fence shall be removed and will become the property of the Contractor. Areas used by the Contractor for the storage of equipment or material, or other use, shall be restored to the original or better condition. Gravel used to traverse grassed areas shall be removed and the area restored to its original condition, including top soil and seeding as necessary.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

SECTION 02510A

WATER DISTRIBUTION SYSTEM

05/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN RAILWAY ENGINEERING & MAINTENANCE-OF-WAY ASSOCIATION
(AREMA)

AREMA Manual	(1999) Manual for Railway Engineering (4 Vol.)
--------------	--

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 36/A 36M	(1997a) Carbon Structural Steel
ASTM A 53	(1999b) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM B 88	(1996) Seamless Copper Water Tube
ASTM B 88M	(1996) Seamless Copper Water Tube (Metric)
ASTM C 76	(1999) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
ASTM C 76M	(1999a) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe (Metric)
ASTM D 1599	(1999) Resistance to Short-Time Hydraulic Failure Pressure of Plastic Pipe, Tubing, and Fittings
ASTM D 1784	(1999a) Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D 1785	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe, Schedules 40, 80, and 120
ASTM D 2241	(1996b) Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)
ASTM D 2464	(1999) Threaded Poly(Vinyl Chloride) (PVC)

Plastic Pipe Fittings, Schedule 80

ASTM D 2466	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40
ASTM D 2467	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D 2564	(1996a) Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D 2657	(1997) Heat Fusion Joining Polyolefin Pipe and Fittings
ASTM D 2774	(1994) Underground Installation of Thermoplastic Pressure Piping
ASTM D 2855	(1996) Making Solvent-Cemented Joints with Poly(Vinyl Chloride) (PVC) Pipe and Fittings
ASTM D 2996	(1995) Filament-Wound "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe
ASTM D 2997	(1995) Centrifugally Cast "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe
ASTM D 3139	(1998) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D 3839	(1994a) Underground Installation of "Fiberglass" (Glass-Fiber-Reinforced Thermosetting Resin) Pipe
ASTM D 4161	(1996) "Fiberglass"(Glass-Fiber-Reinforced Thermosetting Resin) Pipe Joints Using Elastomeric Seals
ASTM F 477	(1999) Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F 1483	(1998) Oriented Poly(Vinyl Chloride), PVC-O, Pressure Pipe

ASME INTERNATIONAL (ASME)

ASME B1.20.1	(1983; R 1992) Pipe Threads, General Purpose (Inch)
ASME B16.1	(1998) Cast Iron Pipe Flanges and Flanged Fittings

ASME B16.3	(1992) Malleable Iron Threaded Fittings
ASME B16.26	(1988) Cast Copper Alloy Fittings for Flared Copper Tubes
ASME B36.10M	(1996) Welded and Seamless Wrought Steel Pipe

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA B300	(1992) Hypochlorites
AWWA B301	(1992) Liquid Chlorine
AWWA C104	(1995) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C105	(1993) Polyethylene Encasement for Ductile-Iron Pipe Systems
AWWA C110	(1993) Ductile-Iron and Gray-Iron Fittings, 3 In. Through 48 In. (75 mm through 1200 mm), for Water and Other Liquids
AWWA C111	(1995) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C115	(1996) Flanged Ductile-Iron Pipe With Ductile-Iron or Gray-Iron Threaded Flanges
AWWA C151	(1996) Ductile-Iron Pipe, Centrifugally Cast, for Water or Other Liquids
AWWA C153	(1994; Errata Nov 1996) Ductile-Iron Compact Fittings, 3 In. Through 24 In. (76 mm through 610 mm) and 54 In. through 64 In. (1,400 mm through 1,600 mm) for Water Service
AWWA C200	(1997) Steel Water Pipe - 6 In. (150 mm) and Larger
AWWA C203	(1997) Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape - Hot-Applied
AWWA C205	(1995) Cement-Mortar Protective Lining and Coating for Steel Water Pipe - 4 In. (100 mm) and Larger - Shop Applied
AWWA C207	(1994) Steel Pipe Flanges for Waterworks Service - Sizes 4 In. Through 144 In. (100 mm through 3,600 mm)

AWWA C208	(1996) Dimensions for Fabricated Steel Water Pipe Fittings
AWWA C300	(1997) Reinforced Concrete Pressure Pipe, Steel-Cylinder Type, for Water and Other Liquids
AWWA C301	(1992) Prestressed Concrete Pressure Pipe, Steel-Cylinder Type, for Water and Other Liquids
AWWA C303	(1995) Concrete Pressure Pipe, Bar-Wrapped, Steel Cylinder Type
AWWA C500	(1993; C500a) Metal-Sealed Gate Valves for Water Supply Service
AWWA C502	(1994; C502a) Dry-Barrel Fire Hydrants
AWWA C503	(1997) Wet-Barrel Fire Hydrants
AWWA C504	(1994) Rubber-Seated Butterfly Valves
AWWA C509	(1994; Addendum 1995) Resilient-Seated Gate Valves for Water Supply Service
AWWA C600	(1993) Installation of Ductile-Iron Water Mains and Their Appurtenances
AWWA C606	(1997) Grooved and Shouldered Joints
AWWA C651	(1992) Disinfecting Water Mains
AWWA C700	(1995) Cold-Water Meters - Displacement Type, Bronze Main Case
AWWA C701	(1988) Cold-Water Meters - Turbine Type, for Customer Service
AWWA C702	(1992) Cold-Water Meters - Compound Type
AWWA C703	(1996) Cold-Water Meters - Fire Service Type
AWWA C704	(1992) Propeller-Type Meters Waterworks Applications
AWWA C706	(1996) Direct-Reading, Remote-Registration Systems for Cold-Water Meters
AWWA C707	(1982; R 1992) Encoder-Type Remote-Registration Systems for Cold-Water Meters

AWWA C800	(1989) Underground Service Line Valves and Fittings
AWWA C900	(1997; C900a) Polyvinyl Chloride (PVC) Pressure Pipe, 4 In. Through 12 In., for Water Distribution
AWWA C901	(1996) Polyethylene (PE) Pressure Pipe and Tubing, 1/2 In. Through 3 In., for Water Service
AWWA C905	(1997) Polyvinyl Chloride (PVC) Water Transmission Pipe, Nominal Diameters 14 In. Through 36 In.
AWWA C909	(1998) Molecularly Oriented Polyvinyl Chloride (PVC) Pressure Pipe, 4 IN through 12 IN (100 mm through 300 mm), for Water Distribution
AWWA C950	(1995) Fiberglass Pressure Pipe
AWWA M23	(1980) Manual: PVC Pipe - Design and Installation

ASBESTOS CEMENT PIPE PRODUCERS ASSOCIATION (ACPPA)

ACPPA Work Practices	(1988) Recommended Work Practices for A/C Pipe
----------------------	--

DUCTILE IRON PIPE RESEARCH ASSOCIATION (DIPRA)

DIPRA-Restraint Design	(1997) Thrust Restraint Design for Ductile Iron Pipe
------------------------	--

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-80	(1997) Bronze Gate, Globe, Angle and Check Valves
-----------	---

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 24	(1995) Installation of Private Fire Service Mains and Their Appurtenances
NFPA 49	(1994) Hazardous Chemicals Data
NFPA 325-1	(1994) Fire Hazard Properties of Flammable Liquids, Gases, and Volatile Solids
NFPA 704	(1996) Identification of the Fire Hazards of Materials for Emergency Response

NFPA 1961 (1997) Fire Hose

NSF INTERNATIONAL (NSF)

NSF 14 (1998) Plastics Piping Components and Related Materials

NSF 61 (1999) Drinking Water System Components - Health Effects (Sections 1-9)

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 21 (1991) White or Colored Silicone Alkyd Paint

SSPC Paint 25 (1991) Red Iron Oxide, Zinc Oxide, Raw Linseed Oil and Alkyd Primer (Without Lead and Chromate Pigments)

1.2 PIPING

This section covers water [supply] [distribution] [service] lines, and connections to building service at a point approximately 1.5 m outside buildings and structures to which service is required. The Contractor shall have a copy of the manufacturer's recommendations for each material or procedure to be utilized available at the construction site at all times.

1.2.1 Service Lines

Piping for water service lines less than 80 mm (3 inches) in diameter shall be polyvinyl chloride (PVC) plastic unless otherwise shown or specified. Piping for water service lines 80 mm (3 inches) and larger shall be ductile iron, polyvinyl chloride (PVC) plastic, filament-wound or centrifugally cast reinforced thermosetting resin, reinforced plastic mortar pressure pipe or steel, unless otherwise shown or specified.

1.2.2 Distribution Lines 80 mm (3 Inches) or Larger

Piping for water distribution lines 80 mm (3 inches) or larger shall be polyvinyl chloride (PVC) through 900 mm (36 inch) nominal diameter plastic, Oriented PVC plastic filament-wound or centrifugally cast reinforced thermosetting resin, reinforced plastic mortar pressure pipe, or reinforced concrete, unless otherwise shown or specified.

1.2.3 Supply Lines 80 mm (3 Inches) or Larger

Piping for water supply lines 80 mm (3 inches) or larger shall be ductile iron, polyvinyl chloride (PVC) plastic, through 900 mm (36 inch) nominal diameter, Oriented PVC plastic filament-wound reinforced or centrifugally cast reinforced thermosetting resin, reinforced plastic mortar pressure pipe, steel, or reinforced concrete, unless otherwise shown or specified.

1.2.4 Sprinkler Supply Lines

Piping for water lines supplying sprinkler systems for building fire protection shall conform to NFPA 24 from the point of connection with the water distribution system to the building 1.5 m line.

1.2.5 Potable Water Lines

Piping and components of potable water systems which come in contact with the potable water shall conform to NSF 61.

1.2.6 Plastic Piping System

Plastic piping system components (PVC, polyethylene, thermosetting resin and reinforced plastic mortar pressure) intended for transportation of potable water shall comply with NSF 14 and be legibly marked with their symbol.

1.2.7 Excavation, Trenching, and Backfilling

Excavation, trenching, and backfilling shall be in accordance with the applicable provisions of Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS, except as modified herein.

1.3 MANUFACTURER'S REPRESENTATIVE

The Contractor shall have a manufacturer's field representative present at the jobsite during the installation and testing of PE, RTRP, and/or RPMP pipe to provide technical assistance and to verify that the materials are being installed in accordance with the manufacturer's prescribed procedures. When the representative feels that the Contractor is installing and testing the PE, RTRP, and/or RPMP pipe in a satisfactory manner, certification shall be written to note which individuals employed by the Contractor are capable of properly installing the pipe. The field representative shall advise the Contractor of unsatisfactory conditions immediately when they occur. Such conditions include improper diameter of pipe ends, damaged interior liner, poorly prepared joints, improper curing of joints, moving pipe before joints are cured, bending pipe to follow abrupt changes in trench contours, leaving pipe ends open in trench overnight, not properly drying joints after rain storms, exceeding effective adhesive life, sharp objects in trench bed, backfill that could damage pipe, improper procedure for concrete encasement of pipe, omission of thrust blocks at changes in direction or any other condition which could have an adverse effect on the satisfactory completion and operation of the piping system.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Installation; GA, RE.

The manufacturer's recommendations for each material or procedure to be utilized.

Satisfactory Installation; GA, RE.

A statement signed by the principal officer of the contracting firm stating that the installation is satisfactory and in accordance with the contract drawings and specifications, and the manufacturer's prescribed procedures and techniques, upon completion of the project and before final acceptance.

SD-06 Test Reports

Bacteriological Disinfection; GA, RE.

Test results from commercial laboratory verifying disinfection.
HYDRANT FLOW TESTING; G, RE],

SD-07 Certificates

1.5 HANDLING

Pipe and accessories shall be handled to ensure delivery to the trench in sound, undamaged condition, including no injury to the pipe coating or lining. If the coating or lining of any pipe or fitting is damaged, the repair shall be made by the Contractor in a satisfactory manner, at no additional cost to the Government. No other pipe or material shall be placed inside a pipe or fitting after the coating has been applied. Pipe shall be carried into position and not dragged. Use of pinch bars and tongs for aligning or turning pipe will be permitted only on the bare ends of the pipe. The interior of pipe and accessories shall be thoroughly cleaned of foreign matter before being lowered into the trench and shall be kept clean during laying operations by plugging or other approved method. Before installation, the pipe shall be inspected for defects. Material found to be defective before or after laying shall be replaced with sound material without additional expense to the Government. Rubber gaskets that are not to be installed immediately shall be stored in a cool and dark place.

1.5.1 Polyethylene (PE) Pipe Fittings and Accessories

PE pipe, fittings, and accessories shall be handled in conformance with AWWA C901.

1.5.2 Miscellaneous Plastic Pipe and Fittings

Polyvinyl Chloride (PVC), Reinforced Thermosetting Resin Pipe (RTRP), and Reinforced Plastic Mortar Pressure (RPMP) pipe and fittings shall be handled and stored in accordance with the manufacturer's recommendations.

Storage facilities shall be classified and marked in accordance with NFPA 704, with classification as indicated in NFPA 49 and NFPA 325-1.

PART 2 PRODUCTS

2.1 PIPE

Pipe shall conform to the respective specifications and other requirements specified below.

2.1.1 Plastic Pipe

2.1.1.1 PE Plastic Pipe

Pipe, tubing, and heat-fusion fittings shall conform to AWWA C901.

2.1.1.2 PVC Plastic Pipe

Pipe, couplings and fittings shall be manufactured of material conforming to ASTM D 1784, Class 12454B.

a. Pipe Less Than 100 mm (4 inch) Diameter:

(1) Screw-Joint: Pipe shall conform to dimensional requirements of ASTM D 1785 Schedule 80, with joints meeting requirements of 1.03 MPa (150 psi) working pressure, 1.38 MPa (200 psi) hydrostatic test pressure, unless otherwise shown or specified. Pipe couplings when used, shall be tested as required by ASTM D 2464.

(2) Elastomeric-Gasket Joint: Pipe shall conform to dimensional requirements of ASTM D 1785 Schedule 40, with joints meeting the requirements of 1.03 MPa (150 psi) working pressure, 1.38 MPa (200 psi) hydrostatic test pressure, unless otherwise shown or specified.

(3) Solvent Cement Joint: Pipe shall conform to dimensional requirements of ASTM D 1785 or ASTM D 2241 with joints meeting the requirements of 1.03 MPa (150 psi) working pressure and 1.38 MPa (200 psi) hydrostatic test pressure.

b. Pipe 100 through 300 mm Diameter: Pipe, couplings and fittings shall conform to AWWA C900, Class 150, CIOD pipe dimensions, elastomeric-gasket joint, unless otherwise shown or specified.

c. Pipe 350 through 900 mm Diameter: Pipe shall conform to AWWA C905 unless otherwise shown or specified.

2.1.1.3 Oriented Polyvinyl Chloride (PVCO) Plastic Pipe

Pipe, couplings, and fittings shall be manufactured of material conforming to ASTM D 1784, Class 12454-B. Pipe shall conform to AWWA C909, Class 150, and to ASTM F 1483 and shall have an outside diameter equal to cast iron outside diameter.

2.1.2 Ductile-Iron Pipe

Ductile-iron pipe shall conform to AWWA C151, working pressure not less than 1.03 MPa (150 psi), unless otherwise shown or specified. Pipe shall be cement-mortar lined in accordance with AWWA C104. Linings shall be standard. When installed underground, pipe shall be coated in accordance with Section 13110 CATHODIC PROTECTION SYSTEM (SACRIFICIAL ANODE). Flanged ductile iron pipe with threaded flanges shall be in accordance with AWWA C115.

2.1.3 Steel Pipe

2.1.3.1 Pipe 80 mm (3 Inches) and Larger, Not Galvanized

Steel pipe, not galvanized, shall conform to AWWA C200 with dimensional requirements as given in ASME B36.10M for pipe 150 mm (6 inches) in diameter and larger, and ASTM A 53 for smaller sizes. Pipe shall be welded or seamless with plain or shouldered and grooved ends in accordance with AWWA C606 for use with mechanical couplings or bell-and-spigot ends with rubber gaskets. Bell-and-spigot ends for sizes less than 150 mm (6 inches) diameter shall be as required by AWWA C200.

2.1.3.2 Galvanized Steel Pipe

Galvanized steel pipe shall conform to ASTM A 53, standard weight.

2.1.4 Copper Tubing

Copper tubing shall conform to ASTM B 88M , Type K, annealed.

2.2 FITTINGS AND SPECIALS

2.2.1 PVC Pipe System

- a. For pipe less than 100 mm (4 inch) diameter, fittings for threaded pipe shall conform to requirements of ASTM D 2464, threaded to conform to the requirements of ASME B1.20.1 for use with Schedule 80 pipe and fittings; fittings for solvent cement jointing shall conform to ASTM D 2466 or ASTM D 2467; and fittings for elastomeric-gasket joint pipe shall be iron conforming to AWWA C110 or AWWA C111. Iron fittings and specials shall be cement-mortar lined (standard thickness) in accordance with AWWA C104.
- b. For pipe 100 mm (4 inch) diameter and larger, fittings and specials shall be iron, bell end in accordance with AWWA C110, 1.03 MPa (150 psi) pressure rating unless otherwise shown or specified, except that profile of bell may have special dimensions as required by the pipe manufacturer; or fittings and specials may be of the same material as the pipe with elastomeric gaskets, all in conformance with AWWA C900. Iron fittings and specials shall be cement-mortar lined (standard thickness) in accordance with AWWA C104. Fittings shall be bell and spigot or plain end pipe,

or as applicable. Ductile iron compact fittings shall be in accordance with AWWA C153.

2.2.2 RTRP and RPMP Pipe

Fittings and specials shall be compatible with the pipe supplied. Filament wound or molded fittings up to 150 mm (6 inches) shall conform to AWWA C950.

Iron fittings shall be cement-mortar lined in accordance with AWWA C104 and shall conform to AWWA C110 and AWWA C111. Fittings shall be suitable for working and testing pressures specified for the pipe.

2.2.3 Ductile-Iron Pipe System

Fittings and specials shall be suitable for 1.03 MPa (150 psi) pressure rating, unless otherwise specified. Fittings and specials for mechanical joint pipe shall conform to AWWA C110. Fittings and specials for use with push-on joint pipe shall conform to AWWA C110 and AWWA C111. Fittings and specials for grooved and shouldered end pipe shall conform to AWWA C606. Fittings and specials shall be cement-mortar lined (standard thickness) in accordance with AWWA C104. Ductile iron compact fittings shall conform to AWWA C153.

2.2.4 Steel Pipe System

2.2.4.1 Galvanized Steel Piping

Steel fittings shall be galvanized. Screwed fittings shall conform to ASME B16.3. Flanged fittings shall conform to AWWA C207.

2.2.4.2 Dielectric Fittings

Dielectric fittings shall be installed between threaded ferrous and nonferrous metallic pipe, fittings and valves, except where corporation stops join mains. Dielectric fittings shall prevent metal-to-metal contact of dissimilar metallic piping elements and shall be suitable for the required working pressure.

2.3 JOINTS

2.3.1 Plastic Pipe Jointing

2.3.1.1 PE Pipe

Joints for pipe fittings and couplings shall be strong tight joints as specified for PE in Paragraph INSTALLATION. Joints connecting pipe of differing materials shall be made in accordance with the manufacturer's recommendation, and as approved by the Contracting Officer.

2.3.1.2 PVC Pipe

Joints, fittings, and couplings shall be as specified for PVC pipe. Joints connecting pipe of differing materials shall be made in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer.

2.3.2 Steel Pipe Jointing

2.3.2.1 Steel Pipe, Not Galvanized

- a. Mechanical couplings shall be as specified.
- b. Bell-and-spigot joints for use with rubber gaskets shall conform to AWWA C200, as appropriate for the type of pipe. Rubber gaskets shall conform to applicable requirements of AWWA C200.
- c. Flanges shall conform to AWWA C207, and shall be used only in above ground installation or where shown on the drawings, or when approved.

2.3.2.2 Mechanical Couplings

Mechanical couplings for steel pipe shall be the sleeve type, or when approved, the split-sleeve type and shall provide a tight flexible joint under all reasonable conditions, such as pipe movements caused by expansion, contraction, slight setting or shifting in the ground, minor variations in trench gradients, and traffic vibrations. Couplings shall be of strength not less than the adjoining pipeline.

2.3.3 Bonded Joints

For all ferrous pipe, a metallic bond shall be provided at each joint, including joints made with flexible couplings, caulking, or rubber gaskets, of ferrous metallic piping to effect continuous conductivity. The bond wire shall be Size 1/0 copper conductor suitable for direct burial shaped to stand clear of the joint. The bond shall be of the thermal weld type.

2.3.4 Isolation Joints

Isolation joints shall be installed between nonthreaded ferrous and nonferrous metallic pipe, fittings and valves. Isolation joints shall consist of a sandwich-type flange isolation gasket of the dielectric type, isolation washers, and isolation sleeves for flange bolts. Isolation gaskets shall be full faced with outside diameter equal to the flange outside diameter. Bolt isolation sleeves shall be full length. Units shall be of a shape to prevent metal-to-metal contact of dissimilar metallic piping elements.

- a. Sleeve-type couplings shall be used for joining plain end pipe sections. The two couplings shall consist of one steel middle ring, two steel followers, two gaskets, and the necessary steel bolts and nuts to compress the gaskets.
- b. Split-sleeve type couplings may be used in aboveground installations when approved in special situations and shall consist of gaskets and a housing in two or more sections with the necessary bolts and nuts.

2.4 VALVES

2.4.1 Check Valves

Check valves shall be designed for a minimum working pressure of 1.03 MPa (150 psi) or as indicated. Valves shall have a clear waterway equal to the full nominal diameter of the valve. Valves shall open to permit flow when inlet pressure is greater than the discharge pressure, and shall close tightly to prevent return flow when discharge pressure exceeds inlet pressure. The size of the valve, working pressure, manufacturer's name, initials, or trademark shall be cast on the body of each valve. Valves 50 mm (2 inches) and larger shall be outside lever and spring.

- a. Valves 50 mm (2 inches) and smaller shall be all bronze designed for screwed fittings, and shall conform to MSS SP-80, Class 150, Types 3 and 4 as suitable for the application.
- b. Valves larger than 50 mm (2 inches) shall be iron body, bronze mounted, shall have flanged ends, and shall be the non-slam type. Flanges shall be the Class 125 type conforming to ASME B16.1.

2.4.2 Gate Valves

Gate valves shall be designed for a working pressure of not less than 1.03 MPa (150 psi). Valve connections shall be as required for the piping in which they are installed. Valves shall have a clear waterway equal to the full nominal diameter of the valve, and shall be opened by turning counterclockwise. The operating nut or wheel shall have an arrow, cast in the metal, indicating the direction of opening.

- a. Valves smaller than 80 mm (3 inches) shall be all bronze and shall conform to MSS SP-80, Type 1, Class 150.
- b. Valves 80 mm (3 inches) and larger shall be iron body, bronze mounted, and shall conform to AWWA C500. Flanges shall not be buried. An approved pit shall be provided for all flanged connections.
- c. Resilient-Seated Gate Valves: For valves 80 to 300 mm (3 to 12 inches) in size, resilient-seated gate valves shall conform to AWWA C509.

2.4.3 Rubber-Seated Butterfly Valves

Rubber-seated butterfly valves shall conform to the performance requirements of AWWA C504. Wafer type valves conforming to the performance requirements of AWWA C504 in all respects, but not meeting laying length requirements will be acceptable if supplied and installed with a spacer providing the specified laying length. All tests required by AWWA C504 shall be met. Flanged-end valves shall be installed in an approved pit and provided with a union or sleeve-type coupling in the pit to permit removal.

Mechanical-end valves 80 through 250 mm in diameter may be direct burial if provided with a suitable valve box, means for manual operation, and an adjacent pipe joint to facilitate valve removal. Valve operators shall restrict closing to a rate requiring approximately 60 seconds, from fully open to fully closed.

2.4.4 Indicator Post for Valves

Each valve shown on the drawings with the designation "P.I.V." shall be equipped with indicator post conforming to the requirements of NFPA 24. Operation shall be by a wrench which shall be attached to each post.

2.5 VALVE BOXES

Valve boxes shall be cast iron or concrete, except that concrete boxes may be installed only in locations not subjected to vehicular traffic. Cast-iron boxes shall be extension type with slide-type adjustment and with flared base. The minimum thickness of metal shall be 5 mm. Concrete boxes shall be the standard product of a manufacturer of precast concrete equipment. The word "WATER" shall be cast in the cover. The box length shall adapt, without full extension, to the depth of cover required over the pipe at the valve location.

2.6 FIRE HYDRANTS

Hydrants shall be dry-barrel type conforming to AWWA C502 with valve opening at least 125 mm (5 inches) in diameter and designed so that the flange at the main valve seat can be removed with the main valve seat apparatus remaining intact, closed and reasonably tight against leakage and with a breakable valve rod coupling and breakable flange connections located no more than 200 mm above the ground grade. Hydrants shall have a 150 mm (6 inch) bell connection, two 65 mm (2-1/2 inch) hose connections and one 115 mm (4-1/2 inch) pumper connection. Outlets shall have American National Standard fire-hose coupling threads. Working parts shall be bronze. Design, material, and workmanship shall be equal to the latest stock pattern ordinarily produced by the manufacturer. Hydrants shall be painted with 1 coat of red iron oxide, zinc oxide primer conforming to SSPC Paint 25 and 2 finish coats of silicone alkyd paint conforming to SSPC Paint 21, LIME GREEN in accordance with NFPA recommendations. Suitable bronze adapter for [the 115 mm (4-1/2 inch)] outlet, with caps, shall be furnished.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Cutting of Pipe

Cutting of pipe shall be done in a neat and workmanlike manner without damage to the pipe. Unless otherwise recommended by the manufacturer and authorized by the Contracting Officer, cutting shall be done with an approved type mechanical cutter. Wheel cutter shall be used when practicable. Copper tubing shall be cut square and all burrs shall be removed. Squeeze type mechanical cutters shall not be used for ductile iron.

3.1.2 Adjacent Facilities

3.1.2.1 Sewer Lines

Where the location of the water pipe is not clearly defined in dimensions on the drawings, the water pipe shall not be laid closer horizontally than 3 m from a sewer except where the bottom of the water pipe will be at least 300 mm above the top of the sewer pipe, in which case the water pipe shall not be laid closer horizontally than 1.8 m from the sewer. Where water lines cross under gravity-flow sewer lines, the sewer pipe, for a distance of at least 3 m each side of the crossing, shall be fully encased in concrete or shall be made of pressure pipe with no joint located within 900 mm horizontally of the crossing. Water lines shall in all cases cross above sewage force mains or inverted siphons and shall be not less than 600 mm above the sewer main. Joints in the sewer main, closer horizontally than 900 mm to the crossing, shall be encased in concrete.

3.1.2.2 Water Lines

Water lines shall not be laid in the same trench with sewer lines.

3.1.2.3 Copper Tubing Lines

Copper tubing shall not be installed in the same trench with ferrous piping materials.

3.1.2.4 Nonferrous Metallic Pipe

Where nonferrous metallic pipe, e.g. copper tubing, crosses any ferrous piping material, a minimum vertical separation of 300 mm shall be maintained between pipes.

3.1.2.5 Casing Pipe

Water pipe shall be encased in a sleeve of rigid conduit for the lengths shown. ~~DELETE TEXT~~ A minimum clearance of at least 50 mm between the inner wall of the sleeve and the maximum outside diameter of the sleeved pipe and joints shall be provided. Sand bedding or suitable pipe support shall be provided for the water pipe through the sleeve. Sleeves of ferrous material shall be provided with corrosion protection as required in Section 13110

3.1.2.6 Structures

Where water pipe is required to be installed within 1 m of existing structures, the water pipe shall be sleeved as required in Paragraph "Casing Pipe". The Contractor shall install the water pipe and sleeve ensuring that there will be no damage to the structures and no settlement or movement of foundations or footings.

3.1.3 Joint Deflection

3.1.3.1 Offset for Flexible Plastic Pipe

Maximum offset in alignment between adjacent pipe joints shall be as recommended by the manufacturer and approved by the Contracting Officer, but shall not exceed 5 degrees.

3.1.3.2 Allowable for Ductile-Iron Pipe

The maximum allowable deflection shall be as given in AWWA C600. If the alignment requires deflection in excess of the above limitations, special bends or a sufficient number of shorter lengths of pipe shall be furnished to provide angular deflections within the limit set forth.

3.1.4 Placing and Laying

Pipe and accessories shall be carefully lowered into the trench by means of derrick, ropes, belt slings, or other authorized equipment. Water-line materials shall not be dropped or dumped into the trench. Abrasion of the pipe coating shall be avoided. Except where necessary in making connections with other lines or as authorized by the Contracting Officer, pipe shall be laid with the bells facing in the direction of laying. The full length of each section of pipe shall rest solidly upon the pipe bed, with recesses excavated to accommodate bells, couplings, and joints. Pipe that has the grade or joint disturbed after laying shall be taken up and relaid. Pipe shall not be laid in water or when trench conditions are unsuitable for the work. Water shall be kept out of the trench until joints are complete. When work is not in progress, open ends of pipe, fittings, and valves shall be securely closed so that no trench water, earth, or other substance will enter the pipes or fittings. Where any part of the coating or lining is damaged, the repair shall be made by and at the Contractor's expense in a satisfactory manner. Pipe ends left for future connections shall be valved, plugged, or capped, and anchored, as shown.

3.1.4.1 Plastic Pipe Installation

RTRP shall be installed in accordance with ASTM D 3839. RPMP shall be installed in accordance with the manufacturer's recommendations. PE Pipe shall be installed in accordance with ASTM D 2774. PVC pipe shall be installed in accordance with AWWA M23.

3.1.4.2 Piping Connections

Where connections are made between new work and existing mains, the connections shall be made by using specials and fittings to suit the actual conditions. When made under pressure, these connections shall be installed using standard methods as approved by the Contracting Officer. Connections to existing asbestos-cement pipe shall be made in accordance with ACPPA Work Practices.

3.1.4.3 Penetrations

Pipe passing through walls of valve pits and structures shall be provided with ductile-iron or Schedule 40 steel wall sleeves. Annular space between walls and sleeves shall be filled with rich cement mortar. Annular space between pipe and sleeves shall be filled with mastic.

3.1.4.4 Flanged Pipe

Flanged pipe shall only be installed above ground or with the flanges in

valve pits.

3.1.5 Jointing

3.1.5.1 Reinforced Concrete Pipe Requirements

The inside and outside annular spaces between abutting sections of concrete pipe shall be filled with rich cement mortar in accordance with the pipe manufacturer's recommendations. Excess mortar shall be removed from interior annular spaces, leaving a smooth and continuous surface between pipe sections. Exposed portions of steel joint rings shall be protected from corrosion by a metallic coating or by an approved nonmetallic coating.

Rubber gaskets shall be handled, lubricated where necessary, and installed in accordance with the pipe manufacturer's recommendations.

3.1.5.2 PE Pipe Requirements

Jointing shall comply with ASTM D 2657, Technique I-Socket Fusion or Technique II-Butt Fusion.

3.1.5.3 PVC Plastic Pipe Requirements

- a. Pipe less than 100 mm (4 inch) diameter: Threaded joints shall be made by wrapping the male threads with approved thread tape or applying an approved lubricant, then threading the joining members together. The joint shall be tightened using strap wrenches to prevent damage to the pipe and/or fitting. To avoid excessive torque, joints shall be tightened no more than one thread past hand-tight. Preformed rubber-ring gaskets for elastomeric-gasket joints shall be made in accordance with ASTM F 477 and as specified. Pipe ends for push-on joints shall be beveled to facilitate assembly and marked to indicate when the pipe is fully seated. The gasket shall be prelubricated to prevent displacement. The gasket and ring groove in the bell or coupling shall match. The manufacturer of the pipe or fitting shall supply the elastomeric gasket. Couplings shall be provided with stops or centering rings to assure that the coupling is centered on the joint. Solvent cement joints shall use sockets conforming to ASTM D 2467. The solvent cement used shall meet the requirements of ASTM D 2564; the joint assembly shall be made in accordance with ASTM D 2855 and the manufacturer's specific recommendations.
- b. Pipe 100 through 300 mm diameter: Joints shall be elastomeric gasket as specified in AWWA C900. Jointing procedure shall be as specified for pipe less than 100 mm (4 inch) diameter with configuration using elastomeric ring gasket.
- c. Pipe 350 through 900 mm diameter: Joints shall be elastomeric gasket push-on joints made in accordance with AWWA M23.

3.1.5.4 Ductile-Iron Pipe Requirements

Mechanical and push-on type joints shall be installed in accordance with AWWA C600 for buried lines or AWWA C606 for grooved and shouldered pipe

above ground or in pits.

3.1.5.5 Galvanized Steel Pipe Requirements

Screw joints shall be made tight with a stiff mixture of graphite and oil, inert filler and oil, or with an approved graphite compound, applied with a brush to the male threads only. Compounds shall not contain lead.

3.1.5.6 Bonded Joints Requirements

Bonded joints shall be installed in accordance with details specified for joints in paragraph JOINTS.

3.1.5.7 Isolation Joints and Dielectric Fittings

Isolation joints and dielectric fittings shall be installed in accordance with details specified in paragraph JOINTS. Dielectric unions shall be encapsulated in a field-poured coal-tar covering, with at least 3 mm thickness of coal tar over all fitting surfaces.

3.1.5.8 Transition Fittings

Connections between different types of pipe and accessories shall be made with transition fittings approved by the Contracting Officer.

3.1.6 Installation of Service Lines

Service lines shall include the pipeline connecting building piping to water distribution lines to the connections with the building service at a point approximately 1.5 m outside the building where such building service exists. Where building services are not installed, the Contractor shall terminate the service lines approximately 1.5 m from the site of the proposed building at a point designated by the Contracting Officer. Such service lines shall be closed with plugs or caps. All service stops and valves shall be provided with service boxes. Service lines shall be constructed in accordance with the following requirements:

3.1.6.1 Service Lines 50 mm (2 Inches) and Smaller

Service lines 50 mm (2 inches) and smaller shall be connected to the main by a directly-tapped corporation stop or by a service clamp. A corporation stop and a copper gooseneck shall be provided with either type of connection. Where 2 or more gooseneck connections to the main are required for an individual service, such connections shall be made with standard branch connections. The total clear area of the branches shall be at least equal to the clear area of the service which they are to supply.

NOTE:

- a. Service lines 40 mm (1-1/2 inches) and smaller shall have a service stop.
- b. Service lines 50 mm (2 inches) in size shall have a gate valve.

3.1.6.2 Service Lines Larger than 50 mm (2 Inches)

Service lines larger than 50 mm (2 inches) shall be connected to the main by a tapped saddle, tapping sleeve and valve, service clamp or reducing tee, depending on the main diameter and the service line diameter, and shall have a gate valve. Lines 80 mm (3 inches) and larger may use rubber-seated butterfly valves as specified above, or gate valves.

3.1.6.3 Service Lines for Sprinkler Supplies

Water service lines used to supply building sprinkler systems for fire protection shall be connected to the water distribution main in accordance with NFPA 24.

3.1.7 Setting of Fire Hydrants, Meters, Valves and Valve Boxes

3.1.7.1 Location of Fire Hydrants

Fire hydrants shall be located and installed as shown. Each hydrant shall be connected to the main with a 150 mm (6 inch) branch line having at least as much cover as the distribution main. Hydrants shall be set plumb with pumper nozzle facing the roadway, with the center of the lowest outlet not less than 450 mm above the finished surrounding grade, and the operating nut not more than 1.2 m above the finished surrounding grade. Fire hydrants designated on the drawings as low profile shall have the lowest outlet not less than 450 mm above the finished surrounding grade, the top of the hydrant not more than 600 mm above the finished surrounding grade. Except where approved otherwise, the backfill around hydrants shall be thoroughly compacted to the finished grade immediately after installation to obtain beneficial use of the hydrant as soon as practicable. The hydrant shall be set upon a slab of concrete not less than 100 mm thick and 400 mm square. Not less than 2 cubic meters of free-draining broken stone or gravel shall be placed around and beneath the waste opening of dry barrel hydrants to ensure drainage.

3.1.7.2 Location of Meters

Meters and meter boxes shall be installed at the locations shown on the drawings. The meters shall be centered in the boxes to allow for reading and ease of removal or maintenance.

3.1.7.3 Location of Valves

After delivery, valves, including those in hydrants, shall be drained to prevent freezing and shall have the interiors cleaned of all foreign matter before installation. Stuffing boxes shall be tightened and hydrants and valves shall be fully opened and fully closed to ensure that all parts are in working condition. Check, pressure reducing, vacuum, and air relief valves shall be installed in valve pits. Valves and valve boxes shall be installed where shown or specified, and shall be set plumb. Valve boxes shall be centered on the valves. Boxes shall be installed over each outside gate valve unless otherwise shown. Where feasible, valves shall be located outside the area of roads and streets. Earth fill shall be tamped around each valve box or pit to a distance of 1.2 m on all sides of the

box, or the undisturbed trench face if less than 1.2 m.

3.1.7.4 Location of Service Boxes

Where water lines are located below paved streets having curbs, the boxes shall be installed directly back of the curbs. Where no curbing exists, service boxes shall be installed in accessible locations, beyond the limits of street surfacing, walks and driveways.

3.1.8 Tapped Tees and Crosses

Tapped tees and crosses for future connections shall be installed where shown.

3.1.9 Thrust Restraint

Plugs, caps, tees and bends deflecting 11.25 degrees or more, either vertically or horizontally, on waterlines 100 mm (4 inches) in diameter or larger, and fire hydrants shall be provided with thrust restraints. Valves shall be securely anchored or shall be provided with thrust restraints to prevent movement. Thrust restraints shall be either thrust blocks or, for ductile-iron pipes, restrained joints.

3.1.9.1 Thrust Blocks

Thrust blocking shall be concrete of a mix not leaner than: 1 cement, 2-1/2 sand, 5 gravel; and having a compressive strength of not less than 14 MPa after 28 days. Blocking shall be placed between solid ground and the hydrant or fitting to be anchored. Unless otherwise indicated or directed, the base and thrust bearing sides of thrust blocks shall be poured directly against undisturbed earth. The sides of thrust blocks not subject to thrust may be poured against forms. The area of bearing shall be as shown or as directed. Blocking shall be placed so that the fitting joints will be accessible for repair. Steel rods and clamps, protected by galvanizing or by coating with bituminous paint, shall be used to anchor vertical down bends into gravity thrust blocks.

3.1.9.2 Restrained Joints

For ductile-iron pipe, restrained joints shall be designed by the Contractor or the pipe manufacturer in accordance with DIPRA-Restraint Design.

3.2 HYDROSTATIC TESTS

Where any section of a water line is provided with concrete thrust blocking for fittings or hydrants, the hydrostatic tests shall not be made until at least 5 days after installation of the concrete thrust blocking, unless otherwise approved.

3.2.1 Pressure Test

After the pipe is laid, the joints completed, fire hydrants permanently installed, and the trench partially backfilled leaving the joints exposed

for examination, the newly laid piping or any valved section of piping shall, unless otherwise specified, be subjected for 1 hour to a hydrostatic pressure test of [1.38] MPa. Water supply lines designated on the drawings shall be subjected for 1 hour to a hydrostatic pressure test of [1.38]MPa. Each valve shall be opened and closed several times during the test. Exposed pipe, joints, fittings, hydrants, and valves shall be carefully examined during the partially open trench test. Joints showing visible leakage shall be replaced or remade as necessary. Cracked or defective pipe, joints, fittings, hydrants and valves discovered in consequence of this pressure test shall be removed and replaced with sound material, and the test shall be repeated until the test results are satisfactory. The requirement for the joints to remain exposed for the hydrostatic tests may be waived by the Contracting Officer

The Contractor may request a waiver, setting forth in writing the reasons for the request and stating the alternative procedure proposed to comply with the required hydrostatic tests. Backfill placed prior to the tests shall be placed in accordance with the requirements of Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS.

3.2.2 Leakage Test

Leakage test shall be conducted after the pressure tests have been satisfactorily completed. The duration of each leakage test shall be at least 2 hours, and during the test the water line shall be subjected to not less than [1.38] MPa pressure. Water supply lines designated on the drawings shall be subjected to a pressure equal to [1.38] MPa. Leakage is defined as the quantity of water to be supplied into the newly laid pipe, or any valved or approved section, necessary to maintain pressure within 34.5 kPa (5 psi) of the specified leakage test pressure after the pipe has been filled with water and the air expelled. Piping installation will not be accepted if leakage exceeds the allowable leakage which is determined by the following formula:

$$L = 0.0001351ND(P \text{ raised to } 0.5 \text{ power})$$

L = Allowable leakage in gallons per hour

N = Number of joints in the length of pipeline tested

D = Nominal diameter of the pipe in inches

P = Average test pressure during the leakage test, in psi gauge

Should any test of pipe disclose leakage greater than that calculated by the above formula, the defective joints shall be located and repaired until the leakage is within the specified allowance, without additional cost to the Government.

3.2.3 Time for Making Test

Except for joint material setting or where concrete thrust blocks necessitate a 5-day delay, pipelines jointed with rubber gaskets, mechanical or push-on joints, or couplings may be subjected to hydrostatic pressure, inspected, and tested for leakage at any time after partial

completion of backfill. Cement-mortar lined pipe may be filled with water as recommended by the manufacturer before being subjected to the pressure test and subsequent leakage test.

3.2.4 Concurrent Hydrostatic Tests

The Contractor may elect to conduct the hydrostatic tests using either or both of the following procedures. Regardless of the sequence of tests employed, the results of pressure tests, leakage tests, and disinfection shall be as specified. Replacement, repair or retesting required shall be accomplished by the Contractor at no additional cost to the Government.

- a. Pressure test and leakage test may be conducted concurrently.
- b. Hydrostatic tests and disinfection may be conducted concurrently, using the water treated for disinfection to accomplish the hydrostatic tests. If water is lost when treated for disinfection and air is admitted to the unit being tested, or if any repair procedure results in contamination of the unit, disinfection shall be reaccomplished.

3.3 BACTERIAL DISINFECTION

3.3.1 Bacteriological Disinfection

Before acceptance of potable water operation, each unit of completed waterline shall be disinfected as prescribed by AWWA C651. After pressure tests have been made, the unit to be disinfected shall be thoroughly flushed with water until all entrained dirt and mud have been removed before introducing the chlorinating material. The chlorinating material shall be either liquid chlorine, calcium hypochlorite, or sodium hypochlorite, conforming to paragraph MISCELLANEOUS ITEMS. The chlorinating material shall provide a dosage of not less than 50 ppm and shall be introduced into the water lines in an approved manner. Polyvinyl Chloride (PVC) pipe lines shall be chlorinated using only the above specified chlorinating material in solution. The agent shall not be introduced into the line in a dry solid state. The treated water shall be retained in the pipe long enough to destroy all non-spore forming bacteria.

Except where a shorter period is approved, the retention time shall be at least 24 hours and shall produce not less than 25 ppm of free chlorine residual throughout the line at the end of the retention period. Valves on the lines being disinfected shall be opened and closed several times during the contact period. The line shall then be flushed with clean water until the residual chlorine is reduced to less than 1.0 ppm. During the flushing period, each fire hydrant on the line shall be opened and closed several times. From several points in the unit, personnel from the Contractor's commercial laboratory shall take at least 3 water samples from different points, approved by the Contracting Officer, in proper sterilized containers and perform a bacterial examination in accordance with state approved methods. The commercial laboratory shall be certified by the state's approving authority for examination of potable water. The disinfection shall be repeated until tests indicate the absence of pollution for at least 2 full days. The unit will not be accepted until satisfactory bacteriological results have been obtained.

3.4 CLEANUP

Upon completion of the installation of water lines, and appurtenances, all debris and surplus materials resulting from the work shall be removed.

-- End of Section --

SECTION 02531A

SANITARY SEWERS

04/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 74	(1998) Cast Iron Soil Pipe and Fittings
ASTM A 123/A 123M	(2000) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM C 14M	(1999) Concrete Sewer, Storm Drain, and Culvert Pipe (Metric)
ASTM C 33	(1999a) Concrete Aggregates
ASTM C 76M	(2000) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe (Metric)
ASTM C 94/C 94M	(2000) Ready-Mixed Concrete
ASTM C 150	(1999a) Portland Cement
ASTM C 270	(2000) Mortar for Unit Masonry
ASTM C 425	(2000) Compression Joints for Vitrified Clay Pipe and Fittings
ASTM C 443	(1998) Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets
ASTM C 443M	(1998) Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets (Metric)
ASTM C 478	(1997) Precast Reinforced Concrete Manhole Sections
ASTM C 478M	(1997) Precast Reinforced Concrete Manhole Sections (Metric)
ASTM C 564	(1997) Rubber Gaskets for Cast Iron Soil

Pipe and Fittings

ASTM C 700	(2000) Vitrified Clay Pipe, Extra Strength, Standard Strength, and Perforated
ASTM C 828	(1998) Low-Pressure Air Test of Vitrified Clay Pipe Lines
ASTM C 924M	Concrete Pipe Sewer Lines by Low Pressure Air Test Method (Metric)
ASTM C 972	(2000) Compression-Recovery of Tape Sealant
ASTM D 412	(1998a) Vulcanized Rubber and Thermoplastic Rubbers and Thermoplastic Elastomers - Tension
ASTM D 624	(2000) Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D 1784	(1999a) Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D 2680	(1995a) Acrylonitrile-Butadiene-Styrene (ABS) and Poly(Vinyl Chloride) (PVC) Composite Sewer Piping
ASTM D 2751	(1996a) Acrylonitrile-Butadiene-Styrene (ABS) Sewer Pipe and Fittings
ASTM D 2996	(1995) Filament-Wound "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe
ASTM D 2997	(1999) Centrifugally Cast "Fiberglass" (Glass-Fiber-Reinforced-Thermosetting-Resin) Pipe
ASTM D 3034	(1998) Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings
ASTM D 3212	(1996a) Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D 3262	(1996) "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Sewer Pipe
ASTM D 3350	(1999) Polyethylene Plastics Pipe and Fittings Materials
ASTM D 3753	(1999) Glass-Fiber-Reinforced Polyester

Manholes

ASTM D 3840	(1999) "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe Fittings for Nonpressure Applications
ASTM F 402	(1993; R 1999) Safe Handling of Solvent Cements, Primers, and Cleaners Used for Joining Thermoplastic Pipe and Fittings
ASTM F 477	(1999) Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F 714	(2000) Polyethylene (PE) Plastic pipe (SDR-PR) Based on Outside Diameter
ASTM F 794	(1999) Poly(Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter
ASTM F 894	(1998a) Polyethylene (PE) Large Diameter Profile Wall Sewer and Drain Pipe
ASTM F 949	(2000) Poly(Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C105	(1999) Polyethylene Encasement for Ductile-Iron Pipe Systems
AWWA C110	(1998) Ductile-Iron and Gray-Iron Fittings, 3 In. Through 48 In. (75 mm through 1200 mm), for Water and Other Liquids
AWWA C111	(2000) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C115	(1999) Flanged Ductile-Iron Pipe with Ductile-Iron or Gray-Iron Threaded Flanges
AWWA C151	(1996) Ductile-Iron Pipe, Centrifugally Cast, for Water or Other Liquids

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 49	(1994) Hazardous Chemicals Data
NFPA 325-1	(1994) Fire Hazard Properties of Flammable Liquids, Gases, and Volatile Solids

NFPA 704 (1996) Identification of the Fire Hazards
of Materials for Emergency Response

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)

UBPPA UNI-B-6 (1990) Recommended Practice for the
Low-Pressure Air Testing of Installed
Sewer Pipe

UBPPA UNI-B-9 (1990; Addenda 1994) Recommended
Performance Specification for Polyvinyl
Chloride (PVC) Profile Wall Gravity Sewer
Pipe and Fittings Based on Controlled
Inside Diameter (Nominal Pipe Sizes 4-48
inch)

1.2 GENERAL REQUIREMENTS

The construction required herein shall include appurtenant structures and building sewers to points of connection with the building drains 1.5 m outside the building to which the sewer system is to be connected. The Contractor shall replace damaged material and redo unacceptable work at no additional cost to the Government. Excavation and backfilling is specified in Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS. Backfilling shall be accomplished after inspection by the Contracting Officer. Before, during, and after installation, plastic pipe and fittings shall be protected from any environment that would result in damage or deterioration to the material. The Contractor shall have a copy of the manufacturer's instructions available at the construction site at all times and shall follow these instructions unless directed otherwise by the Contracting Officer. Solvents, solvent compounds, lubricants, elastomeric gaskets, and any similar materials required to install the plastic pipe shall be stored in accordance with the manufacturer's recommendation and shall be discarded if the storage period exceeds the recommended shelf life. Solvents in use shall be discarded when the recommended pot life is exceeded.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-07 Certificates

Portland Cement; FIO, RE

Certificates of compliance stating the type of cement used in manufacture of concrete pipe, fittings and precast manholes.

Joints; FIO, RE

Joints installation shall comply with the manufacturer's

instructions.

PART 2 PRODUCTS

2.1 PIPE

Pipe shall conform to the respective specifications and other requirements specified below.

2.1.1 Concrete Pipe

Concrete pipe 600 mm or less in diameter, unless otherwise shown or specified, shall be nonreinforced and conform to ASTM C 14M , Class 2.

2.1.2 Plastic Pipe

Acrylonitrile-butadiene-styrene (ABS) and polyvinyl chloride (PVC) composite sewer piping shall conform to ASTM D 2680.

2.1.2.1 ABS Pipe

ASTM D 2751.

2.1.2.2 PVC Pipe

ASTM D 3034, Type PSM with a maximum SDR of 35, Size 380 mm or less in diameter. ASTM F 949 for corrugated sewer pipes with a smooth interior. PVC shall be certified by the compounder as meeting the requirements of ASTM D 1784, cell Class 12454B. The pipe stiffness shall be greater than or equal to 735/D for cohesionless material pipe trench backfills.

2.1.2.3 High Density Polyethylene Pipe

ASTM F 894, Class 63, size 450 mm through 3000 mm. ASTM F 714, size 100 mm through 1200 mm. The polyethylene shall be certified by the resin producer as meeting the requirements of ASTM D 3350, cell Class 334433C. The pipe stiffness shall be greater than or equal to 1170/D for cohesionless material pipe trench backfills.

2.1.3 Reinforced Plastic Mortar Pipe (RPMP)

ASTM D 3262.

2.1.4 Reinforced Thermosetting Resin Pipe (RTRP)

ASTM D 3262.

2.1.4.1 Filament Wound RTRP-I

RTRP-I shall conform to ASTM D 2996, except pipe shall have an outside diameter equal to cast iron outside diameter or standard weight steel pipe.

The pipe shall be suitable for a normal working pressure of 1.03 MPa at 22.8 degrees C. The inner surface of the pipe shall have a smooth uniform continuous resin-rich surface liner conforming to ASTM D 2996.

2.1.4.2 Centrifugally Cast RTRP-II

RTRP-II shall conform to ASTM D 2997. Pipe shall have an outside diameter equal to standard weight steel pipe.

2.1.5 Ductile Iron Pipe

Pipe shall conform to AWWA C151 unless otherwise shown or specified.

2.1.6 Cast Iron Soil Pipe

Cast iron soil pipe shall conform to ASTM A 74, Class SV, except where Class XH is indicated. When installed underground, pipe shall be encased with 0.8 mm thick polyethylene in accordance with AWWA C105.

2.1.7 Clay Pipe

ASTM C 700

2.2 REQUIREMENTS FOR FITTINGS

Fittings shall be compatible with the pipe supplied and shall have a strength not less than that of the pipe. Fittings shall conform to the respective specifications and other requirements specified below.

2.2.1 Fittings for Concrete Pipe

ASTM C 14M for pipe 600 mm or less in diameter. ASTM C 76M for pipe greater than 600 mm in diameter.

2.2.2 Fittings for Plastic Pipe

ABS and PVC composite sewer pipe fittings shall conform to ASTM D 2680.

2.2.2.1 Fittings for ABS Pipe

ASTM D 2751.

2.2.2.2 Fittings for PVC Pipe

ASTM D 3034 for type PSM pipe. ASTM F 949 for corrugated sewer pipe with a smooth interior. UBPPA UNI-B-9 and ASTM F 794, Series 46, for ribbed sewer pipe with smooth interior.

2.2.2.3 Fittings for High Density Polyethylene Pipe

ASTM F 894.

2.2.3 Fittings for RPMP

ASTM D 3840.

2.2.4 Fittings for RTRP

ASTM D 3262.

2.2.5 Fittings for Ductile Iron Pipe

Mechanical fittings shall conform to AWWA C110, rated for 1.03 MPa.

Push-on fittings shall conform to AWWA C110 and AWWA C111, rated for 10.3 MPa

2.2.6 Fittings for Cast Iron Soil Pipe

ASTM A 74.

2.2.7 Fittings for Clay Pipe

ASTM C 700

2.3 JOINTS

Joints installation shall comply with the manufacturer's instructions.

2.3.1 Concrete Pipe Jointing

Joints and gaskets shall conform to ASTM C 443M .

2.3.2 Plastic Pipe Jointing

Flexible plastic pipe (PVC or high density polyethylene pipe) gasketed joints shall conform to ASTM D 3212.

2.3.2.1 ABS Pipe Jointing

ASTM D 2751, solvent weld or bell and spigot O-ring joint, size 300 mm or less in diameter, dimensions and tolerances in accordance with Table 2 of ASTM D 2751.

2.3.2.2 High Density Polyethylene Pipe Jointing

Rubber gasket joints shall conform to ASTM C 443M .

2.3.3 RPMP Jointing

Joints shall be bell and spigot gasket coupling utilizing an elastomeric gasket in accordance with ASTM D 4161 and ASTM F 477.

2.3.4 RTRP Jointing

Joints shall be bell and spigot type utilizing an elastomeric gasket in accordance with ASTM F 477.

2.3.5 Ductile Iron Pipe Jointing

Push-on joints shall conform to AWWA C111. Mechanical joints shall conform to AWWA C111 as modified by AWWA C151. Flanged joints shall conform to AWWA C115.

2.3.6 Cast Iron Soil Pipe Jointing

Rubber gaskets for compression joints shall conform to ASTM C 564. Packing material for caulked joints shall be twisted jute or oakum, tarred type, or asphalt-saturated cellulose-fiber. Joints for acid resisting cast iron soil pipe shall be made with acid resistant non-asbestos packing. The packing shall not contain material which would affect adhesion of the joint sealing material to the pipe. Lead shall be suitable for caulking of joints.

2.3.7 Clay Pipe Jointing

Compression joints shall conform to ASTM C 425.

2.4 BRANCH CONNECTIONS

Branch connections shall be made by use of regular fittings or solvent cemented saddles as approved. Saddles for ABS and PVC composite pipe shall conform to Figure 2 of ASTM D 2680; saddles for ABS pipe shall comply with Table 3 of ASTM D 2751; and saddles for PVC pipe shall conform to Table 4 of ASTM D 3034.

2.5 FRAMES AND COVERS

Frames and covers shall be cast iron, ductile iron or reinforced concrete. Cast iron frames and covers shall be as indicated or shall be of type suitable for the application, circular, without vent holes. The frames and covers shall have a combined weight of not less than 181.4 kg. Reinforced concrete frames and covers shall be as indicated or shall conform to ASTM C 478 or ASTM C 478M. The word "Sewer" shall be stamped or cast into covers so that it is plainly visible.

2.6 STEEL LADDER

Not Used

2.7 CEMENT MORTAR

Cement mortar shall conform to ASTM C 270, Type M with Type II cement.

2.7.1 Portland Cement

Portland cement shall conform to ASTM C 150, Type III for concrete used in concrete pipe, concrete pipe fittings, and manholes and type optional with the Contractor for cement used in concrete cradle, concrete encasement, and thrust blocking. Where aggregates are alkali reactive, as determined by Appendix XI of ASTM C 33, a cement containing less than 0.60 percent alkalies shall be used.

2.7.2 Portland Cement Concrete

Portland cement concrete shall conform to ASTM C 94/C 94M, compressive strength of 28 at 28 days, except for concrete cradle and encasement or

concrete blocks for manholes. Concrete used for cradle and encasement shall have a compressive strength of 17 MPa minimum at 28 days. Concrete in place shall be protected from freezing and moisture loss for 7 days.

2.8 STRUCTURES

2.8.1 Precast Reinforced Concrete Manhole Sections

Precast reinforced concrete manhole sections shall conform to ASTM C 478, except that portland cement shall be as specified herein. Joints shall be cement mortar, an approved mastic, rubber gaskets, a combination of these types; or the use of external preformed rubber joint seals and extruded rolls of rubber with mastic adhesive on one side.

2.8.2 Glass-Fiber-Reinforced Polyester Manholes

Glass-fiber-reinforced polyester manholes shall conform to ASTM D 3753.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Adjacent Facilities

3.1.1.1 Water Lines

Where the location of the sewer is not clearly defined by dimensions on the drawings, the sewer shall not be closer horizontally than 3 m to a water-supply main or service line, except that where the bottom of the water pipe will be at least 300 mm above the top of the sewer pipe, the horizontal spacing may be a minimum of 2 m. Where gravity-flow sewers cross above water lines, the sewer pipe for a distance of 3 m on each side of the crossing shall be fully encased in concrete or shall be acceptable pressure pipe with no joint closer horizontally than 1 m to the crossing. The thickness of the concrete encasement including that at the pipe joints shall be not less than 100 mm.

3.1.1.2 Roads, Railroads, and Airfields

Water pipe shall be encased in a sleeve of rigid conduit for the lengths shown. DELETE TEXT

A minimum clearance of at least 50 mm between the inner wall of the sleeve and the maximum outside diameter of the sleeved pipe and joints shall be provided. Sand bedding shall be provided for the water pipe through the sleeve. Sleeves of ferrous material shall be provided with the corrosion protection as required for the conditions encountered at the site of installation.

3.1.1.3 Structural Foundations

Where sewer pipe is to be installed within 1 m of an existing or proposed building or structural foundation such as a retaining wall, control tower footing, water tank footing, or any similar structure, the sewer pipe shall

be sleeved as specified above. Contractor shall ensure there is no damage to these structures, and no settlement or movement of foundations or footing.

3.1.2 Pipe Laying

- a. Pipe shall be protected during handling against impact shocks and free fall; the pipe interior shall be free of extraneous material.
- b. Pipe laying shall proceed upgrade with the spigot ends of bell-and-spigot pipe and tongue ends of tongue-and-groove pipe pointing in the direction of the flow. Each pipe shall be laid accurately to the line and grade shown on the drawings. Pipe shall be laid and centered so that the sewer has a uniform invert. As the work progresses, the interior of the sewer shall be cleared of all superfluous materials.
- c. Before making pipe joints, all surfaces of the portions of the pipe to be joined shall be clean and dry. Lubricants, primers, and adhesives shall be used as recommended by the pipe manufacturer. The joints shall then be placed, fitted, joined, and adjusted to obtain the degree of water tightness required.
- d. ABS composite pipe ends with exposed truss and filler material shall be coated with solvent weld material before making the joint to prevent water or air passage at the joint between the inner and outer wall of the pipe.
- e. Installations of solvent weld joint pipe, using ABS or PVC pipe and fittings shall be in accordance with ASTM F 402. The Contractor shall ensure adequate trench ventilation and protection for workers installing the pipe.

3.1.2.1 Caulked Joints

The packing material shall be well packed into the annular space to prevent the entrance of lead into the pipe. The remainder of the space shall be filled with molten lead that is hot enough to show a rapid change in color when stirred. Scum shall be removed before pouring. The lead shall be caulked to form a tight joint without overstraining the bell and shall have a minimum depth of 25 mm after caulking.

3.1.2.2 Trenches

Trenches shall be kept free of water and as dry as possible during bedding, laying, and jointing and for as long a period as required. When work is not in progress, open ends of pipe and fittings shall be satisfactorily closed so that no trench water or other material will enter the pipe or fittings.

3.1.2.3 Backfill

As soon as possible after the joint is made, sufficient backfill material shall be placed along the pipe to prevent pipe movement off line or grade.

Plastic pipe shall be completely covered to prevent damage from ultraviolet light.

3.1.2.4 Width of Trench

If the maximum width of the trench at the top of the pipe, as specified in Section 02316 EXCAVATION, TRENCHING, AND BACKFILLING FOR UTILITIES SYSTEMS, is exceeded for any reason other than by direction, the Contractor shall install, at no additional cost to the Government, concrete cradling, pipe encasement, or other bedding required to support the added load of the backfill.

3.1.2.5 Jointing

Joints between different pipe materials shall be made as specified, using approved jointing materials.

3.1.2.6 Handling and Storage

Pipe, fittings and joint material shall be handled and stored in accordance with the manufacturer's recommendations. Storage facilities for plastic pipe, fittings, joint materials and solvents shall be classified and marked in accordance with NFPA 704, with classification as indicated in NFPA 49 and NFPA 325-1.

3.1.3 Leakage Tests

Lines shall be tested for leakage by low pressure air testing, infiltration tests or exfiltration tests, as appropriate. Low pressure air testing for vitrified clay pipes shall be as prescribed in ASTM C 828. Low pressure air testing for concrete pipes shall be as prescribed in ASTM C 828. Low pressure air testing for PVC pipe shall be as prescribed in UBPPA UNI-B-6. Low pressure air testing procedures for other pipe materials shall use the pressures and testing times prescribed in ASTM C 828 and ASTM C 924M, after consultation with the pipe manufacturer. Prior to infiltration or exfiltration tests, the trench shall be backfilled up to at least the lower half of the pipe. If required, sufficient additional backfill shall be placed to prevent pipe movement during testing, leaving the joints uncovered to permit inspection. Visible leaks encountered shall be corrected regardless of leakage test results. When the water table is 600 mm or more above the top of the pipe at the upper end of the pipeline section to be tested, infiltration shall be measured using a suitable weir or other device acceptable to the Contracting Officer. When the Contracting Officer determines that infiltration cannot be properly tested, an exfiltration test shall be made by filling the line to be tested with water so that a head of at least 600 mm is provided above both the water table and the top of the pipe at the upper end of the pipeline to be tested. The filled line shall be allowed to stand until the pipe has reached its maximum absorption, but not less than 4 hours. After absorption, the head shall be re-established. The amount of water required to maintain this water level during a 2-hour test period shall be measured. Leakage as measured by either the infiltration test or exfiltration test shall not exceed 94 L per 1 mm diameter per km of pipeline per day. When leakage exceeds the maximum amount specified, satisfactory correction shall

be made and retesting accomplished. Testing, correction, and retesting shall be made at no additional cost to the Government.

3.1.4 Test for Deflection

When flexible pipe is used, a deflection test shall be made on the entire length of the installed pipeline not less than 30 days after the completion of all work including the leakage test, backfill, and placement of any fill, grading, paving, concrete, or superimposed loads. Deflection shall be determined by use of a deflection device or by use of a spherical, spheroidal, or elliptical ball, a cylinder, or circular sections fused to a common shaft. The ball, cylinder, or circular sections shall have a diameter, or minor diameter as applicable, of 92.5 percent of the inside diameter of the pipe, but 95 percent for RPMP and RTRP. A tolerance of plus 0.5 percent will be permitted. The ball, cylinder, or circular sections shall be of a homogeneous material throughout, shall have a density greater than 1.0 as related to water at 4.0 degrees C and shall have a surface brinell hardness of not less than 150. The device shall be center bored and through bolted with a 6 mm minimum diameter steel shaft having a yield strength of 480 MPa or more, with eyes at each end for attaching pulling cables. The eye shall be suitably backed with flange or heavy washer; a pull exerted on the opposite end of the shaft shall produce compression throughout the remote end of the ball, cylinder or circular section. Circular sections shall be spaced so that the distance from the external faces of the front and back sections shall equal or exceed the diameter of the circular section. Failure of the ball, cylinder, or circular section to pass freely through a pipe run, either by being pulled through or by being flushed through with water, shall be cause for rejection of that run. When a deflection device is used for the test in lieu of the ball, cylinder, or circular sections described, such device shall be approved prior to use. The device shall be sensitive to 1.0 percent of the diameter of the pipe being measured and shall be accurate to 1.0 percent of the indicated dimension. Installed pipe showing deflections greater than 7.5 percent of the normal diameter of the pipe, or 5 percent for RTRP and RPMP, shall be retested by a run from the opposite direction. If the retest also fails, the suspect pipe shall be replaced at no cost to the Government.

3.2 CONCRETE CRADLE AND ENCASEMENT

The pipe shall be supported on a concrete cradle, or encased in concrete where indicated or directed.

3.3 INSTALLATION OF WYE BRANCHES

Wye branches shall be installed where sewer connections are indicated or where directed. Cutting into piping for connections shall not be done except in special approved cases. When the connecting pipe cannot be adequately supported on undisturbed earth or tamped backfill, the pipe shall be encased in concrete backfill or supported on a concrete cradle as directed. Concrete required because of conditions resulting from faulty construction methods or negligence by the Contractor shall be installed at no additional cost to the Government. The installation of wye branches in an existing sewer shall be made by a method which does not damage the

integrity of the existing sewer. One acceptable method consists of removing one pipe section, breaking off the upper half of the bell of the next lower section and half of the running bell of wye section. After placing the new section, it shall be rotated so that the broken half of the bell will be at the bottom. The two joints shall then be made with joint packing and cement mortar.

3.4 MANHOLE DETAILS

3.4.1 General Requirements

Manholes shall be constructed of glass-fiber-reinforced polyester, prefabricated plastic, concrete, or precast concrete manhole sections. The invert channels shall be smooth and semicircular in shape conforming to the inside of the adjacent sewer section. Changes in direction of flow shall be made with a smooth curve of as large a radius as the size of the manhole will permit. Changes in size and grade of the channels shall be made gradually and evenly. The invert channels shall be formed directly in the concrete of the manhole base, or shall be built up with brick and mortar, or shall be half tile laid in concrete, or shall be constructed by laying full section sewer pipe through the manhole and breaking out the top half after the surrounding concrete has hardened. Pipe connections shall be made to manhole using water stops, standard O-ring joints, special manhole coupling, or shall be made in accordance with the manufacturer's recommendation. The Contractor's proposed method of connection, list of materials selected, and specials required, shall be approved prior to installation. The floor of the manhole outside the channels shall be smooth and shall slope toward the channels not less than 100 mm per meter nor more than 200 mm per meter. Free drop inside the manholes shall not exceed 500 mm, measured from the invert of the inlet pipe to the top of the floor of the manhole outside the channels; drop manholes shall be constructed whenever the free drop would otherwise be greater than 500 mm.

3.4.2 Jointing, Plastering and Sealing

Mortar joints shall be completely filled and shall be smooth and free from surplus mortar on the inside of the manhole. Mortar and mastic joints between precast rings shall be full-bedded in jointing compound and shall be smoothed to a uniform surface on both the interior and exterior of the manhole. Installation of rubber gasket joints between precast rings shall be in accordance with the recommendations of the manufacturer. Precast rings may also be sealed by the use of extruded rolls of rubber with mastic adhesive on one side.

3.4.3 Setting of Frames and Covers

Unless otherwise indicated, tops of frames and covers shall be set flush with finished grade in paved areas or 50 mm higher than finished grade in unpaved areas. Frame and cover assemblies shall be sealed to manhole sections using external preformed rubber joint seals that meet the requirements of ASTM D 412 and ASTM D 624, or other methods specified in paragraph Jointing, Plastering and Sealing, unless otherwise specified.

3.4.4 External Preformed Rubber Joint Seals

External preformed rubber joint seals and extruded rolls of rubber with mastic adhesive shall meet the requirements of ASTM D 412 and ASTM C 972 to ensure conformance with paragraph Leakage Tests. The seal shall be multi-section with neoprene rubber top section and all lower sections made of Ethylene Propylene Di Monomer (EPDM) rubber with a minimum thickness of 1.5 mm. Each unit shall consist of a top and a bottom section and shall have mastic on the bottom of the bottom section and mastic on the top and bottom of the top section. The mastic shall be non-hardening butyl rubber sealant and shall seal to the cone/top slab of the manhole/catch basin and over the lip of the casting. One unit shall seal a casting and up to six, 50 mm adjusting rings. The bottom section shall be 305 mm in height. A 152 mm high top section will cover up to two, 50 mm adjusting rings. A 305 mm high bottom section will cover up to six, 50 mm adjusting rings. Extension sections shall cover up to two more adjusting rings. Each extension shall overlap the bottom section by 50 mm and shall be overlapped by the top section by 50 mm.

3.5 CONNECTING TO EXISTING MANHOLES

Pipe connections to existing manholes shall be made so that finish work will conform as nearly as practicable to the applicable requirements specified for new manholes, including all necessary concrete work, cutting, and shaping. The connection shall be centered on the manhole. Holes for the new pipe shall be of sufficient diameter to allow packing cement mortar around the entire periphery of the pipe but no larger than 1.5 times the diameter of the pipe. Cutting the manhole shall be done in a manner that will cause the least damage to the walls.

3.6 BUILDING CONNECTIONS

Building connections shall include the lines to and connection with the building waste drainage piping at a point approximately 1.5 m outside the building, unless otherwise indicated. Where building drain piping is not installed, the Contractor shall terminate the building connections approximately 1.5 m from the site of the building at a point and in a manner designated.

3.7 CLEANOUTS AND OTHER APPURTENANCES

Cleanouts and other appurtenances shall be installed where shown on the drawings or as directed by the Contracting Officer, and shall conform to the detail of the drawings.

-- End of Section --

SECTION 02712A

LIME-MODIFIED SUBGRADE
12/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 25	(1999) Chemical Analysis of Limestone, Quicklime, and Hydrated Lime
ASTM C 50	(1994) Sampling, Inspection, Packing, and Marking of Lime and Limestone Products
ASTM C 110	(1995) Test Methods for Physical Testing of Quicklime, Hydrated Lime, and Limestone
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM D 422	(1963; R 1998) Particle-Size Analysis of Soils
ASTM D 1556	(1990; R 1996el) Density and Unit Weight of Soil in Place by the Sand-Cone Method
ASTM D 1557	(1998) Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/cu. ft. (2,700 kN-m/cu.m.))
ASTM D 1632	(1996) Making and Curing Soil-Cement Compression and Flexure Test Specimens in the Laboratory
ASTM D 1633	(1996) Compressive Strength of Molded Soil-Cement Cylinders
ASTM D 2167	(1994) Density and Unit Weight of Soil in

Place by the Rubber Balloon Method

ASTM D 2487	(1992) Classification of Soil for Engineering Purposes
ASTM D 2922	(1996el) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R 1996el) Water Content of Soil and Rock in Place By Nuclear Methods (Shallow Depth)
ASTM D 4318	(1998) Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM E 11	(1995) Wire-Cloth Sieves for Testing Purposes

1.2 DEFINITIONS

1.2.1 Lime-Modified Subgrade

Lime-Modified Subgrade, as used in this specification, is a mixture of lime and satisfactory in-place or select borrow material uniformly blended, wetted, and thoroughly compacted, and cured to produce a lime stabilized pavement subgrade which meets the criteria set forth in the plans and this specification.

1.2.2 Degree of Compaction

Degree of compaction required is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D 1557 abbreviated as percent laboratory maximum density.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Plant, Equipment, Machines, and Tools; G, RE

List of proposed equipment to be used in performance of construction work including descriptive data..

Waybills and Delivery Tickets; , RE

Copies of waybills and delivery tickets during the progress of

the work. Certified waybills and delivery tickets for all materials actually used.

SD-06 Test Reports

Sampling and Testing; G, RE
Field Density; G, RE

Calibration curves and related test results prior to using the device or equipment being calibrated. Copies of field test results within 24 hours after the tests are performed. Certified copies of test results of materials and sources not less than 30 days before material is required for the work.

SD-07 Certificates

Lime; G, GL

Source from which lime is to be obtained with certified mill test results showing the lime meets specified requirements.

1.4 JOB DESCRIPTION

The work specified consists of the construction of a lime-modified subgrade.

The work shall be performed in accordance with this specification and shall conform to the lines, grades, notes, and typical sections shown in the drawings. Sources of materials shall be selected well in advance of the time when materials will be required in the work. TEXT DELETED

1.5 PLANT, EQUIPMENT, MACHINES, AND TOOLS

1.5.1 General Requisites

Plant, equipment, machines, and tools used in the work shall be subject to approval and shall be maintained in satisfactory working condition at all times. Other compacting equipment may be used in lieu of that specified, where it can be demonstrated that the results are equivalent. Protective equipment, apparel, and barriers shall be provided to protect the eyes, respiratory system, and the skin of workers exposed to contact with lime dust or slurry.

1.5.2 Pulverizing/Mixing Equipment

The pulverizing and mixing equipment shall be self-propelled, four wheel drive and operated by a single operator. It shall be capable of pulverizing the soil in a single pass for the full depth to be modified, and for a width of at least 2.44 meters. The in-situ mixer shall be capable of uniformly blending and mixing the lime into the subgrade soil. The rotor shall be capable of up or down cutting. The rotor shall be equipped with tap-in, knock-out, bullet-type teeth.

1.5.3 Steel-Wheeled Rollers

Steel-wheeled rollers shall be the self-propelled type with a total weight

of not less than 9 metric tons, and a minimum weight of 135 kilograms per millimeter width of rear wheel. Wheels of the rollers shall be equipped with adjustable scrapers. The use of vibratory rollers is optional.

1.5.4 Pneumatic-Tired Rollers

Pneumatic-tired rollers shall have 4 or more tires, each loaded to a minimum of 13.6 metric tons and inflated to a minimum pressure of 1.035 MPa. The loading shall be equally distributed to all wheels, and the tires shall be uniformly inflated. Towing equipment shall also be pneumatic-tired.

1.5.5 Mechanical Spreader

Mechanical spreader shall be self-propelled or attached to a propelling unit capable of moving the spreader and material truck. The device shall be steerable and shall have variable speeds forward and reverse. The spreader and propelling unit shall be carried on tracks, rubber tires, or drum-type steel rollers that will not disturb the underlying material. The spreader shall contain a hopper, an adjustable screed, and outboard bumper rolls; and shall be designed to have a uniform, steady flow of material from the hopper. The spreader shall be capable of laying material without segregation across the full width of the lane to a uniform thickness and to a uniform loose density so that when compacted, the layer or layers shall conform to thickness and grade requirements indicated. The Contracting Officer may require a demonstration of the spreader prior to approving use in performance of the work.

1.5.6 Sprinkling Equipment

Sprinkling equipment shall consist of tank trucks, pressure distributors, or other approved equipment designed to apply controlled quantities of water uniformly over variable widths of surface.

1.5.7 Tampers

Tampers shall be of an approved mechanical type, operated by either pneumatic pressure or internal combustion, and shall have sufficient weight and striking power to produce the compaction required.

1.5.8 Straightedge

The Contractor shall furnish and maintain at the site, in good condition, one 3.66 meters straightedge for each bituminous paver, for use in the testing of the finished surface. Straightedge shall be made available for Government use. Straightedges shall be constructed of aluminum or other lightweight metal and shall have blades of box or box-girder cross section with flat bottom reinforced to insure rigidity and accuracy. Straightedges shall have handles to facilitate movement on pavement.

1.6 WEATHER LIMITATIONS

Work on the base course shall not be performed during freezing temperatures. When the temperature is below 5 degrees C, the completed

base course shall be protected against freezing by a sufficient covering of straw, or by other approved methods, until the course has dried out. Any areas of completed base course that are damaged by freezing, rainfall, or other weather conditions shall be brought to a satisfactory condition without additional cost to the Government. Lime shall not be applied when the atmospheric temperature is less than 5 degrees C. No lime shall be applied to soils that are frozen or contain frost, or when the underlying material is frozen. If the temperature falls below 2 degrees C, completed lime-treated areas shall be protected against any detrimental effects of freezing.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Lime

Lime shall be a standard brand of hydrated or granular quicklime conforming to the following physical and chemical requirements. Granulated quicklime shall be delivered to the jobsite as a slurry. If in the opinion of the Contracting Officer, the use of dry powder lime application causes a dust control concern, all lime applications shall be applied in slurry form.

2.1.1.1 Hydrated Lime

Hydrated lime for this purpose shall be a product consisting of hydrated lime and insoluble inert material and conforming to the following chemical composition and residue:

- a. Available Lime Index as Calcium Hydroxide, minimum 90%
- b. residue retained on a 600 um sieve, maximum 1%
- c. residue retained on a 75 um sieve, maximum 20%

2.1.1.2 Granular Quicklime

Granular quicklime is a calcined material, the major part of which is calcium oxide or calcium oxide in natural association with a lesser amount of magnesium oxide capable of slaking with water. This specification applies specifically to limes made from calcium-type limestones. When tested under the appropriate methods of test, the lime shall conform to the following requirements:

- a. Available Lime Index as Calcium Oxide (CaO): Not less than 90%
- b. Fineness (Dry Sieve):

Sieve Size

Percentage Retained

16 mm	0-5
425 um	75-100
75 um	85-100

- c. Residue after slaking (Wet Sieve):

Sieve Size

Percentage Retained

850 um

0-5

2.1.2 Material to be Modified

Material to be modified shall consist of satisfactory material. Satisfactory material shall be free of deleterious substances such as sticks, debris, organic matter, and stones greater than 75 mm in any dimension. At least 10 percent of the material shall pass the 0.425 mm sieve. Satisfactory material shall comprise any materials classified by ASTM D 2487 as GP, GM, SW, SM, ML, CL, or CH. Unsatisfactory materials shall comprise any materials classified by ASTM D 2487 as Pt, OH, OL, MH.

2.1.3 Water

Water shall be clean, fresh, and free from injurious amounts of oil, acid, salt, alkali, organic matter, and other substances deleterious to the lime or soil-lime mixture, and shall be subject to approval.

PART 3 EXECUTION

3.1 LIME STABILIZATION MIXTURE

The Contractor shall construct a working platform for new pavement construction by lime-modifying the subgrade soil. To accomplish this, the Contractor shall incorporate at least 5 percent hydrated lime by weight (based on oven-dry weight of the soil) or at least 3.8 percent granular quicklime by weight (based on the oven-dry weight of soil) to the minimum depth shown on the drawings below top of subgrade. The material to be stabilized shall be thoroughly pulverized and, when lime is applied in the dry state, the mix shall be thoroughly blended at a moisture content below optimum. After blending, water shall be blended into the dry mix in amounts necessary to bring the moisture content to optimum. Field moisture content shall be controlled within plus or minus 2 percent of optimum. When the modified subgrade is constructed in more than one layer, the previously constructed layer shall be cleaned of loose and foreign matter by sweeping with power sweeper or power brooms except that hand brooms may be used in areas where power cleaning is not practicable. Adequate drainage shall be provided during the entire construction period to prevent water from collecting or standing on the area to be stabilized or on pulverized, mixed, or partially mixed material. Line and grade stakes shall be provided as necessary for control. Grade stakes shall be in lines parallel to the centerline of the area under construction and suitably spaced for string lining.

3.2 PREPARATION OF AREA TO BE MODIFIED

After pavement and subgrade excavation, the area shall be cleaned of debris. The area will be inspected for adequate compaction and shall be capable of withstanding, without displacement, the compaction specified for the soil-lime mixture. Debris and removed unsatisfactory in-place material shall be disposed of as specified.

3.2.1 In-Place Material to be Modified

The entire area shall be graded to conform to the lines, grades, and cross sections shown in the plans prior to being processed. Soft, yielding areas and ruts or other irregularities in the surface shall be corrected. The material in the affected areas shall be loosened and unsatisfactory material removed. Approved select material shall be added where directed. The area shall then be shaped to line, grade, and cross section, and shall be compacted to the specified density.

3.2.2 Grade Control

Underlying material shall be excavated to sufficient depth for the required stabilized-course thickness so that the finished stabilized course with the subsequent surface course will meet the fixed grade. Finished and completed stabilized area shall conform to the lines, grades, cross section, and dimensions indicated.

3.3 INSTALLATION

3.3.1 Mixed In-Place Method

3.3.1.1 Scarifying and Pulverizing of Soil

Prior to application of lime, the soil shall be scarified and pulverized to a sufficient width and depth to obtain a uniform mixture of soil, lime and water, and to form a compacted lime-modified subgrade conforming to the cross section indicated. Scarification shall be controlled so that the layer beneath the layer to be treated is not disturbed. Depth of pulverizing shall not exceed the depth of scarification.

3.3.1.2 Application of Lime

Pulverized material shall be shaped to approximately the cross section indicated. Lime shall be applied so that when uniformly mixed with the soil, the specified lime content is obtained, and a sufficient quantity of lime-treated soil is produced to construct a compacted lime-treated course conforming to the lines, grades, and cross section indicated. Mechanical spreaders shall be used in applying bulk lime. Distributors shall be used in applying slurry. If lime is spread by hand, the bags shall be spotted accurately on the area being stabilized so that when the bags are opened the lime will be dumped and spread uniformly on the area being processed. No equipment except that used in spreading and mixing shall pass over the freshly applied lime.

3.3.1.3 Initial Mixing

Immediately after the lime has been distributed, the lime and soil shall be mixed. Initial mixing shall be sufficient to alleviate any dusting or wetting of the lime that might occur in the event of wind or rainstorms. This may be accomplished several days in advance of the final application and mixing.

3.3.1.4 Water Application and Moist Mixing

Moisture content of the mixture shall be determined in preparation for final mixing. Moisture in the mixture following final mixing shall not be less than the water content determined to be optimum based on dry weight of soil and shall not exceed the optimum water content by more than 2 percentage points. Water may be added in increments as large as the equipment will permit; however, such increment of water shall be partially incorporated in the mix to avoid concentration of water near the surface. After the last increment of water has been added, mixing shall be continued until the water is uniformly distributed throughout the full depth of the mixture, including satisfactory moisture distribution along the edges of the section.

3.3.2 Edges of Modified Course

Approved material shall be placed along the edges of the stabilized course in a quantity that will compact to the thickness of the course being constructed, or to the thickness of each layer in a multiple-layer course, allowing at least a 300 mm width of the shoulder to be rolled and compacted simultaneously with the rolling and compacting of each layer of the stabilized course.

3.3.3 Layer Thickness

After final mixing the material shall be compacted in lift thickness no more than 200 mm or less than 75 mm. If the minimum density cannot be obtained throughout the entire lift, the Contractor shall construct the lime modified subgrade course in two or more lifts.

3.3.4 Compaction

Before compaction operations are started and as a continuation of the mixing operation, the mixture shall be thoroughly loosened and pulverized to the full depth. Compaction shall be started immediately after mixing is completed. During final compaction, the surface shall be moistened, if necessary, and shaped to the required lines, grades, and cross section. Rolling shall begin at the outside edge of the surface and proceed to the center, overlapping on successive trips at least one-half the width of the roller. Alternate trips of the roller shall be slightly different lengths.

At all times, the speed of the roller shall not cause displacement of the mixture to occur. Areas inaccessible to the rollers shall be compacted with mechanical tampers, and shall be shaped and finished by hand methods.

3.3.4.1 Rigid Pavement Subgrade

Subgrade for portland cement concrete pavements (rigid pavements) shall be compacted to at least 90 percent of laboratory maximum density for the full depth of the lime modified subgrade course.

3.3.4.2 Bituminous Pavement Subgrade

Subgrade for bituminous pavements shall be compacted to at least 95 percent of laboratory maximum density for the full depth of the lime modified subgrade course.

3.3.5 Finishing

The surface of the top layer shall be finished to the grade and cross section shown. The surface shall be of uniform texture. Light blading during rolling may be necessary for the finished surface to conform to the lines, grades, and cross sections. If the surface for any reason becomes rough, corrugated, uneven in texture, or traffic-marked prior to completion, the unsatisfactory portions shall be scarified, reworked, relaid, or replaced as directed. If any portion of the course, when laid, becomes watersoaked for any reason, that portion shall be removed immediately, and the mix placed in a windrow and aerated until a moisture content within the limits specified is obtained; and then spread, shaped, and rolled as specified above.

3.3.6 Construction Joints

At the end of each phase of construction, a straight transverse construction joint shall be formed by cutting back into the completed work to form a true vertical face free of loose or shattered material. Material along construction joints not properly compacted shall be removed and replaced with soil-lime mixture that is mixed, moistened, and compacted as specified.

3.3.7 Curing and Protection

Immediately after the soil-lime area has been finished as specified above, the surface shall be protected against rapid drying for 7 days by moist curing. The modified subgrade shall be protected from freezing during the curing period.

3.3.7.1 Moist Curing

The area shall be moistened by sprinkling and shall be kept moist for the 7-day curing period.

3.4 SAMPLING AND TESTING

3.4.1 General Requirements

Sampling and testing shall be the responsibility of the Contractor, and shall be performed by an approved commercial testing laboratory or by facilities furnished by the Contractor. Work requiring testing will not be permitted until the facilities have been inspected and approved. The first inspection will be at the expense of the Government. Cost incurred for any subsequent inspection required because of failure of the facilities to pass the first inspection will be charged to the Contractor. Tests shall be performed in sufficient numbers and at the locations and times directed to ensure that materials and compaction meet specified requirements. Certified copies of the test results shall be furnished to the Contracting Officer.

3.4.2 Results

Results shall verify that the material complies with the specification. When deficiencies are found, the initial analysis shall be repeated and the material already placed shall be retested to determine the extent of unacceptable material. All in-place unacceptable material shall be replaced.

3.4.3 Sampling

Lime shall be sampled in accordance with ASTM C 50. During construction, no substitution shall be made in the materials, without retesting.

3.4.4 Sieve Analysis

Before starting work, one sample of material to be stabilized shall be tested in accordance with ASTM C 136 and ASTM D 422 on sieves conforming to ASTM E 11. After the initial test, a minimum of one analysis shall be performed for each 1000 metric tons of material placed, with a minimum of three analyses for each day's run until the course is completed.

3.4.5 Liquid Limit and Plasticity Index

One liquid limit and plasticity index shall be performed for each sieve analysis. Liquid limit and plasticity index shall be in accordance with ASTM D 4318.

3.4.6 Lime Source

The source of lime shall be designated by the Contractor. The Contractor shall furnish certified mill test reports at least 30 days prior to use in the construction. The certified mill test report shall show that the lime meets all requirements specified herein. Lime shall be tested for the specified chemical and physical requirements in accordance with ASTM C 25 and ASTM C 110.

3.4.7 Moisture-Density Determinations

Tests for determination of maximum density and optimum moisture shall be the responsibility of the Contractor in accordance with the requirements of ASTM D 1557. Samples shall be representative of the materials to be placed. An optimum moisture-density curve shall be obtained for each principal type of materials or combination of materials encountered or utilized. Results of these tests shall be the basis of control for compaction. The moisture-density determination, shall include test results on lime modified soil for Atterberg limits, grain size determinations, specific gravity.

3.4.8 Verification Testing

During construction of the lime-modified subgrade, the Contractor shall verify the application rate and depth of stabilization.

3.5 FIELD QUALITY CONTROL

Tests shall provide a moisture-density relationship for the lime-soil mixture. Results of field quality control testing shall verify that materials comply with this specification. When deficiencies are found, the initial analysis shall be repeated and the material already placed shall be retested to determine the extent of unacceptable material. All in-place unacceptable material shall be replaced or repaired, as directed by the Contracting Officer, at no additional cost to the Government.

3.5.1 Thickness Control

Completed thicknesses of the stabilized course shall be within 13 mm of the thickness indicated. Where the measured thickness of the stabilized course is more than 13 mm deficient, such areas shall be corrected by scarifying, adding mixture of proper gradation, reblading, and recompact as directed. Where the measured thickness of the stabilized course is more than 13 mm thicker than indicated, it shall be considered as conforming to the specified thickness requirement. Average job thickness shall be the average of all thickness measurements taken for the job, but shall be within 6 mm of the thickness indicated. Thickness of the stabilized course shall be measured at intervals which ensure one measurement for each 400 square meters of stabilized course. Measurements shall be made in 75 mm diameter test holes penetrating the stabilized course.

3.5.2 Field Density

Field in-place density shall be determined in accordance with ASTM D 1556, ASTM D 2167, or ASTM D 2922. When ASTM D 2922 is used, the calibration curves shall be checked, and adjusted if necessary, using the sand cone method as described in paragraph Calibration of the ASTM publication. ASTM D 2922 results in a wet unit weight of soil and when using this method, ASTM D 3017 shall be used to determine the moisture content of the soil. The calibration curves furnished with the moisture gauges shall be checked along with density calibration checks as described in ASTM D 3017. If ASTM D 2922 is used, in-place densities shall be checked by ASTM D 1556 at least once per lift for each 420 square meter of stabilized material. Calibration curves and calibration tests results shall be furnished to the Contracting Officer within 24 hours of conclusion of the tests. At least one field density test shall be performed for each 250 square meters of each layer of base material.

3.6 TRAFFIC

Completed portions of the lime-treated soil area may be opened immediately to light traffic provided the curing is not impaired. After the curing period has elapsed, completed areas may be opened to all traffic, provided the stabilized course has hardened sufficiently to prevent marring or distorting of the surface by equipment or traffic. Heavy equipment shall not be permitted on the area during the curing period. Lime and water may be hauled over the completed area with pneumatic-tired equipment if approved. Finished portions of lime-stabilized soil that are traveled on by equipment used in constructing an adjoining section shall be protected in a manner to prevent equipment from marring or damaging completed work.

3.7 MAINTENANCE

Stabilized area shall be maintained in a satisfactory condition until the completed work is accepted. Maintenance shall include immediate repairs of any defects and shall be repeated as often as necessary to keep the area intact. Defects shall be corrected as specified herein.

3.8 DISPOSAL OF UNSATISFACTORY MATERIALS

Removed in-place materials that are unsuitable for stabilization, material that is removed for the required correction of defective areas, waste material, and debris shall be disposed of as directed.

-- End of Section --

SECTION 02714A

DRAINAGE LAYER

07/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 29/C 29M	(1997) Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C 88	(1999a) Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C 117	(1995) Materials Finer Than 75 micrometer (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C 131	(1996) Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C 136	(1996a) Sieve Analysis of Fine and Coarse Aggregates
ASTM D 75	(1987; R 1997) Sampling Aggregates
ASTM D 2487	(2000) Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D 2922	(1996e1) Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
ASTM D 3017	(1988; R 1996e1) Water Content of Soil and Rock In Place by Nuclear Methods (Shallow Depth)
ASTM D 4791	(1999) Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate

ASTM E 548

(1994el) General Criteria Used for
Evaluating Laboratory Competence

1.2 SYSTEM DESCRIPTION

The Contractor shall build a graded aggregate drainage layer under the pavements and shoulders as indicated and specified.

1.2.1 Aggregate Drainage Layer

A drainage layer consisting of a graded aggregate rapid draining material (RDM) meeting the gradations of Table I.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Sampling and Testing; G, RE

Copies of field test results within 24 hours of completion of tests.

Approval of Materials; G, RE

Material sources and material test results prior to field use.

Evaluation; G, RE

Test section construction report.

1.4 FIELD COMPACTION

Field compaction requirements shall be based on the results of a test section constructed by the Contractor, using the materials, methods, and equipment proposed for use in the work. The test section shall meet the requirements of paragraph TEST SECTION.

1.5 EQUIPMENT

1.5.1 General Requirements

All plant, equipment, and tools used in the performance of the work will be subject to approval before the work is started and shall be maintained in satisfactory working condition at all times.

1.5.2 Placement Equipment

An asphalt paving machine shall be used to place drainage layer material. Alternate methods may be used if it can be demonstrated in the test section that these methods obtain the specified results.

1.5.3 Compaction Equipment

A dual or single smooth 10 ton (min.) vibratory drum roller which provides a maximum compactive effort without crushing the drainage layer aggregate shall be used to compact drainage layer material.

1.6 WEATHER LIMITATION

Drainage layer material shall be placed when the atmospheric temperature is above 2 degrees C . Areas of completed drainage layer or underlying courses that are damaged by freezing, rainfall, or other weather conditions or by contamination from sediments, dust, dirt, or foreign material shall be corrected by the Contractor to meet specified requirements.

1.7 SAMPLING AND TESTING

1.7.1 General Requirements

Sampling and testing shall be the responsibility of the Contractor. Sampling and testing shall be performed by an approved commercial testing laboratory, or by the Contractor subject to approval. If the Contractor elects to establish testing facilities of his own, approval of such facilities shall be based on compliance with ASTM E 548, and no work requiring testing will be permitted until the Contractor's facilities have been inspected and approved. The first inspection of the facilities will be at the expense of the Government and any subsequent inspections required because of failure of the first inspection shall be at the expense of the Contractor. Such costs will be deducted from the total amount due the Contractor. Drainage layer materials shall be tested to establish compliance with the specified requirements.

1.7.2 Sampling

Aggregate samples shall be taken in accordance with ASTM D 75.

1.7.3 Test Methods

1.7.3.1 Sieve Analyses

Sieve analyses shall be made in accordance with ASTM C 117 and ASTM C 136.

1.7.3.2 Density Tests

Field density tests for RDM drainage layers shall be made in accordance with ASTM D 2922 by Direct Transmission Method for the full depth of the lift. When using this method, ASTM D 3017 shall be used to determine the moisture content of the aggregate drainage layer material. The calibration

curves furnished with the moisture gauges shall be checked along with density calibration checks as described in ASTM D 3017. The calibration checks of both the density and moisture gauges shall be made by the prepared containers of material method, as described in paragraph "Calibration" of ASTM D 2922, on each different type of material being tested at the beginning of a job and at intervals as directed by the Contracting Officer.

1.7.3.3 Soundness Test

Soundness tests shall be made in accordance with ASTM C 88.

1.7.3.4 Los Angeles Abrasion Test

Los Angeles abrasion tests shall be made in accordance with ASTM C 131.

1.7.3.5 Flat or Elongated Particles Tests

Flat and/or elongated particles tests shall be made in accordance with ASTM D 4791.

1.7.3.6 Fractured Faces Tests

When aggregates are supplied from crushed gravel, approved test methods shall be used to assure the aggregate meets the requirements for fractured faces in paragraph AGGREGATES.

1.7.4 Initial Tests

One of each of the following tests shall be performed on the proposed material prior to commencing construction to demonstrate that the proposed material meets all specified requirements when furnished. If materials from more than one source are going to be utilized, this testing shall be completed for each source.

- a. Sieve Analysis including 0.02 mm size material.
- b. Flat and/or elongated particles
- c. Fractured Faces
- d. Los Angeles abrasion.
- e. Soundness.

1.7.5 Testing Frequency

1.7.5.1 Aggregate Drainage Layer

Sieve analysis, field density, and moisture content tests shall be performed at a rate of at least one test for every 1000 square meters, per lift, of completed area and not less than one test for each day's production. Sieve analyses shall be performed at a rate of at least one test for every 1000 square meters of completed area or fraction thereof.

Soundness tests, Los Angeles abrasion tests, fractured faces tests and flat and/or elongated particles tests shall be performed at the rate of one test for every 10,000 square meters of production, or fraction thereof.

1.7.6 Approval of Materials

1.7.6.1 Aggregate

The aggregate source shall be selected at least 60 days prior to field use in the test section. Tentative approval of the source will be based on certified test results to verify that materials proposed for use meet the contract requirements. Final approval of both the source and the material will be based on test section performance and tests for gradation, soundness, Los Angeles abrasion, flat and/or elongated particles tests and fractured faces tests. For aggregate drainage layer materials, these tests shall be performed on samples taken from the completed and compacted drainage layer course within the test section.

PART 2 PRODUCTS

2.1 AGGREGATES

Aggregates shall consist of clean, sound, hard, durable, angular particles of crushed stone, or crushed gravel which meet the specification requirements. The aggregates shall be free of silt and clay as defined by ASTM D 2487, vegetable matter, and other objectionable materials or coatings.

2.1.1 Aggregate Quality

The aggregate shall have a soundness loss not greater than 18 percent weighted average at 5 cycles when tested in magnesium sulfate in accordance with ASTM C 88. The aggregate shall have a percentage of loss on abrasion not to exceed 40 after 500 revolutions as determined by ASTM C 131. The percentage of flat and/or elongated particles shall be determined by ASTM D 4791 with the following modifications. The aggregates shall be separated into 2 size fractions. Particles greater than 12.5 mm sieve and particles passing the 12.5 mm sieve and retained on the 4.75 mm sieve. The percentage of flat and/or elongated particles in either fraction shall not exceed 20. A flat particle is one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3. When the aggregate is supplied from more than one source, aggregate from each source shall meet the specified requirements. When the aggregate is supplied from crushed gravel it shall be manufactured from gravel particles, 90 percent of which by weight are retained on the maximum-size sieve listed in TABLE I. In the portion retained on each sieve specified, the crushed gravel shall contain at least 90 percent by weight of crushed pieces having two or more freshly fractured faces with the area of each face being at least equal to 75 percent of the smallest midsectional area of the face. When two fractures are contiguous, the angle between planes of the fractures must be at least 30 degrees in order to count as 2 fractured faces.

2.1.2 Gradation Requirements

Drainage layer aggregates shall be well graded within the limits specified in TABLE I.

TABLE I. GRADATION OF DRAINAGE LAYER MATERIAL

Percentage by Weight Passing Square-Mesh Sieve

Sieve Designation	Rapid draining Material (RDM)
37.50 mm	100
25.00 mm	70-100
19.00 mm	55-100
12.50 mm	40-80
9.50 mm	30-65
4.75 mm	10-50
2.36 mm	0-25
1.18 mm	0-5

NOTE 1: The values are based on aggregates of uniform specific gravity, and the percentages passing the various sieves may require appropriate correction by the Contracting Officer when aggregates of varying specific gravities are used.

NOTE 2: For RDM, the coefficient of uniformity (CU) shall be greater than 3.5. (CU = D₆₀/D₁₀). The contractor is responsible for adjusting the RDM gradation within the ranges listed in Table I to provide a stable construction surface for the proposed equipment and method of transporting materials.

TEXT DELETED

PART 3 EXECUTION

3.1 STOCKPILING AGGREGATES

Aggregates shall be stockpiled at locations designated by the Contracting Officer. Stockpile areas shall be cleared and leveled prior to stockpiling aggregates. Aggregates shall be stockpiled to prevent segregation and contamination. Aggregates obtained from different sources shall be stockpiled separately.

3.2 TEST SECTION

3.2.1 Data

A test section shall be constructed to evaluate the ability to carry traffic, including placement of overlaying material and the constructability of the drainage layer including required mixing, placement, and compaction procedures. Test section data will be used by the Contracting Officer to validate the required number of compaction passes given in paragraph Compaction Requirements and the field dry density

requirements for full scale production.

3.2.2 Scheduling

The test section shall be constructed a minimum of 30 days prior to the start of full scale production to provide sufficient time for an evaluation of the proposed materials, equipment and procedures including Government QA testing.

3.2.3 Location and Size

The test section shall be placed inside the production paving limits. The underlying courses and subgrade preparation, required for the pavement section, shall be completed, inspected and approved in the test section prior to constructing the drainage layer. The test section shall be a minimum of 30 m long and two full paving lanes wide side by side.

3.2.4 Initial Testing

Certified test results, to verify that the materials proposed for use in the test section meet the contract requirements, shall be provided by the Contractor and approved by the Contracting Officer prior to the start of the test section.

3.2.5 Mixing, Placement, and Compaction

Mixing, placement, and compaction shall be accomplished using equipment meeting the requirements of paragraph EQUIPMENT. Compaction equipment speed shall be no greater than 2.4 km/hour. Compaction shall start from the outside edges of the paving lane and proceed to the centerline of the lift being placed. The roller shall stay a minimum of one half the roller width from the outside edge of the drainage layer being placed until the desired density is obtained. The outside edge shall then be rolled.

3.2.6 Procedure

3.2.6.1 RDM Aggregate Drainage Layer Tests

The test section shall be constructed with aggregate in a wet state so as to establish a correlation between number of roller passes and dry density achievable during field production. Three separate areas within the test section shall be designated, each area shall be tested for density, moisture, and gradation. All testing shall be completed in the middle third of the test section being placed. Density and moisture content tests shall be conducted in accordance with ASTM D 2922 and ASTM D 3017. Sieve analysis tests shall be conducted on samples, taken adjacent to the density test locations. One set of tests (i.e. density, moisture, and sieve analysis) shall be taken before the third compaction pass and after each subsequent compaction pass at three separate locations as directed by the Contracting Officer. A pass shall be considered the movement of a roller over the drainage layer area for one direction only. Compaction for the RDM shall consist of a maximum of 5 passes in the vibrating state and one final pass in the static state. Compaction passes and density readings shall continue until the difference between the average dry densities of

any two consecutive passes is less than or equal to 16 kg per cubic meter.

3.2.7 Evaluation

Within 10 days of completion of the test section, the Contractor shall submit to the Contracting Officer a Test Section Construction Report complete with all required test data and correlations. The Contracting Officer will evaluate the data and validate the required number of passes of the roller, the need for a final static pass of the roller, and provide the dry density for field density control during construction.

3.3 PREPARATION OF UNDERLYING COURSE

Prior to constructing the drainage layer, the underlying course shall be cleaned of all foreign materials. During construction, the underlying course shall contain no frozen material. The underlying course shall conform to Section 02721 SUBBASE COURSES. Ruts or soft yielding spots in the underlying courses having inadequate compaction and deviations of the surface from the requirements set forth herein shall be corrected by loosening and removing soft or unsatisfactory material and by adding approved material, reshaping to line, and grade, and recompacting to specified density. The finished underlying course shall not be disturbed by traffic or other operations and shall be maintained by the Contractor in a satisfactory condition until the drainage layer is placed.

3.4 TRANSPORTING MATERIAL

3.4.1 Aggregate Drainage Layer Material

Aggregate drainage layer material shall be transported to the site in a manner which prevents segregation and contamination of materials.

3.5 PLACING

3.5.1 General Requisites

Drainage layer material shall be placed on the underlying course in lifts of uniform thickness using equipment meeting the requirements of paragraph EQUIPMENT. When a compacted layer 150 mm or less in thickness is required, the material shall be placed in a single lift. When a compacted layer in excess of 150 mm is required, the material shall be placed in lifts of equal thickness. No lift shall exceed 150 mm or be less than 75 mm when compacted. The lifts when compacted after placement shall be true to the grades or levels required with the least possible surface disturbance. Where the drainage layer is placed in more than one lift, the previously constructed lift shall be cleaned of loose and foreign material.

Such adjustments in placing procedures or equipment shall be made to obtain true grades and minimize segregation and degradation of the drainage layer material.

3.5.2 Hand Spreading

In areas where machine spreading is impractical, drainage layer material shall be spread by hand. The material shall be spread uniformly in a loose

layer to prevent segregation. The material shall conform to the required grade and thickness after compaction.

3.6 COMPACTION REQUIREMENTS

Compaction shall be accomplished using rollers meeting the requirements of paragraph EQUIPMENT and operating at a rolling speed of no greater than 2.4 km per hour. Each lift of drainage material, including shoulders when specified under the shoulders, shall be compacted with the number of passes of the roller as follows: RDM material shall use 4 passes in the vibratory state and one in the static. The Contracting Officer will validate the number of roller passes after the test section is evaluated and before production starts. In addition, a minimum field dry density, as specified by the Contracting Officer, shall be maintained. If the required field dry density is not obtained, the number of roller passes shall be adjusted in accordance with paragraph DEFICIENCIES. Aggregate shall be compacted in a moisture state as determined in the test section. Excessive rolling resulting in crushing of aggregate particles shall be avoided. In all places not accessible to the rollers, the drainage layer material shall be compacted with mechanical hand operated tampers.

3.7 FINISHING

The top surface of the drainage layer shall be finished after final compaction as determined from the test section. Adjustments in rolling and finishing procedures shall be made to obtain grades and minimize segregation and degradation of the drainage layer material.

3.8 EDGES OF DRAINAGE LAYER

Shoulder material or subbase course material shall be placed along the edges of the drainage layer course in a quantity that will compact to the thickness of the layer being constructed. At least 10.3 m width of the shoulder shall be rolled and compacted simultaneously with the rolling and compacting of each lift of the drainage layer.

3.9 SMOOTHNESS TEST

The surface of the top lift shall not deviate more than 10 mm when tested with either a 3.66 m straightedge applied parallel with and at right angles to the centerline of the area to be paved. Deviations exceeding 10 mm shall be corrected in accordance with paragraph DEFICIENCIES.

3.10 THICKNESS CONTROL

The completed thickness of the drainage layer shall be within 13 mm of the thickness indicated. Thickness shall be measured at intervals providing at least one measurement for each 500 square meters of drainage layer. Measurements shall be made in test holes at least 75 mm in diameter. Where the measured thickness is more than 13 mm deficient, such areas shall be corrected in accordance with paragraph DEFICIENCIES. Where the measured thickness is 13 mm more than indicated, it will be considered as conforming to the requirements plus 13 mm, provided the surface of the drainage layer is within 13 mm of established grade. The average job

thickness shall be the average of all job measurements as specified above but within 8 mm of the thickness shown on the drawings.

3.11 DEFICIENCIES

3.11.1 Grade and Thickness

Deficiencies in grade and thickness shall be corrected so that both grade and thickness tolerances are met. Thin layers of material shall not be added to the top surface of the drainage layer to meet grade or increase thickness. If the elevation of the top of the drainage layer is more than 13 mm above the plan grade it shall be trimmed to grade and finished in accordance with paragraph FINISHING. If the elevation of the top surface of the drainage layer is 13 mm or more below the required grade, the surface of the drainage layer shall be scarified to a depth of at least 75 mm, new material shall be added, and the layer shall be blended and recompact to bring it to grade. Where the measured thickness of the drainage layer is more than 13 mm deficient, such areas shall be corrected by excavating to the required depth and replaced with new material to obtain a compacted lift thickness of at least 75 mm. The depth of required excavation shall be controlled to keep the final surface elevation within grade requirements and to preserve layer thicknesses of materials below the drainage layer.

3.11.2 Density

Density shall be considered deficient if the field dry density test results are below the dry density specified by the Contracting Officer. If the densities are deficient, the layer shall be rolled with 2 additional passes of the specified roller. If the dry density is still deficient, work will be stopped until the cause of the low dry densities can be determined and reported to the Contracting Officer.

3.11.3 Smoothness

Deficiencies in smoothness shall be corrected as if they are deficiencies in grade or thickness. All tolerances for grade and thickness shall be maintained while correcting smoothness deficiencies.

-- End of Section --

SECTION 04220A

NONBEARING MASONRY VENEER/STEEL STUD WALLS
01/02

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI Cold-Formed Manual	(1996) Cold-Formed Steel Design Manual
-------------------------	--

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 123/A 123M	(2001) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 153/A 153M	(2001) Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A 36/A 36M	(2000a) Carbon Structural Steel
ASTM A 572/A 572M	(2000a) High Strength Low-Alloy Columbiam-Vanadium Structural Steel
ASTM A 653/A 653M	(2000) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A 82	(1997a ¹) Steel Wire, Plain, for Concrete Reinforcement
ASTM A 992/A 992M	(2000) Steel for Structural Shapes For Use in Building Framing
ASTM C 1072	(2000) Measurement of Masonry Flexural Bond Strength
ASTM C 1177/C 1177M	(1999) Glass Mat Gypsum Substrate for Use as Sheathing
ASTM C 216	(2000) Facing Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C 270	(2000) Mortar for Unit Masonry

ASTM C 494/C 494M	(1999ae1) Chemical Admixtures for Concrete
ASTM C 578	(1995) Rigid, Cellular Polystyrene Thermal Insulation
ASTM C 591	(1994) Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C 665	(1998) Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
ASTM C 67	(2000) Sampling and Testing Brick and Structural Clay Tile
ASTM C 780	(2000) Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry
ASTM C 79/C 79M	(2000) Treated Core and Nontreated Core Gypsum Sheathing Board
ASTM C 91	(1999) Masonry Cement
ASTM C 954	(2000) Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
ASTM C 955	(2000a) Load-Bearing (Transverse and Axial) Steel Studs, Runners (Tracks), and Bracing or Bridging for Screw Application of Gypsum Panel Products and Metal Plaster Bases
ASTM D 1056	(2000) Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D 1330	(1985; R 1995e1) Rubber Sheet Gaskets
ASTM D 1667	(1997) Flexible Cellular Materials - Vinyl Chloride Polymers and Copolymers (Closed-Cell Foam)
ASTM D 2103	(1997) Polyethylene Film and Sheeting
ASTM D 226	(1997a) Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING

ENGINEERS (ASHRAE)

ASHRAE Handbook-IP (1997) Handbook, Fundamentals I-P Edition

AMERICAN WELDING SOCIETY (AWS)

AWS D1.3 (1998) Structural Welding Code - Sheet Steel

U.S. DEPARTMENT OF COMMERCE (DOC)

PS-1 (1995) Construction and Industrial Plywood

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G,NWO

Details of cold-formed steel framing and support around openings, including framing connections, steel lintels, attachment to other building elements and bridging. Drawings shall indicate thickness, material, dimensions, protective coatings, and section properties of all steel lintels used in exterior wall framing. Drawings shall also indicate size and type of all fasteners including size and type of all welds. If the Contractor opts to furnish inch-pound (IP) masonry products, drawings showing elevation of walls exposed to view and indicating the location of all cut masonry products shall be submitted for approval.

SD-04 Samples

Expansion Joint Materials; FIO
Clay or Shale Brick; G,RE

Sample Panel; G,RE

A portable panel, approximately 600 by 600 mm , containing approximately 24 brick facings to establish the range of color and texture. One of each type of masonry veneer anchor used.

SD-06 Test Reports

Masonry Veneer/Steel Stud Wall System; G,NWO

Calculations, including tabular data as necessary, demonstrating

the structural adequacy of the cold-formed steel framing system for the specified loadings and deflection criteria in accordance with the provisions of AISI-01 Test results demonstrating that the veneer anchors are structurally adequate to resist the specified loadings shall be submitted for approval.

Insulation, Vapor and Moisture Barrier; G,RE

Calculations demonstrating the insulation shown on the drawings provides the specified U-value for heat transmission of the completed exterior wall construction; this analysis shall be in accordance with ASHRAE Handbook-IP. Manufacturer's descriptive data and installation instructions for the insulation, the vapor barrier and the moisture barrier.

SD-07 Certificates

Clay or Shale Brick; FIO

Joint Reinforcement; FIO

Expansion Joint Materials; FIO

Insulation; FIO

Exterior Sheathing; FIO

Moisture Barrier; FIO

Vapor Retarder; FIO

Veneer Anchors; FIO

Welding; FIO

Certificates stating that the materials and welders meet the requirements specified. Each certificate shall be signed by an authorized certification official and shall include their organization and position and shall identify the products covered under their certifying signature.

1.3 SAMPLE PANEL

After the material samples are approved and prior to starting masonry work, a sample masonry panel shall be built on the project site where directed. The sample panel shall be not less than 1.8 m long by 1.2 m high. The panel shall be of typical wall thickness for the construction represented. The panel shall show color range, texture, bond pattern, expansion joints, and cleaning of the masonry as required in the work. The panel shall also show cold-formed steel framing, insulation, gypsum wallboard, gypsum sheathing, moisture barrier, vapor barrier, veneer anchors, joint reinforcement, flashing and weep holes. The approved sample panel shall be used as a standard of workmanship required in the actual installation. The sample panel shall be protected from weather and construction operations and shall not be removed until the masonry veneer/steel stud wall work has been completed and accepted.

1.4 DELIVERY, HANDLING AND STORAGE

Materials shall be delivered and handled avoiding chipping, breakage, bending or other damage, and contact with soil or other contaminating

materials. The masonry products shall be stored off the ground and protected from inclement weather. Cementitious materials shall be delivered in unopened containers plainly marked and labeled with manufacturer's names and brands. Cementitious materials shall be stored in dry, weather-tight enclosures or covers. Sand and other aggregates shall be stored preventing contamination or segregation and under a weather-tight covering permitting good air circulation. Finish of the framing members shall be maintained at all times, using an approved high zinc dust content galvanizing repair paint whenever necessary to prevent the formation of rust. Insulation, moisture barrier, and gypsum sheathing shall be stored in dry, well ventilated, weather-tight areas protected from sunlight and excessive heat. Air infiltration type vapor barrier shall be stored in accordance with the manufacturer's recommendations.

1.5 EFFLORESCENCE TESTS

Efflorescence tests shall be performed by an approved commercial testing laboratory. Sampling for the tests shall be the responsibility of the Contractor. Brick shall be sampled and tested for efflorescence in accordance with ASTM C 67 and the rating shall be: "not effloresced".

PART 2 PRODUCTS

2.1 VENEER WYTHE

The source of masonry materials which will affect the appearance of the finished work shall not be changed after the work has started except with the Contracting Officer's approval. The Contractor has the option to use either hard metric or substitute inch-pound (soft-metric) masonry products.

If the Contractor decides to substitute inch-pound masonry products, the following additional requirements shall be met:

- a. The dimensions indicated on the drawings shall not be altered to accommodate inch-pound masonry products either horizontally or vertically. The 100 mm building module shall be maintained, except for the actual physical size of the masonry products themselves.
- b. Mortar joint widths shall be maintained as specified.
- c. Masonry inch-pound products shall not be reduced in size by more than one-third ($1/3$) in height and one-half ($1/2$) in length. Masonry products shall not be cut at ends of walls, corners, and other openings.
- d. Cut, exposed masonry products shall be held to a minimum and shall be located where they will have the least impact on the aesthetics of the facility.
- e. Other building components built into the masonry products, such as window frames, door frames, louvers, fire dampers, etc., that are required to be metric, shall remain metric.

f. Additional metric guidance shall conform to Section 01415
METRIC MEASUREMENTS.

2.1.1 Clay or Shale Brick

Clay or shale brick veneer shall be masonry units conforming to ASTM C 216, Type FBS. Color range and texture shall be as indicated on drawings and shall conform to the approved sample to match adjacent Barracks and Soldier Community Center. Grade SW shall be used for all brickwork. Brick unit sizes shall be modular.

2.2 MORTAR

Mortar shall conform to ASTM C 270, Type S. Mortar mix shall be based on proportion specifications. Laboratory testing of mortar shall be in accordance with the preconstruction evaluation of mortar section of ASTM C 780. Cement shall have a low alkali content and be of one brand. Aggregates shall be from one source. Mortar shall have a minimum 28-day compressive strength of 12.4 MPa.

2.2.1 Masonry Cement

Masonry cement in conformance with ASTM C 91 may be used in the mortar. When using a masonry cement a comparative test shall be performed between a Portland cement-lime mortar and the masonry cement mortar proposed for the project to evaluate the ASTM C 1072 bond and the ASTM C 780 compressive strength of the two mixes. The test shall be conducted with the proposed masonry units for the project. The masonry cement mortar will be acceptable if the bond and compressive strength values are equal to or higher than the portland cement-lime mix. The air-content of the masonry cement shall be limited to 12 percent maximum.

2.2.2 Admixtures

In cold weather, a non-chloride based accelerating admixture may be used subject to approval. Accelerating admixtures shall be non-corrosive, contain less than 0.2 percent chlorides, and conform to ASTM C 494/C 494M, Type C.

2.3 JOINT REINFORCEMENT

Joint reinforcement shall be of steel wire conforming to ASTM A 82. Fabrication shall be by welding. Tack welding will not be permitted. Reinforcement shall be zinc-coated after fabrication in accordance with ASTM A 153/A 153M, Class B-2. Joint reinforcement shall consist of 2 continuous longitudinal wires in the veneer wythe. Minimum wire cross section shall be 11 square mm (0.017 square inches).

2.4 COLD-FORMED STEEL FRAMING

Cold-formed framing shall consist of steel studs, top and bottom tracks, runners, horizontal bridging, and other cold-formed members and other accessories. The cold-formed framing system shall be designed in accordance

with AISI-01. The steel studs and other cold-formed steel framing members within the wall shall be designed to resist the wind loadings given on the contract drawings. Wind loads shall be applied both inward and outward perpendicular to the wall system without exceeding AISI-01 allowable stresses and with deflection limited to $L/600$ times the vertical stud span.

All members and components made of sheet steel shall be hot-dip galvanized in accordance with ASTM A 653/A 653M with a minimum coating thickness of G 60. Framing covered herein shall be used only in framing the exterior masonry veneer steel stud wall system as indicated on the contract drawings. Metal framing for interior partitions are specified in Specification Section 09250 GYPSUM BOARD.

2.4.1 Steel Studs

Steel studs shall conform to ASTM A653/A653M, Grade 33, having a minimum yield strength of 230 MPa. Stud section properties shall be as required by the Contractor's design, but properties shall not be less than the following or as indicated on the contract drawings:

Base Metal Thickness	1.2mm (18 Gage)Minimum
Stud Depth	As indicated on the contract drawings
Flange Width	35mm
Return Lip	6mm
Maximum Stud Spacing	400mm

Section properties shall be as determined by AISI-01

2.4.2 Runners, Tracks, Bridging and Accessories

Cold-formed steel sheet framing members, components, and accessories, other than the steel studs, shall conform to ASTM C 955 and be of steel conforming to ASTM A 653/A 653M, Grade 33, having a minimum yield strength of 230 MPa.

2.5 INSULATION

The Contractor shall comply with EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

2.5.1 Blanket Insulation

Insulation placed between the steel studs shall be batt or blanket type mineral wool conforming to ASTM C 665, Type I.

2.5.2 Rigid Board-Type Insulation

Insulation for wall cavities shall be unfaced rigid board-type insulation. Rigid board-type insulation shall be either polystyrene conforming to ASTM C 578, Type I or II, Grade 2 or polyurethane conforming to ASTM C 591. Insulation thickness shall be sufficient to provide an R-value of 6.

2.6 GYPSUM WALLBOARD

Gypsum wallboard that is installed on the interior side of the cold-formed steel framing system shall be as specified in Section 09250 GYPSUM BOARD.

2.7 EXTERIOR SHEATHING

Gypsum or plywood sheathing that is installed on the exterior side of the cold-formed steel framing system shall have a minimum thickness of 13 mm and shall be 1.2 m wide. Gypsum sheathing shall conform to ASTM C 79/C 79M.

Gypsum sheathing shall have a water-resistant gypsum core with a water-repellent paper firmly bonded to the core.

2.8 MOISTURE PROTECTION

2.8.1 Moisture Barrier

Moisture barrier shall be a tear and puncture resistant olefin building wrap (polyethylene or polypropylene) with a moisture vapor transmission rate of 200 g per square meter per 24 hours in accordance with ASTM E 96, Desiccant Method B at 23 degrees C. Moisture barrier shall be Tyvek CommercialWrap or equivalent.

2.8.2 Vapor Retarder

The vapor retarder shall be polyethylene film conforming to ASTM D 2103, 0.15 mm (6 mil) minimum thickness.

2.8.3 Staples

Staples for attaching the moisture barrier to the exterior sheathing shall be the type and size best suited to provide a secure connection. Staples shall be made from either galvanized steel or stainless steel wire.

2.8.4 Joint Tape

Tape for sealing the joints in the vapor retarder shall be laminated tape with pressure sensitive adhesive as recommended by the manufacturer of the polyethylene film.

2.9 VENEER ANCHORS

Anchor assemblies for the attachment of the masonry veneer to the cold-formed steel framing and structural steel members shall be as shown on the contract drawings and as required by this specification. Anchors shall transfer the design loadings from the masonry veneer to the cold-formed steel framing system or other support without exceeding the allowable stresses and deflections in the anchors. Length of anchor wires shall be such that the outermost wires lie between 32 mm from each face of the masonry veneer. Anchor wires shall not have drips. Wires for veneer anchors shall be rectangular or triangular hoops formed from 5 mm diameter steel wire conforming to ASTM A 82. Anchor assemblies including wires and anchor plates shall be hot-dip galvanized conforming to ASTM A 153/A 153M,

Class B-2. The veneer anchor shall have a minimum capacity of 900 newtons. The load-displacement capacity of each veneer anchor, both in direct pull-out for tension and compression, shall be not less than 350 kilo newtons per meter (2000 pounds per inch) (or a deflection of 2.85 mm per kilo newton (0.05 inches per 100 pounds) of load in tension or compression). In the direction perpendicular to the masonry veneer, the anchor assembly shall have a maximum play of 1.6 mm. Veneer anchors shall be provided at 400mm maximum vertically and at each stud horizontally.

2.9.1 NOT USED 2.9.2 NOT USED 2.10 CONNECTIONS

Screws, bolts and anchors shall be hot-dip galvanized in accordance with ASTM A 123/A 123M or ASTM A 153/A 153M as appropriate.

2.10.1 Framing Screws, Bolts and Anchors

Screws, bolts and anchors used in the assembly of the cold-formed steel framing system shall be as required by the design of the framing system for the specified loadings, but not less than required by the contract drawings and by this specification. Screw, bolt and anchor sizes and locations shall be shown on the shop drawings.

2.10.2 Welding

Welded connections shall be designed and all welding shall be performed in accordance with AWS D1.3, as modified by AISI Cold-Formed Manual. Welders shall be qualified in accordance with AWS D1.3. All welds shall be cleaned and touched-up with zinc-rich paint.

2.10.3 Veneer Anchor Screws

Screws for attachment of the veneer anchors to the cold-formed steel framing members shall be as required by design to provide the needed pullout load capacity but not less than No. 12. Screws shall be shown on the shop drawings. The length of screws shall be such that the screws penetrate the holding member by not less than 16 mm.

2.10.4 Gypsum Sheathing Screws

Screws for attachment of gypsum sheathing to cold-formed steel framing shall conform to ASTM C 954.

2.11 SYNTHETIC RUBBER WASHERS

Synthetic rubber washers for placement between veneer anchors and the moisture barrier on the outside face of the exterior sheathing shall conform to ASTM D 1330, Grade I.

2.12 NOT USED 2.13 FLASHING

Copper or stainless steel flashing shall conform to the requirements in Specification Section 07600A SHEET METALWORK, GENERAL. Flashing shall be supplied in a continuous sheet extending from the exterior sheathing across the cavity and through the masonry veneer as shown.

2.14 STEEL LINTELS

Steel angles used for lintels shall conform to ASTM A 36/A 36M, ASTM A 572/A 572M, or ASTM A 992/A 992M. Lintels shall be provided as shown on the contract drawings and shall be hot-dip galvanized in accordance with ASTM A 123/A 123M.

2.15 CAULKING AND SEALANTS

Caulking and sealants shall be as specified in Specification Section 07900A JOINT SEALING.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Wall sections, types of construction and dimensions shall be as shown. Metal door and window frames and other special framing shall be built and anchored into the wall system as indicated.

3.2 STEEL STUD WALL FRAMING

The top track of the stud wall system shall be slip jointed to accommodate vertical deflections of the supporting members as shown on the contract drawings. Top and bottom tracks shall be anchored at each stud location as shown on the contract drawings. Both flanges of all steel studs shall be securely fastened with screws to the flanges of the top and bottom tracks as shown on the contract drawings. All details for affixing steel studs to runners and all other sheet steel framing members along with all details necessary for anchorage of the steel stud wall system to the building structural systems shall be submitted for approval. Horizontal bridging shall be provided as necessary. Studs shall be spaced as required to resist the specified design wind loadings, but not exceeding 400 mm on center. Coordinate stud spacing with sheathing, wall openings, and anchor requirements. At wall openings for doors, windows and other similar features, the framing system shall provide for the installation and anchorage of the required subframes or finish frames. Steel frames shall be securely attached through built-in anchors to the nearest stud on each side of the opening with self-drilling screws. Double studs shall be provided at both jambs of all door openings.

3.3 NOT USED3.4 INSULATION

The actual installed thickness of insulation shall provide a maximum thermal R of 19 for the completed exterior wall construction as determined in accordance with ASHRAE Handbook-IP. Insulation thickness shall be as shown on the approved drawings. Installation, except as otherwise specified or shown, shall be in accordance with the manufacturer's instructions which shall be approved by the Contracting Officer. Insulation shall be installed between wall framing members. Rigid insulation shall be installed in accordance with the manufacturer's instructions with proper connections through the insulation to prevent the insulation from carrying loads directly. Insulation with facings shall be

secured to the sides of the framing members to provide a continuous seal so that the entire weight of the insulation is carried by the framing members.

Where electrical outlets, ducts, pipes, vents or other utility items occur, insulation shall be placed on the dry side of the item away from excessive humidity.

3.5 GYPSUM WALLBOARD

Gypsum wallboard sheathing shall be installed on the interior face of the cold-formed steel framing system where required for architectural finish. Where interior sheathing is not required for architectural finish, sheathing may be installed as required to provide lateral support for compression flanges of studs under outward-acting wind loads. In lieu of interior sheathing where sheathing is not required for architectural finish, contractor may elect to provide lateral support for compression flanges of studs with bridging. Bridging may be omitted if calculations for the framing system show that it is not required. At locations where the cold-formed steel framing system fronts x-braced bays of the structural steel framing system, interior face sheathing shall not be provided and lateral support for steel stud compression flanges shall be provided solely by bridging as required. Installation of interior sheathing shall be as specified in Specification Section 09250 GYPSUM BOARD except at vertical slip joints, the gypsum wallboard shall be connected to the vertical studs to prevent movement at the slip joint.

3.6 EXTERIOR SHEATHING

Sheathing shall be installed on the exterior face of the cold-formed steel framing system with self-drilling screws. Screws shall be located a minimum of 10 mm from the ends and edges of sheathing panels and shall be spaced not more than 200 mm on each supporting member except at vertical slip joints, the sheathing shall be connected to the vertical studs to prevent movement of the slip joint. Edges and ends of gypsum sheathing panels shall be butted snugly with vertical joints staggered to provide full and even support for the moisture barrier. Holes and gaps resulting from abandoned screw installations, from damage to panels, and from cutting and fitting of panels at junctures with doors, windows, foundation walls, floor slabs and other similar locations shall be filled with exterior rubber-base caulk.

3.7 MOISTURE PROTECTION

3.7.1 Moisture Barrier

The asphalt-saturated felt or other approved moisture barrier shall be installed on the outer face of the exterior sheathing. The moisture barrier shall be installed horizontally and shingled with each sheet lapped not less than 150 mm over the sheet below. Vertical end joints shall be lapped not less than 150 mm and shall be staggered. Attachment of the moisture barrier shall be with staples spaced not greater than 400 mm on center or as required by the manufacturer.

3.7.2 Vapor Retarder

A vapor retarder shall be installed [between the steel studs and the gypsum wall board] [between the steel studs and the exterior sheathing]. The vapor retarder shall be installed in accordance with the manufacturer's recommendations to form a complete retarder to vapor infiltration. The joints shall be lapped and sealed with tape.

3.8 VENEER ANCHORS

Veneer anchors shall be attached with screws through the sheathing and rigid insulation to the steel studs or other support members at the locations shown. When rigid insulation is used, the method of connecting the veneer anchor through the insulation shall be approved by the Contracting Officer. Veneer anchors shall be installed with the outermost wires lying between 16 mm from each face of the masonry veneer. Synthetic rubber washers shall be used between the anchor connector plates and the moisture barrier. A clutch torque slip screw gun shall be used on screws attaching veneer anchors to cold-formed steel members. Veneer anchors with corrugated sheet metal or wire mesh members extending across the wall cavity shall not be used. Veneer anchors shall be provided at 400mm maximum vertically and at each stud horizontally.

3.9 FLASHING

Continuous flashing shall be provided at the bottom of the wall cavity just above grade. Flashing shall also be provided above and below openings at lintels and sills, and as indicated on the contract drawings. Flashing shall be as detailed and as specified in Specification Section 07600A SHEET METALWORK, GENERAL. Flashing shall be lapped a minimum of 150 mm at joints and shall be sealed with a mastic as recommended by the flashing manufacturer. Ends over doors, windows and openings shall be turned up and secured. Flashing shall be lapped under the moisture barrier a minimum of 150 mm and securely attached to the gypsum sheathing. Flashing shall extend through the exterior face of the masonry veneer and shall be turned down to form a drip.

3.10 MASONRY VENEER

Exterior masonry wythes shall be constructed to the thickness indicated on the contract drawings. A cavity consisting of a 50 mm minimum width air space will be provided between the moisture barrier and the masonry veneer.

Masonry veneer shall not be installed until the exterior sheathing, moisture barrier, veneer anchors and flashing have been installed on the cold-formed steel framing system. Extreme care shall be taken to avoid damage to the moisture barrier and flashing during construction of the masonry veneer. Any portion of the moisture barrier and flashing that is damaged shall be repaired or replaced prior to completion of the veneer. Masonry shall be laid in running bond pattern.. Longitudinal reinforcement consisting of 2 continuous galvanized steel wire shall be placed in the veneer wythe. The minimum wire size shall be 9 gauge. Vertical joints on alternating courses shall be aligned and kept vertically plumb. Solid masonry units shall be laid in a non-furrowed full bed of mortar, beveled and sloped toward the center of the wythe on which the mortar is placed. Units shall be shoved into place so that the vertical mortar joints are completely full and tight. Units that have been disturbed after the mortar

has stiffened shall be removed, cleaned and relaid. Mortar which protrudes more than 13 mm into the cavity space shall be removed. Means shall be provided to ensure that the cavity space is kept clean of mortar droppings and other loose debris. Chases and raked-out joints shall be kept free from mortar and debris. Faces of units used in finished exposed areas shall be free from chipped edges, material texture or color defects or other imperfections distracting from the appearance of the finished work.

3.10.1 Surface Preparation

Surfaces on which masonry is to be laid shall be cleaned of laitance or other foreign material. No units having a film of water shall be laid.

3.10.2 Hot Weather Construction

Temperatures of masonry units and mortar shall not be greater than 50 degrees C when laid. Masonry erected when the ambient air temperature is more than 37 degrees C in the shade and when the relative humidity is less than 50 percent shall be given protection from the direct exposure to wind and sun for 48 hours after the installation.

3.10.3 Cold Weather Construction

Temperatures of masonry units and mortar shall not be less than 4 degrees C when laid. When the ambient air temperature is 0 degrees C or less, masonry veneer under construction shall be protected and maintained at a temperature greater than 0 degrees C for a period of 48 hours after installation. The proposed method of maintaining the temperature within the specified range shall be submitted for approval prior to implementation. No units shall be laid on a surface having a film of frost or water.

3.10.4 Tolerances

Masonry shall be laid plumb, level and true to line within the tolerances specified in TABLE 1. All masonry corners shall be square unless otherwise indicated on the drawings.

TABLE 1

Variation From Plumb

In adjacent units	3 mm
In 3 m	6 mm
In 6 m	10 mm
In 12 m or more	13 mm

Variation From Level Or Grades

In 3 m	3 mm
In 6 m	6 mm

In 12 m or more	13 mm
-----------------	-------

Variation From Linear Building Lines

In 6 m	13 mm
In 12 m or more	19 mm

Variation From Cross Sectional Dimensions Of Walls

Plus	13 mm
Minus	6 mm

3.10.5 Mixing of Mortar

Mortar shall be mixed in a mechanically operated mortar mixer for at least 3 minutes but not more than 5 minutes. Measurement of ingredients for mortar shall be by volume. Measurement of sand shall be accomplished by the use of a container of known capacity or shovel count based on a container of known capacity. Water shall be mixed with the dry ingredients in sufficient amount to provide a workable mixture which will adhere to the vertical surfaces of the masonry units. Mortar that has stiffened because of loss of water through evaporation shall be rettempered by adding water to restore the proper consistency and workability. Mortar that has reached its initial set or that has not been used within 2-1/2 hours shall be discarded.

3.10.6 Cutting and Fitting

Wherever possible, full units shall be used in lieu of cut units. Where cut units are required to accommodate the design, cutting shall be done by masonry mechanics using power masonry saws. Wet-cut units shall be dried to the same surface-dry appearances of uncut units before being placed in the work. Cut edges shall be clean, true and sharp. Openings to accommodate pipes, conduits, and other accessories shall be neatly formed so that framing or escutcheons required will completely conceal the cut edges. Insofar as practicable, all cutting and fitting shall be accomplished while masonry work is being erected.

3.10.7 Masonry Units

When being laid, masonry units shall have suction sufficient to hold the mortar and to absorb water from the mortar, but shall be damp enough to allow the mortar to remain in a plastic state to permit the unit to be leveled and plumbed immediately after being laid without destroying bond. Masonry units with frogging shall be laid with the frog side down and better or face side exposed to view. Masonry units that are cored, recessed or otherwise deformed may be used in sills or in other areas except where deformations will be exposed to view.

3.10.8 Mortar Joints

Mortar joint widths shall be uniform and such that the specified widths are

maintained throughout. Joints shall be of thickness equal to the difference between the actual and nominal dimensions of the masonry units in either height or length but in no case shall the joints be less than 6 mm nor more than 13 mm wide. Joints shall be tooled slightly concave. Tooling shall be accomplished when mortar is thumbprint hard and in a manner that will compress and seal the mortar joint and produce joints of straight and true lines free of tool marks.

3.10.9 Joint Reinforcement

Unless otherwise shown, joint reinforcement shall be spaced at 400 mm on center vertically. Joint reinforcement shall not be placed in the same masonry course as veneer anchors. Longitudinal wires shall be fully embedded in mortar for their entire length. Splices in joint reinforcement shall be lapped a minimum of 150 mm. Joint reinforcement must be discontinuous at all veneer expansion joints. The minimum cover for joint reinforcement is 16 mm.

3.10.10 Veneer Expansion Joints

Brick expansion joints shall be provided at the locations shown on the drawings. Details of joints shall be as indicated on the drawings. Joints shall be clean and free of mortar and shall contain only backer rod and sealant, installed in accordance with Specification Section 07900A JOINT SEALING. Horizontal reinforcement shall not extend through the joints.

3.10.11 Weep Holes

Weep holes shall be provided at all flashing locations at intervals of 600 mm. Weep holes shall be placed in head joints just above the flashing. Weep holes shall be formed by leaving head joints open or head joint vents may be used. Weep holes shall be kept free of mortar and other obstructions.

3.10.12 Head Joint Vents

Head joint vents shall be provided near the top of the veneer wythe at the same spacing as the weep holes.

3.10.13 Discontinuous Work

When necessary to temporarily discontinue the work, masonry shall be stepped back for joining when work resumes. Tothing may be used only when specifically approved. Before resuming work, loose mortar shall be removed and the exposed joint shall be thoroughly cleaned. Top of walls subjected to rain or snow shall be covered with nonstaining waterproof covering or membrane when work is not in process. Covering shall extend a minimum of 600 mm down on each side of the wall and shall be held securely in place.

3.10.14 Cleaning

Mortar daubs or splashings shall be completely removed from finished exposed masonry surfaces before they harden or set up. Before completion of the work, defects in mortar joints shall be raked out as necessary,

filled with mortar, and tooled to match the adjacent existing mortar in the joints. The proposed cleaning method shall be done on the sample wall panel and the sample panel shall be examined for discoloration or stain. If the sample panel is discolored or stained, the method of cleaning shall be changed to ensure that the masonry surfaces in the structure will not be adversely affected. Masonry surfaces shall not be cleaned, other than removing excess surface mortar, until mortar in joints has hardened. Cleaning shall be accomplished with the use of stiff bristle fiber brushes, wooden paddles, wooden scrapers, or other suitable nonmetallic tools. The exposed brick surfaces shall be saturated with water and cleaned with a proprietary brick cleaning agent recommended by the clay products manufacturer. The cleaning agent shall not adversely affect the brick masonry surfaces. Proprietary cleaning agents shall be used in conformance with the cleaning product manufacturer's printed recommendations.] Efflorescence or other stains shall be removed in conformance with the recommendations of the masonry unit manufacturer. After construction and cleaning, masonry surfaces shall be left clean, free of mortar daubs, stain, and discolorations, including scum from cleaning operations, and will have tight mortar joints throughout. Metallic tools and brushes shall not be used for cleaning.

3.11 NOT USED

-- End of Section --

SECTION 06100A

ROUGH CARPENTRY
10/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)

AF&PA T101 (1997) National Design Specification for
Wood Construction

AF&PA T11 (1988) Manual for Wood Frame Construction

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA A135.4 (1995) Basic Hardboard

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

AITC TC Manual (1994) Timber Construction Manual

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A208.1 (1999) Particleboard Mat Formed Woods

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 79/C 79M (2000) Treated Core and Nontreated Core
Gypsum Sheathing Board

ASTM C 208 (1995) Cellulosic Fiber Insulating Board

ASTM C 516 (1980; R 1996e1) Vermiculite Loose Fill
Thermal Insulation

ASTM C 518 (1998) Steady-State Heat Flux Measurements
and Thermal Transmission Properties By
Means of the Heat Flow Meter Apparatus

ASTM C 552	(2000) Cellular Glass Thermal Insulation
ASTM C 553	(1999) Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
ASTM C 578	(1995) Rigid, Cellular Polystyrene Thermal Insulation
ASTM C 591	(1994) Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C 612	(2000) Mineral Fiber Block and Board Thermal Insulation
ASTM C 726	(2000) Mineral Fiber Roof Insulation Board
ASTM C 739	(2000) Cellulosic Fiber (Wood-Base) Loose-Fill Thermal Insulation
ASTM C 764	(1999) Mineral Fiber Loose-Fill Thermal Insulation
ASTM C 1136	(1995) Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C 1177/C 1177M	(1999) Glass Mat Gypsum Substrate for Use as Sheathing
ASTM C 1289	(1998) Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
ASTM D 2898	(1994; R 1999) Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing
ASTM D 3498	(1999) Standard Specification for Adhesives for Field-Gluing Plywood to Lumber Framing for Floor Systems
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials
ASTM E 96	(2000) Water Vapor Transmission of Materials
ASTM E 154	(1988; R 1999) Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover

ASTM F 547 (1977; R 1995) Definitions of Terms
Relating to Nails for Use with Wood and
Wood-Base Materials

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

AWPA C9 (1997) Plywood - Preservative Treatment by
Pressure Processes

AWPA C20 (1999) Structural Lumber Fire-Retardant
Pressure Treatment

AWPA C27 (1999) Plywood - Fire-Retardant Pressure
Treatment

AWPA M4 (1999) Standard for the Care of
Preservative-Treated Wood Products

AWPA P5 (2000) Standards for Waterborne
Preservatives

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1209 Interim Safety Standard for Cellulose
Insulation

U.S. DEPARTMENT OF COMMERCE (DOC)

PS-1 (1996) Voluntary Product Standard -
Construction and Industrial Plywood

FACTORY MUTUAL ENGINEERING AND RESEARCH (FM)

FM LPD 1-49 (1995) Loss Prevention Data Sheet -
Perimeter Flashing

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

NHLA Rules (1994) Rules for the Measurement &
Inspection of Hardwood & Cypress

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules (1997) Standard Grading Rules for
Northeastern Lumber

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

SCMA Specs (1986; Supple No. 1, Aug 1993) Standard Specifications for Grades of Southern Cypress

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB Rules (1994; Supple 8 thru 11) Standard Grading Rules for Southern Pine Lumber

TRUSS PLATE INSTITUTE (TPI)

TPI 1 (1995; Errata) National Design Standard for Metal Plate-Connected Wood Truss Construction and Commentary; and Appendix 1

TPI HIB (1991) Handling, Installing & Bracing Metal Plate Connected Wood Trusses

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (1996; Supples VII(A-E), VIII(A-C)) Grading Rules for West Coast Lumber

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA Grading Rules (1999) Western Lumber Grading Rules 95

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Structural Wood Members; G, NWO, Installation of Framing.

Drawings of prefabricated wood trusses indicating materials, shop fabrication, and field erection details; including methods of fastening.

Nailers and Nailing Strips; G, RE,

Drawings of field erection details, including materials and methods of fastening nailers in conformance with Factory Mutual wind uplift rated systems specified in other Sections of these specifications.

SD-03 Product Data

Structural Wood Members; G, NWO

Design analysis and calculations of prefabricated wood trusses showing design criteria used to accomplish the applicable analysis.

Product Installations; G, NWO

List containing name and location of successful installation of similar type of prefabricated wood trusses specified herein.

SD-07 Certificates

Grading and Marking; G, RE,

Manufacturer's certificates (approved by an American Lumber Standards approved agency) attesting that lumber and material not normally grade marked meet the specified requirements. Certificate of Inspection for grade marked material by an American Lumber Standards Committee (ALSC) recognized inspection agency prior to shipment.

Insulation; G, RE,

Certificate attesting that the cellulose, perlite, glass and mineral fiber, glass mat gypsum roof board, polyurethane, or polyisocyanurate insulation furnished for the project contains recovered material, and showing an estimated percent of such recovered material.

1.3 DELIVERY AND STORAGE

Materials shall be delivered to the site in undamaged condition, stored off ground in fully covered, well ventilated areas, and protected from extreme changes in temperature and humidity.

PART 2 PRODUCTS

2.1 LUMBER AND SHEATHING

2.1.1 Grading and Marking

2.1.1.1 Lumber Products

Solid sawn and finger-jointed lumber shall bear an authorized gradestamp or grademark recognized by ALSC, or an ALSC recognized certification stamp, mark, or hammerbrand. Surfaces that are to be exposed to view shall not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

2.1.1.2 Fabricated Structural Members

Prefabricated wood trusses shall be fabricated in accordance with TPI 1.

2.1.1.3 Plywood and Other Sheathing Products

Materials shall bear the grademark or other identifying marks indicating grades of material and rules or standards under which produced, including requirements for qualifications and authority of the inspection organization. Except for plywood and wood structural panels, bundle marking will be permitted in lieu of marking each individual piece. Surfaces that are to be exposed to view, other than the Barracks attic area, shall not bear grademarks or other types of identifying marks.

2.1.2 Sizes

Lumber and material sizes shall conform to requirements of the rules or standards under which produced. Unless otherwise specified, lumber shall be surfaced on four sides. Unless otherwise specified, sizes indicated are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced.

2.1.3 Treatment

Exposed areas of treated wood that are cut or drilled after treatment shall receive a field treatment in accordance with AWPA M4. Items of all-heart material of cedar, cypress, or redwood will not require preservative treatment, except when in direct contact with soil. Except as specified for all-heart material of the previously mentioned species, the following items shall be treated:

- a. Wood members in contact with or within 455 mm of soil.
- b. Wood members in contact with water.
- c. Wood members exposed to the weather including those used in builtup roofing systems or as nailing strips or nailers over fiberboard or gypsum-board wall sheathing as a base for wood siding.
- d. Wood members set into concrete regardless of location, including flush-with-deck wood nailers for roofs.
- e. Wood members in contact with concrete that is in contact with soil or water or that is exposed to weather.

2.1.3.1 Lumber and Timbers

Lumber and timbers shall be treated in accordance with AWPA C2 with waterborne preservatives listed in AWPA P5 to a retention level as follows:

- a. 4 kg per cubic meter (0.25 pcf) intended for above ground use.
- b. 6.4 kg per cubic meter (0.40 pcf) intended for ground contact and fresh water use.

2.1.3.2 Plywood

Plywood shall be treated in accordance with AWPA C9 with waterborne preservatives listed in AWPA P5 to a retention level as follows:

- a. 4 kg per cubic meter (0.25 pcf) intended for above ground use.
- b. 6.4 kg per cubic meter (0.40 pcf) intended for ground contact and fresh water use.

2.1.4 Moisture Content

At the time lumber and other materials are delivered and when installed in the work their moisture content shall be as follows:

- a. Treated and Untreated Lumber Except Roof Planking: 100 mm or less, nominal thickness, 19 percent maximum. 125 mm or more, nominal thickness, 23 percent maximum in a 75 mm perimeter of the timber cross-section.
- b. Roof Planking: 15 percent maximum.
- c. Materials Other Than Lumber: In accordance with standard under which product is produced.

2.1.5 Fire-Retardant Treatment

Fire-retardant treated wood shall be pressure treated in accordance with AWPA C20 for lumber and AWPA C27 for plywood. Material use shall be defined in AWPA C20 and AWPA C27 for Interior Type A and B and Exterior Type. Treatment and performance inspection shall be by an independent and qualified testing agency that establishes performance ratings. Each piece or bundle of treated material shall bear identification of the testing agency to indicate performance in accordance with such rating. Treated materials to be exposed to rain wetting shall be subjected to an accelerated weathering technique in accordance with ASTM D 2898 prior to being tested for compliance with AWPA C20 or AWPA C27.

2.1.6 Structural Wood Members

Species and grades shall be as listed in AF&PA T01. Structural lumber used in prefabricated trusses and other fabricated structural members for engineered uses shall have allowable design values of 5.52 MPa in bending (single-member uses); 6.38 MPa (repetitive-member uses); 3.28 MPa in tension parallel to the grain; 4.31 MPa in compression perpendicular to the grain; 4.14 MPa in compression parallel to the grain; 0.66 MPa in horizontal shear; and a modulus of elasticity of 10343 MPa. Design of members and fastenings shall conform to AITC TC Manual. Other stress graded or dimensioned items such as blocking, carriages, and studs shall be standard or No. 2 grade except that studs may be stud grade.

2.1.7 Sheathing

Sheathing shall be gypsum board, or plywood, for wall sheathing as indicated in Section 04220 NONBEARING MASONRY VEENER/STUD WALLS; and plywood for roof sheathing.

2.1.7.1 Plywood

Plywood shall conform to PS-1, APA PRP-108 or PS-2, Grade C-D or sheathing grade with exterior glue. Sheathing for walls shall have a span rating of 32/16 or greater. Sheathing for roofs shall have a span rating of 32/16 or greater, except that sheathing for the Barracks roof shall have minimum span ratings as indicated on the contract drawings.

2.1.7.2 [Enter Appropriate Subpart Title Here]

2.1.8 [Enter Appropriate Subpart Title Here]

2.1.9 Miscellaneous Wood Members

2.1.9.1 Nonstress Graded Members

Members shall include bridging, corner bracing, furring, grounds, and nailing strips. Members shall be in accordance with TABLE I for the species used. Sizes shall be as follows unless otherwise shown:

Member	Size mm (inch)
Bridging	25 x 75 (1 x 3) or 25 x 100 (1 x 4) for use between members 50 x 300 (2 x 12) and smaller; 50 x 100 (2 x 4) for use between members larger than 50 x 300 (2 x 12).
Corner bracing	25 x 100 (1 x 4).
Furring	25 (1) x 50 (2) 75 (3)
Grounds	Plaster thickness by 38.
Nailing strips	25 x 75 (1 x 3) or 25 x 100 (1 x 4) when used for interior finish; otherwise 50 mm (2 inch) stock for roofing (SCB).

2.1.9.2 [Enter Appropriate Subpart Title Here]

2.1.9.3 Sill Plates

Sill plates shall be standard or number 2 grade.

2.1.9.4 Blocking

Blocking shall be standard or number 2 grade.

2.1.9.5 Rough Bucks and Frames

Rough bucks and frames shall be straight standard or number 2 grade.

2.2 ACCESSORIES AND NAILS

Markings shall identify both the strength grade and the manufacturer.

Accessories and nails shall conform to the following:

2.2.1 [Enter Appropriate Subpart Title Here]

2.2.2 Bolts: Lag, Toggle, and Miscellaneous Bolts and Screws

Type, size, and finish best suited for intended use. Finish options include zinc compounds, cadmium, and aluminum paint impregnated finishes.

2.2.3 Clip Angles

Steel, 5 mm (3/16 inch) thick, size best suited for intended use; or zinc-coated steel or iron commercial clips designed for connecting wood members.

2.2.4 Expansion Anchors

Type and size as indicated on the contract drawings.

2.2.5 [Enter Appropriate Subpart Title Here]

2.2.6 Metal Bridging

Optional to wood bridging; zinc-coated steel, size and design to provide rigidity equivalent to specified wood bridging.

2.2.7 Nails and Staples

ASTM F 547, size and type best suited for purpose; staples shall be as recommended by the manufacturer of the materials to be joined. For sheathing, length of nails shall be sufficient to extend 25 mm into supports. In general, 8-penny or larger nails shall be used for nailing through 25 mm thick lumber and for toe nailing 50 mm thick lumber; 16-penny or larger nails shall be used for nailing through 50 mm thick lumber. Nails used with treated lumber and sheathing shall be galvanized. Nailing shall be in accordance with the recommended nailing schedule contained in AF&PA T11. Where detailed nailing requirements are not specified, nail size and spacing shall be sufficient to develop an adequate strength for the connection. The connection's strength shall be verified against the nail capacity tables in AF&PA T01. Reasonable judgement backed by experience shall ensure that the designed connection will not cause the wood to split. If a load situation exceeds a reasonable limit for nails, a specialized connector shall be used.

2.2.8 Timber Connectors

Unless otherwise specified, timber connectors shall be in accordance with TPI 1, APA EWS T300C or AITC TC Manual.

2.3 INSULATION

Thermal resistance of insulation shall be not less than the R-values shown.

Contractor shall comply with EPA requirements in conformance with Section 01670 RECYCLED / RECOVERED MATERIALS. Insulation shall be the standard product of a manufacturer and factory marked or identified with

manufacturer's name or trademark and R-value. Identification shall be on individual pieces or individual packages. Materials containing more than one percent asbestos will not be allowed.

2.3.1 Batt or Blanket

(Exterior Walls: Section 04220 NONBEARING MASONRY VENEER/STEEL STUD WALLS, para.2.5.1)

2.3.1.1 Glass Fiber Batts and Rolls

Glass fiber batts and rolls shall conform to ASTM C 665, Type I unfaced insulation and Type II kraft faced insulation. Insulation shall have a 0.25 mm (10 mil) thick, white, puncture resistant woven-glass cloth with vinyl facing on one side. Width and length shall suit construction conditions.

2.3.1.2 Mineral Fiber Batt

Mineral fiber batt shall conform to ASTM C 665, Type I unfaced insulation and Type II kraft faced insulation, Class C.

2.3.1.3 Mineral Fiber Blanket

Mineral fiber blanket shall conform to ASTM C 553, Type I, Class 6. Blankets shall be sized to suit construction conditions, resilient type for use below and above ambient temperature to 195 degrees C. Blankets shall have a factory applied vapor-barrier facing on one side with 50 mm nailing tabs on both edges. Vapor barriers shall be fire retardant, high vapor transmission, and aluminum foil laminated to crepe paper type conforming to ASTM C 1136, Type II. Nominal density shall be 12 kg per cubic meter.

2.3.2 Loose Fill or Granular Fill

2.3.2.1 Mineral Fiber (Attic)

Mineral fiber shall conform to ASTM C 764, Type I. Blown-in mineral fiber insulation shall conform to ASTM C 764, Type I, Category 1, one percent or less loss on ignition.

2.3.3 Sill Sealer

Mineral wool, 25 mm thick and compressible to 0.8 mm, width of sill, designed to perform as an air, dirt, and insect seal in conformance with ASTM C 665, Type I.

2.3.4 Rigid Insulation

2.3.4.1 Polystyrene Board

Polystyrene board shall be extruded and conform to ASTM C 578, Type IV.

2.3.4.2 Polyurethane or Polyisocyanurate Board

Polyurethane or polyisocyanurate board shall have a minimum recovered material content of 9 percent by weight of core material in the polyurethane or polyisocyanurate portion. Unfaced preformed polyurethane shall conform to ASTM C 591. Faced polyisocyanurate shall conform to ASTM C 1289.

2.4 VAPOR RETARDER

Vapor retarder shall be polyethylene sheeting conforming to ASTM E 154 or other equivalent material. Vapor retarder shall have a maximum vapor permeance rating of 29 ng per Pa per second per square meter (0.5 perms) as determined in accordance with ASTM E 96, unless otherwise specified.

2.5 MOISTURE BARRIER

Moisture barrier shall be a tear and puncture resistant olefin building wrap (polyethylene or polypropylene) with a moisture vapor transmission rate of 200 g per square meter per 24 hours in accordance with ASTM E 96, Desiccant Method B at 23 degrees C. Moisture barrier shall be Tyvek CommercialWrap or equivalent.

PART 3 EXECUTION

3.1 INSTALLATION OF FRAMING

3.1.1 General

General framing shall be in accordance with AF&PA T11. Members shall be closely fitted, accurately set to required lines and levels, and rigidly secured in place. Members shall be framed for passage of ducts. Members shall be cut, notched, or bored in accordance with applicable requirements of AF&PA T01 for the passage of pipes, wires, or conduits.

3.1.2 Structural Members

Members shall be adequately braced before erection. Members shall be aligned and all connections completed before removal of bracing. Individually wrapped members shall be unwrapped only after adequate protection by a roof or other cover has been provided. Scratches and abrasions of factory-applied sealer shall be treated with two brush coats of the same sealer used at the factory.

3.1.3 Partition and Wall Framing

Unless otherwise shown, studs shall be spaced 400 maximum on centers. Studs shall be doubled at openings. Unless otherwise indicated, headers for openings shall be made of two pieces of stud material set on edge or solid lumber of equivalent size. Plates of partitions resting on concrete floors shall be anchored in place with expansion anchors and powder-driven fasteners as indicated on the contract drawings. Walls and load bearing

partitions shall be provided with double top plates with members lapped at least 600 mm and well spiked together.

3.1.4 [Enter Appropriate Subpart Title Here]

3.2 INSTALLATION OF SHEATHING

3.2.1 Plywood Panels

Sheathing shall be applied with edges 3 mm apart at side and end joints, and nailed at supported edges at 150 mm on center and at intermediate supports 300 mm on center unless otherwise shown. Nailing of edges shall be 9.5 mm from the edges. Wall sheathing shall extend over top and bottom plates, and if applied horizontally the vertical joints shall be made over supports and staggered. Roof sheathing shall be applied with long dimension at right angles to supports, end joints made over supports, and end joints staggered.

3.2.2 [Enter Appropriate Subpart Title Here]

3.3 [Enter Appropriate Subpart Title Here]

3.4 INSTALLATION OF MISCELLANEOUS WOOD MEMBERS

3.4.1 Bridging

Wood bridging shall have ends accurately bevel-cut to afford firm contact and shall be nailed at each end with two nails. Metal bridging shall be installed as recommended by the manufacturer. The lower ends of bridging shall be driven up tight and secured after subflooring or roof sheathing has been laid and partition framing installed.

3.4.2 Corner Bracing

Corner bracing shall be installed when required by type of sheathing used or when siding, other than panel siding, is applied directly to studs. Corner bracing shall be let into the exterior surfaces of the studs at an angle of approximately 45 degrees, shall extend completely over wall plates, and shall be secured at each bearing with two nails.

3.4.3 Blocking

Blocking shall be provided as necessary for application of siding, sheathing, wallboard, and other materials or building items, and to provide firestopping. Blocking for firestopping shall ensure a maximum dimension of 2400 mm for any concealed space. Blocking shall be cut to fit between framing members and rigidly nailed thereto.

3.4.4 Nailers and Nailing Strips

Nailers and nailing strips shall be provided as necessary for the attachment of finish materials. Nailers used in conjunction with roof deck installation shall be installed flush with the roof deck system. Stacked nailers shall be assembled with spikes or nails spaced not more than 450 mm

on center and staggered. Beginning and ending nails shall not be more than 150 mm for nailer end. Ends of stacked nailers shall be offset approximately 300 mm in long runs and alternated at corners. Anchors shall extend through the entire thickness of the nailer. Strips shall be run in lengths as long as practicable, butt jointed, cut into wood framing members when necessary, and rigidly secured in place. Nailers and nailer installation for Factory Mutual wind uplift rated roof systems specified in other Sections of these specifications shall conform to the recommendations contained in FM LPD 1-49.

3.4.5 Furring Strips

Furring strips shall be provided at the locations shown. Furring strips shall be installed at 400 mm on center unless otherwise shown, run in lengths as long as practicable, butt jointed and rigidly secured in place.

3.4.6 Rough Bucks and Frames

Rough bucks shall be set straight, true, and plumb, and secured with anchors near top and bottom of each wood member and at intermediate intervals of not more than 900 mm. Anchors for concrete shall be expansion bolts, and anchors for masonry shall be 5 x 32 mm (3/16 x 1-1/4 inch) steel straps extending not less than 200 mm into the masonry and turned down 50 mm into the masonry.

3.4.7 Wood Bumpers

Wood bumpers shall be bored, countersunk and securely bolted in place.

3.4.8 Sill Plates

Sill plates shall be set level and square and anchor bolted at not more than 1800 mm on centers and not more than 300 mm from end of each piece. A minimum of two anchors shall be used for each piece.

3.5 INSTALLATION OF TIMBER CONNECTORS

Installation of timber connectors shall conform to applicable requirements of AF&PA T01.

3.6 INSTALLATION OF INSULATION

Insulation shall be installed after construction has advanced to a point that the installed insulation will not be damaged by remaining work. For thermal insulation the actual installed thickness shall provide the thermal resistance shown. For acoustical insulation the installed thickness shall be as shown. Insulation shall be installed on the weather side of such items as electrical boxes and water lines. Unless otherwise specified, installation shall be in accordance with the manufacturer's recommendation.

3.7 INSTALLATION OF VAPOR RETARDER

Vapor retarder shall be applied to provide a continuous barrier at window and door frames, and at all penetrations such as electrical outlets and

switches, plumbing connections, and utility service penetrations. Joints in the vapor retarder shall be lapped and sealed according to the manufacturer's recommendations.

3.8 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

Special inspections and testing for seismic-resisting systems and components shall be done in accordance with Section 01452 SPECIAL INSPECTION FOR SEISMIC-RESISTING SYSTEMS.

3.9 INSTALLATION OF AIR INFILTRATION BARRIER

Air infiltration barrier shall be installed in accordance with the manufacturer's recommendations.

3.10 TABLES

TABLE I. SPECIES AND GRADE

Subflooring, Roof Sheathing, Wall Sheathing, Furring						
Grading Rules	Species	Const Standard	No. 2 Comm	No. 2 Board Comm	No. 3 Comm	
NHLA Rules	Cypress			X		
NELMA Grading Rules	Northern White Cedar					X
	Eastern White Pine	X				
	Northern Pine	X				
	Balsam Fir					X
	Eastern Hemlock- Tamarack					X
RIS GCRL	Redwood		X			
SCMA Specs	Cypress			X		
SPIB Rules	Southern Pine		X			
WCLIB 17	Douglas Fir-Larch	X				
	Hem-Fir	X				
	Sitka Spruce	X				
	Mountain Hemlock	X				
	Western Cedar	X				
WWPA Grading Rules	Douglas Fir-Larch	X				
	Hem-Fir	X				
	Idaho White Pine	X				
	Lodgepole Pine				X	
	Ponderosa Pine				X	
	Sugar Pine				X	
	Englemann Spruce				X	
	Douglas Fir South				X	
	Mountain Hemlock				X	
	Subalpine Fir				X	
	Western Cedar				X	

TABLE II. SPECIES AND GRADE

Wood Bumpers			
Grading Rules	Species	No. 1	No. 2
NHLA Rules	Red Oak	X	
NELMA Grading Rules	Northern Pine		X
	Eastern Hemlock-		X
	Tamarack		
SPIB Rules	Southern Pine	X	
WCLIB 17	Douglas Fir-Larch		X
	Hem-Fir		X
WWPA Grading Rules	Douglas Fir-Larch		X
	Hem-Fir		X
	Douglas Fir-South		X

-- End of Section --

SECTION 07311A

ROOFING, STRIP SHINGLES
08/98

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 225	(2000) Asphalt Shingles (Organic Felt) Surfaced with Mineral Granules
ASTM D 226	(1997a) Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 1970	(2000) Self-Adhering Polymer Modified Bituminous Sheet Materials Used as Steep Roofing Underlayment for Ice Dam Protection
ASTM D 3018	(1990; R 1994el) Class A Asphalt Shingles Surfaced With Mineral Granules
ASTM D 3161	(1999a) Wind-Resistance of Asphalt Shingles (Fan-Induced Method)
ASTM D 3462	(1999) Asphalt Shingles Made From Glass Felt and Surfaced with Mineral Granules
ASTM D 4869	(1988; R 1993el) Asphalt-Saturated Organic Felt Shingle Underlayment Used in Roofing
ASTM E 108	(1999) Fire Tests of Roof Coverings

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

NRCA Shingle Manual	(1996) Asphalt Shingle Roofing Manual
---------------------	---------------------------------------

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Application of Roofing Materials; G, RE

Manufacturer's catalog data, description of underlayment, shingles, fasteners, ridge vents, and flashing. Manufacturer's instructions, annotated or supplemented by the Contractor to indicate configuration and method for installing the materials, and for waterproofing of joints where flashings change direction. The number, spacing and orientation of fasteners shall be specified.

SD-04 Samples

Shingles; G, RE

Full shingle sample and manufacturer's standard size samples of materials and products requiring color or finish selection.

1.3 DELIVERY AND STORAGE OF MATERIALS

Materials shall be delivered in manufacturer's unopened bundles and containers with the manufacturer's brand and name marked clearly thereon. Shingles shall be stored in accordance with manufacturer's printed instructions. Roll goods shall be stored on end in an upright position or in accordance with manufacturer's recommendations. Immediately before laying, roofing felt shall be stored for 24 hours in an area maintained at a temperature not lower than 10 degrees C.

1.4 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period shall be provided.

PART 2 PRODUCTS

2.1 MATERIALS

Materials shall conform to the following requirements:

2.1.1 Metal Drip Edges

Metal drip edges shall be minimum 26 gauge galvanized steel or an equivalent non-corrosive non-staining material, as shown.

2.1.2 Underlayment

Organic felt; ASTM D 4869 or ASTM D 226, non perforated Type II, heavy-duty number 30.

2.1.3 Leak Barrier Underlayment

Self-adhering leak barrier or ice dam underlayment shall comply with ASTM D 1970 for sealability around nails.

2.1.4 Ventilators

2.1.4.1 Aluminum Ridge Vents

Ridge vents shall be constructed of prefinished aluminum in minimum 3 m long sections and shall be approximately 0.30 m wide. Vents shall be designed to prevent infiltration of insects, rain, and snow.

2.1.4.2 Nailable Plastic Shingle Over Type Ridge Vents

Ridge vents shall be constructed of UV stabilized nailable rigid polypropylene material, approximately 0.30 m wide and 25 mm thick, and shall be in 1.2 m long interlocking sections with self-aligning ends or corrugated polyethylene rigid roll or rigid strip ridge vent with aluminum wind deflectors on each side. Vents shall be designed to prevent infiltration of insects, rain, and snow.

2.1.4.3 Nailable Mesh Shingle Over Type Ridge Vents

Ridge vents shall be constructed of UV stabilized nailable polyester mesh material, approximately 0.30 m wide. Vents shall be designed to prevent infiltration of insects, rain, and snow.

2.1.5 Nails

Nails shall be round head 11 or 12 gauge galvanized steel or equivalent corrosion resistant roofing nails. Nail heads shall be 9.5 mm minimum diameter, with flat and smooth low profile. Shanks shall be barbed or otherwise deformed for added pull-out resistance. Nails shall be long enough to penetrate all layers of roofing materials and achieve secure anchorage into the roof deck. Nails shall extend through the underside of plywood or wood panel roof decks, and shall penetrate at least 19 mm into wood plank decks.

2.1.6 Shingles

Shingles shall be approximately 333 by 1000 mm in dimension and architectural design. Shingles shall have self-sealing adhesive strips and shall meet a wind velocity rating of 100 km/h plus or minus 5 percent in accordance with ASTM D 3161. Shingles shall be manufacturer's standard type for project area. Organic shingles shall comply with ASTM D 225 Type I (uniform or non-uniform thickness) and ASTM E 108 Class C (a high degree of fire protection), and shall weigh not less than 14.2 kg per square meter (Glass felt shingles shall comply with ASTM D 3018 and ASTM D 3462 Type I (self-sealing), ASTM E 108 Class A (a light degree of fire protection), and shall weigh not less than 16 kg. Shingles shall be installed on the following buildings: Barracks and Soldier Community Building. Shingles shall have 25-year limited product warranty within a wind velocity of 60 mph or more.

2.1.7 Ice and Water Barrier

Special roofing membranes shall be a self-adhering, self-sealing product

such as "WinterGuard" manufactured by CertainTeed Corps., "Ice and Water Shield" manufactured by Grace Construction Products, or "Weather Watch Ice and Water Barrier" manufactured by GAF Building Materials Corps. They shall be conforming to ASTM D 146 and ASTM D 412 (composite of polyethylene film and rubberized asphalt) or ASTM D 1970 (polymer modified bituminous sheet materials).

2.2 COLOR

Shingle color shall be in accordance with EXTERIOR FINISH AND COLOR SCHEDULE.

PART 3 EXECUTION

3.1 PREPARATION OF SURFACES

The construction of any bay or section of roof decking shall be completed before roofing work is started. Roof surfaces shall be smooth, firm, dry, and free from loose boards, large cracks, and projecting ends that might damage the roofing. Vents and other projections through roofs shall be properly flashed and secured in position, and projecting nails shall be driven flush with the deck.

3.2 APPLICATION OF ROOFING MATERIALS

3.2.1 Flashings

Metal flashings shall conform to Section 07600 SHEET METALWORK, GENERAL. Metal flashings shall be provided at the intersections of roofs and adjoining walls and at projections through the deck such as chimneys and vent stacks. Valley flashing shall be of the open, in accordance with NRCA Shingle Manual.

3.2.2 Metal Drip Edges

Metal drip edges shall be provided along the eaves and rakes. The metal drip edge shall be applied directly over the underlayment along the rakes and directly on the wood deck at the eaves. Metal drip edges shall extend back from the edge of the deck not less than 75 mm and shall be secured with compatible nails spaced not more than 250 mm on center along the inner edge.

3.2.3 Underlayment

Before any shingles are applied, a single layer of asphalt-saturated-felt underlayment shall be applied to the roof deck sheathing. A ice and water barrier underlayment shall be applied at the following locations: Starting from the eaves to a point 600mm inside the interior wall line ; starting from the gable roof ridges to a point 1200mm inward; 600mm down on both sides from the roof ridge; 600mm up on both sides from the valleys. Roof surfaces to receive ice and water barrier membrane shall be prepared in accordance with manufacturer's instructions prior to application of the membrane. Membrane shall be applied directly to the roof deck (plywood) at locations indicated by the specs and on the drawings. Installation procedures shall follow manufacturer's printed instructions.

3.2.4 Ridge Vents

Ridge vents shall be provided along the ridge lines where shown. Ridge vents shall be installed in accordance with the manufacturer's printed instructions.

3.2.5 Shingles

Shingles with the correct recommended exposure shall be applied in accordance with the manufacturer's printed instructions as they appear on the bundle wrapping.

-- End of Section --

SECTION 08120

ALUMINUM DOORS AND FRAMES

09/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA 45 (1980) Aluminum Finishes

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 603.8 (1992; Addendum 1993) Pigmented Organic Coatings on Extruded Aluminum

AAMA 605.2 (1992; Addendum 1995) High Performance Organic Coatings on Architectural Extrusions and Panels

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 36/A 36M (1997; Rev. A) Carbon Structural Steel

ASTM B 209M (1995) Aluminum and Aluminum-Alloy Sheet and Plate (Metric)

ASTM B 209 (1996) Aluminum and Aluminum-Alloy Sheet and Plate

ASTM B 221M (1996) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)

ASTM B 221 (1996) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

ASTM E 283 (1991) Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

ASTM E 331 (1996) Water Penetration of Exterior Windows, Curtain Walls, and Doors by Uniform Static Air Pressure Difference

1.2 PERFORMANCE REQUIREMENTS

1.2.1 Structural

Shapes and thicknesses of framing members shall be sufficient to withstand the design wind load indicated with a deflection of not more than 1/175 times the length of the member and a safety factor of not less than 1.65. Provide glazing beads, moldings, and trim of not less than 1.25 mm nominal thickness.

1.2.2 Air Infiltration

When tested in accordance with ASTM E 283, air infiltration shall not exceed 2.63 by 10⁻⁵ cms per square meter of fixed area at a test pressure of 0.30 kPa (80 kilometers per hour wind).

1.2.3 Water Penetration

When tested in accordance with ASTM E 331, there shall be no water penetration at a pressure of 0.38 kPa of fixed area.

1.3 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-02 Shop Drawings

Doors and frames; G, RE

Show elevations of each door type, size of doors and frames, metal gages, details of door and frame construction, methods of anchorage, glazing details, weatherstripping, provisions for and location of hardware, and details of installation.

SD-08 Manufacturer's Instructions

Doors and frames; G, RE

Submit detail specifications and instructions for installation, adjustments, cleaning, and maintenance.

1.4 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for damage. Unload and store with minimum handling. Provide storage space in dry location with adequate ventilation, free from dust or water, and easily accessible for inspection and handling. Stack materials on nonabsorptive strips or wood platforms. Do not cover doors and frames with tarps, polyethylene film, or similar coverings. Protect finished surfaces during shipping and handling using manufacturer's standard method, except that no coatings or lacquers shall be applied to surfaces to which calking and glazing compounds must adhere.

PART 2 PRODUCTS

2.1 DOORS AND FRAMES

Swing-type aluminum doors and frames of size, design, and location indicated. Provide doors complete with frames, framing members , transoms, adjoining sidelights, and accessories.

2.2 MATERIALS

2.2.1 Anchors

Stainless steel or steel with hot-dipped galvanized finish.

2.2.2 Weatherstripping

Continuous wool pile, silicone treated, or type recommended by door manufacturer.

2.2.3 Aluminum Alloy for Doors and Frames

ASTM B 221M, Alloy 6063-T5 for extrusions. ASTM B 209M, alloy and temper best suited for aluminum sheets and strips.

2.2.4 Fasteners

Hard aluminum or stainless steel.

2.2.5 Structural Steel

ASTM A 36/A 36M.

2.2.6 Aluminum Paint

Type as recommended by aluminum door manufacturer.

2.3 FABRICATION

2.3.1 Aluminum Frames

Extruded aluminum shapes with contours approximately as indicated. Provide removable glass stops and glazing beads for frames accommodating fixed glass. Use countersunk stainless steel Phillips screws for exposed fastenings, and space not more than 300 mm o.c. Mill joints in frame members to a hairline fit, reinforce, and secure mechanically.

2.3.2 Aluminum Doors

Of type, size, and design indicated and not less than 45 mm thick. Minimum wall thickness, 3 mm, except beads and trim, 1.25 mm. Door sizes shown are nominal and shall include standard clearances as follows: 2.5 mm at hinge and lock stiles, 3 mm between meeting stiles, 3 mm at top rails, 5 mm between bottom and threshold, and 17 mm between bottom and floor. Bevel single-acting doors 2 or 3 mm at lock, hinge, and meeting stile edges. Double-acting doors shall have rounded edges at hinge stile, lock stile,

and meeting stile edges.

2.3.2.1 Full Glazed Stile and Rail Doors

Doors shall have medium stiles and rails as indicated. Fabricate from extruded aluminum hollow seamless tubes or from a combination of open-shaped members interlocked or welded together. Fasten top and bottom rail together by means of welding or by 10 or 13 mm diameter cadmium-plated tensioned steel tie rods. Provide an adjustable mechanism of jack screws or other methods in the top rail to allow for minor clearance adjustments after installation.

2.3.3 Welding and Fastening

Where possible, locate welds on unexposed surfaces. Dress welds on exposed surfaces smoothly. Select welding rods, filler wire, and flux to produce a uniform texture and color in finished work. Remove flux and spatter from surfaces immediately after welding. Exposed screws or bolts will be permitted only in inconspicuous locations, and shall have countersunk heads. Weld concealed reinforcements for hardware in place.

2.3.4 Weatherstripping

Provide on stiles and rails of exterior doors. Fit into slots which are integral with doors or frames. Weatherstripping shall be replaceable without special tools, and adjustable at meeting rails of pairs of doors. Installation shall allow doors to swing freely and close positively. Air leakage of a single leaf weatherstripped door shall not exceed 5.48×10^{-5} cubic meter per second of air per square meter of door area when tested in accordance with ASTM E 283.

2.3.5 Anchors

On the backs of subframes, provide anchors of the sizes and shapes indicated for securing subframes to adjacent construction. Anchor transom bars at ends and mullions at head and sill. Place anchors near top and bottom of each jamb and at intermediate points not more than 635 mm apart.

2.3.6 Provisions for Hardware

Hardware is specified in Section 08710, "Door Hardware." Deliver hardware templates and hardware (except field-applied hardware) to the door manufacturer for use in fabrication of aluminum doors and frames. Cut, reinforce, drill, and tap doors and frames at the factory to receive template hardware. Provide doors to receive surface-applied hardware, except push plates, kick plates, and mop plates, with reinforcing only; drill and tap in the field. Provide hardware reinforcements of stainless steel or steel with hot-dipped galvanized finish, and secure with stainless steel screws.

2.3.7 Provisions for Glazing

Provide extruded aluminum snap-in glazing beads on interior side of doors. Provide extruded aluminum, theft-proof, snap-in glazing beads or fixed

glazing beads on exterior or security side of doors. Glazing beads shall have vinyl insert glazing gaskets. Design glazing beads to receive glass of thickness indicated or specified. Glazing is specified in Section 08800N, "Glazing."

2.3.8 Finishes

Provide exposed aluminum surfaces with factory finish of anodic coating or organic coating.

2.3.8.1 Anodic Coating

Clean exposed aluminum surfaces and provide an anodized finish conforming to AA 45. Finish shall be electrolytically deposited color-anodized, designation AA-M10-C22-A44, Architectural Class I 0.0175 mm or thicker. Color shall be as indicated.

2.3.8.2 Organic Coating

Clean and prime exposed aluminum surfaces. Provide a high-performance finish in accordance with AAMA 605.2 with total dry film thickness of not less than 0.03 mm. The finish color shall be as indicated.

PART 3 EXECUTION

3.1 INSTALLATION

Plumb, square, level, and align frames and framing members to receive doors, transoms and adjoining sidelights. Anchor frames to adjacent construction as indicated and in accordance with manufacturer's printed instructions. Anchor bottom of each frame to rough floor construction with 2.4 mm thick stainless steel angle clips secured to back of each jamb and to floor construction; use stainless steel bolts and expansion rivets for fastening clip anchors. Seal metal-to-metal joints between framing members as specified in Section 07920N, "Joint Sealants." Hang doors to produce clearances specified in paragraph entitled "Aluminum Doors," of this section. After erection and glazing, adjust doors and hardware to operate properly.

3.2 PROTECTION FROM DISSIMILAR MATERIALS

3.2.1 Dissimilar Metals

Where aluminum surfaces come in contact with metals other than stainless steel, zinc, or small areas of white bronze, protect from direct contact by one or a combination of the following methods:

- a. Paint the dissimilar metal with one coat of heavy-bodied bituminous paint.
- b. Apply a good quality elastomeric sealant between the aluminum and the dissimilar metal.
- c. Paint the dissimilar metal with one coat of primer and one coat of

aluminum paint.

- d. Use a nonabsorptive tape or gasket in permanently dry locations.

3.2.2 Drainage from Dissimilar Metals

In locations where drainage from dissimilar metals has direct contact with aluminum, provide protective paint, to prevent aluminum discoloration.

3.2.3 Masonry and Concrete

Provide aluminum surfaces in contact with mortar, concrete, or other masonry materials with one coat of heavy-bodied bituminous paint.

3.2.4 Wood or Other Absorptive Materials

Provide aluminum surfaces in contact with absorptive materials subject to frequent moisture, and aluminum surfaces in contact with treated wood, with two coats of aluminum paint or one coat of heavy-bodied bituminous paint. In lieu of painting the aluminum, the Contractor shall have the option of painting the wood or other absorptive surface with two coats of aluminum paint and sealing the joints with elastomeric sealant.

3.3 CLEANING

Upon completion of installation, clean door and frame surfaces in accordance with door manufacturer's recommended procedure. Do not use abrasive, caustic, or acid cleaning agents.

3.4 PROTECTION

Protect doors and frames from damage and from contamination by other materials such as cement mortar. Prior to completion and acceptance of the work, restore damaged doors and frames to original condition, or replace with new ones.

-- End of Section --

SECTION 08810A

GLASS AND GLAZING
05/97

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1	(1984; R 1994) Safety Performance Specifications and Methods of Test for Safety Glazing Materials Used in Buildings
------------	---

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 509	(1994) Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C 669	(1995) Glazing Compounds for Back Bedding and Face Glazing of Metal Sash
ASTM C 864	(1999) Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM C 1036	(1991; R 1997) Flat Glass
ASTM C 1048	(1997b) Heat-Treated Flat Glass - Kind HS, Kind FT Coated and Uncoated Glass
ASTM C 1172	(1996e1) Laminated Architectural Flat Glass
ASTM C 1349	(1996) Architectural Flat Glass Clad Polycarbonate
ASTM D 395	(1998) Rubber Property - Compression Set
ASTM E 119	(1998) Fire Tests of Building Construction and Materials
ASTM E 773	(1997) Accelerated Weathering of Sealed Insulating Glass Units
ASTM E 774	(1997) Classification of the Durability of

Sealed Insulating Glass Units

ASTM E 1300 (1998) Determining the Minimum Thickness and Type of Glass Required to Resist a Specified Load

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7 (1995) Minimum Design Loads for Buildings and Other Structures

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201 Safety Standard for Architectural Glazing Materials

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-378 (Basic) Putty Linseed Oil Type, (for Wood-Sash-Glazing)

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual (1997) Glazing Manual

GANA Standards Manual (1995) Engineering Standards Manual

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80 (1999) Fire Doors and Fire Windows

NFPA 252 (1995) Fire Tests of Door Assemblies

NFPA 257 (1996) Fire Tests for Window and Glass Block Assemblies

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation; G, RE,

Drawings showing complete details of the proposed setting methods, mullion details, edge blocking, size of openings, frame details, materials, and types and thickness of glass.

TEXT DELETED

SD-03 Product Data

Insulating Glass; G, RE,
Glazing Accessories; G, RE

Manufacturer's descriptive product data, handling and storage recommendations, installation instructions, and cleaning instructions.

SD-04 Samples

Insulating Glass; G, RE

Two 203 x 254 mm samples of each of the following: tinted glass, patterned glass, heat-absorbing glass, and insulating glass units.

SD-07 Certificates

Insulating Glass; G, RE

Certificates stating that the glass meets the specified requirements. Labels or manufacturers marking affixed to the glass will be accepted in lieu of certificates.

1.3 SYSTEM DESCRIPTION

Glazing systems shall be fabricated and installed watertight and airtight to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, and defects in the work. Glazed panels shall comply with the safety standards, as indicated in accordance with ANSI Z97.1. Glazed panels shall comply with indicated wind/snow loading in accordance with ASTM E 1300.

1.4 DELIVERY, STORAGE AND HANDLING

Glazing compounds shall be delivered to the site in the manufacturer's unopened containers. Glass shall be stored indoors in a safe, well ventilated dry location in accordance with manufacturer's instructions, and shall not be unpacked until needed for installation. Glass shall not be stored on site over 1 month.

1.5 PROJECT/SITE CONDITIONS

Glazing work shall not be started until outdoor temperature is above 5 degrees C and rising, unless procedures recommended by glass manufacturer and approved by Contracting Officer are made to warm the glass and rabbet surfaces. Ventilation shall be provided to prevent condensation of moisture on glazing work during installation. Glazing work shall not be performed during damp or raining weather.

1.6 WARRANTY

1.6.1 Insulating Glass

Manufacturer shall warrant the insulating glass to be free of fogging or film formation on the internal glass surfaces caused by failure of the hermetic seal for a period of 10 years from Date of Substantial Completion. Warranty shall be signed by manufacturer.

1.6.2 Monolithic Reflective Glass

Manufacturer shall warrant the monolithic reflective glass to be free of peeling or deteriorating of coating for a period of 10 years after Date of Substantial Completion. Warranty shall be signed by manufacturer.

1.6.3 Monolithic Opacified Spandrel

Manufacturer shall warrant the opacifier film on the spandrel to be free of peeling for a period of five years after Date of Substantial Completion. Warranty shall be signed by manufacturer.

PART 2 PRODUCTS

2.1 FLOAT GLASS

2.1.1 Annealed Glass

Annealed glass shall be Type I transparent flat type, Class 1 - clear , Quality q3 - glazing select, 79-91 percent light transmittance, 73-100 percent shading coefficient, conforming to ASTM C 1036. .

2.2 ROLLED GLASS

2.2.1 Wired Glass

Wired glass shall be Type II flat type, Class 1 - translucent , Quality q8 - glazing, Form 1 - wired and polished both sides , 79-91 percent light transmittance, 73-100 percent shading coefficient, conforming to ASTM C 1036.

Wire mesh shall be polished stainless steel Mesh 2 - square . Wired glass for fire-rated windows shall bear an identifying UL label or the label of a nationally recognized testing agency, and shall be rated for 45 minutes when tested in accordance with NFPA 257. Wired glass for fire-rated doors shall be tested as part of a door assembly in accordance with NFPA 252.

2.3 INSULATING GLASS

Insulating glass shall be Class A preassembled units of dual-seal construction consisting of lites of glass separated by an aluminum, steel, or stainless steel, spacer and dehydrated space conforming to ASTM E 773 and ASTM E 774. Spacer shall be roll-formed, with bent or tightly welded or keyed and sealed joints to completely seal the spacer periphery and eliminate moisture and hydrocarbon vapor transmission into airspace through the corners. Primary seal shall be compressed polyisobutylene and the secondary seal shall be a specially formulated silicone. Glass types shall be as follows:

2.3.1 Low-E Insulating Glass

For Low-E insulating units, interior glass panes shall be Type I laminated glass Type I , Class 1-clear and exterior glass panes shall be Type I tempered glass , Class 2-tinted with anti-reflective low-emissivity coating on No. 2 surface (inside surface of exterior pane), Quality q3 - glazing select, conforming to ASTM C 1036. Glass performance shall be K-Value/Winter Nighttime 0.31, shading coefficient 85 percent. Color shall be bronze . Insulating glass shall be installed in exterior aluminum doors and exterior aluminum windows.

2.4 HEAT-TREATED GLASS

Heat-treated glass shall conform to the following requirements.

2.4.1 Tempered Glass

Tempered glass shall be kind FT fully tempered transparent flat type, Class 1-clear and Class 2-tinted as indicated, Condition A uncoated surface, Quality q3 - glazing select, 68-91 percent light transmittance, 73-100 percent shading coefficient conforming to ASTM C 1048 and GANA Standards Manual. Color shall be clear and bronze as indicated .

2.5 LAMINATED GLAZINGS

2.5.1 Laminated Glass

Laminated glass shall consist of two layers of Type I transparent float glass, Class 1-clear Quality q3 - glazing select, conforming to ASTM C 1036. Glass shall be bonded together with 1.52 mm thick PVB interlayer under pressure, or alternatives such as resin laminates, conforming to requirements of 16 CFR 1201 and ASTM C 1172. Color shall be clear .

2.6 FIRE/SAFETY RATED GLASS

Fire/safety rated glass shall be laminated Type I transparent flat type, Class 1-clear. Glass shall have a 60 minute rating when tested in accordance with ASTM E 119. Glass shall be permanently labeled with appropriate markings.

2.7 MIRRORS

2.7.1 Glass Mirrors

Glass for mirrors shall be Type I transparent flat type, Class 1-clear , Glazing Quality q1 6 mm (1/4 inch) thick conforming to ASTM C 1036. Glass color shall be clear. Glass shall be coated on one surface with silver coating, copper protective coating, and mirror backing paint. Silver coating shall be highly adhesive pure silver coating of a thickness which shall provide reflectivity of 83 percent or more of incident light when viewed through 6 mm (1/4 inch) thick glass, and shall be free of pinholes or other defects. Copper protective coating shall be pure bright reflective copper, homogeneous without sludge, pinholes or other defects, and shall be of proper thickness to prevent "adhesion pull" by mirror

backing paint. Mirror backing paint shall consist of two coats of special scratch and abrasion-resistant paint , and shall be baked in uniform thickness to provide a protection for silver and copper coatings which will permit normal cutting and edge fabrication.

2.7.2 One-Way Mirrors

Glass for one-way mirrors shall be Type I transparent flat type, Class 1 clear, Glazing Quality q1, 6 mm (1/4 inch) thick conforming to ASTM C 1036.

Glass shall be coated on one face with a hard adherent film of chromium or other approved coating of proven equivalent durability. Glass shall transmit not less than 5 percent nor more than 11 percent of total incident light in visible region, and shall reflect from front surface of coating not less than 45 percent of total incident light in visible region.

2.7.3 Mirror Accessories

2.7.3.1 Mastic

Mastic for setting mirrors shall be a polymer type mirror mastic resistant to water, shock, cracking, vibration and thermal expansion. Mastic shall be compatible with mirror backing paint, and shall be approved by mirror manufacturer.

2.7.3.2 Mirror Frames

Mirrors shall be provided with mirror frames (J-mold channels) fabricated of one-piece roll-formed Type 304 stainless steel with No. 4 brushed satin finish and concealed fasteners which will keep mirrors snug to wall. Frames shall be 32 x 6 x 6 mm (1-1/4 x 1/4 x 1/4 inch) continuous at top and bottom of mirrors. Concealed fasteners of type to suit wall construction material shall be provided with mirror frames.

2.7.3.3 Mirror Clips

Concealed fasteners of type to suit wall construction material shall be provided with clips.

2.8 GLAZING ACCESSORIES

2.8.1 Preformed Tape

Preformed tape shall be elastomeric rubber extruded into a ribbon of a width and thickness suitable for specific application. Tape shall be of type which will remain resilient, have excellent adhesion, and be chemically compatible to glass, metal, or wood.

2.8.2 Sealant

Sealant shall be elastomeric conforming to ASTM C 920, Type S or M, Grade NS, Class 12.5, Use G, of type chemically compatible with setting blocks, preformed sealing tape and sealants used in manufacturing insulating glass. Color of sealant shall be medium bronze .

2.8.3 Glazing Gaskets

Glazing gaskets shall be extruded with continuous integral locking projection designed to engage into metal glass holding members to provide a watertight seal during dynamic loading, building movements and thermal movements. Glazing gaskets for a single glazed opening shall be continuous one-piece units with factory-fabricated injection-molded corners free of flashing and burrs. Glazing gaskets shall be in lengths or units recommended by manufacturer to ensure against pull-back at corners. Glazing gasket profiles shall be as indicated on drawings.

2.8.3.1 Fixed Glazing Gaskets

Fixed glazing gaskets shall be closed-cell (sponge) smooth extruded compression gaskets of cured elastomeric virgin neoprene compounds conforming to ASTM C 509, Type 2, Option 1.

2.8.3.2 Wedge Glazing Gaskets

Wedge glazing gaskets shall be high-quality extrusions of cured elastomeric virgin neoprene compounds, ozone resistant, conforming to ASTM C 864, Option 1, Shore A durometer between 65 and 75.

2.8.3.3 Aluminum Framing Glazing Gaskets

Glazing gaskets for aluminum framing shall be permanent, elastic, non-shrinking, non-migrating, watertight and weathertight.

2.8.4 Putty and Glazing Compound

Glazing compound shall conform to ASTM C 669 for face-glazing metal sash. Putty shall be linseed oil type conforming to CID A-A-378 for face-glazing primed wood sash. Putty and glazing compounds shall not be used with insulating glass or laminated glass.

2.8.5 Setting and Edge Blocking

Neoprene setting blocks shall be dense extruded type conforming to ASTM D 395, Method B, Shore A durometer between 70 and 90. Edge blocking shall be Shore A durometer of 50 (+ or - 5). Silicone setting blocks shall be required when blocks are in contact with silicone sealant. Profiles, lengths and locations shall be as required and recommended in writing by glass manufacturer.

PART 3 EXECUTION

3.1 PREPARATION

Openings and framing systems scheduled to receive glass shall be examined for compliance with approved shop drawings, GANA Glazing Manual and glass manufacturer's recommendations including size, squareness, offsets at corners, presence and function of weep system, face and edge clearance requirements and effective sealing between joints of glass-framing members. Detrimental materials shall be removed from glazing rabbet and glass

surfaces and wiped dry with solvent. Glazing surfaces shall be dry and free of frost.

3.2 INSTALLATION

Glass and glazing work shall be performed in accordance with approved shop drawings, GANA Glazing Manual, glass manufacturer's instructions and warranty requirements. Glass shall be installed with factory labels intact and removed only when instructed. Wired glass and fire/safety rated glass shall be installed in accordance with NFPA 80. Edges and corners shall not be ground, nipped or cut after leaving factory. Springing, forcing or twisting of units during installation will not be permitted.

3.3 CLEANING

Upon completion of project, outside surfaces of glass shall be washed clean and the inside surfaces of glass shall be washed and polished in accordance with glass manufacturer's recommendations.

3.4 PROTECTION

Glass work shall be protected immediately after installation. Glazed openings shall be identified with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Reflective glass shall be protected with a protective material to eliminate any contamination of the reflective coating. Protective material shall be placed far enough away from the coated glass to allow air to circulate to reduce heat buildup and moisture accumulation on the glass. Glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities shall be removed and replaced with new units.

-- End of Section --

SECTION 09250

GYPSUM BOARD
11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A108.11 (1992) Interior Installation of
Cementitious Backer Units

ANSI A118.9 (1992) Cementitious Backer Units

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 36/C 36M (1999) Gypsum Wallboard

ASTM C 79/C 79M (2001) Standard Specification for Treated
Core and Nontreated Core Gypsum Sheathing
Board

ASTM C 442/C 442M (1999; Rev. A) Gypsum Backing Board and
Coreboard

ASTM C 475 (1994) Joint Compound and Joint Tape for
Finishing Gypsum Board

ASTM C 514 (1996) Nails for the Application of Gypsum
Board

ASTM C 630/C 630M (2001) Water-Resistant Gypsum Backing Board

ASTM C 840 (2001) Application and Finishing of Gypsum
Board

ASTM C 954 (2000) Steel Drill Screws for the
Application of Gypsum Board or Metal
Plaster Bases to Steel Studs from 0.033
in. (0.84 mm) to 0.112 in. (2.84 mm) in
Thickness

ASTM C 1002 (2000) Steel Drill Screws for the

	Application of Gypsum Panel Products or Metal Plaster Bases
ASTM C 1047	(1999) Accessories for Gypsum Wallboard and Gypsum Veneer Base
ASTM C 1177/C 1177M	(1999) Standard Specification for Glass Mat Gypsum Substrate for use as Sheathing
ASTM C 1178/C 1178M	(1999) Glass Mat Water-Resistant Gypsum Backing Board
ASTM C 1396/C 1396M	(2000) Standard Specification for Gypsum Board
ASTM D 226	(1997) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 412	(1998) Standard Test Methods for Vulcanized Rubber and Thermoplastic Rubbers and Thermoplastic Elastomers-Tension
ASTM D 624	(2000) Standard Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D 1037	(1999) Standard Test Methods for Evaluating Properties of Wood-Base Fiber and Particle Panel Materials
ASTM D 1149	(1999) Standard Test Method for Rubber Deterioration-Surface Ozone Cracking in a Chamber
ASTM D 5420	(1998) Standard Test Method for Impact Resistance of Flat, Rigid Plastic Specimen by Means of a Striker Impacted by a Falling Weight (Gardner Impact)
ASTM E 84	(2001) Surface Burning Characteristics of Building Materials
ASTM E 695	(1997) Standard Method for Measure Relative Resistance of Wall, Floor and Roof Construction to Impact Loads

GYPSUM ASSOCIATION (GA)

GA 214	(1996) Recommended Levels of Gypsum Board
--------	---

Finish

GA 216 (2000) Application and Finishing of Gypsum Board

GA 253 (1999) Application of Gypsum Sheathing

GA 600 (2000) Fire Resistance and Sound Control Design Manual

UNDERWRITERS LABORATORIES (UL)

UL Fire Resist Dir (2000) Fire Resistance Directory

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-03 Product Data; G, RE

Cementitious backer units

Glass Mat Water-Resistant Gypsum Tile Backing Board

Water-Resistant Gypsum Backing Board

Glass Mat Covered or Reinforced Gypsum Sheathing

Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Impact Resistant Gypsum Board

Accessories

Submit for each type of gypsum board and for cementitious backer units.

SD-04 Samples

Predecorated gypsum board; G, RE

Submit for each color and pattern of predecorated gypsum board. Where colors are not indicated, submit color selection samples of not less than eight of the manufacturer's standard colors.

SD-07 Certificates

Asbestos Free Materials; G, RE

Certify that gypsum board types, gypsum backing board types, cementitious backer units, and joint treating materials do not

contain asbestos.

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery

Deliver materials in the original packages, containers, or bundles with each bearing the brand name, applicable standard designation, and name of manufacturer, or supplier.

1.3.2 Storage

Keep materials dry by storing inside a sheltered building. Where necessary to store gypsum board and cementitious backer units outside, store off the ground, properly supported on a level platform, and protected from direct exposure to rain, snow, sunlight, and other extreme weather conditions. Provide adequate ventilation to prevent condensation.

1.3.3 Handling

Neatly stack gypsum board and cementitious backer units flat to prevent sagging or damage to the edges, ends, and surfaces.

1.4 ENVIRONMENTAL CONDITIONS

1.4.1 Temperature

Maintain a uniform temperature of not less than 10 degrees C in the structure for at least 48 hours prior to, during, and following the application of gypsum board, cementitious backer units, and joint treatment materials, or the bonding of adhesives.

1.4.2 Exposure to Weather

Protect gypsum board and cementitious backer unit products from direct exposure to rain, snow, sunlight, and other extreme weather conditions.

1.5 QUALIFICATIONS

Manufacturer shall specialize in manufacturing the types of material specified and shall have a minimum of 5 years of documented successful experience. Installer shall specialize in the type of gypsum board work required and shall have a minimum of 3 years of documented successful experience.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to specifications, standards and requirements specified herein. Provide gypsum board types, gypsum backing board types, cementitious backing units, and joint treating materials manufactured from asbestos free materials only.

2.1.1 Gypsum Board

ASTM C 36/C 36M and ASTM C 1396/C 1396M.

2.1.1.1 Regular

1200 mm wide, 15.9 mm thick, tapered edges.

2.1.1.2 Type X (Special Fire-Resistant)

1200 mm wide, 12.7 and 15.9 mm thick, tapered edges.

2.1.2 Gypsum Backing Board

ASTM C 442/C 442M, gypsum backing board shall be used as a base in a multilayer system.

2.1.2.1 Regular

1200 mm wide, 15.9 mm thick, square edges.

2.1.2.2 Type X (Special Fire-Resistant)

1200 mm wide, 12.7 mm thick, square edges.

2.1.3 Regular Water-Resistant Gypsum Backing Board

ASTM C 630/C 630M

2.1.3.1 Regular

1200 mm wide, 12.7 mm thick, tapered edges.

2.1.4 Glass Mat Water-Resistant Gypsum Tile Backing Board

ASTM C 1178/C 1178M

2.1.4.1 Regular

1200 mm wide, 15.9 mm thick, square edges.

2.1.5 DELETED

2.1.5.1 DELETED

2.1.6 Impact Resistant Gypsum Board

1200 mm wide, 15.9 mm thick, tapered edges.

Reinforced gypsum panel with imbedded fiber mesh or lexan backing testing in accordance with the following tests. Provide fasteners that meet manufacturer requirements and specifications stated within this section. Impact resistant gypsum board, when tested in accordance with ASTM E 84, shall have a flame spread rating of 15 for face and 50 or less for back or less and a smoke developed rating of 50 or less.

2.1.6.1 Structural Failure Test

ASTM E 695 or ASTM D 2394 for structural failure (drop penetration). ASTM E 695 using a 27.2 kg sand filled leather bag, resisting no less than 407 N-m cumulative impact energy before failure or ASTM D 2394 using 139.7 mm hemispherical projectile resisting no less than 357 N-m before failure. Test specimen stud spacing shall be 406 mm or greater on center.

2.1.6.2 Indentation Test

ASTM D 5420 or ASTM D 1037 for indentation resistance. ASTM D 5420 using a .907 kg weight with a 16 mm hemispherical impacting head dropped once 915 mm creating not more than 3.5 mm indentation or ASTM D 1037 using no less than 213 kg weight applied to the 11.13 mm diameter ball to create not more than a 0.5 mm indentation depth.

2.1.7 Abuse-Resistant Gypsum Board

A gypsum core wall panel with additives to enhance surface indentation resistance, and impact resistance of the core and surfaced with abrasion resistant paper on front and long edges with heavy liner paper bonded to the back side; and complying with ASTM C 36/C 1396, Type X (Hi-Abuse Brand Wallboard). 1200 mm wide, 15.9 mm thick, tapered edges. Provide fasteners that meet manufacturer requirements.

2.1.7.1 Impact Resistance

No failure after 100 impacts when tested in accordance with ASTM E 695, modified.

2.1.7.2 Indentation Resistance

Not less than the following loads to produce the indicated depth of surface indentation when tested in accordance with ASTM D 1037, modified:

- a. 0.100 in.: 232 lbs.
- b. 0.200 in.: 469 lbs.

2.1.7.3 3M Surface Abrasion Resistance

Not greater than the following depths when tested using the indicated number of cycles in accordance with ASTM D 4977, modified:

- a. 50: 0.000 in.
- b. 100: 0.000 in.
- c. 150: 0.001 in.
- c. 200: 0.001 in.
- d. 250: 0.001 in.

2.1.7.4 Taber Surface Abrasion Resistance

Not greater than the following depths when tested using the indicated number of cycles in accordance with ASTM D 4060, modified:

- a. 25: 0.002 in.
- a. 50: 0.004 in.

- b. 75: 0.007 in.
- c. 100: 0.009 in.
- d. 125: 0.010 in.

2.1.7.5 Impact/Penetration Resistance Rating

Not less than 36 ft.-lbs. When tested in accordance with ASTM D 2394, modified.

2.1.8 Cementitious Backer Units

ANSI A118.9.

2.1.9 Joint Treatment Materials

ASTM C 475.

2.1.9.1 Embedding Compound

Specifically formulated and manufactured for use in embedding tape at gypsum board joints and compatible with tape, substrate and fasteners.

2.1.9.2 Finishing or Topping Compound

Specifically formulated and manufactured for use as a finishing compound.

2.1.9.3 All-Purpose Compound

Specifically formulated and manufactured to serve as both a taping and a finishing compound and compatible with tape, substrate and fasteners.

2.1.9.4 Setting or Hardening Type Compound

Specifically formulated and manufactured for use with fiber glass mesh tape.

2.1.9.5 Joint Tape

Cross-laminated, tapered edge, reinforced paper, or fiber glass mesh tape recommended by the manufacturer.

2.1.10 Fasteners

2.1.10.1 Nails

ASTM C 514.

2.1.10.2 Screws

ASTM C 1002, Type "G", Type "S" or Type "W" steel drill screws for fastening gypsum board to gypsum board, wood framing members and steel framing members less than 0.84 mm thick. ASTM C 954 steel drill screws for fastening gypsum board to steel framing members 0.84 to 2.84 mm thick. Provide cementitious backer unit screws with a polymer coating.

2.1.10.3 Staples

1.5 mm thick flattened galvanized wire staples with 11.1 mm wide crown outside measurement and divergent point for base ply of two-ply gypsum board application. Use as follows:

<u>Length of Legs (mm)</u>	<u>Thickness of Gypsum Board (mm)</u>
28.6	12.7
31.8	15.9

2.1.11 Adhesives

Do not use adhesive containing benzene, carbon tetrachloride, or trichloroethylene.

2.1.11.1 Adhesive for Fastening Gypsum Board to Metal Framing

Type recommended by gypsum board manufacturer.

2.1.11.2 [Enter Appropriate Subpart Title Here]2.1.11.3 Adhesive for Laminating

For laminating two-ply gypsum board systems , provide adhesive recommended by gypsum board manufacturer.

2.1.12 Gypsum Studs

25 mm minimum high and 150 mm minimum width. Studs may be of 25 mm thick gypsum board or multilayers laminated to required thickness. Conform to ASTM C 36/C 36M or ASTM C 442/C 442M for material.

2.1.13 Accessories

ASTM C 1047. Fabricate from corrosion protected steel or plastic designed for intended use. Accessories manufactured with paper flanges are not acceptable. Flanges shall be free of dirt, grease, and other materials that may adversely affect bond of joint treatment. Provide prefinished or job decorated materials.

2.1.14 DELETED

2.1.15 Water

Clean, fresh, and potable.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Framing and Furring

Verify that framing and furring are securely attached and of sizes and spacing to provide a suitable substrate to receive gypsum board and cementitious backer units. Verify that all blocking, headers and supports are in place to support plumbing fixtures and to receive soap dishes, grab bars, towel racks, and similar items. Do not proceed with work until framing and furring are acceptable for application of gypsum board and cementitious backer units.

3.1.2 Gypsum Board and Framing

Verify that surfaces of gypsum board and framing to be bonded with an adhesive are free of dust, dirt, grease, and any other foreign matter. Do not proceed with work until surfaces are acceptable for application of gypsum board with adhesive.

3.1.3 Concrete Walls

Verify that surfaces of concrete walls to receive gypsum board applied with adhesive are dry, free of dust, oil, form release agents, protrusions and voids, and any other foreign matter. Do not proceed with work until surfaces are acceptable for application of gypsum board with adhesive.

3.2 APPLICATION OF GYPSUM BOARD

Apply gypsum board to framing and furring members in accordance with ASTM C 840 or GA 216 and the requirements specified herein. Apply gypsum board with separate panels in moderate contact; do not force in place. Stagger end joints of adjoining panels. Neatly fit abutting end and edge joints. Use gypsum board of maximum practical length. Cut out gypsum board as required to make neat close joints around openings. In vertical application of gypsum board, provide panels in lengths required to reach full height of vertical surfaces in one continuous piece. Surfaces of gypsum board and substrate members may be bonded together with an adhesive, except where prohibited by fire rating(s). Treat edges of cutouts for plumbing pipes, screwheads, and joints with water-resistant compound as recommended by the gypsum board manufacturer. Provide type of gypsum board for use in each system specified herein as indicated.

3.2.1 Adhesive Application to Concrete Walls

Apply in accordance with ASTM C 840, System VI or GA 216.

3.2.2 Application of Gypsum Board to Steel Framing and Furring

Apply in accordance with ASTM C 840, System VIII or GA 216.

3.2.3 Arches and Bending Radii

Apply gypsum board in accordance with ASTM C 840, System IX or GA 216.

3.2.4 Gypsum Board for Wall Tile or Tile Base Applied with Adhesive

In dry areas (areas other than tubs, shower enclosures, saunas, steam rooms, gang shower rooms), apply glass matt water-resistant gypsum tile

backing board or water-resistant gypsum backing board in accordance with ASTM C 840, System X or GA 216.

3.2.5 DELETED

3.2.6 DELETED

3.2.7 Floating Interior Angles

Locate the attachment fasteners adjacent to ceiling and wall intersections in accordance with ASTM C 840, System XII or GA 216, for single-ply and two-ply applications of gypsum board to wood framing.

3.2.8 Control Joints

Install expansion and contraction joints in ceilings and walls in accordance with ASTM C 840, System XIII or GA 216, unless indicated otherwise. Control joints between studs in fire-rated construction shall be filled with firesafing insulation to match the fire-rating of construction.

3.2.9 Application of Impact Resistant and Abuse-Resistant Gypsum Board

Apply in accordance with applicable system of ASTM C 840 as specified or GA 216. Follow manufacturers written instructions on how to cut, drill and attach board.

3.3 APPLICATION OF CEMENTITIOUS BACKER UNITS

3.3.1 Application

In wet areas (tubs, shower enclosures, saunas, steam rooms, gang shower rooms), apply cementitious backer units in accordance with ANSI A108.11. A 7.6 kg asphalt impregnated, continuous felt paper membrane shall be placed behind cementitious backer units, between backer units and studs or base layer of gypsum board. Membrane shall be placed with a minimum 150 mm overlap of sheets laid shingle style.

3.3.2 Joint Treatment

ANSI A108.11.

3.4 FINISHING OF GYPSUM BOARD

Tape and finish gypsum board in accordance with ASTM C 840, GA 214 and GA 216. Plenum areas above ceilings shall be finished to Level 1 in accordance with GA 214. Water resistant gypsum backing board, ASTM C 630/C 630M, to receive ceramic tile shall be finished to Level 2 in accordance with GA 214. Walls and ceilings to receive a heavy-grade wall covering or heave textured finish before painting shall be finished to Level 3 in

accordance with GA 214. Walls and ceilings without critical lighting to receive flat paints, light textures, or wall coverings shall be finished to Level 4 in accordance with GA 214. Unless otherwise specified, all gypsum board walls, partitions and ceilings shall be finished to Level 5 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Do not use fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer.

3.4.1 Uniform Surface

Wherever gypsum board is to receive eggshell, semigloss or gloss paint finish, or where severe, up or down lighting conditions occur, finish gypsum wall surface in accordance to GA 214 Level 5. In accordance with GA 214 Level 5, apply a thin skim coat of joint compound to the entire gypsum board surface, after the two-coat joint and fastener treatment is complete and dry.

3.5 SEALING

Seal openings around pipes, fixtures, and other items projecting through gypsum board and cementitious backer units as specified in Section 07900a "Joint Sealing." Apply material with exposed surface flush with gypsum board or cementitious backer units.

3.5.1 Sealing for Glass Mat or Reinforced Gypsum Board Sheathing

Apply silicone sealant in a 9.5 mm bead to all joints and trowel flat. Apply enough of the same sealant to all fasteners penetrating through the glass mat gypsum board surface to completely cover the penetration when troweled flat. Construction and materials shall not be placed behind sheathing until a visual inspection of sealed joints during daylight hours has been completed by Contracting Officer.

3.6 FIRE-RESISTANT ASSEMBLIES

Wherever fire-rated construction is indicated, provide materials and application methods, including types and spacing of fasteners, wall and ceiling framing in accordance with the specifications contained in UL Fire Resist Dir for the Design Number(s) indicated, or GA 600 for the File Number(s) indicated. Joints of fire-rated gypsum board enclosures shall be closed and sealed in accordance with UL test requirements or GA requirements. Penetrations through rated partitions and ceilings shall be sealed tight in accordance with tested systems. Fire ratings shall be as indicated.

3.7 PATCHING

Patch surface defects in gypsum board to a smooth, uniform appearance, ready to receive finish as specified.

-- End of Section --

SECTION 09650A

RESILIENT FLOORING

07/96

PART 1 GENERAL

Where components or finishes are required only in specific building/facility types within this project, their location shall be designated by the following abbreviations:

BRKS = Barracks Buildings
SCB = Soldier Community Building
BHQ = Battalion Headquarters Building
COF = Company Operations Facilities

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 2240	(1997) Rubber Property - Durometer Hardness
ASTM D 4078	(1992; R 1996) Water Emulsion Floor Polish
ASTM E 648	(1997) Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM E 662	(1995) Specific Optical Density of Smoke Generated by Solid Materials
ASTM F 1066	(1995a) Vinyl Composition Floor Tile
ASTM F 1303	(1997) Sheet Vinyl Floor Covering with Backing
ASTM F 1344	(1993) Rubber Floor Tile
ASTM F 1700	(1996) Solid Vinyl Floor Tile

1.2 FIRE RESISTANCE REQUIREMENTS

Flooring in corridors and exits shall have a minimum average critical radiant flux of 0.45 watts per square centimeter when tested in accordance with ASTM E 648. The smoke density rating shall be less than 450 when

tested in accordance with ASTM E 662.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. All items designated with a "G, RE", including product literature, calculations, component data, certificates, diagrams, drawings, and samples shall be submitted concurrently in one complete system submittal. Omission of any required submittal item from the package shall be sufficient cause for disapproval of the entire submittal. Unless otherwise indicated in the submittal review commentary, disapproval of any item within the package shall require a re-submittal of the entire system package, in which all deficiencies shall be corrected. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Floor Patterns and Borders; G, RE.

Installer's shop drawings showing proposed tile location, patterns, accent tile locations, and border locations including border dimensions. Submittal of duplicated or photocopied project drawing floor tile layouts in lieu of installer produced original shop drawings indicates contractor's full compliance of the tile placement and pattern/border locations as shown on the project drawings with no variances.

SD-03 Data

Resilient Flooring and Accessories; G, RE.

Manufacturer's descriptive data and installation instructions including cleaning and maintenance instructions.

SD-04 Samples

Resilient Flooring and Accessories; G, RE.

Three samples of each indicated color and type of flooring and base. Sample size shall be minimum 60 mm x 100 mm.

SD-06 Test Reports

Resilient Flooring and Accessories; G, RE.

Copies of test reports showing that representative product samples of the flooring proposed for use have been tested by an independent testing laboratory within the past three years or when formulation change occurred and conforms to the requirements specified.

1.4 DELIVERY AND STORAGE

Materials shall be delivered to the building site in original unopened containers bearing the manufacturer's name, project identification, and handling instructions. Materials shall be stored in a clean dry area with temperature maintained above 21 degrees C for 2 days prior to installation, and shall be stacked according to manufacturer's recommendations. Materials shall be protected from the direct flow of heat from hot-air registers, radiators and other heating fixtures and appliances.

1.5 ENVIRONMENTAL REQUIREMENTS

Areas to receive resilient flooring shall be maintained at a temperature above 21 degrees C and below 38 degrees C for 2 days before application, during application and 2 days after application. A minimum temperature of 13 degrees C shall be maintained thereafter.

1.6 SCHEDULING

Resilient flooring application shall be scheduled after the completion of other work which would damage the finished surface of the flooring.

1.7 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided.

PART 2 PRODUCTS

2.1 VINYL-COMPOSITION TILE TYPE (VCT)

Vinyl-composition tile shall conform to ASTM F 1066, Class 1, (solid color tile), Class 2, (through pattern tile), Composition 1, asbestos-free, and shall be 305 mm square and 3.2 mm thick. Tile shall have the color and pattern uniformly distributed throughout the thickness of the tile. Flooring in any one continuous area shall be from the same lot and shall have the same shade and pattern.

2.2 RUBBER TILE (RFT) {BRKS}

Rubber tile shall conform to ASTM F 1344 Class 1 homogeneous construction, Type A (solid color) 500 mm square by 3 mm thick. Surface shall be a textured slate pattern.

2.3 RESILIENT BASE

Rubber wall base shall be Type TS, thermoset vulcanized extruded type and shall conform to ASTM F 1861, Group 1 (solid). All rubber wall base shall be 102 mm high and a minimum thickness of 3.18 mm. All rubber wall base shall be a manufacturer's standard product in a straight or coved profile, and in locations as indicated and shown on the drawings. No pre-formed outside corners shall be allowed. Rubber wall base shall be provided in continuous roll form (36.5 M coil) to minimize seaming. Factory-cut lengths are not allowed.

2.4 FLOORING TRANSITION STRIP (FTS)

A vinyl or rubber transition strip tapered to meet abutting material shall be provided in composition, profiles, and sizes as shown on the drawings. Colors shall be as shown on the Interior Finish Materials Legend in the drawings.

2.5 COLOR

Color and pattern for resilient flooring and colors for wall bases shall as indicated in the Interior Finish Materials Legend on the drawings.

2.6 ADHESIVE

Adhesive for flooring and wall base shall be as recommended by the flooring manufacturer.

2.7 POLISH

Polish shall conform to ASTM D 4078.

2.8 CAULKING AND SEALANTS

Caulking and sealants shall be in accordance with Section 07900 JOINT SEALING.

PART 3 EXECUTION

3.1 EXAMINATION/VERIFICATION OF CONDITIONS

The Contractor shall examine and verify that site conditions are in agreement with the design package and shall report all conditions that will prevent a proper installation. The Contractor shall not take any corrective action without written permission from the Government.

3.2 SURFACE PREPARATION

Flooring shall be in a smooth, true, level plane, except where indicated as sloped. Before any work under this section is begun, all defects such as rough or scaling concrete, low spots, high spots, and uneven surfaces shall have been corrected, and all damaged portions of concrete slabs shall have been repaired as recommended by the flooring manufacturer. Concrete curing compounds, other than the type that does not adversely affect adhesion, shall be entirely removed from the slabs. Paint, varnish, oils, release agents, sealers, waxers, and adhesives shall be removed, as recommended by the flooring manufacturer.

3.3 MOISTURE TEST

The suitability of the concrete subfloor for receiving the resilient flooring with regard to moisture content shall be determined by a moisture test as recommended by the flooring manufacturer.

3.4 INSTALLATION OF VINYL-COMPOSITION TILE

Tile flooring shall be installed with adhesive in accordance with the manufacturer's installation instructions. Tile lines and joints shall be kept square, symmetrical, tight, and even. Edge width shall vary as necessary to maintain full-size tiles in the field, but no edge tile shall be less than one-half the field tile size, except where irregular shaped rooms make it impossible. Flooring shall be cut to, and fitted around, all permanent fixtures, built-in furniture and cabinets, pipes, and outlets. Edge tile shall be cut, fitted, and scribed to walls and partitions after field flooring has been applied.

3.4.1 Floor Patterns and Borders

Tile patterns and borders shall be as shown on the drawings and approved shop drawings. Accent tiles shall be placed in location and quantity as shown on the drawings. Border widths and locations shall be as shown on the drawings.

3.5 INSTALLATION OF RUBBER FLOOR TILE

Rubber floor tile shall be installed with adhesive in accordance with the manufacturer's written installation instructions. Tiles shall be laid to maximize full tile width wherever possible. Flooring shall be cut to, and fitted around, all permanent fixtures, pipes, and outlets.

3.6 INSTALLATION OF RUBBER WALL BASE

Wall base shall be installed with adhesive in accordance with the manufacturer's written instructions. Base joints shall be tight and base shall be even with adjacent resilient flooring. Voids along the top edge of base at masonry walls shall be filled with caulk.

3.6.1 Wall Base Corners

Wall base corners shall not be separate preformed components. Inside and outside corners shall be formed from roll goods utilizing a scribing method as recommended by the wall base manufacturer to provide a continuous one-piece appearance at all corners.

3.7 INSTALLATION OF FLOOR TRANSITION STRIPS

Transition strips shall be installed with manufacturer's recommended adhesive and in accordance with manufacturer's recommended installation instructions. Transition strips shall be installed tight to adjacent flooring materials and with proper overlap where specified.

3.8 CLEANING

Immediately upon completion of installation of tile in a room or an area, flooring and adjacent surfaces shall be cleaned to remove all surplus adhesive. After installation, flooring shall be washed with a cleaning solution, rinsed thoroughly with clear cold water, and, except for raised pattern rubber flooring, rubber tile and sheet rubber flooring, rubber stair treads, and static control vinyl tile, given two coats of polish in accordance with manufacturers written instructions. After each polish

coat, floors shall be buffed to an even luster with an electric polishing machine. Raised pattern rubber flooring, rubber tile and sheet rubber flooring, rubber stair treads, and static control vinyl tile shall be cleaned and maintained as recommended by the manufacturer.

3.9 PROTECTION

From the time of laying until acceptance, flooring shall be protected from damage as recommended by the flooring manufacturer. Flooring which becomes damaged, loose, broken, or curled shall be removed and replaced.

-- End of Section --

SECTION 10430A

EXTERIOR SIGNAGE

06/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF-45 (1997) Designation System for Aluminum Finishes

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1 (1984; R 1994) Safety Performance Specifications and Methods of Test for Safety Glazing Materials Used in Buildings

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 36/A 36M (2000) Carbon Structural Steel

ASTM A 123/A 123M (2000) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A 570/A 570M (1998) Steel, Sheet and Strip, Carbon, Hot-Rolled, Structural Quality

ASTM A 653/A 653M (2000) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM A 924/A 924M (1999) General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process

ASTM B 26/B 26M (1999) Aluminum-Alloy Sand Castings

ASTM B 62 (1993) Composition Bronze or Ounce Metal Castings

ASTM B 108 (1999) Aluminum-Alloy Permanent Mold Castings

ASTM B 209 (1996) Aluminum and Aluminum-Alloy Sheet

and Plate

ASTM B 209M	(2000) Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM B 221	(2000) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B 221M	(2000) Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM C 1036	(1991; R 1997) Flat Glass
ASTM D 3841	(1997) Glass-Fiber-Reinforced Polyester Plastic Panels
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 505	(1988) Metal Finishes Manual for Architectural and Metal Products
---------------	---

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE AMS 3611	(1994; Rev D) Plastic Sheet, Polycarbonate General Purpose
--------------	--

1.2 GENERAL

All exterior signage shall be provided by a single manufacturer. Exterior signage shall be of the design, detail, sizes, types, and message content shown on the drawings, shall conform to the requirements specified, and shall be provided at the locations indicated. Signs shall be complete with lettering, framing as detailed, and related components for a complete installation. Recyclable materials shall conform to EPA requirements in accordance with Section 01670 RECYCLED / RECOVERED MATERIALS.

1.3 CHARACTER PROPORTIONS AND HEIGHTS

Letters and numbers on indicated signs for handicapped-accessible buildings shall have a width-to-height ratio between 3:5 and 1:1 and a stroke-width-to-height ratio between 1:5 and 1:10. Characters and numbers on indicated signs shall be sized according to the viewing distance from which they are to be read. The minimum height is measured using an upper case letter "X". Lower case characters are permitted.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Approved Detail Drawings; G, RE.

Drawings showing elevations of each type of sign; dimensions, details, and methods of mounting or anchoring; shape and thickness of materials; and details of construction. A schedule showing the location, each sign type, and message shall be included.

SD-03 Product Data

Manufacturer's descriptive data and catalog cuts.

Installation; G, RE.

Manufacturer's installation instructions and cleaning instructions.

Exterior Signs; G, RE.

Exterior signage schedule in electronic media with spread sheet format. Spread sheet shall include sign location, sign type, and message.

SD-04 Samples

Exterior Signs; G, RE.

One 300 mm length of framing for illuminated signs. One sample of each type of sign. Each sample shall consist of a complete sign panel with letters and symbols. Samples may be installed in the work, provided each sample is identified and location recorded. Two samples of manufacturer's standard color chips for each material requiring color selection and 305 mm square sample of sign face color sample.

1.5 QUALIFICATIONS

Signs, plaques, and dimensional letters shall be the standard product of a manufacturer regularly engaged in the manufacture of the products. Items of equipment shall essentially duplicate equipment that has been in satisfactory use at least 2 years prior to bid opening.

1.6 DELIVERY AND STORAGE

Materials shall be wrapped for shipment and storage, delivered to the jobsite in manufacturer's original packaging, and stored in a clean, dry

area in accordance with manufacturer's instructions.

1.7 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period shall be provided.

PART 2 PRODUCTS

2.1 [Enter Appropriate Subpart Title Here]2.1.1 [Enter Appropriate Subpart Title Here]2.1.1.1 Exterior Sheeting Panels

Panels shall be provided in sizes shown on drawings. Panels shall be fabricated a minimum of 6 mm thick fiberglass reinforced plastic (FRP). Top and end panels shall be removable and shall be secured by 5 mm socket head jack nuts. Finish for metal panels shall be two-component acrylic polyurethane .

2.1.1.2 Mounting

Mounting shall be provided by securing to substrate as shown.

2.1.1.3 Finishes

Base finish shall be two-component acrylic polyurethane . Metal panel system finish shall be baked enamel or two-component acrylic polyurethane .

2.2 [Enter Appropriate Subpart Title Here]

2.3 GRAPHICS FOR EXTERIOR SIGNAGE SYSTEMS

2.3.1 Graphics

Signage graphics shall match exterior graphics to Phase I Whole Barracks Renewal construction.

2.4 [Enter Appropriate Subpart Title Here]2.4.1 [Enter Appropriate Subpart Title Here]2.4.1.1 [Enter Appropriate Subpart Title Here]

2.4.2 [Enter Appropriate Subpart Title Here]2.4.2.1 [Enter Appropriate Subpart Title Here]2.5 ANCHORS AND FASTENERS

Exposed anchor and fastener materials shall be compatible with metal to which applied and shall match in color and finish and shall be non-rusting, non-corroding, and non-staining. Exposed fasteners shall be tamper-proof.

2.6 SHOP FABRICATION AND MANUFACTURE

2.6.1 Factory Workmanship

Work shall be assembled in the shop, as far as practical, ready for installation at the site. Work that cannot be shop assembled shall be given a trial fit in the shop to ensure proper field assembly. Holes for bolts and screws shall be drilled or punched. Drilling and punching shall produce clean, true lines and surfaces.

2.6.2 Dissimilar Materials

Where dissimilar metals are in contact, or where aluminum is in contact with concrete, mortar, masonry, wet or pressure-treated wood, or absorptive materials subject to wetting, the surfaces shall be protected with a coat of asphalt varnish or a coat of zinc-molybdate primer to prevent galvanic or corrosive action.

2.6.3 Shop Painting

Surfaces of miscellaneous metal work, except nonferrous metal, corrosion resisting steel, and zinc-coated work, shall be given one coat of zinc-molybdate primer or an approved rust-resisting treatment and metallic primer in accordance with manufacturer's standard practice. Surfaces of items to be embedded in concrete shall not be painted. Upon completion of work, damaged surfaces shall be recoated.

2.7 COLOR, FINISH, AND CONTRAST

Color of products shall be as selected by the Contracting Officers Representative, and shall match the building modules from the first phase of construction, and shall be in accordance with the Post installation design guide. Characters and symbols shall contrast with their background - either light characters on a dark background or dark characters on a light background.

PART 3 EXECUTION

3.1 INSTALLATION

Signs, plaques, or dimensional letters shall be installed in accordance with approved manufacturer's instructions at locations shown on the approved detail drawings. Circuits installed underground shall conform to the requirements of Section 16375 ELECTRICAL DISTRIBUTION SYSTEM, UNDERGROUND. Steel conduits installed underground and illuminated signage mounted directly on buildings shall be in conformance with the requirements of Section 16415 ELECTRICAL WORK, INTERIOR. Signs shall be installed plumb and true at mounting heights indicated, and by method shown or specified. Signs mounted on other surfaces shall not be installed until finishes on such surfaces have been completed.

3.1.1 Anchorage

Anchorage and fastener materials shall be in accordance with approved manufacturer's instructions for the indicated substrate. Anchorage not otherwise specified or indicated shall include slotted inserts, expansion shields, and powder-driven fasteners when approved for concrete; toggle bolts and through bolts for masonry; machine carriage bolts for steel; lag bolts and screws for wood.

3.1.2 Protection and Cleaning

The work shall be protected against damage during construction. Hardware and electrical equipment shall be adjusted for proper operation. Glass,

frames, and other sign surfaces shall be cleaned in accordance with manufacturer's instructions. After signs are completed and inspected, the Contractor shall cover all project identification, directional, and other signs which may mislead the public. Covering shall be maintained until instructed to be removed by the Contracting Officer or until the facility is to be opened for business. Signs shall be cleaned, as required, at time of cover removal.

-- End of Section --

SECTION 10500

LOCKERS
05/99

PART 1 GENERAL

Where components or finishes are required only in specific building/facility types within this project, their location shall be designated by the following abbreviations:

BRKS = Barracks Buildings
SCB = Soldier Community Building
BHQ = Battalion Headquarters Building
COF = Company Operations Facilities

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. All items designated with a "G, RE", including product literature, calculations, component data, certificates, diagrams, drawings, and samples shall be submitted concurrently in one complete system submittal. Omission of any required submittal item from the package shall be sufficient cause for disapproval of the entire submittal. Unless otherwise indicated in the submittal review commentary, disapproval of any item within the package shall require a re-submittal of the entire system package, in which all deficiencies shall be corrected. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Data

Manufacturer's data; G, RE.

Submit manufacturer's data and written specifications on lockers.

SD-04 Drawings

Drawings; G, RE.

Submit shop drawings showing layout, elevations and details of all lockers. Indicate materials and thickness.

SD-14 SD Samples

Manufacturer's finishes; G, RE.

Submit actual color chips a minimum of 150 mm by 150 mm of locker finish colors. Finish and color of all components shall match those specified in

the drawings Interior Finish Materials Legend. Finish and color shall not be limited to manufacturer's standard finish selections but shall be standard or custom color as required to meet the project color requirements.

1.2 DELIVERY AND STORAGE

Deliver materials in manufacturer's original unopened containers. Provide blocking as required, store materials under cover and protect against damage.

1.3 SCHEDULING

Lockers shall not be assembled, installed and set in place until all interior room finishes and materials at the installation location have been applied or installed and are completely set or dry.

PART 2 PRODUCTS

2.1 LOCKERS (LK-1) {BHQ, COF}

Lockers shall be double tiered as indicated and located on the drawings. Lockers shall be wardrobe storage type, equal to Republic Storage Systems Lockers, Canton, OH, (John Burrow, 816/380-7120), "Quiet" model. All major steel parts shall be fabricated from mild, cold rolled steel, free from imperfections and capable of taking a high grade enamel finish. Standard equipment shall include one double prong ceiling hook and three single prong wall hooks attached with two bolts for each hook component. Finish shall be baked-on enamel. Overall dimensions shall be 305 mm wide x 457 mm deep x 1829 mm high.

2.1.1 Locker Body

All locker body components, tops, bottoms, shelves, sides, and backs shall be made of 24 gauge steel. Tops, bottoms, and shelves shall have single flanges on all four sides. Backs shall be flanged on three sides. A double bend shall be provided on the front edge of all shelves. All nuts and bolts shall be zinc or cadmium plated.

2.1.1.1 Sloping Top

All locker units shall receive a continuous sloping top with slip joint splices, hip and valley ends and corners without exposed fasteners. All sloped top components shall be fabricated from 24 gauge steel.

2.1.2 Locker Doors

Door shall be 16 gauge steel, formed with a full channel shape on the lock bar side to fully conceal the lock bar, channel formation on the hinge side and right angle formations across the top and bottom. Locker doors shall include a minimum of 4 louver ventilation slots, top and bottom.

2.1.2.1 Locker Door Hinges

Provide three hinges for each door on locker. Each hinge shall be 2 inches

long, five knuckle tight pin type, securely welded to frame and secured to door with rivets.

2.1.2.2 Locker Door Latching Mechanism

Door latching device shall be a one-piece, pre-lubricated, spring steel latch completely contained within the lock bar, under tension, to provide rattle-free operation. The lock bar shall be pre-painted, double-channel steel construction. The lock bar shall be securely contained within the door channel by self-lubricating polyethylene guides that isolate the lock bar from metal-to-metal contact with the door. There shall be three latching points for lockers over 1066 mm in height and two latching points for all lockers under 1066 mm in height. The lock bar travel shall be limited by contacting resilient high-quality, elastomeric cushioning devices concealed inside the lock bar.

2.1.2.3 Recessed Handle

A non-protruding 14 gauge lifting trigger shall be provided for actuating the lock bar when opening the door. It shall be contained in a formed 20 gauge stainless steel pocket with exposed portion encased in molded ABS thermoplastic cover that provides isolation from metal to metal contact. The trigger shall be an integral part of the steel slide plate which transfers the lifting force to the lock bar. The stainless steel pocket shall contain a recessed mounting area for the various lock types available and also mounting for the number plate.

2.1.2.4 Locker Door Number Plate

Each door shall have a polished aluminum number plate with black background and etched aluminum numerals not less than 9.5 mm high. Plates shall be attached with pop rivets.

2.1.3 Door Frames

Door frames shall be 16 gauge steel formed into deep 25 mm face channel shapes with a continuous vertical door strike integral with the frame on both sides of the door opening. Cross frame members of 16 gauge channel shapes, including intermediate cross frame on double tier lockers shall be securely welded to vertical framing members to insure a square and rigid assembly.

2.1.3.1 Frame Hooks/Silencers

Frame hooks to accept latching shall be of heavy gauge steel, set close in and welded to the door frame. Continuous vertical door strike shall protect frame hooks from door slam damage. A soft rubber silencer shall be provided and securely installed on each frame hook.

2.1.4 2.1.4 Locker Base (BHQ Only)

Provide a minimum 16-gauge, 102 mm high, continuous metal Zee base flanged outward at the top for support of lockers and inward at the bottom for anchoring to floor. Lengths to be as long as practical with reinforced

hairline joints. Bases shall be finished to match lockers.

2.2 TA-50 GEAR LOCKERS (TYPE LK-2) {COF}

All lockers shall be double tiered as indicated and located on the drawings. Lockers shall be wardrobe storage type, equal to Republic Storage Systems Lockers, "All Welded Ventilated" model. Locker units shall be shipped pre-assembled and ready to install. No nuts, bolts, or rivets shall be utilized or allowed in assembly of main locker groups. All major steel parts shall be fabricated from mild, cold rolled steel, free from imperfections and capable of taking a high grade enamel finish. Standard equipment shall include one double prong ceiling hook and three single prong wall hooks attached with two bolts for each hook component. Finish shall be baked-on enamel. Overall dimensions of each double tiered unit shall be 610 mm wide x 610 mm deep x 1829 mm high.

2.2.1 Locker Body

All locker body components, tops, bottoms, shelves, sides, and backs shall be made of 16 gauge steel. All uprights shall contain a diamond-shaped opening, 19mm wide by 38mm high, in a pattern and quantity to provide maximum ventilation on all sides. Exposed panels at end of rows shall be solid without ventilation. Tops, bottoms, and shelves shall be fully flanged on all sides. Backs shall be flanged on three sides. A double bend shall be provided on the front edge of all shelves. All nuts and bolts shall be zinc or cadmium plated.

2.2.1.1 Sloping Top

All locker units shall receive a continuous sloping top with slip joint splices, hip and valley ends and corners without exposed fasteners. All sloped top components shall be fabricated from 24 gauge steel.

2.2.2 Locker Doors

Door shall be 14 gauge steel, formed from one piece, with a full channel shape on the lock bar side to fully conceal the lock bar, channel formation on the hinge side and right angle formations across the top and bottom. Locker doors shall include a mini-louver penetration pattern, both at the top and bottom of the door to provide ventilation while concealing the locker contents.

2.2.2.1 Locker Door Hinges

Provide two hinges for each locker door. Each hinge shall be 2 inches long, five knuckle tight pin type, securely welded to frame and secured to door with rivets.

2.2.2.2 Locker Door Latching Mechanism

Door latching device shall be a one-piece, pre-lubricated, spring steel latch completely contained within the lock bar, under tension, to provide

rattle-free operation. The lock bar shall be pre-painted, double-channel steel construction. The lock bar shall be securely contained within the door channel by self-lubricating polyethylene guides that isolate the lock bar from metal-to-metal contact with the door. There shall be three latching points for lockers over 1066 mm in height and two latching points for all lockers under 1066 mm in height. The lock bar travel shall be limited by contacting resilient high-quality, elastomeric cushioning devices concealed inside the lock bar.

2.2.2.3 Recessed Handle

A non-protruding 14 gauge lifting trigger shall be provided for actuating the lock bar when opening the door. It shall be contained in a formed 20 gauge stainless steel pocket with exposed portion encased in molded ABS thermoplastic cover that provides isolation from metal to metal contact. The trigger shall be an integral part of the steel slide plate which transfers the lifting force to the lock bar. The stainless steel pocket shall contain a recessed mounting area for the various lock types available and also mounting for the number plate.

2.2.2.4 Locker Door Number Plate

Each door shall have a polished aluminum number plate with black background and etched aluminum numerals not less than 10mm high. Plates shall be attached with pop rivets.

2.2.3 Door Frames

Door frames shall be 16 gauge steel formed into deep 25 mm face channel shapes with a continuous vertical door strike integral with the frame on both sides of the door opening. Cross frame members of 16 gauge channel shapes, including intermediate cross frame on double tier lockers shall be securely welded to vertical framing members to insure a square and rigid assembly.

2.2.3.1 Frame Hooks/Silencers

Frame hooks to accept latching shall be of heavy gauge steel, set close in and welded to the door frame. Continuous vertical door strike shall protect frame hooks from door slam damage. A soft rubber silencer shall be provided and securely installed on each frame hook.

2.2.4 Locker Base

Provide a minimum 16 gauge, 152mm height, continuous metal "Zee" base flanged outward at top for support of lockers and inward at bottom for anchoring to floor. lengths to be as long as practical with reinforced hairline joints. Bases shall be finished to match the lockers.

2.3 2.3 LOCKER BENCH (COF)

Locker benches shall be laminated maple, 32 mm full finished thickness. All corners are to be rounded and sanded. Top and edges have two coats of a clear finish with one coat on the bottom. Bench tops are to be 241 mm

wide and furnished in lengths as shown on the drawings (whole foot increments- metric equivalents). Tops to be mounted on pedestals consisting of 32 mm O.D. tubing with 10 gauge steel flanges welded to each end. The overall height of bench assembly shall be 445 mm. Pedestals are to be finished to match locker color located in the same area.

2.4 COLOR

Locker colors shall match those indicated in the drawing Interior Finish Materials Legend and project colorboards.

PART 3 EXECUTION

3.1 INSTALLATION

Install lockers and floor mounted benches in areas indicated. Install in accordance with approved shop drawings, details shown on project drawings, and manufacturers recommendations. Fasten lockers together and then to walls and floor with minimum of two fasteners per locker and appropriate expansion anchors, wall furring strips, and recessed floor plate in the raised concrete base.

3.2 CLEAN-UP

Upon completion of installation, clean all surfaces. Touch-up all scratches and marks with touch-up paint provided by locker manufacturer.

-- End of Section --

SECTION 10520

FIRE EXTINGUISHER CABINETS

05/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM E-814 (1999) TEST

1.2 RELATED WORK

1.2.1 Field Painting

Field painting shall be as specified in Section 09900, PAINTING.

1.3 SUBMITTALS

Government approval is required for submittals with a "GA" designation; submittals having an "FIO" designation are for information only. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Data

Fire Extinguisher Cabinet; G, RE

Submittal shall include manufacturer's catalog literature and data.

SD-06 Instructions

Fire Extinguisher Cabinet; G, RE

Manufacturer's printed installation instructions.

1.4 STORAGE

Fire extinguisher cabinets shall be delivered to the job site boxed in the manufacturer's original container with the brands and names clearly marked thereon. They shall be stored in a dry location that is adequately ventilated and free from dust, water or other contaminants. Fire extinguisher cabinets shall be handled carefully to prevent damage. Damaged items that cannot be restored to like new condition shall be replaced.

PART 2 PRODUCTS

2.1 FIRE EXTINGUISHER CABINET

Semi-recessed fire extinguisher cabinets shall be similar to J.L. Industries' Ambassador or approved equal as follows:

- No. 1017L22 with decal Fire-FX in fire rated partitions (Barracks only)
- No. 1017L22 with decal in non-fire rated partitions (Barracks only)
- No. 1017S21 with decal in non-fire rated partitions (COF, SCB & BNHQ only)

A surface-mounted cabinet shall be located as indicated on the drawings and shall be similar to J.L. Industries' No. 1013S21 with decal or approved equal.

2.1.1 Tank

The Tank shall be manufactured of 20 gauge steel minimum. The tank shall have a factory applied white baked enamel or electrostatic white epoxy primer finish. The minimum inside dimensions of the tank shall be 610 mm by 228 mm by 152 mm. Semi-recessed fire extinguisher cabinets shall be fire rated in accordance with ASTM E-814. The government will furnish fire extinguishers to the contractor to install in cabinets.

2.1.2 Trim

Trim shall be semi-recessed style with rolled edge projecting not more than 64 mm. Trim shall be 20 gauge steel construction with a factory applied white baked enamel or electrostatic white epoxy primer finish. All exposed joints shall be fully welded and ground smooth.

2.1.3 Door

Door construction shall be 20 gauge steel with a factory applied white baked enamel or electrostatic white epoxy primer finish. Doors shall have a continuous piano hinge of a metal compatible with the door construction. Doors shall be locked and have break glass door glazing with style as specified.

PART 3 EXECUTION

3.1 INSTALLATION

Install fire extinguisher cabinets in prepared openings and secure in accordance with the manufacturer's instructions. Install cabinet so that bottom of cabinet is the correct height from finish floor as shown on drawings. Upon completion doors shall be free from warp, twist or distortion. Doors shall be lubricated, properly adjusted and demonstrated to operate freely when opened.

3.1.1 Installation in Fire Rated Walls

Fire extinguisher cabinets installed in fire rated walls or partitions shall be rated cabinets in accordance with ASTM E 814.

3.2 FINISH

The trim, tank and door shall be painted white. The decal letters shall be red.

-- End of Section --

SECTION 10605N

WIRE MESH PARTITIONS

09/99

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred within the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG-673 (1986) Cold-Formed Steel Design Manual

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 36/A 36M (1996) Carbon Structural Steel

1.2 SUBMITTALS

Submit the following in accordance with Section 01330, "Submittal Procedures."

SD-02 Shop Drawings

Wire mesh partitions G, RE

Show layout, details, materials, dimensions, finishes, and all information necessary for fabrication and installation.

SD-03 Product Data

Wire mesh partitions G, RE

Submit for each type of partition, door, and window.

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials in manufacturer's original, unopened containers or packaging with labels intact and legible. Deliver, store, and handle materials so as to prevent damage. Replace damaged or defective materials with new.

1.4 DESCRIPTION OF WORK

Wire mesh partitions shall be all wire type, normal duty for normal industrial use in the Barracks only and heavy duty for extra heavy industrial use in the Company Operations Facilities only, and shall be provided complete with fasteners, capping bars, adjustable floor sockets, bracing, doors, service windows, hardware, and other items necessary for a

complete, useable, and rigid installation.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Steel Shapes, Plates, and Bars

ASTM A 36/A 36M.

2.1.2 Cold-Formed Steel

AISI SG-673.

2.1.3 Wire Mesh

Carbon steel wire, woven diamond mesh, intermediate crimped.

2.1.4 Floor Sockets

Cast or forged steel or ductile iron, adjustable, approximately 64 mm high.

2.2 NORMAL DUTY PARTITIONS (For Baracks Only)

2.2.1 Wire Mesh

10 gage wire, 38 mm mesh.

2.2.2 Vertical Frames

32 by 16 mm cold-rolled C section channels or 32 by 16 by 3 mm channels.
Provide only C channels where frames are installed toe to toe without posts.

2.2.3 Horizontal Frames

25 by 16 mm channels.

2.2.4 Center Reinforcing Bar

One 25 by 13 by 3 mm channel with all wires woven through, or two 25 by 10 by 3 mm channels bolted together with mesh in between.

2.2.5 Capping Bar

56 by 25 by 3 mm channel or 50 by 6 mm flat bar.

2.2.6 Corner Posts

Structural steel angles, 32 by 32 by 3 mm.

2.2.7 Line Posts

Unless otherwise indicated, provide partitions more than 3600 mm high with flat bar line posts bolted between vertical frame channels. Sizes of posts

shall be as follows:

Partition Height	Size of Posts
3600 to 4400 mm	44 by 7.9 mm or 50 by 6 mm
4400 to 5900 mm	63 by 7.9 mm
5900 to 7100 mm	75 to 7.9 mm

2.2.8 Hinged Doors

Frames shall be 32 by 13 by 3 mm channels with 32 by 3 mm flat bar cover on top and bottom rails and on hinge stile and a 35 by 20 by 3 mm angle riveted to the lock stile. Provide 1 1/2 pairs of regular weight, wrought steel, non-removable pin, butt hinges riveted or welded to the door and the door opening frame for each door.

2.2.9 Sheet Metal Base

Not Used.

2.3 HEAVY DUTY PARTITIONS (For Company Operations Facilities Only)

2.3.1 Wire Mesh

6 gage wire, 50 mm mesh.

2.3.2 Panel Frames

38 by 20 by 3 mm steel channels.

2.3.3 Center Reinforcing Bar

One 38 by 20 by 3 mm channel with all wires woven through, or two 32 by 10 by 3 mm channels bolted together with mesh in between.

2.3.4 Capping Bar

Structural steel channel, 75 mm by 1.9 kg.

2.3.5 Corner Posts

Structural steel angles, 45 by 45 by 3 mm.

2.3.6 Line Posts

Unless otherwise indicated, provide partitions with flat bar line posts bolted between vertical frame channels. Sizes of posts shall be as follows:

Partition Height	Size of Posts
2100 to 3600 mm	62 by 7.9 mm

Partition Height	Size of Posts
3600 to 4800 mm	75 by 7.9 mm or 62 by 10 mm
4800 to 6000 mm	87 by 7.9 mm

2.3.7 Hinged Doors

Frames shall be 38 by 20 by 3 mm channels with 38 by 3 mm flat bar cover on top and bottom rails and on hinge stile and a 41 by 22 by 3 mm angle riveted to the lock stile. Provide 1 1/2 pairs of heavyweight, wrought steel, non-removable pin, butt hinges riveted or welded to the door and the door opening frame for each door.

2.4 SLIDING DOORS

Not Used.

2.5 DOOR OPENING FRAMES

Provide frames the same size and shape as the vertical frames for the mesh panels.

2.6 LOCKS

Provide each door in the Company Operations Facility with a heavy duty fixed staple hasp welded to the plate stop & door frame. Attach a heavy duty fixed staple welded to the partition frame. Provide each door in the Barracks with a normal duty fixed staple hasp welded to the plate stop & door frame. Attach a normal duty fixed staple welded to the partition frame.

2.7 SERVICE WINDOWS

Slide up type, mounted in standard mesh panel reinforced with channel tracks. Opening shall be 600 mm wide by 450 mm high unless otherwise indicated. Provide two spring loaded latches, operable only from the inside, to lock window in open and closed positions. Form shelf of 10 gage sheet steel, 300 mm deep by 625 mm wide, unless otherwise indicated.

2.8 FABRICATION

2.8.1 Standard Panels

Wire shall be woven into diamond mesh, intermediate crimped, and securely clinched to frames. Joints shall be mortised and tenoned. Wire shall be continuous at center reinforcing bars, either woven through a single channel or bolted between two channels. Panel vertical frames shall have 6 mm bolt holes 300 mm o.c. for normal duty partitions(Barracks) and shall have 10 mm bolt holes 450 mm o.c. for heavy duty partitions(COF's).

2.8.2 Sheet Metal Base Panels

Not Used.

2.8.3 Doors and Service Windows

Construction shall be similar to that specified for panels. Wire mesh shall be the same as that used in the adjacent partition panels.

2.8.4 Finish

Thoroughly clean ferrous metal, treat with phosphate. Color shall be as indicated in the Interior Finish Material Legend sheet A9.1.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Wire Mesh Partitions

Install plumb, level, and true to line, within a tolerance of 3 mm in 3 m or the height or run of the partition, if less than 3 meters. Anchor floor sockets to the floor with expansion bolts. Vertical frames and posts shall be bolted together with 6 mm bolts 300 mm o.c. for normal duty partitions(Barracks) 10 mm bolts 450 mm o.c. for heavy duty partitions.(COF's) Secure top frames to a continuous capping bar with 6 mm diameter U bolts not more than 650 mm o.c.

3.1.2 Doors and Service Windows

Install in accordance with the manufacturers' recommendations. Adjust as required so that doors, windows, and hardware operate freely and properly.

3.1.3 Bracing

Brace free standing partitions more than 6 meters in length, at intervals not greater than 6 meters with a structural steel I section or tube post welded to a 225 by 225 mm steel base plate anchored to the floor with 4 expansion bolts.

3.1.4 Touch-Up

Clean and paint scratches, abrasions, and other damage to shop painted surfaces to match the shop-applied finish.

-- End of Section --

SECTION 13851A

FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE
08/98

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI S3.41 (1990; R 1996) Audible Emergency
Evacuation Signals

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

47 CFR 15 Radio Frequency Devices

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41 (1991; R 1995) Surge Voltages in
Low-Voltage AC Power Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (1999) National Electrical Code

NFPA 72 (1996; Errata Oct 96, Dec 96; TIA 96-1,
96-2, 96-3) National Fire Alarm Code

NFPA 90A (1996) Installation of Air Conditioning
and Ventilating Systems

NFPA 1221 (1994) Installation, Maintenance and Use
of Public Fire Service Communication
Systems

UNDERWRITERS LABORATORIES (UL)

UL 6 (1997) Rigid Metal Conduit

UL 38 (1994; Rev Nov 1994) Manually Actuated
Signaling Boxes for Use with
Fire-Protective Signaling Systems

UL 268 (1996; Rev thru Jun 1998) Smoke Detectors
for Fire Protective Signaling Systems

UL 268A	(1998) Smoke Detectors for Duct Applications
UL 464	(1996; Rev May 1997) Audible Signal Appliances
UL 521	(1993; Rev Oct 1994) Heat Detectors for Fire Protective Signaling Systems
UL 797	(1993; Rev thru Mar 1997) Electrical Metallic Tubing
UL 864	(1996) Control Units for Fire-Protective Signaling Systems
UL 1242	(1996; Rev Mar 1998) Intermediate Metal Conduit
UL 1971	(1995; Rev thru May 1997) Signaling Devices for the Hearing Impaired

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fire Alarm Reporting System; G, EC

Detail drawings, prepared and signed by a Registered Professional Engineer or a NICET Level 4 Fire Alarm Technician, consisting of a complete list of equipment and material, including manufacturer's descriptive and technical literature, catalog cuts, and installation instructions. Note that the contract drawings show layouts based on typical detectors. The Contractor shall check the layout based on the actual detectors to be installed and make any necessary revisions in the detail drawings. The detail drawings shall also contain complete wiring and schematic diagrams for the equipment furnished, equipment layout, and any other details required to demonstrate that the system has been coordinated and will properly function as a unit. Detailed point-to-point wiring diagram shall be prepared and signed by a Registered Professional Engineer or a NICET Level 4 Fire Alarm Technician showing points of connection. Diagram shall include connections between system devices, appliances, control panels, supervised devices, and equipment that is activated or controlled by the panel.

SD-03 Product Data

Storage Batteries; G, EC

Substantiating battery calculations for supervisory and alarm power requirements. Ampere-hour requirements for each system component and each panel component, and the battery recharging period shall be included.

Voltage Drop; G, EC

Voltage drop calculations for notification appliance circuits to indicate that sufficient voltage is available for proper appliance operation.

Special Tools and Spare Parts; G, RE

Spare parts data for each different item of material and equipment specified, not later than 3 months prior to the date of beneficial occupancy. Data shall include a complete list of parts and supplies with the current unit prices and source of supply and a list of the parts recommended by the manufacturer to be replaced after 1 year of service.

Technical Data and Computer Software; G, EC

Technical data which relates to computer software.

Training; G, RE

Lesson plans, operating instructions, maintenance procedures, and training data, furnished in manual format, for the training courses. The operations training shall familiarize designated government personnel with proper operation of the fire alarm system. The maintenance training course shall provide the designated government personnel adequate knowledge required to diagnose, repair, maintain, and expand functions inherent to the system.

Testing; G, RE

Detailed test procedures, prepared and signed by a Registered Professional Engineer or a NICET Level 4 Fire Alarm Technician, for the fire detection and alarm system 60 days prior to performing system tests.

SD-06 Test Reports

Testing; G, RE

Test reports, in booklet form, showing field tests performed to prove compliance with the specified performance criteria, upon completion and testing of the installed system. Each test report shall document readings, test results and indicate the final position of controls. The Contractor shall include the NFPA 72

Certificate of Completion and NFPA 72 Inspection and Testing Form, with the appropriate test reports.

SD-07 Certificates

Equipment; G, RE

Certified copies of current approvals or listings issued by an independent test lab if not listed by UL, FM or other nationally recognized testing laboratory, showing compliance with specified NFPA standards.

Qualifications; G, RE

Proof of qualifications for required personnel. The installer shall submit proof of experience for the Professional Engineer, fire alarm technician, and the installing company.

SD-10 Operation and Maintenance Data

Technical Data and Computer Software; G,
Six copies of operating manual outlining step-by-step procedures required for system startup, operation, and shutdown. The manual shall include the manufacturer's name, model number, service manual, parts list, and complete description of equipment and their basic operating features. copies of maintenance manual listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guide. The manuals shall include conduit layout, equipment layout and simplified wiring, and control diagrams of the system as installed. The manuals shall include complete procedures for system revision and expansion, detailing both equipment and software requirements. Original and backup copies of all software delivered for this project shall be provided, on each type of media utilized. Manuals shall be approved prior to training.

1.3 GENERAL REQUIREMENTS

1.3.1 Standard Products

Material and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid opening. Equipment shall be supported by a service organization that can provide service within 24 hours of notification.

1.3.2 Nameplates

Major components of equipment shall have the manufacturer's name, address, type or style, voltage and current rating, and catalog number on a noncorrosive and nonheat-sensitive plate which is securely attached to the equipment.

1.3.3 Keys and Locks

Locks shall be keyed alike. Four keys for the system shall be provided.

1.3.4 Tags

Tags with stamped identification number shall be furnished for keys and locks.

1.3.5 Verification of Dimensions

After becoming familiar with details of the work, the Contractor shall verify dimensions in the field and shall advise the Contracting Officer of any discrepancy before performing the work.

1.3.6 Compliance

The fire detection and alarm system and the central reporting system shall be configured in accordance with NFPA 72; exceptions are acceptable as directed by the Contracting Officer. The equipment furnished shall be compatible and be UL listed, FM approved, or approved or listed by a nationally recognized testing laboratory in accordance with the applicable NFPA standards.

1.3.7 Qualifications

1.3.7.1 Engineer and Technician

a. Registered Professional Engineer with verification of experience and at least 4 years of current experience in the design of the fire protection and detection systems.

b. National Institute for Certification in Engineering Technologies (NICET) qualifications as an engineering technician in fire alarm systems program with verification of experience and current NICET certificate.

c. The Registered Professional Engineer may perform all required items under this specification. The NICET Fire Alarm Technician shall perform only the items allowed by the specific category of certification held.

1.3.7.2 Installer

The installing Contractor shall provide the following: NICET Fire Alarm Technicians to perform the installation of the system. A NICET Level 4 Fire Alarm Technician shall supervise the installation of the fire alarm system. NICET Level 2 or higher Fire Alarm Technician shall install and terminate fire alarm devices, cabinets and panels. An electrician or NICET Level 1 Fire Alarm Technician shall install conduit for the fire alarm system. The Fire Alarm technicians installing the equipment shall be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.3.7.3 Design Services

Installations requiring designs or modifications of fire detection, fire

alarm, or fire suppression systems shall require the services and review of a qualified fire protection engineer. For the purposes of meeting this requirement, a qualified fire protection engineer is defined as an individual meeting one of the following conditions:

- a. An engineer having a Bachelor of Science or Masters of Science Degree in Fire Protection Engineering from an accredited university engineering program, plus a minimum of 2 years' work experience in fire protection engineering.
- b. A registered professional engineer (P.E.) in fire protection engineering.
- c. A registered PE in a related engineering discipline and member grade status in the National Society of Fire Protection Engineers.
- d. An engineer with a minimum of 10 years' experience in fire protection engineering and member grade status in the National Society of Fire Protection Engineers.

1.4 SYSTEM DESIGN

1.4.1 Operation

The fire alarm and detection system shall be a complete, supervised fire alarm reporting system. The system shall be activated into the alarm mode by actuation of any alarm initiating device. The system shall remain in the alarm mode until the initiating device is reset and the fire alarm control panel is reset and restored to normal. Alarm initiating devices shall be connected, Style D, to signal line circuits (SLC), Style 6, in accordance with NFPA 72. Alarm notification appliances shall be connected to notification appliance circuits (NAC), Style Z in accordance with NFPA 72.

A looped conduit system shall be provided so that if the conduit and all conductors within are severed at any point, all IDC, NAC and SLC will remain functional. The conduit loop requirement is not applicable to the signal transmission link from the local panels (at the protected premises) to the Supervising Station (fire station, fire alarm central communication center). Textual, audible, and visual appliances and systems shall comply with NFPA 72. Fire alarm system components requiring power, except for the control panel power supply, shall operate on 24 Volts dc. Addressable system shall be microcomputer (microprocessor or microcontroller) based with a minimum word size of eight bits and shall provide the following features:

- a. Sufficient memory to perform as specified and as shown for addressable system.
- b. Individual identity of each addressable device for the following conditions: alarm; trouble; open; short; and appliances missing/failed remote detector - sensitivity adjustment from the panel for smoke detectors
- c. Capability of each addressable device being individually disabled or enabled from the panel.

- d. Each SLC shall be sized to provide 40 percent addressable expansion without hardware modifications to the panel.

1.4.2 Operational Features

The system shall have the following operating features:

- a. Monitor electrical supervision of IDC, SLC, and NAC. Smoke detectors shall have combined alarm initiating and power circuits.
- b. Monitor electrical supervision of the primary power (ac) supply, battery voltage, placement of alarm zone module (card, PC board) within the control panel, and transmitter tripping circuit integrity.
- c. A trouble buzzer and trouble LED/LCD (light emitting diode/liquid crystal diode) to activate upon a single break, open, or ground fault condition which prevents the required normal operation of the system. The trouble signal shall also operate upon loss of primary power (ac) supply, low battery voltage, removal of alarm zone module (card, PC board), and disconnection of the circuit used for transmitting alarm signals off-premises. A trouble alarm silence switch shall be provided which will silence the trouble buzzer, but will not extinguish the trouble indicator LED/LCD. Subsequent trouble and supervisory alarms shall sound the trouble signal until silenced. After the system returns to normal operating conditions, the trouble buzzer shall again sound until the silencing switch returns to normal position, unless automatic trouble reset is provided.
- d. A one person test mode. Activating an initiating device in this mode will activate an alarm for a short period of time, then automatically reset the alarm, without activating the transmitter during the entire process.
- e. A transmitter disconnect switch to allow testing and maintenance of the system without activating the transmitter but providing a trouble signal when disconnected and a restoration signal when reconnected.
- f. Evacuation alarm silencing switch which, when activated, will silence alarm devices, but will not affect the zone indicating LED/LCD nor the operation of the transmitter. This switch shall be over-ridden upon activation of a subsequent alarm from an unalarmed device and the NAC devices will be activated.
- g. Electrical supervision for circuits used for supervisory signal services (i.e., sprinkler systems, valves, etc.). Supervision shall detect any open, short, or ground.
- h. Confirmation or verification of all smoke detectors. The control panel shall interrupt the transmission of an alarm signal to the system control panel for a factory preset period. This

interruption period shall be adjustable from 1 to 60 seconds and be factory set at 20 seconds. Immediately following the interruption period, a confirmation period shall be in effect during which time an alarm signal, if present, will be sent immediately to the control panel. Fire alarm devices other than smoke detectors shall be programmed without confirmation or verification.

- i. The fire alarm control panel shall provide supervised addressable relays for HVAC shutdown. In addition, a switch shall be mounted in the control panel which will shut down all HVAC equipment when initiated. An override at the HVAC panel shall not be provided.
- j. Provide one person test mode - Activating an initiating device in this mode will activate an alarm for a short period of time, then automatically reset the alarm, without activating the transmitter during the entire process.
- k. The fire alarm control panel shall provide the required monitoring and supervised control outputs needed to accomplish elevator recall.
- l. The fire alarm control panel shall monitor the fire sprinkler system, or other fire protection extinguishing system.
- m. The control panel and field panels shall be software reprogrammable to enable expansion or modification of the system without replacement of hardware or firmware. Examples of required changes are: adding or deleting devices or zones; changing system responses to particular input signals; programming certain input signals to activate auxiliary devices.
- n. Zones for IDC and NAC shall be arranged as indicated on the contract drawings .

1.4.3 Alarm Functions

An alarm condition on a circuit shall automatically initiate the following functions:

- a. Transmission of signals over the station radio fire reporting system. The signals shall be as follows: The devices are further described on the fire alarm matrix for each building.

Company Operations Facilities and Battalion Headquarters:

1. Alarm Initiating Devices
2. Water Flow
3. All valve and transmitter door tamper switches
4. All trouble conditions

Barracks/Soldier Community Building

All barracks and soldier community building alarms will be

transmitted from a transmitter in the soldier community building.
The zones will be as indicated

Barracks 7002A

1. Alarm Initiating Devices (One zone for each floor)
2. Water Flow (One zone for each floor)
3. All valve and transmitter door tamper switches (One zone)
4. All fire alarm panel trouble conditions (One zone)
5. Trouble condition from single module smoke detector initiation for 7002A (One zone for each floor)
6. Alarm for multiple smoke detectors in the same module. (One zone for each floor).

Barracks 7002B

1. Alarm Initiating Devices (One zone for each floor)
2. Water Flow (One zone for each floor)
3. All valve and transmitter door tamper switches (One zone)
4. All fire alarm panel trouble conditions (One zone)
5. Trouble condition from single module smoke detector initiation for 7002A (One zone for each floor)
6. Alarm for multiple smoke detectors in the same module (one zone for each floor).

Soldier Community Center

1. Alarm Initiating Devices
2. Water Flow
3. All valve and transmitter door tamper switches
4. All trouble conditions

Provide 10 additional zones for the barracks complex transmitter only..

- b. Visual indications of the alarmed devices on the fire alarm control panel display and on the remote audible/visual display.
- c. Continuous sounding or operation of alarm notification appliances throughout the building as required by ANSI S3.41.
- f. Deactivation of the air handling units throughout the building.

1.4.4 Primary Power

Operating power shall be provided as required by paragraph Power Supply for the System. Transfer from normal to emergency power or restoration from emergency to normal power shall be fully automatic and not cause transmission of a false alarm. Loss of ac power shall not prevent transmission of a signal via the fire reporting system upon operation of

any initiating circuit.

1.4.5 Battery Backup Power

Battery backup power shall be through use of rechargeable, sealed-type storage batteries and battery charger.

1.5 TECHNICAL DATA AND COMPUTER SOFTWARE

Technical data and computer software (meaning technical data which relates to computer software) which is specifically identified in this project, and which may be defined/required in other specifications, shall be delivered, strictly in accordance with the CONTRACT CLAUSES, and in accordance with the Contract Data Requirements List, DD Form 1423. Data delivered shall be identified by reference to the particular specification paragraph against which it is furnished. Data to be submitted shall include complete system, equipment, and software descriptions. Descriptions shall show how the equipment will operate as a system to meet the performance requirements of this contract. The data package shall also include the following:

- (1) Identification of programmable portions of system equipment and capabilities.
- (2) Description of system revision and expansion capabilities and methods of implementation detailing both equipment and software requirements.
- (3) Provision of operational software data on all modes of programmable portions of the fire alarm and detection system.
- (4) Description of Fire Alarm Control Panel equipment operation.
- (5) Description of auxiliary and remote equipment operations.
- (6) Library of application software.
- (7) Operation and maintenance manuals as specified in SD-19 of the Submittals paragraph.

1.6 DELIVERY AND STORAGE

Equipment delivered and placed in storage shall be stored with protection from the weather, humidity and temperature variation, dirt, dust, and any other contaminants.

PART 2 PRODUCTS

2.1 CONTROL PANEL

Control Panel shall comply with the applicable requirements of UL 864. Panel shall be modular, installed in a surface mounted steel cabinet with hinged door and cylinder lock. Control panel shall be a clean, uncluttered, and orderly assembled panel containing components and equipment required to provide the specified operating and supervisory

functions of the system. The panel shall have prominent rigid plastic, phenolic or metal identification plates for LED/LCDs, zones, SLC, controls, meters, fuses, and switches. Nameplates for fuses shall also include ampere rating. The LED/LCD displays shall be located on the exterior of the cabinet door or be visible through the cabinet door. Control panel switches shall be within the locked cabinet. A suitable means (single operation) shall be provided for testing the control panel visual indicating devices (meters or LEDs/LCDs). Meters and LEDs shall be plainly visible when the cabinet door is closed. Signals and LEDs/LCDs shall be provided to indicate by zone any alarm, supervisory or trouble condition on the system. Loss of power, including batteries, shall not require the manual reloading of a program. Upon restoration of power, startup shall be automatic, and shall not require any manual operation. The loss of primary power or the sequence of applying primary or emergency power shall not affect the transmission of alarm, supervisory or trouble signals. Visual annunciation shall be provided for LED/LCD visual display as an integral part of the control panel and shall identify with a word description and id number each device. Cabinets shall be provided with ample gutter space to allow proper clearance between the cabinet and live parts of the panel equipment. If more than one modular unit is required to form a control panel, the units shall be installed in a single cabinet large enough to accommodate units. Cabinets shall be painted red .

2.1.1 Remote System Audible/Visual Display

Audible appliance shall have a minimum sound level output rating of dBA at 3.05 m and operate in conjunction with the panel integral display. The audible device shall be silenced by a system silence switch on the remote system. The audible device shall be silenced by the system silence switch located at the remote location, but shall not extinguish the visual indication. The remote LED/LCD visual display shall provide identification, consisting of the word description and id number for each device as displayed on the control panel. An annunciator panel and a LED/LCD visual display should be provided at each location identified as FAAP on the drawings. A rigid plastic, phenolic or metal identification sign which reads "Fire Alarm Annunciator Panel" shall be provided at the remote audible/visual display. The remote visual appliance located with the audible appliance shall not be extinguished until the trouble or alarm has been cleared.

2.1.2 Circuit Connections

Circuit conductors entering or leaving the panel shall be connected to screw-type terminals with each conductor and terminal marked for identification.

2.1.3 System Expansion and Modification Capabilities

Any equipment and software needed by qualified technicians to implement future changes to the fire alarm system shall be provided as part of this contract.

2.1.4 Addressable Initiating Device Circuits Module

The initiating device being monitored shall be configured as a Style D initiating device circuits. The system shall be capable of defining any module as an alarm module and report alarm trouble, loss of polling, or as a supervisory module, and reporting supervisory short, supervisory open or loss of polling. The module shall be UL listed as compatible with the control panel. The monitor module shall provide address setting means compatible with the control panel's SLC supervision and store an internal identifying code. Monitor module shall contain an integral LED that flashes each time the monitor module is polled. Pull stations with a monitor module in a common backbox are not required to have an LED.

2.2 STORAGE BATTERIES

Storage batteries shall be provided and shall be 24 Vdc sealed, lead-calcium type requiring no additional water. The batteries shall have ample capacity, with primary power disconnected, to operate the fire alarm system for a period of 72 hours. Following this period of battery operation, the batteries shall have ample capacity to operate all components of the system, including all alarm signaling devices in the total alarm mode for a minimum period of 15 minutes. Batteries shall be located at the bottom of the panel. Batteries shall be provided with overcurrent protection in accordance with NFPA 72. Separate battery cabinets shall have a lockable, hinged cover similar to the fire alarm panel. The lock shall be keyed the same as the fire alarm control panel. Cabinets shall be painted to match the fire alarm control panel.

2.3 BATTERY CHARGER

Battery charger shall be completely automatic, 24 Vdc with high/low charging rate, capable of restoring the batteries from full discharge (18 Volts dc) to full charge within 48 hours. A pilot light indicating when batteries are manually placed on a high rate of charge shall be provided as part of the unit assembly, if a high rate switch is provided. Charger shall be located in control panel cabinet or in a separate battery cabinet.

2.4 ADDRESSABLE MANUAL FIRE ALARM STATIONS

Addressable manual fire alarm stations shall conform to the applicable requirements of UL 38. Manual stations shall be connected into signal line circuits. Stations shall be installed on surface or flush mounted outlet boxes as indicated. Manual stations shall be mounted at 1220 mm. Stations shall be ~~DELETE TEXT~~ double action type. Stations shall be finished in red, with raised letter operating instructions of contrasting color. Stations requiring the breaking of glass or plastic panels for operation are not acceptable. Stations employing glass rods are not acceptable. The use of a key or wrench shall be required to reset the station. Gravity or mercury switches are not acceptable. Switches and contacts shall be rated for the voltage and current upon which they operate. Addressable pull stations shall be capable of being field programmed, shall latch upon operation and remain latched until manually reset. Stations shall have a separate screw terminal for each conductor. Surface mounted boxes shall be matched and painted the same color as the fire alarm manual stations.

2.5 FIRE DETECTING DEVICES

Fire detecting devices shall comply with the applicable requirements of NFPA 72, NFPA 90A, UL 268, UL 268A, and UL 521. The detectors shall be provided as indicated. Detector base shall have screw terminals for making connections. No solder connections will be allowed. Detectors located in concealed locations (above ceiling, raised floors, etc.) shall have a remote visible indicator LED/LCD. Addressable fire detecting devices, except flame detectors, shall be dynamically supervised and uniquely identified in the control panel. All fire alarm initiating devices shall be individually addressable, except where indicated. Installed devices shall conform to NFPA 70 hazard classification of the area where devices are to be installed.

2.5.1 Heat Detectors

Heat detectors shall be designed for detection of fire by combination fixed temperature and rate-of-rise principle. Heat detector spacing shall be rated in accordance with UL 521. Detectors located in areas subject to moisture, exterior atmospheric conditions, or hazardous locations as defined by NFPA 70, shall be types approved for such locations. Heat detectors located in attic spaces or similar concealed spaces below the roof shall be intermediate temperature rated.

2.5.1.1 Combination Fixed-Temperature and Rate-of-Rise Detectors

Detectors shall be designed for surface outlet box mounting and supported independently of wiring connections. Contacts shall be self-resetting after response to rate-of-rise principle. Under fixed temperature actuation, the detector shall have a permanent external indication which is readily visible. Detector units located in boiler rooms, showers, or other areas subject to abnormal temperature changes shall operate on fixed temperature principle only. The UL 521 test rating for the fixed temperature portion shall be as shown. The UL 521 test rating for the Rate-of-Rise detectors shall be rated for 15 by 15 m.

2.5.2 Smoke Detectors

Smoke detectors shall be designed for detection of abnormal smoke densities. Smoke detectors shall be photoelectric type. Detectors shall contain a visible indicator LED/LCD that shows when the unit is in alarm condition. Detectors shall not be adversely affected by vibration or pressure. Detectors shall be the plug-in type in which the detector base contains terminals for making wiring connections. Detectors that are to be installed in concealed (above false ceilings, etc.) locations shall be provided with a remote indicator LED/LCD suitable for mounting in a finished, visible location.

2.5.2.1 Photoelectric Detectors

Detectors shall operate on a light scattering concept using an LED light source. Failure of the LED shall not cause an alarm condition. Detectors shall be factory set for sensitivity and shall require no field adjustments of any kind. Detectors shall have an obscuration rating in accordance with UL 268. Addressable smoke detectors shall be capable of having the

sensitivity being remotely adjusted by the control panel.

2.5.2.2 Duct Detectors

Duct-mounted photoelectric smoke detectors shall be furnished and installed where indicated and in accordance with NFPA 90A. Units shall consist of a smoke detector as specified in paragraph Photoelectric Detectors, mounted in a special housing fitted with duct sampling tubes. Detector circuitry shall be mounted in a metallic enclosure exterior to the duct. Detectors shall have a manual reset. Detectors shall be rated for air velocities that include air flows between 2.5 and 20 m/s. Detectors shall be powered from the fire alarm panel. Sampling tubes shall run the full width of the duct. The duct detector package shall conform to the requirements of NFPA 90A, UL 268A, and shall be UL listed for use in air-handling systems. The control functions, operation, reset, and bypass shall be controlled from the fire alarm control panel. Lights to indicate the operation and alarm condition; and the test and reset buttons shall be visible and accessible with the unit installed and the cover in place. Detectors mounted above 1.83 m and those mounted below 1.83 m that cannot be easily accessed while standing on the floor, shall be provided with a remote detector indicator panel containing test and reset switches. Remote lamps and switches as well as the affected fan units shall be properly identified in etched plastic placards. Detectors shall have auxiliary contacts to provide control, interlock, and shutdown functions specified in Section 15950 HEATING, VENTILATING AND AIR CONDITIONING (HVAC) CONTROL SYSTEMS. The detectors shall be supplied by the fire alarm system manufacturer to ensure complete system compatibility.

2.6 NOTIFICATION APPLIANCES

Audible appliances shall conform to the applicable requirements of UL 464. Devices shall be connected into notification appliance circuits. Devices shall have a separate screw terminal for each conductor. Audible appliances shall generate a unique audible sound from other devices provided in the building and surrounding area. Surface mounted audible appliances shall be painted white. Recessed audible appliances shall be installed with a grill that is painted white.

2.6.1 Alarm Horns

Horns shall be surface mounted, with the matching mounting back box recessed vibrating type suitable for use in an electrically supervised circuit. Horns shall produce a sound rating of at least 85 dBA at 3.05 m.

Horns used in exterior locations shall be specifically listed or approved for outdoor use and be provided with metal housing and protective grilles.

2.6.2 Visual Notification Appliances

Visual notification appliances shall conform to the applicable requirements of UL 1971 and the contract drawings. Appliances shall have clear high intensity optic lens, xenon flash tubes, and output white light. Strobe flash rate shall be between 1 to 3 flashes per second and a minimum of 75 candela. Strobe shall be semi-flush mounted.

2.6.3 Combination Audible/Visual Notification Appliances

Combination audible/visual notification appliances shall provide the same requirements as individual units except they shall mount as a unit in standard backboxes. Units shall be factory assembled. Any other audible notification appliance employed in the fire alarm systems shall be approved by the Contracting Officer.

2.7 FIRE DETECTION AND ALARM SYSTEM PERIPHERAL EQUIPMENT

2.7.1 Conduit

Conduit and fittings shall comply with NFPA 70, UL 6, UL 1242, and UL 797.

2.7.2 Wiring

Wiring shall conform to NFPA 70. Wiring for 120 Vac power shall be No. 12 AWG minimum. The SLC wiring shall be copper cable in accordance with the manufacturers requirements. Wiring for fire alarm dc circuits shall be No. 14 AWG minimum. Voltages shall not be mixed in any junction box, housing, or device, except those containing power supplies and control relays. Wiring shall conform to NFPA 70. System field wiring shall be solid copper and installed in metallic conduit or electrical metallic tubing, except that rigid plastic conduit may be used under slab-on-grade. Conductors shall be color coded. Conductors used for the same functions shall be similarly color coded. Wiring code color shall remain uniform throughout the circuit. Pigtail or T-tap connections to initiating device circuits, supervisory alarm circuits, and notification appliance circuits are prohibited. T-tapping using screw terminal blocks is allowed for style 5 addressable systems.

2.7.3 Special Tools and Spare Parts

Software, connecting cables and proprietary equipment, necessary for the maintenance, testing, and reprogramming of the equipment shall be furnished to the Contracting Officer. Two spare fuses of each type and size required shall be furnished. Two percent of the total number of each different type of detector, but no less than two each, shall be furnished. Spare fuses shall be mounted in the fire alarm panel.

2.8 TRANSMITTERS

2.8.1 Radio Alarm Transmitters

Transmitters shall be compatible with proprietary supervising station receiving equipment. Each radio alarm transmitter shall be the manufacturer's recognized commercial product, completely assembled, wired, factory tested, and delivered ready for installation and operation. Transmitters shall be provided in accordance with applicable portions of NFPA 72, NFPA 1221, and 47 CFR 15. Transmitter electronics module shall be contained within the physical housing as an integral, removable assembly. The proprietary supervising station receiving equipment is Monaco D700, BT2-8 Building Transceiver with the number of zones as specified in Part 2. and the transceiver shall be fully compatible with this equipment. At the

contractors option, and if UL listed, the transmitter may be housed in the same panel as the fire alarm control panel.

2.8.1.1 Transmitter Power Supply

Each radio alarm transmitter shall be powered by a combination of locally available 120-volt ac power and a sealed, lead-calcium battery.

a. Operation: Each transmitter shall operate from 120-volt ac power. In the event of 120-volt ac power loss, the transmitter shall automatically switch to battery operation. Switchover shall be accomplished with no interruption of protective service, and shall automatically transmit a trouble message. Upon restoration of ac power, transfer back to normal ac power supply shall also be automatic.

b. Battery Power: Transmitter standby battery capacity shall provide sufficient power to operate the transmitter in a normal standby status for a minimum of 72 hours and be capable of transmitting alarms during that period.

2.8.1.2 Radio Alarm Transmitter Housing

Transmitter housing shall be NEMA Type 1. The housing shall contain a lock that is keyed identical to the fire alarm system for the building. Radio alarm transmitter housing shall be factory painted with a suitable priming coat and not less than two coats of a hard, durable weatherproof enamel.

2.8.1.3 Antenna

The Contractor shall provide omnidirectional, antennas for radio alarm transmitters with a driving point impedance to match transmitter output. The antenna and antenna mounts shall be corrosion resistant and designed to withstand wind velocities of 161 km/h. Antennas shall not be mounted to any portion of the building roofing system.

PART 3 EXECUTION

3.1 INSTALLATION

All work shall be installed as shown and in accordance with the manufacturer's diagrams and recommendations, unless otherwise specified. Smoke detectors shall not be installed until construction is essentially complete and the building has been thoroughly cleaned.

3.1.1 Power Supply for the System

A single dedicated circuit connection for supplying power from a branch circuit to each building fire alarm system shall be provided. The power shall be supplied as shown on the drawings. The power supply shall be equipped with a locking mechanism and marked in red with the words "FIRE ALARM CIRCUIT CONTROL".

3.1.2 Wiring

Conduit size for wiring shall be in accordance with NFPA 70. Wiring for the fire alarm system shall not be installed in conduits, junction boxes, or outlet boxes with conductors of lighting and power systems. Not more than two conductors shall be installed under any device screw terminal. The wires under the screw terminal shall be straight when placed under the terminal then clamped in place under the screw terminal. The wires shall be broken and not twisted around the terminal. Circuit conductors entering or leaving any mounting box, outlet box enclosure, or cabinet shall be connected to screw terminals with each terminal and conductor marked in accordance with the wiring diagram. Connections and splices shall be made using screw terminal blocks. The use of wire nut type connectors in the system is prohibited. Wiring within any control equipment shall be readily accessible without removing any component parts. The fire alarm equipment manufacturer's representative shall be present for the connection of wiring to the control panel. Minimum conduit size to run Fire Alarm signal and low voltage conductors shall be 21mm. SLC circuit conductors shall be twisted pair. SLC conductors shall be shielded if sharing conduit with NAC conductors or non shielded if SLC conductors are run in separate conduits.

3.1.3 Control Panel

The control panel and its assorted components shall be mounted so that no part of the enclosing cabinet is less than 300 mm nor more than 2000 mm above the finished floor. Manually operable controls shall be between 900 and 1100 mm above the finished floor. Panel shall be installed to comply with the requirements of UL 864.

3.1.4 Detectors

Detectors shall be located and installed in accordance with NFPA 72. Detectors shall be connected into signal line circuits or initiating device circuits as indicated on the drawings. Detectors shall be at least 300 mm from any part of any lighting fixture. Detectors shall be located at least 900 mm from diffusers of air handling systems. Each detector shall be provided with appropriate mounting hardware as required by its mounting location. Detectors which mount in open space shall be mounted directly to the end of the stubbed down rigid conduit drop. Conduit drops shall be firmly secured to minimize detector sway. Where length of conduit drop from ceiling or wall surface exceeds 900 mm, sway bracing shall be provided. Contractor shall coordinate smoke detector sensitivities with COR. Contractor should adjust the system and if required, make further adjustments during construction until final acceptance.

3.1.5 Notification Appliances

Notification appliances shall be mounted 2003 mm above the finished floor or 150 mm below the ceiling, whichever is lower.

3.1.6 Annunciator Equipment

Annunciator equipment shall be mounted where indicated on the drawings.

3.1.7 Addressable Initiating Device Circuits Module

The initiating device circuits module shall be used to connect supervised conventional initiating devices (water flow switches, water pressure switches, manual fire alarm stations, high/low air pressure switches, and tamper switches). The module shall mount in an electrical box adjacent to or connected to the device it is monitoring and shall be capable of Style B supervised wiring to the initiating device. In order to maintain proper supervision, there shall be no T-taps allowed on style B lines. Addressable initiating device circuits modules shall monitor only one initiating device each. Contacts in suppression systems and other fire protection subsystems shall be connected to the fire alarm system to perform supervisory and alarm functions as specified in NFPA 72, as indicated on the drawings and as specified herein.

3.1.8 Addressable Control Module

Addressable and control modules shall be installed in the outlet box or adjacent to the device they are controlling. If a supplementary suppression releasing panel is provided, then the monitor modules shall be mounted in a common enclosure adjacent to the suppression releasing panel and both this enclosure and the suppression releasing panel shall be in the same room as the releasing devices. All interconnecting wires shall be supervised unless an open circuit or short circuit abnormal condition does not affect the required operation of the fire alarm system. If control modules are used as interfaces to other systems, such as HVAC or elevator control, they shall be within the control panel or immediately adjacent to it. Control modules that control a group of notification appliances shall be adjacent to the first notification appliance in the notification appliance circuits. Control modules that connect to devices shall supervise the notification appliance circuits. Control modules that connect to auxiliary systems or interface with other systems (non-life safety systems) and where not required by NFPA 72, shall not require the secondary circuits to be supervised. Contacts in suppression systems and other fire protection subsystems shall be connected to the fire alarm system to perform required alarm functions as specified in NFPA 72, as indicated on the drawings and as specified herein.

3.2 OVERVOLTAGE AND SURGE PROTECTION

3.2.1 Power Line Surge Protection

All equipment connected to alternating current circuits shall be protected from surges per IEEE C62.41 B3 combination waveform and NFPA 70. Fuses shall not be used for surge protection. The surge protector shall be rated for a maximum let thru voltage of 350 Volts ac (line-to-neutral) and 350 Volt ac (neutral-to-ground).

3.2.2 Low Voltage DC Circuits Surge Protection

All IDC, NAC, and communication cables/conductors, except fiber optics, shall have surge protection installed at each point where it exits or enters a building. Equipment shall be protected from surges per IEEE C62.41 B3 combination waveform and NFPA 70. The surge protector shall be rated to protect the 24 Volt dc equipment. The maximum dc clamping voltages

shall be 36 V (line-to-ground) and 72 Volt dc (line-to-line).

3.2.3 Signal Line Circuit Surge Protection

All SLC cables/conductors, except fiber optics, shall have surge protection/isolation circuits installed at each point where it exits or enters a building. The circuit shall be protected from surges per IEEE C62.41 B3 combination waveform and NFPA 70. The surge protector/isolator shall be rated to protect the equipment.

3.3 GROUNDING

Grounding shall be provided by connecting to building ground system.

3.4 TESTING

The Contractor shall notify the Contracting Officer at least 10 days before the preliminary and acceptance tests are to be conducted. The tests shall be performed in accordance with the approved test procedures in the presence of the Contracting Officer. The control panel manufacturer's representative shall be present to supervise tests. The Contractor shall furnish instruments and personnel required for the tests.

3.4.1 Preliminary Tests

Upon completion of the installation, the system shall be subjected to functional and operational performance tests including tests of each installed initiating and notification appliance, when required. Tests shall include the meggering of system conductors to determine that the system is free from grounded, shorted, or open circuits. The megger test shall be conducted prior to the installation of fire alarm equipment. If deficiencies are found, corrections shall be made and the system shall be retested to assure that it is functional. After completing the preliminary testing the Contractor shall complete and submit the NFPA 72, Certificate of Completion.

3.4.2 Acceptance Test

Acceptance testing shall not be performed until the Contractor has completed and submitted the Certificate of Completion. Testing shall be in accordance with NFPA 72. The recommended tests in NFPA 72 shall be considered mandatory and shall verify that previous deficiencies have been corrected. The Contractor shall complete and submit the NFPA 72, Inspection and Testing Form. The test shall include all requirements of NFPA 72 and the following:

- a. Test of each function of the control panel.
- b. Test of each circuit in both trouble and normal modes.
- c. Tests of each alarm initiating devices in both normal and trouble conditions.
- d. Tests of each control circuit and device.

- e. Tests of each alarm notification appliance.
- f. Tests of the battery charger and batteries.
- g. Complete operational tests under emergency power supply.
- h. Visual inspection of wiring connections.
- i. Opening the circuit at each alarm initiating device and notification appliance to test the wiring supervisory feature.
- j. Ground fault
- k. Short circuit faults
- l. Stray voltage
- m. Loop resistance

3.5 TRAINING

Training course shall be provided for the operations and maintenance staff.

The course shall be conducted in the building where the system is installed or as designated by the Contracting Officer. The training period for systems operation shall consist of 1 training days (8 hours per day) and shall start after the system is functionally completed but prior to final acceptance tests. The training period for systems maintenance shall consist of 2 training days (8 hours per day) and shall start after the system is functionally completed but prior to final acceptance tests. The instructions shall cover items contained in the operating and maintenance instructions. In addition, training shall be provided on performance of expansions or modifications to the fire detection and alarm system.

-- End of Section --

SECTION 15400A

PLUMBING, GENERAL PURPOSE

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

- | | |
|----------|---|
| ARI 1010 | (1994) Self-Contained, Mechanically Refrigerated Drinking-Water Coolers |
| ARI 700 | (1999) Specifications for Fluorocarbon and Other Refrigerants |

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

- | | |
|---------------|---|
| ANSI Z21.10.1 | (1998; Z21.10.1a; Z21.10.1b; Z21.10.1c)
Gas Water Heaters Vol. I, Storage Water Heaters with Input Ratings of 75,000 Btu Per Hour or Less |
| ANSI Z21.10.3 | (1998) Gas Water Heaters Vol.III, Storage Water Heaters With Input Ratings Above 75,000 Btu Per Hour, Circulating and Instantaneous Water Heaters |
| ANSI Z21.22 | (1999) Relief Valves and Automatic Gas Shutoff Devices for Hot Water Supply Systems |

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

- | | |
|------------|---|
| ASTM A 74 | (1998) Cast Iron Soil Pipe and Fittings |
| ASTM A 888 | (1998e1) Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications |
| ASTM B 306 | (1999) Copper Drainage Tube (DWV) |
| ASTM B 32 | (1996) Solder Metal |
| ASTM B 370 | (1998) Copper Sheet and Strip for Building Construction |

ASTM B 42	(1998) Seamless Copper Pipe, Standard Sizes
ASTM B 43	(1998) Seamless Red Brass Pipe, Standard Sizes
ASTM B 813	(2000) Liquid and Paste Fluxes for Soldering Applications of Copper and Copper Alloy Tube
ASTM B 88	(1999) Seamless Copper Water Tube
ASTM B 88M	(1999) Seamless Copper Water Tube (Metric)
ASTM C 564	(1997) Rubber Gaskets for Cast Iron Soil Pipe and Fittings
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM D 2235	(1996a) Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings
ASTM D 2564	(1996a) Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D 2661	(1997ael) Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM D 2665	(2000) Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM D 2822	(1991; R 1997el) Asphalt Roof Cement
ASTM D 2855	(1996) Making Solvent-Cemented Joints with Poly(Vinyl Chloride) (PVC) Pipe and Fittings
ASTM D 3138	(1995) Solvent Cements for Transition Joints Between Acrylonitrile-Butadiene-Styrene (ABS) and Poly(Vinyl Chloride) (PVC) Non-Pressure Piping Components
ASTM D 3139	(1998) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D 3212	(1996a) Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D 3308	(1997) PTFE Resin Skived Tape
ASTM D 3311	(1994) Drain, Waste, and Vent (DWV) Plastic Fittings Patterns

ASTM E 1	(1998) ASTM Thermometers
ASTM F 1760	(1997) Coextruded Poly(Vinyl Chloride) (PVC) Non-Pressure Plastic Pipe Having Reprocessed-Recycled Content
ASTM F 409	(1999a) Thermoplastic Accessible and Replaceable Plastic Tube and Tubular Fittings
ASTM F 477	(1999) Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F 493	(1997) Solvent Cements for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe and Fittings
ASTM F 628	(2000) Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe with a Cellular Core
ASTM F 891	(2000) Coextruded Poly (Vinyl chloride) (PVC) Plastic Pipe with a Cellular Core

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 34	(1997) Number Designation and Safety Classification of Refrigerants
ASHRAE 90.1	(1989; 90.1b; 90.1c; 90.1d; 90.1e; 90.1g; 90.1i; 90.1l-1995; 90.1m-1995; 90.1n-1997) Energy Efficient Design of New Buildings Except Low-Rise Residential Buildings

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1001	(1990) Pipe Applied Atmospheric Type Vacuum Breakers
ASSE 1002	(1986) Water Closet Flush Tank Ball Cocks
ASSE 1003	(1995) Water Pressure Reducing Valves for Domestic Water Supply Systems
ASSE 1005	(1986) Water Heater Drain Valves - 3/4-Inch Iron Pipe Size
ASSE 1011	(1995) Hose Connection Vacuum Breakers
ASSE 1012	(1995) Backflow Preventers with Intermediate Atmospheric Vent

ASSE 1013	(1999) Reduced Pressure Principle Backflow Preventers
ASSE 1018	(1986) Trap Seal Primer Valves Water Supply Fed
ASSE 1020	(1998) Pressure Vacuum Breaker Assembly (Recommended for Outdoor Usage)
ASSE 1037	(1990; Rev thru Mar 1990) Pressurized Flushing Devices (Flushometers) for Plumbing Fixtures

AMERICAN WATER WORKS ASSOCIATION(AWWA)

AWWA B300	(1999) Hypochlorites
AWWA B301	(1992; Addenda B301a - 1999) Liquid Chlorine
AWWA C105	(1999) Polyethylene Encasement for Ductile-Iron Pipe Systems
AWWA C203	(1997; Addenda C203a - 1999) Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape - Hot-Applied
AWWA C606	(1997) Grooved and Shouldered Joints
AWWA C700	(1995) Cold-Water Meters - Displacement Type, Bronze Main Case
AWWA C701	(1988) Cold-Water Meters - Turbine Type, for Customer Service
AWWA D100	(1996) Welded Steel Tanks for Water Storage
AWWA EWW	(1999) Standard Methods for the Examination of Water and Wastewater
AWWA M20	(1973) Manual: Water Chlorination Principles and Practices

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8	(1992) Filler Metals for Brazing and Braze Welding
AWS B2.2	(1991) Brazing Procedure and Performance Qualification

ASME INTERNATIONAL (ASME)

ASME A112.1.2	(1991; R 1998) Air Gaps in Plumbing Systems
ASME A112.14.1	(1975; R 1998) Backwater Valves
ASME A112.18.1M	(1996) Plumbing Fixture Fittings
ASME A112.19.1M	(1994; R 1999 Enameled Cast Iron Plumbing Fixtures
ASME A112.19.2M	(1998) Vitreous China Plumbing Fixtures
ASME A112.19.3M	(1987; R 1996) Stainless Steel Plumbing Fixtures (Designed for Residential Use
ASME A112.21.1M	(1991; R 1998) Floor Drains
ASME A112.36.2M	(1991; R 1998) Cleanouts
ASME A112.6.1M	(1997) Supports for Off-the-Floor Plumbing Fixtures for Public Use
ASME B1.20.1	(1983; R 1992) Pipe Threads, General Purpose (Inch)
ASME B16.15	(1985; R 1994) Cast Bronze Threaded Fittings Classes 125 and 250
ASME B16.18	(1984; R 1994) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.21	(1992) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.22	(1995; B16.22a1998) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.23	(1992; Errata Jan 1994) Cast Copper Alloy Solder Joint Drainage Fittings - DWV
ASME B16.24	(1991; R 1998) Cast Copper Alloy Pipe Flanges, Class 150, 300, 400, 600, 900, 1500, and 2500, and Flanged Fittings, Class 150 and 300
ASME B16.29	(1994) Wrought Copper and Wrought Copper Alloy Solder Joint Drainage Fittings - DWV
ASME B16.34	(1997) Valves - Flanged, Threaded, and Welding End
ASME B31.5	(1992; B31.5a1994) Refrigeration Piping
ASME B40.1	(1991) Gauges - Pressure Indicating Dial Type - Elastic Element

ASME CSD-1 (1998) Controls and Safety Devices for
Automatically Fired Boilers

CAST IRON SOIL PIPE INSTITUTE (CISPI)

CISPI 301 (1997) Hubless Cast Iron Soil Pipe and
Fittings for Sanitary and Storm Drain,
Waste, and Vent Piping Applications

CISPI 310 (1997) Coupling for Use in Connection with
Hubless Cast Iron Soil Pipe and Fittings
for Sanitary and Storm Drain, Waste, and
Vent Piping Applications

CISPI HSN-85 (1985) Neoprene Rubber Gaskets for Hub and
Spigot Cast Iron Soil Pipe and Fittings

COPPER DEVELOPMENT ASSOCIATION (CDA)

CDA Tube Handbook (1995) Copper Tube Handbook

FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH
(FCCCHR)

FCCCHR-CCC (1993) Manual of Cross-Connection Control

HYDRAULIC INSTITUTE (HI)

HI 1.1-1.5 (1994) Centrifugal Pumps

INTERNATIONAL ASSOCIATION OF PLUMBING AND MECHANICAL OFFICIALS
(IAPMO)

IAPMO Z124.5 (1997) Plastic Toilet (Water Closets) Seats

INTERNATIONAL CODE COUNCIL (ICC)

CABO A117.1 (1998) Accessible and Usable Buildings and
Facilities

ICC Plumbing Code (2000) International Plumbing Code (IPA)

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS
INDUSTRY (MSS)

MSS SP-110 (1996) Ball Valves Threaded,
Socket-Welding, Solder Joint, Grooved and
Flared Ends

MSS SP-58 (1993) Pipe Hangers and Supports -
Materials, Design and Manufacture

MSS SP-67 (1995) Butterfly Valves

MSS SP-69	(1996) Pipe Hangers and Supports - Selection and Application
MSS SP-70	(1998) Cast Iron Gate Valves, Flanged and Threaded Ends
MSS SP-71	(1997) Gray Iron Swing Check Valves, Flanges and Threaded Ends
MSS SP-72	(1999) Ball Valves with Flanged or Butt-Welding Ends for General Service
MSS SP-73	(1991; R 1996) Brazing Joints for Copper and Copper Alloy Pressure Fittings
MSS SP-78	(1998) Cast Iron Plug Valves, Flanged and Threaded Ends
MSS SP-80	(1997) Bronze Gate, Globe, Angle and Check Valves
MSS SP-85	(1994) Cast Iron Globe & Angle Valves, Flanged and Threaded Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 31	(1997; TIA 97-1) Installation of Oil Burning Equipment
NFPA 54	(1999) National Fuel Gas Code
NFPA 90A	(1999) Installation of Air Conditioning and Ventilating Systems

NSF INTERNATIONAL (NSF)

NSF 14	(1999) Plastics Piping Components and Related Materials
NSF 61	(1999) Drinking Water System Components - Health Effects (Sections 1-9)

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)

PPFA-01	(1998) Plastic Pipe in Fire Resistive Construction
---------	---

PLUMBING AND DRAINAGE INSTITUTE (PDI)

PDI WH 201	(1992) Water Hammer Arresters
------------	-------------------------------

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J 1508 (1997) Hose Clamps

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-240 (Rev A; Canc. Notice 1) Shower Head, Ball Joint

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 430 Energy Conservation Program for Consumer Products

PL 93-523 (1974; Amended 1986) Safe Drinking Water Act

1.2 STANDARD PRODUCTS

Specified materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacture of such products. Specified equipment shall essentially duplicate equipment that has performed satisfactorily at least two years prior to bid opening.

1.3 ELECTRICAL WORK

Motors, motor controllers and motor efficiencies shall conform to the requirements of Section 16415A ELECTRICAL WORK, INTERIOR. Electrical motor-driven equipment specified herein shall be provided complete with motors. Equipment shall be rated at 60 Hz, single phase, ac unless otherwise indicated. Where a motor controller is not provided in a motor-control center on the electrical drawings, a motor controller shall be provided. Motor controllers shall be provided complete with properly sized thermal-overload protection in each ungrounded conductor, auxiliary contact, and other equipment, at the specified capacity, and including an allowable service factor.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Plumbing System; G, RE.
Detail drawings consisting of illustrations, schedules, performance charts, instructions, brochures, diagrams, and other information to illustrate the requirements and operations of each system. Detail drawings for the complete plumbing system including piping layouts and locations of connections; dimensions for roughing-in, foundation, and support points; schematic

diagrams and wiring diagrams or connection and interconnection diagrams. Detail drawings shall indicate clearances required for maintenance and operation. Details shall include loadings and proposed support methods. Mechanical drawing plans, elevations, views, and details, shall be drawn to scale.

Electrical Schematics; G, RE.

Complete electrical schematic lineless or full line interconnection and connection diagram for each piece of mechanical equipment having more than one automatic or manual electrical control device.

SD-03 Product Data

Welding Data; G, RE.

Pipe and Fittings; G, RE.

Pipe Joint Materials; G, RE.

Miscellaneous Materials; G, RE.

Pipe Hangars and Supports; G, RE.

Valves; G, RE, RE.

Plumbing Fixtures; G, RE.

Fixture Supports; G, RE.

Backflow Preventers; G, RE.

Drains; G, RE.

Water Heater; G, EC.

Recirculation Pump; G, RE.

Water Meter; G, RE.

Water Hammer Arresters; G, RE.

Vibration-Absorbing Features; G, RE.

Details of vibration-absorbing features, including arrangement, foundation plan, dimensions and specifications.

Plumbing System; G, RE.

Diagrams, instructions, and other sheets proposed for posting.

Manufacturer's recommendations for the installation of bell and spigot and hubless joints for cast iron soil pipe.

SD-06 Test Reports

Tests, Flushing and Disinfection.

Test reports in booklet form showing all field tests performed to adjust each component and all field tests performed to prove compliance with the specified performance criteria, completion and testing of the installed system. Each test report shall indicate the final position of controls.

Backflow Prevention Assembly Tests..

Certification of proper operation shall be as accomplished in accordance with state regulations by an individual certified by the state to perform such tests. If no state requirement exists, the Contractor shall have the manufacturer's representative test the device, to ensure the unit is properly installed and performing as intended. The Contractor shall provide written

documentation of the tests performed and signed by the individual performing the tests.

SD-07 Certificates

Materials and Equipment;

Where materials or equipment are specified to comply with requirements of AGA, ASME, or NSF proof of such compliance shall be included. The label or listing of the specified agency will be acceptable evidence. In lieu of the label or listing, a written certificate may be submitted from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency. Where equipment is specified to conform to requirements of the ASME Boiler and Pressure Vessel Code, the design, fabrication, and installation shall conform to the code.

Bolts;

Written certification by the bolt manufacturer that the bolts furnished comply with the specified requirements. The certification shall include illustrations of product-required markings, the date of manufacture, and the number of each type of bolt to be furnished based on this certification.

SD-10 Operation and Maintenance Data

Plumbing System;

Six copies of the operation manual outlining the step-by-step procedures required for system startup, operation and shutdown. The manual shall include the manufacturer's name, model number, service manual, parts list, and brief description of all equipment and their basic operating features. Six copies of the maintenance manual listing routine maintenance procedures, possible breakdowns and repairs. The manual shall include piping and equipment layout and simplified wiring and control diagrams of the system as installed.

1.5 REGULATORY REQUIREMENTS

Plumbing work shall be in accordance with ICC Plumbing Code.

1.6 PROJECT/SITE CONDITIONS

The Contractor shall become familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.7 BATTALION HEADQUARTERS AND COMPANY OPERATIONS FACILITIES (2-COF & 4-COF)

For the Battalion Headquarters, 4-COF, and 2-COF buildings, complete layout and sizing of the domestic water supply, drain, waste, and vent piping not shown. Submit Risers for government approval with shop drawings and include in asbuilt drawings. Note drawing requirements for domestic water

pipe sizing. For drain, waste, and vent piping located above floor slab, generally only floor slab and roof penetrations are shown on the plans. Note location on plans for the vent through roof. For Battalion Headquarters, except for lines serving only drinking fountains, use 50mm drain and waste pipe below finished floor in lieu of 32mm shown on plans. For Battalion Headquarters, 4-COF, and 2-COF buildings, use 100mm drain and waste pipe below finish floor for lines serving two shower floor drains.

1.8 CONDENSATE DRAIN LINES FOR FAN-COILS (FCU-1A, FCU-2A, AND FCU-1B), HEATING & VENTILATING UNITS (HVV-1A, 2A, 3A, 4A, 1B, & 2B), AND BLOWER COILS (BC-1A, BC-2A, & BC-1B) LOCATED IN COMPANY OPERATION FACILITIES (2-COF & 4-COF)

Condensate drain lines shown on drawings AM1.3 and AM1.4 for HVV-1A, 2A, 3A, and 4A, and BC-1A & 2A, shall be 50mm and routed along the underside of the Arms Vault ceiling to the Arms Vault floor drains. Install 50mm condensate drain line for FCU-1A, FCU-2A, and FCU-1B, shown on drawings AM1.3, AM1.4, and BM1.2 respectively, and route to mechanical room floor drains without passing over Comm. Room. Install condensate drain lines for HVV-1B and HVV-2B that is 50mm and routed along the underside of the Arms Vault ceiling to the Arms Vault floor drain.

PART 2 PRODUCTS

2.1 MATERIALS

Materials for various services shall be in accordance with TABLES I and II.

Pipe schedules shall be selected based on service requirements. Pipe fittings shall be compatible with the applicable pipe materials. Plastic pipe, fittings, and solvent cement shall meet NSF 14 and shall be NSF listed for the service intended. Polypropylene pipe and fittings shall conform to dimensional requirements of Schedule 40, Iron Pipe size. Pipe threads (except dry seal) shall conform to ASME B1.20.1. Material or equipment containing lead shall not be used in any potable water system. In line devices such as water meters, building valves, check valves, meter stops, valves, fittings and back flow preventers shall comply with PL 93-523 and NSF 61, Section 8. End point devices such as drinking water fountains, lavatory faucets, kitchen and bar faucets, residential ice makers, supply stops and end point control valves used to dispense water for drinking must meet the requirements of NSF 61, Section 9. Hubless cast-iron soil pipe shall not be installed underground, under concrete floor slabs. Plastic pipe shall not be installed in air plenums.

2.1.1 Pipe Joint Materials

Hubless cast-iron soil pipe shall not be used under ground. Joints and gasket materials shall conform to the following:

- a. Coupling for Cast-Iron Pipe: for hub and spigot type ASTM A 74, AWWA C606. For hubless type: CISPI 310
- b. Coupling for Steel Pipe: AWWA C606.
- d. Flange Gaskets: Gaskets shall be made of non-asbestos material in

accordance with ASME B16.21. Gaskets shall be flat, 1.6 mm (1/16 inch) thick, and contain Aramid fibers bonded with Styrene Butadiene Rubber (SBR) or Nitro Butadiene Rubber (NBR). Gaskets shall be the full face or self centering flat ring type. Gaskets used for hydrocarbon service shall be bonded with NBR.

- e. Neoprene Gaskets for Hub and Cast-Iron Pipe and Fittings: CISPI HSN-85.
- f. Brazing Material: Brazing material shall conform to AWS A5.8, BCuP-5.
- g. Brazing Flux: Flux shall be in paste or liquid form appropriate for use with brazing material. Flux shall be as follows: lead-free; have a 100 percent flushable residue; contain slightly acidic reagents; contain potassium borides; and contain fluorides.
- h. Solder Material: Solder metal shall conform to ASTM B 32.
- i. Solder Flux: Flux shall be liquid form, non-corrosive, and conform to ASTM B 813, Standard Test 1.
- j. PTFE Tape: PTFE Tape, for use with Threaded Metal or Plastic Pipe, ASTM D 3308.
- k. Rubber Gaskets for Cast-Iron Soil-Pipe and Fittings (hub and spigot type and hubless type): ASTM C 564.
- m. Flexible Elastomeric Seals: ASTM D 3139, ASTM D 3212 or ASTM F 477.
- o. Solvent Cement for Transition Joints between ABS and PVC Nonpressure Piping Components: ASTM D 3138.
- p. Plastic Solvent Cement for ABS Plastic Pipe: ASTM D 2235.
- q. Plastic Solvent Cement for PVC Plastic Pipe: ASTM D 2564 and ASTM D 2855.
- r. Plastic Solvent Cement for CPVC Plastic Pipe: ASTM F 493.

2.1.2 Miscellaneous Materials

Miscellaneous materials shall conform to the following:

- a. Water Hammer Arrestor: PDI WH 201.
- b. Copper, Sheet and Strip for Building Construction: ASTM B 370.
- c. Asphalt Roof Cement: ASTM D 2822.
- d. Hose Clamps: SAE J 1508.
- e. Supports for Off-The-Floor Plumbing Fixtures: ASME A112.6.1M.

- f. Metallic Cleanouts: ASME A112.36.2M.
- h. Coal-Tar Protective Coatings and Linings for Steel Water Pipeline: AWWA C203.
- i. Hypochlorites: AWWA B300.
- j. Liquid Chlorine: AWWA B301.
- l. Gauges - Pressure and Vacuum Indicating Dial Type - Elastic Element: ASME B40.1.
- m. Thermometers: ASTM E 1. Mercury shall not be used in thermometers.

2.1.3 Pipe Insulation Material

Insulation shall be as specified in Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.2 PIPE HANGERS, INSERTS, AND SUPPORTS

Pipe hangers, inserts, and supports shall conform to MSS SP-58 and MSS SP-69.

2.3 VALVES

Valves shall be provided on supplies to equipment and fixtures. Valves 65 mm (2-1/2 inches) and smaller shall be bronze with threaded bodies for pipe and solder-type connections for tubing. Valves 80 mm (3 inches) and larger shall have flanged iron bodies and bronze trim. Pressure ratings shall be based upon the application. Valves shall conform to the following standards:

Description	Standard
Butterfly Valves	MSS SP-67
Cast-Iron Gate Valves, Flanged and Threaded Ends	MSS SP-70
Cast-Iron Swing Check Valves, Flanged and Threaded Ends	MSS SP-71
Ball Valves with Flanged Butt-Welding Ends for General Service	MSS SP-72
Ball Valves Threaded, Socket-Welding, Solder Joint, and Flared Ends	MSS SP-110
Cast-Iron Plug Valves, Flanged and Threaded Ends	MSS SP-78
Bronze Gate, Globe, Angle, and Check Valves	MSS SP-80

Description	Standard
Steel Valves, Socket Welding and Threaded Ends	ASME B16.34
Cast-Iron Globe and Angle Valves, Flanged and Threaded Ends	MSS SP-85
Backwater Valves	ASME A112.14.1
Vacuum Relief Valves	ANSI Z21.22
Water Pressure Reducing Valves	ASSE 1003
Water Heater Drain Valves	ASSE 1005
Trap Seal Primer Valves	ASSE 1018
Temperature and Pressure Relief Valves for Hot Water Supply Systems	ANSI Z21.22
Temperature and Pressure Relief Valves for Automatically Fired Hot Water Boilers	ASME CSD-1 Safety Code No., Part CW, Article 5

2.3.1 Hose Bibbs

Wall faucets with vacuum-breaker backflow preventer shall be brass with 20 mm (3/4 inch) male inlet threads, hexagon shoulder, and 20 mm (3/4 inch) hose connection. Faucet handle shall be securely attached to stem.

2.3.2 Freeze-proof Wall Hydrants

Wall hydrants with vacuum-breaker backflow preventer shall have a nickel-brass or nickel-bronze wall plate or flange with nozzle and detachable key handle. A brass or bronze operating rod shall be provided within a galvanized iron casing of sufficient length to extend through the wall so that the valve is inside the building, and the portion of the hydrant between the outlet and valve is self-draining. A brass or bronze valve with coupling and union elbow having metal-to-metal seat shall be provided. Valve rod and seat washer shall be removable through the face of the hydrant. The hydrant shall have 20 mm (3/4 inch) exposed hose thread on spout and 20 mm (3/4 inch) male pipe thread on inlet. Unless shown otherwise, hydrants shall be installed 600 mm above finished grade.

2.3.3 Relief Valves

Water heaters and hot water storage tanks shall have a combination pressure and temperature (P&T) relief valve. The pressure relief element of a P&T relief valve shall have adequate capacity to prevent excessive pressure buildup in the system when the system is operating at the maximum rate of heat input. The temperature element of a P&T relief valve shall have a relieving capacity which is at least equal to the total input of the heaters when operating at their maximum capacity. Relief valves shall be

rated according to ANSI Z21.22. Relief valves for systems where the maximum rate of heat input is less than 59 kW (200,000 Btuh) shall have 20 mm (3/4 inch) minimum inlets, and 20 mm (3/4 inch) outlets. Relief valves for systems where the maximum rate of heat input is greater than 59 kW (200,000 Btuh) shall have 25 mm (1 inch) minimum inlets, and 25 mm (1 inch) outlets. The discharge pipe from the relief valve shall be the size of the valve outlet.

2.4 FIXTURES

Fixtures shall be water conservation type, in accordance with ICC Plumbing Code. Fixtures for use by the physically handicapped shall be in accordance with CABO A117.1. Vitreous china, nonabsorbent, hard-burned, and vitrified throughout the body shall be provided. Porcelain enameled ware shall have specially selected, clear white, acid-resisting enamel coating evenly applied on surfaces. No fixture will be accepted that shows cracks, crazes, blisters, thin spots, or other flaws. Fixtures shall be equipped with appurtenances such as traps, faucets, stop valves, and drain fittings. Each fixture and piece of equipment requiring connections to the drainage system, except grease interceptors, shall be equipped with a trap.

Brass expansion or toggle bolts capped with acorn nuts shall be provided for supports, and polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Fixtures with the supply discharge below the rim shall be equipped with backflow preventers. Internal parts of flush and/or flushometer valves, shower mixing valves, shower head face plates, and overflow tees and shoes of bathtub waste drains may contain acetal resin, fluorocarbon, nylon, acrylonitrile-butadiene-styrene (ABS) or other plastic material, if the material has provided satisfactory service under actual commercial or industrial operating conditions for not less than 2 years. Plastic in contact with hot water shall be suitable for 82 degrees C (180 degrees F) water temperature. Plumbing fixtures shall be as indicated in paragraph PLUMBING FIXTURE SCHEDULE.

2.5 BACKFLOW PREVENTERS

Backflow preventers shall be approved and listed by the Foundation For Cross-Connection Control & Hydraulic Research. Reduced pressure principle assemblies, double check valve assemblies, atmospheric (nonpressure) type vacuum breakers, and pressure type vacuum breakers shall be tested, approved, and listed in accordance with FCCCHR-CCC. Backflow preventers with intermediate atmospheric vent shall conform to ASSE 1012. Reduced pressure principle backflow preventers shall conform to ASSE 1013. Hose connection vacuum breakers shall conform to ASSE 1011. Pipe applied atmospheric type vacuum breakers shall conform to ASSE 1001. Pressure vacuum breaker assembly shall conform to ASSE 1020. Air gaps in plumbing systems shall conform to ASME A112.1.2.

2.6 DRAINS

2.6.1 Floor and Shower Drains

Floor and shower drains shall consist of a galvanized body, integral seepage pan, and adjustable perforated or slotted chromium-plated bronze, nickel-bronze, or nickel-brass strainer, consisting of grate and threaded

collar. Floor drains shall be cast iron except where metallic waterproofing membrane is installed. Drains shall be of double drainage pattern for embedding in the floor construction. The seepage pan shall have weep holes or channels for drainage to the drainpipe. The strainer shall be adjustable to floor thickness. A clamping device for attaching flashing or waterproofing membrane to the seepage pan without damaging the flashing or waterproofing membrane shall be provided when required. Drains shall be provided with threaded connection. Between the drain outlet and waste pipe, a neoprene rubber gasket conforming to ASTM C 564 may be installed, provided that the drain is specifically designed for the rubber gasket compression type joint. Floor and shower drains shall conform to ASME A112.21.1M.

2.6.2 Floor Sinks

Floor sinks shall be square, with 300 mm (12 inch) nominal overall width or diameter and 250 mm (10 inch) nominal overall depth. Floor sink shall have an acid-resistant enamel interior finish with cast-iron body, aluminum sediment bucket, and perforated grate of cast iron in industrial areas and stainless steel in finished areas. The outlet pipe size shall be as indicated or of the same size as the connecting pipe.

2.7 TRAPS

Unless otherwise specified, traps shall be plastic per ASTM F 409 or copper-alloy adjustable tube type with slip joint inlet and swivel. Traps shall be without a cleanout. Tubes shall be copper alloy with walls not less than 0.813 mm (0.032 inch) thick within commercial tolerances, except on the outside of bends where the thickness may be reduced slightly in manufacture by usual commercial methods. Inlets shall have rubber washer and copper alloy nuts for slip joints above the discharge level. Swivel joints shall be below the discharge level and shall be of metal-to-metal or metal-to-plastic type as required for the application. Nuts shall have flats for wrench grip. Outlets shall have internal pipe thread, except that when required for the application, the outlets shall have sockets for solder-joint connections. The depth of the water seal shall be not less than 50 mm (2 inches). The interior diameter shall be not more than 3.2 mm (1/8 inch) over or under the nominal size, and interior surfaces shall be reasonably smooth throughout. A copper alloy "P" trap assembly consisting of an adjustable "P" trap and threaded trap wall nipple with cast brass wall flange shall be provided for lavatories. The assembly shall be a standard manufactured unit and may have a rubber-gasketed swivel joint.

2.8 WATER HEATERS

Water heater types and capacities shall be as indicated. Each water heater shall have replaceable anodes. Each primary water heater shall have controls with an adjustable range that includes 32 to 71 degrees C (90 to 160 degrees F). Each gas-fired water heater and booster water heater shall have controls with an adjustable range that includes 49 to 82 degrees C (120 to 180 degrees F). Hot water systems utilizing recirculation systems shall be tied into building off-hour controls. The thermal efficiencies and standby heat losses shall conform to TABLE III for each

type of water heater specified. The only exception is that storage water heaters and hot water storage tanks having more than 2000 liters storage capacity need not meet the standard loss requirement if the tank surface area is insulated to R-12.5 and if a standing light is not used. Plastic materials polyetherimide (PEI) and polyethersulfone (PES) are forbidden to be used for vent piping of combustion gases.

2.8.1 Automatic Storage Type

Heaters shall be complete with control system, temperature gauge, and pressure gauge, and shall have ASME rated combination pressure and temperature relief valve.

2.8.1.1 Gas-Fired Type

Gas-fired water heaters shall conform to ANSI Z21.10.1 when input is 22 KW (75,000 BTU per hour) or less or ANSI Z21.10.3 for heaters with input greater than 22 KW (75,000 BTU per hour).

2.9 PUMPS

2.9.1 Circulating Pumps

Domestic hot water circulating pumps shall be electrically driven, single-stage, centrifugal, with mechanical seals, suitable for the intended service. Pump capacities, efficiencies, motor sizes, speeds, and impeller types shall be as shown. Pump and motor shall be supported by the piping on which it is installed. The shaft shall be one-piece, heat-treated, corrosion-resisting steel with impeller and smooth-surfaced housing of bronze. Motor shall be totally enclosed, fan-cooled and shall have sufficient wattage (horsepower) for the service required. Pump shall conform to HI 1.1-1.5. Pump motors smaller than 746 W (Fractional horsepower pump motors) shall have integral thermal overload protection in accordance with Section 16415A ELECTRICAL WORK, INTERIOR. Guards shall shield exposed moving parts.

2.9.2 Flexible Connectors

Flexible connectors shall be provided at the suction and discharge of each pump that is 1 hp or larger. Connectors shall be constructed of neoprene, rubber, or braided bronze, with Class 150 standard flanges. Flexible connectors shall be line size and suitable for the pressure and temperature of the intended service.

2.10 DOMESTIC WATER SERVICE METER

Cold water meters 50 mm and smaller shall be positive displacement type conforming to AWWA C700. Cold water meters 64 mm and larger shall be turbine type conforming to AWWA C701. Meter register may be round or straight reading type. Meter shall be provided with a pulse generator, remote readout register and all necessary wiring and accessories. Maximum pressure drop through the water meter at peak design flowrate shall be 70 kPa.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Equipment shall be installed in accordance with the manufacturer's instructions. Piping located in air plenums shall conform to NFPA 90A requirements. Plastic pipe shall not be installed in air plenums. Piping located in shafts that constitute air ducts or that enclose air ducts shall be noncombustible in accordance with NFPA 90A. Installation of plastic pipe where in compliance with NFPA may be installed in accordance with PPFA-01. The plumbing system shall be installed complete with necessary fixtures, fittings, traps, valves, and accessories. Water and drainage piping shall be extended 1.5 m outside the building, unless otherwise indicated. A gate valve and drain shall be installed on the water service line inside the building approximately 150 mm above the floor from point of entry. Piping shall be connected to the exterior service lines or capped or plugged if the exterior service is not in place. Sewer and water pipes shall be laid in separate trenches, except when otherwise shown. Exterior underground utilities shall be at least 300 mm below the average local frost depth or as indicated on the drawings. If trenches are closed or the pipes are otherwise covered before being connected to the service lines, the location of the end of each plumbing utility shall be marked with a stake or other acceptable means. Valves shall be installed with control no lower than the valve body.

3.1.1 Water Pipe, Fittings, and Connections

3.1.1.1 Utilities

The piping shall be extended to fixtures, outlets, and equipment. The hot-water and cold-water piping system shall be arranged and installed to permit draining. The supply line to each item of equipment or fixture, except faucets, flush valves, or other control valves which are supplied with integral stops, shall be equipped with a shutoff valve to enable isolation of the item for repair and maintenance without interfering with operation of other equipment or fixtures. Supply piping to fixtures, faucets, hydrants, shower heads, and flushing devices shall be anchored to prevent movement.

3.1.1.2 Cutting and Repairing

The work shall be carefully laid out in advance, and unnecessary cutting of construction shall be avoided. Damage to building, piping, wiring, or equipment as a result of cutting shall be repaired by mechanics skilled in the trade involved.

3.1.1.3 Mains, Branches, and Runouts

Piping shall be installed as indicated. Pipe shall be accurately cut and worked into place without springing or forcing. Structural portions of the building shall not be weakened. Aboveground piping shall run parallel with the lines of the building, unless otherwise indicated. Branch pipes from service lines may be taken from top, bottom, or side of main, using crossover fittings required by structural or installation conditions.

Supply pipes, valves, and fittings shall be kept a sufficient distance from other work and other services to permit not less than 12 mm between finished covering on the different services. Bare and insulated water lines shall not bear directly against building structural elements so as to transmit sound to the structure or to prevent flexible movement of the lines. Water pipe shall not be buried in or under floors unless specifically indicated or approved. Changes in pipe sizes shall be made with reducing fittings. Use of bushings will not be permitted except for use in situations in which standard factory fabricated components are furnished to accommodate specific accepted installation practice. Change in direction shall be made with fittings, except that bending of pipe 100 mm (4 inches) and smaller will be permitted, provided a pipe bender is used and wide sweep bends are formed. The center-line radius of bends shall be not less than six diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be acceptable.

3.1.1.4 Pipe Drains

Pipe drains indicated shall consist of 20 mm (3/4 inch) hose bibb with renewable seat and full port ball valve ahead of hose bibb. At other low points, 20 mm (3/4 inch) brass plugs or caps shall be provided. Disconnection of the supply piping at the fixture is an acceptable drain.

3.1.1.5 Expansion and Contraction of Piping

Allowance shall be made throughout for expansion and contraction of water pipe. Each hot-water and hot-water circulation riser shall have expansion loops or other provisions such as offsets, changes in direction, etc., where indicated and/or required. Risers shall be securely anchored as required or where indicated to force expansion to loops. Branch connections from risers shall be made with ample swing or offset to avoid undue strain on fittings or short pipe lengths. Horizontal runs of pipe over 15 m in length shall be anchored to the wall or the supporting construction about midway on the run to force expansion, evenly divided, toward the ends. Sufficient flexibility shall be provided on branch runouts from mains and risers to provide for expansion and contraction of piping. Flexibility shall be provided by installing one or more turns in the line so that piping will spring enough to allow for expansion without straining.

3.1.1.6 Commercial-Type Water Hammer Arresters

Commercial-type water hammer arresters shall be provided on hot- and cold-water supplies and shall be located as generally indicated, with precise location and sizing to be in accordance with PDI WH 201. Water hammer arresters, where concealed, shall be accessible by means of access doors or removable panels. Commercial-type water hammer arresters shall conform to PDI WH 201. Vertical capped pipe columns will not be permitted.

3.1.2 Joints

Installation of pipe and fittings shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints shall be

made up with fittings of compatible material and made for the specific purpose intended.

3.1.2.1 Threaded

Threaded joints shall have American Standard taper pipe threads conforming to ASME B1.20.1. Only male pipe threads shall be coated with graphite or with an approved graphite compound, or with an inert filler and oil, or shall have a polytetrafluoroethylene tape applied.

3.1.3.3 Unions and Flanges

Unions, flanges and mechanical couplings shall not be concealed in walls, ceilings, or partitions. Unions shall be used on pipe sizes 65 mm (2-1/2 inches) and smaller; flanges shall be used on pipe sizes 80 mm (3 inches) and larger.

3.1.2.2 Cast Iron Soil, Waste and Vent Pipe

Bell and spigot compression and hubless gasketed clamp joints for soil, waste and vent piping shall be installed per the manufacturer's recommendations.

3.1.2.3 Copper Tube and Pipe

The tube or fittings shall not be annealed when making connections.

- a. Brazed. Brazed joints shall be made in conformance with AWS B2.2, MSS SP-73, and CDA Tube Handbook with flux and are acceptable for all pipe sizes. Copper to copper joints shall include the use of copper-phosphorus or copper-phosphorus-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) shall include the use of flux with either a copper-phosphorus, copper-phosphorus-silver or a silver brazing filler metal.
- b. Soldered. Soldered joints shall be made with flux and are only acceptable for piping 50 mm (2 inches) and smaller. Soldered joints shall conform to ASME B31.5 and CDA Tube Handbook.

3.1.2.4 Plastic Pipe

Acrylonitrile-Butadiene-Styrene (ABS) pipe shall have joints made with solvent cement. PVC and CPVC pipe shall have joints made with solvent cement elastomeric, threading, (threading of Schedule 80 Pipe is allowed only where required for disconnection and inspection; threading of Schedule 40 Pipe is not allowed), or mated flanged.

3.1.3 Dissimilar Pipe Materials

Connections between ferrous and non-ferrous copper water pipe shall be made with dielectric unions or flange waterways. Connecting joints between plastic and metallic pipe shall be made with transition fitting for the specific purpose.

3.1.4 Corrosion Protection for Buried Pipe and Fittings

3.1.4.1 Cast Iron and Ductile Iron

Pressure pipe shall have protective coating, a cathodic protection system, and joint bonding. Pipe, fittings, and joints shall have a protective coating. The protective coating shall be completely encasing polyethylene tube or sheet in accordance with AWWA C105. Joints and fittings shall be cleaned, coated with primer, and wrapped with tape. The pipe shall be cleaned, coated, and wrapped prior to pipe tightness testing. Joints and fittings shall be cleaned, coated, and wrapped after pipe tightness testing. Tape shall conform to AWWA C203 and shall be applied with a 50 percent overlap. Primer shall be as recommended by the tape manufacturer.

3.1.5 Pipe Sleeves and Flashing

Pipe sleeves shall be furnished and set in their proper and permanent location.

3.1.5.1 Sleeve Requirements

Pipes passing through concrete or masonry walls or concrete floors or roofs shall be provided with pipe sleeves fitted into place at the time of construction. Sleeves are not required for supply, drainage, waste and vent pipe passing through concrete slab on grade, except where penetrating a membrane waterproof floor. A modular mechanical type sealing assembly may be installed in lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve. The seals shall consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe and sleeve using galvanized steel bolts, nuts, and pressure plates. The links shall be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tightening of the bolt shall cause the rubber sealing elements to expand and provide a watertight seal between the pipe and the sleeve. Each seal assembly shall be sized as recommended by the manufacturer to fit the pipe and sleeve involved. Sleeves shall not be installed in structural members, except where indicated or approved. Each sleeve shall extend through its respective floor, or roof, and shall be cut flush with each surface, except for special circumstances. Pipe sleeves passing through floors in wet areas such as mechanical equipment rooms, lavatories, and other plumbing fixture areas shall extend a minimum of 100 mm above the finished floor. Unless otherwise indicated, sleeves shall be of a size to provide a minimum of 6 mm (1/4 inch) clearance between bare pipe or insulation and inside of sleeve or between insulation and inside of sleeve. Sleeves in bearing walls and concrete slab on grade floors shall be steel pipe or cast-iron pipe. Sleeves in nonbearing walls or ceilings may be steel pipe, cast-iron pipe, galvanized sheet metal with lock-type longitudinal seam, or plastic. Except as otherwise specified, the annular space between pipe and sleeve, or between jacket over insulation and sleeve, shall be sealed as indicated with sealants conforming to ASTM C 920 and with a primer, backstop material and surface preparation as specified in Section 07900A JOINT SEALING. The annular space between pipe and

sleeve, between bare insulation and sleeve or between jacket over insulation and sleeve shall not be sealed for interior walls which are not designated as fire rated. Sleeves through below-grade walls in contact with earth shall be recessed 12 mm (1/2 inch) from wall surfaces on both sides. Annular space between pipe and sleeve shall be filled with backing material and sealants in the joint between the pipe and masonry wall as specified above. Sealant selected for the earth side of the wall shall be compatible with dampproofing/waterproofing materials that are to be applied over the joint sealant. Pipe sleeves in fire-rated walls shall conform to the requirements in Section 07840A FIRESTOPPING.

3.1.5.2 Flashing Requirements

Pipes passing through roof shall be installed through a 4.9 kg per square meter (16 ounce) copper flashing, each within an integral skirt or flange.

Flashing shall be suitably formed, and the skirt or flange shall extend not less than 200 mm from the pipe and shall be set over the roof or floor membrane in a solid coating of bituminous cement. The flashing shall extend up the pipe a minimum of 250 mm. For cleanouts, the flashing shall be turned down into the hub and caulked after placing the ferrule. Pipes passing through pitched roofs shall be flashed, using lead or copper flashing, with an adjustable integral flange of adequate size to extend not less than 200 mm from the pipe in all directions and lapped into the roofing to provide a watertight seal. The annular space between the flashing and the bare pipe or between the flashing and the metal-jacket-covered insulation shall be sealed as indicated. Flashing for dry vents shall be turned down into the pipe to form a waterproof joint. Pipes, up to and including 250 mm (10 inches) in diameter, passing through roof or floor waterproofing membrane may be installed through a cast-iron sleeve with caulking recess, anchor lugs, flashing-clamp device, and pressure ring with brass bolts. Flashing shield shall be fitted into the sleeve clamping device. Pipes passing through wall waterproofing membrane shall be sleeved as described above. A waterproofing clamping flange shall be installed.

3.1.5.3 Waterproofing

Waterproofing at floor-mounted water closets shall be accomplished by forming a flashing guard from soft-tempered sheet copper. The center of the sheet shall be perforated and turned down approximately 40 mm to fit between the outside diameter of the drainpipe and the inside diameter of the cast-iron or steel pipe sleeve. The turned-down portion of the flashing guard shall be embedded in sealant to a depth of approximately 40 mm; then the sealant shall be finished off flush to floor level between the flashing guard and drainpipe. The flashing guard of sheet copper shall extend not less than 200 mm from the drainpipe and shall be lapped between the floor membrane in a solid coating of bituminous cement. If cast-iron water closet floor flanges are used, the space between the pipe sleeve and drainpipe shall be sealed with sealant and the flashing guard shall be upturned approximately 40 mm to fit the outside diameter of the drainpipe and the inside diameter of the water closet floor flange. The upturned portion of the sheet fitted into the floor flange shall be sealed.

3.1.5.4 Optional Counterflashing

Instead of turning the flashing down into a dry vent pipe, or caulking and sealing the annular space between the pipe and flashing or metal-jacket-covered insulation and flashing, counterflashing may be accomplished by utilizing the following:

- a. A standard roof coupling for threaded pipe up to 150 mm (6 inches) in diameter.
- b. A tack-welded or banded-metal rain shield around the pipe.

3.1.5.5 Pipe Penetrations of Slab on Grade Floors

Where pipes, fixture drains, floor drains, cleanouts or similar items penetrate slab on grade floors, except at penetrations of floors with waterproofing membrane as specified in paragraphs Flashing Requirements and Waterproofing, a groove 6 to 13 mm wide by 6 to 10 mm deep shall be formed around the pipe, fitting or drain. The groove shall be filled with a sealant as specified in Section 07900A JOINT SEALING.

3.1.6 Fire Seal

Where pipes pass through fire walls, fire-partitions, fire-rated pipe chase walls or floors above grade, a fire seal shall be provided as specified in Section 07840A FIRESTOPPING.

3.1.7 Supports

3.1.7.1 General

Hangers used to support piping 50 mm (2 inches) and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors shall be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures shall be supported by variable spring hangers and supports or by constant support hangers. In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support members shall not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run. Threaded sections of rods shall not be formed or bent.

3.1.7.2 Pipe Supports and Structural Bracing, Seismic Requirements

Piping and attached valves shall be supported and braced to resist seismic loads as specified in Sections 13080 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT and 15070A SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT. Structural steel required for reinforcement to properly support piping, headers, and equipment, but not shown, shall be provided. Material used for supports shall be as specified in Section 05120A STRUCTURAL STEEL.

3.1.7.3 Pipe Hangers, Inserts, and Supports

Installation of pipe hangers, inserts and supports shall conform to MSS SP-58 and MSS SP-69, except as modified herein.

- a. Types 5, 12, and 26 shall not be used.
- b. Type 3 shall not be used on insulated pipe.
- c. Type 18 inserts shall be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustment may be used if they otherwise meet the requirements for type 18 inserts.
- d. Type 19 and 23 C-clamps shall be torqued per MSS SP-69 and shall have both locknuts and retaining devices furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.
- e. Type 20 attachments used on angles and channels shall be furnished with an added malleable-iron heel plate or adapter.
- f. Type 24 may be used only on trapeze hanger systems or on fabricated frames.
- g. Type 39 saddles shall be used on insulated pipe 100 mm (4 inches) and larger when the temperature of the medium is 15 degrees C or higher. Type 39 saddles shall be welded to the pipe.
- h. Type 40 shields shall:
 - (1) Be used on insulated pipe less than 100 mm (4 inches).
 - (2) Be used on insulated pipe 100 mm (4 inches) and larger when the temperature of the medium is 15 degrees C or less.
 - (3) Have a high density insert for all pipe sizes. High density inserts shall have a density of 128 kg per cubic meter (8 pcf) or greater.
- i. Horizontal pipe supports shall be spaced as specified in MSS SP-69 and a support shall be installed not over 300 mm from the pipe fitting joint at each change in direction of the piping. Pipe supports shall be spaced not over 1.5 m apart at valves. Operating temperatures in determining hanger spacing for PVC or CPVC pipe shall be 49 degrees C for PVC and 82 degrees C for CPVC. Horizontal pipe runs shall include allowances for expansion and contraction.
- j. Vertical pipe shall be supported at each floor, except at slab-on-grade, at intervals of not more than 4.5 m nor more than 2 m from end of risers, and at vent terminations. Vertical pipe risers shall include allowances for expansion and contraction.
- k. Type 35 guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided to allow longitudinal

pipe movement. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered. Lateral restraints shall be provided as needed. Where steel slides do not require provisions for lateral restraint the following may be used:

- (1) On pipe 100 mm (4 inches) and larger when the temperature of the medium is 15 degrees C or higher, a Type 39 saddle, welded to the pipe, may freely rest on a steel plate.
 - (2) On pipe less than 100 mm (4 inches) a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
 - (3) On pipe 100 mm (4 inches) and larger carrying medium less than 15 degrees C a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
- l. Pipe hangers on horizontal insulated pipe shall be the size of the outside diameter of the insulation. The insulation shall be continuous through the hanger on all pipe sizes and applications.
 - m. Where there are high system temperatures and welding to piping is not desirable, the type 35 guide shall include a pipe cradle, welded to the guide structure and strapped securely to the pipe. The pipe shall be separated from the slide material by at least 100 mm or by an amount adequate for the insulation, whichever is greater.
 - n. Hangers and supports for plastic pipe shall not compress, distort, cut or abrade the piping, and shall allow free movement of pipe except where otherwise required in the control of expansion/contraction.

3.1.1.8 Pipe Cleanouts

Pipe cleanouts shall be the same size as the pipe except that cleanout plugs larger than 100 mm (4 inches) will not be required. A cleanout installed in connection with cast-iron soil pipe shall consist of a long-sweep 1/4 bend or one or two 1/8 bends extended to the place shown. An extra-heavy cast-brass or cast-iron ferrule with countersunk cast-brass head screw plug shall be caulked into the hub of the fitting and shall be flush with the floor. Cleanouts in connection with other pipe, where indicated, shall be T-pattern, 90-degree branch drainage fittings with cast-brass screw plugs, except plastic plugs shall be installed in plastic pipe. Plugs shall be the same size as the pipe up to and including 100 mm (4 inches). Cleanout tee branches with screw plug shall be installed at the foot of soil and waste stacks, at the foot of interior downspouts, on each connection to building storm drain where interior downspouts are indicated, and on each building drain outside the building. Cleanout tee branches may be omitted on stacks in single story buildings with slab-on-grade construction or where less than 450 mm of crawl space is provided under the floor. Cleanouts on pipe concealed in partitions shall be provided with chromium plated bronze, nickel bronze, nickel brass or

stainless steel flush type access cover plates. Round access covers shall be provided and secured to plugs with securing screw. Square access covers may be provided with matching frames, anchoring lugs and cover screws. Cleanouts in finished walls shall have access covers and frames installed flush with the finished wall. Cleanouts installed in finished floors subject to foot traffic shall be provided with a chrome-plated cast brass, nickel brass, or nickel bronze cover secured to the plug or cover frame and set flush with the finished floor. Heads of fastening screws shall not project above the cover surface. Where cleanouts are provided with adjustable heads, the heads shall be cast iron.

3.2 WATER HEATERS AND HOT WATER STORAGE TANKS

3.2.1 Relief Valves

No valves shall be installed between a relief valve and its water heater or storage tank. The P&T relief valve shall be installed where the valve actuator comes in contact with the hottest water in the heater. Whenever possible, the relief valve shall be installed directly in a tapping in the tank or heater; otherwise, the P&T valve shall be installed in the hot-water outlet piping. A vacuum relief valve shall be provided on the cold water supply line to the hot-water storage tank or water heater and mounted above and within 150 mm above the top of the tank or water heater.

3.2.2 Installation of Gas-Fired Water Heater

Installation shall conform to NFPA 54 for gas fired and NFPA 31 for oil fired. Storage water heaters that are not equipped with integral heat traps and having vertical pipe risers shall be installed with heat traps directly on both the inlet and outlet. Circulating systems need not have heat traps installed. An acceptable heat trap may be a piping arrangement such as elbows connected so that the inlet and outlet piping make vertically upward runs of not less than 600 mm just before turning downward or directly horizontal into the water heater's inlet and outlet fittings. Commercially available heat traps, specifically designed by the manufacturer for the purpose of effectively restricting the natural tendency of hot water to rise through vertical inlet and outlet piping during standby periods may also be approved.

3.2.3 Heat Traps

Piping to and from each water heater and hot water storage tank shall be routed horizontally and downward a minimum of 600 mm before turning in an upward direction.

3.2.4 Connections to Water Heaters

Connections of metallic pipe to water heaters shall be made with dielectric unions or flanges.

3.3 FIXTURES AND FIXTURE TRIMMINGS

Polished chromium-plated pipe, valves, and fittings shall be provided where exposed to view. Angle stops, straight stops, stops integral with the

faucets, or concealed type of lock-shield, and loose-key pattern stops for supplies with threaded, sweat or solvent weld inlets shall be furnished and installed with fixtures. Where connections between copper tubing and faucets are made by rubber compression fittings, a beading tool shall be used to mechanically deform the tubing above the compression fitting. Exposed traps and supply pipes for fixtures and equipment shall be connected to the rough piping systems at the wall, unless otherwise specified under the item. Floor and wall escutcheons shall be as specified. Drain lines and hot water lines of fixtures for handicapped personnel shall be insulated and do not require polished chrome finish. Plumbing fixtures and accessories shall be installed within the space shown.

3.3.1 Fixture Connections

Where space limitations prohibit standard fittings in conjunction with the cast-iron floor flange, special short-radius fittings shall be provided. Connections between earthenware fixtures and flanges on soil pipe shall be made gastight and watertight with a closet-setting compound or neoprene gasket and seal. Use of natural rubber gaskets or putty will not be permitted. Fixtures with outlet flanges shall be set the proper distance from floor or wall to make a first-class joint with the closet-setting compound or gasket and fixture used.

3.3.2 Flushometer Valves

Flushometer valves shall be secured to prevent movement by anchoring the long finished top spud connecting tube to wall adjacent to valve with approved metal bracket. Bumpers for water closet seats shall be installed on the flushometer stop.

3.3.3 Height of Fixture Rims Above Floor

Lavatories shall be mounted with rim 775 mm above finished floor. Wall-hung drinking fountains and water coolers shall be installed with rim 1020 mm above floor. Wall-hung service sinks shall be mounted with rim 700 mm above the floor. Installation of fixtures for use by the physically handicapped shall be in accordance with CABO A117.1.

3.3.4 Shower Bath Outfits

The area around the water supply piping to the mixing valves and behind the escutcheon plate shall be made watertight by caulking or gasketing.

3.3.5 Fixture Supports

Fixture supports for off-the-floor lavatories, urinals, water closets, and other fixtures of similar size, design, and use, shall be of the chair-carrier type. The carrier shall provide the necessary means of mounting the fixture, with a foot or feet to anchor the assembly to the floor slab. Adjustability shall be provided to locate the fixture at the desired height and in proper relation to the wall. Support plates, in lieu of chair carrier, shall be fastened to the wall structure only where it is not possible to anchor a floor-mounted chair carrier to the floor slab.

3.3.5.1 Support for Solid Masonry Construction

Chair carrier shall be anchored to the floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate shall be imbedded in the masonry wall.

3.3.5.2 Support for Concrete-Masonry Wall Construction

Chair carrier shall be anchored to floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate shall be fastened to the concrete wall using through bolts and a back-up plate.

3.3.5.3 Support for Steel Stud Frame Partitions

Chair carrier shall be used. The anchor feet and tubular uprights shall be of the heavy duty design; and feet (bases) shall be steel and welded to a square or rectangular steel tube upright. Wall plates, in lieu of floor-anchored chair carriers, shall be used only if adjoining steel partition studs are suitably reinforced to support a wall plate bolted to these studs.

3.3.5.4 Wall-Mounted Water Closet Gaskets

Where wall-mounted water closets are provided, reinforced wax, treated felt, or neoprene gaskets shall be provided. The type of gasket furnished shall be as recommended by the chair-carrier manufacturer.

3.3.6 Backflow Prevention Devices

Plumbing fixtures, equipment, and pipe connections shall not cross connect or interconnect between a potable water supply and any source of nonpotable water. Backflow preventers shall be installed where indicated and in accordance with ICC Plumbing Code at all other locations necessary to preclude a cross-connect or interconnect between a potable water supply and any nonpotable substance. In addition backflow preventers shall be installed at all locations where the potable water outlet is below the flood level of the equipment, or where the potable water outlet will be located below the level of the nonpotable substance. Backflow preventers shall be located so that no part of the device will be submerged. Backflow preventers shall be of sufficient size to allow unrestricted flow of water to the equipment, and preclude the backflow of any nonpotable substance into the potable water system. Bypass piping shall not be provided around backflow preventers. Access shall be provided for maintenance and testing. Each device shall be a standard commercial unit.

3.3.7 Access Panels

Access panels shall be provided for concealed valves and controls, or any item requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced, maintained, or replaced. Access panels shall be as specified in Section 05500A MISCELLANEOUS METAL.

3.3.8 Sight Drains

Sight drains shall be installed so that the indirect waste will terminate 50 mm above the flood rim of the funnel to provide an acceptable air gap.

3.3.9 Traps

Each trap shall be placed as near the fixture as possible, and no fixture shall be double-trapped. Traps installed on cast-iron soil pipe shall be cast iron. Traps installed on steel pipe or copper tubing shall be recess-drainage pattern, or brass-tube type. Traps installed on plastic pipe may be plastic conforming to ASTM D 3311. Traps for acid-resisting waste shall be of the same material as the pipe.

3.4 IDENTIFICATION SYSTEMS

3.4.1 Identification Tags

Identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and valve number shall be installed on valves, except those valves installed on supplies at plumbing fixtures. Tags shall be 35 mm (1-3/8 inch) minimum diameter, and marking shall be stamped or engraved. Indentations shall be black, for reading clarity. Tags shall be attached to valves with No. 12 AWG, copper wire, chrome-plated beaded chain, or plastic straps designed for that purpose.

3.4.2 Pipe Color Code Marking

Color code marking of piping shall be as specified in Section 09900 PAINTING, GENERAL.

3.5 ESCUTCHEONS

Escutcheons shall be provided at finished surfaces where bare or insulated piping, exposed to view, passes through floors, walls, or ceilings, except in boiler, utility, or equipment rooms. Escutcheons shall be fastened securely to pipe or pipe covering and shall be satin-finish, corrosion-resisting steel, polished chromium-plated zinc alloy, or polished chromium-plated copper alloy. Escutcheons shall be either one-piece or split-pattern, held in place by internal spring tension or setscrew.

3.6 PAINTING

Painting of pipes, hangers, supports, and other iron work, either in concealed spaces or exposed spaces, is specified in Section 09900 PAINTING, GENERAL.

3.7 TESTS, FLUSHING AND DISINFECTION

3.7.1 Plumbing System

The following tests shall be performed on the plumbing system in accordance with ICC Plumbing Code.

- a. Drainage and Vent Systems Test. The final test shall include a

smoke test.

b. Building Sewers Tests.

c. Water Supply Systems Tests.

3.7.1.1 Test of Backflow Prevention Assemblies

Backflow prevention assembly shall be tested using gauges specifically designed for the testing of backflow prevention assemblies. Gauges shall be tested annually for accuracy in accordance with the University of Southern California's Foundation of Cross Connection Control and Hydraulic Research or the American Water Works Association Manual of Cross Connection (Manual M-14). Report form for each assembly shall include, as a minimum, the following:

Data on Device	Data on Testing Firm
Type of Assembly	Name
Manufacturer	Address
Model Number	Certified Tester
Serial Number	Certified Tester No.
Size	Date of Test
Location	
Test Pressure Readings	Serial Number and Test Data of
Gauges	

If the unit fails to meet specified requirements, the unit shall be repaired and retested.

3.7.2 Defective Work

If inspection or test shows defects, such defective work or material shall be replaced or repaired as necessary and inspection and tests shall be repeated. Repairs to piping shall be made with new materials. Caulking of screwed joints or holes will not be acceptable.

3.7.3 System Flushing

3.7.3.1 During Flushing

Before operational tests or disinfection, potable water piping system shall be flushed with potable water. Sufficient water shall be used to produce a water velocity that is capable of entraining and removing debris in all portions of the piping system. This requires simultaneous operation of all fixtures on a common branch or main in order to produce a flushing velocity of approximately 1.2 meters per second (4 fps) through all portions of the piping system. In the event that this is impossible due to size of system, the Contracting Officer (or the designated representative) shall specify the number of fixtures to be operated during flushing. Contractor shall provide adequate personnel to monitor the flushing operation and to ensure that drain lines are unobstructed in order to prevent flooding of the facility. Contractor shall be responsible for any flood damage resulting from flushing of the system. Flushing shall be continued until entrained dirt and other foreign materials have been removed and until discharge

water shows no discoloration.

3.7.3.2 After Flushing

System shall be drained at low points. Strainer screens shall be removed, cleaned, and replaced. After flushing and cleaning, systems shall be prepared for testing by immediately filling water piping with clean, fresh potable water. Any stoppage, discoloration, or other damage to the finish, furnishings, or parts of the building due to the Contractor's failure to properly clean the piping system shall be repaired by the Contractor. When the system flushing is complete, the hot-water system shall be adjusted for uniform circulation. Flushing devices and automatic control systems shall be adjusted for proper operation. All faucets and drinking water fountains, to include any device considered as an end point device by NSF 61, Section 9, shall be flushed a minimum of 1 L per 24 hour period, ten times over a 14 day period.

3.7.4 Operational Test

Upon completion of flushing and prior to disinfection procedures, the Contractor shall subject the plumbing system to operating tests to demonstrate satisfactory functional and operational efficiency. Such operating tests shall cover a period of not less than 8 hours for each system and shall include the following information in a report with conclusion as to the adequacy of the system:

- a. Time, date, and duration of test.
- b. Water pressures at the most remote and the highest fixtures.
- c. Operation of each fixture and fixture trim.
- d. Operation of each valve, hydrant, and faucet.
- e. Pump suction and discharge pressures.
- f. Temperature of each domestic hot-water supply.
- g. Operation of each floor and roof drain by flooding with water.
- h. Operation of each vacuum breaker and backflow preventer.
- i. Complete operation of each water pressure booster system, including pump start pressure and stop pressure.

3.7.5 Disinfection

After operational tests are complete, the entire domestic hot- and cold-water distribution system shall be disinfected. System shall be flushed as specified, before introducing chlorinating material. The chlorinating material shall be hypochlorites or liquid chlorine. Water chlorination procedure shall be in accordance with AWWA M20. The

chlorinating material shall be fed into the water piping system at a constant rate at a concentration of at least 50 parts per million (ppm). A properly adjusted hypochlorite solution injected into the main with a hypochlorinator, or liquid chlorine injected into the main through a solution-feed chlorinator and booster pump, shall be used. The chlorine residual shall be checked at intervals to ensure that the proper level is maintained. Chlorine application shall continue until the entire main is filled. The water shall remain in the system for a minimum of 24 hours. Each valve in the system being disinfected shall be opened and closed several times during the contact period to ensure its proper disinfection. Following the 24-hour period, no less than 25 ppm chlorine residual shall remain in the system. Water tanks shall be disinfected by the addition of chlorine directly to the filling water. Following a 6 hour period, no less than 50 ppm chlorine residual shall remain in the tank. If after the 24 hour and 6 hour holding periods, the residual solution contains less than 25 ppm and 50 ppm chlorine respectively, flush the piping and tank with potable water, and repeat the above procedures until the required residual chlorine levels are satisfied. The system including the tanks shall then be flushed with clean water until the residual chlorine level is reduced to less than one part per million. During the flushing period each valve and faucet shall be opened and closed several times. Samples of water in disinfected containers shall be obtained from several locations selected by the Contracting Officer. The samples of water shall be tested for total coliform organisms (coliform bacteria, fecal coliform, streptococcal, and other bacteria) in accordance with AWWA EWW. The testing method used shall be either the multiple-tube fermentation technique or the membrane-filter technique. Disinfection shall be repeated until tests indicate the absence of coliform organisms (zero mean coliform density per 100 milliliters) in the samples for at least 2 full days. The system will not be accepted until satisfactory bacteriological results have been obtained.

3.7.6 Flushing of Potable Water System

As an option to the system flushing specified above, the potable water system shall be flushed and conditioned until the residual level of lead is less than that specified by the base industrial hygienist. The water supply to the building shall be tested separately to ensure that any lead contamination found during potable water system testing is due to work being performed inside the building.

3.8 PLUMBING FIXTURE SCHEDULE

P-1 WATER CLOSET (Barracks Buildings & Small Office in Battalion Headquarters):

Siphon-jet, elongated bowl, top supply spud, ASME A112.19.2M, floor mounted. Floor flange shall be copper alloy, cast iron, or plastic.

Gasket shall be wax type.

Seat - IAPMO Z124.5, Type A, white plastic, elongated, open front.

Flush Tank - An adequate quantity of water shall be provided to flush and clean the fixture served. The water supply to flush tanks equipped for

manual flushing shall be controlled by a float valve or other automatic device designed to refill the tank after each discharge, and to completely shut off the water flow to the tank when the tank is filled to operational capacity. Water closets having their flush valve seat located below the flood level rim of the closet bowl shall have a ballcock installed within a sheath or in a separate and isolated compartment of the tank, both to have visible discharge onto the floor in case of failure. Provision shall be made to automatically supply water to the fixture so as to refill the trap seal after each flushing. The water supply to flush tanks equipped for automatic flushing shall be controlled by a suitable timing device. Ballcocks shall meet ASSE 1002.

P-1 WATER CLOSET (2-COFs, 4-COFs, & Battalion Headquarters except for small office):

Siphon-jet, elongated bowl, top supply spud, ASME A112.19.2M, wall mounted. Floor flange shall be copper alloy, cast iron, or plastic.

Gasket shall be wax type.

Seat - IAPMO Z124.5, Type A, white plastic, elongated, open front.

Flushometer Valve - ASSE 1037, large diaphragm type with non-hold-open feature, backcheck angle control stop, and vacuum breaker. Minimum upper chamber inside diameter of not less than 66.7 mm (2-5/8 inches) at the point where the diaphragm is sealed between the upper and lower chambers. The maximum water use shall be 6 liters per flush.

P-2 WATER CLOSET HANDICAPPED:

Height of top rim of bowl shall be in accordance with CABO A117.1; other features are the same as P-1 for 2-COFs, 4-COFs, & Battalion Headquarters except small office.

P-3 URINAL:

Wall hanging, with integral trap and extended shields, ASME A112.19.2M siphon jet. Top supply connection, back outlet.

Flushometer Valve - Similar to Flushometer Valve for P-1. The maximum water use shall be 3.8 liters per flush.

P-4 BATHTUB AND SHOWER HEAD:

Eljer Ventura Tub or equal, enameled steel, 1523mm (60inches) long x 762mm (30inches) wide x 365mm (14 11/32inches) high, slip resistant bottom, 40 gallon capacity, ASME A112.19.1M raised bottom.

Drain Assembly - Plug, cup strainer, overflow assembly, washers, couplings, pop-up lever, trip lever, stopper, fittings, etc., shall be brass, cast copper alloy, or wrought copper alloy.

Bath Showers: Bath showers shall include bathtub spout, shower head, valves, and diverters. A shower head shall be nonadjustable spray, stainless steel, or chromium plated brass with ball joint. Handles shall be chrome plated die cast zinc alloy. Diverter shall be integral with single mixing valves or mounted hot and cold water valves. Tub spout shall be copper alloy. Mount shower head at 1900mm above finished floor.

P-5 LAVATORY:

Faucet - Single faucet shall be used. Faucets shall meet the requirements of NSF 61, Section 9. Faucets shall have metal replaceable cartridge control unit or metal cartridge units with diaphragm which can be replaced without special tools. Valves and handles shall be copper alloy. Flow shall be limited to 1 liter per cycle at a flowing water pressure of 549 kPa if a metering device or fitting is used that limits the period of water discharge such as a foot switch or fixture occupancy sensor. If a metering device is not used, the flow shall be limited to 0.16 liters per second at a flowing pressure of 549 kPa.

Handles - Two lever type handles required, one for hot, and one for cold. Cast, formed, or drop forged copper alloy.

Drain - Barracks buildings shall contain pop-up drain shall include stopper, lift rods, jam nut, washer, and tail piece. The SCB, 2-COFs, 4-COFs, and Battalion Headquarters shall not contain stoppers, but shall contain a strainer that is copper alloy or stainless steel. See paragraph FIXTURES for optional plastic accessories.

P-7 KITCHEN SINK (SCB and Battalion Headquarters):

Battalion Headquarters; Single bowl deep sin, Elkay model DLR222212 or approved equal. Self rim with holes for faucet and handles, overall dimensions 22 inches wide x 22 inches long, single bowl compartment 19 x 16 x 12 inches deep, seamless 18 gauge 304 stainless steel with full undercoat.

Battalion Headquarters; Faucet, Handles, and Spout - Two-wing handle center set type with high arc gooseneck. Faucets shall meet the requirements of NSF 61, Section 9. Spout body, base, dome, and handles are chrome-plated brass. Handles, gooseneck, etc shall be chrome-plated brass. Faucet is protected from back siphonage by combination of two check valves and a vacuum breaker. Flow shall be limited to 0.16 liters per second (2.5gpm) at a flowing water pressure of 549kPa (80psig).

Soldier Community Building SCB; Elkay model STCR-3322-L or approved equal. Self rim with holes for faucet and spout, double bowl, left compartment 14 x 15 3/4 x 10 inches deep, right compartment 14 x 15 3/4 x 7 inches deep with waste disposer drain opening, seamless 20 guage 302 stainless steel with full undercoat, right compartment equipped with food waste disposer. The food waste disposer shall contain a 3/4 horsepower motor with 2700rpm grinding action and delux sound insulation.

Soldier Community Building; Faucet, Handles, and Spout - Single lever

control with pullout retractable spray, Elkay model LK4330FCR or equal. Faucets shall meet the requirements of NSF 61, Section 9. Spout body, base, dome, and handles are chrome-plated brass. Faucet is protected from back siphonage by combination of two check valves and a vacuum breaker. Flow shall be limited to 0.16 liters per second (2.5gpm) at a flowing water pressure of 549kPa (80psig).

Drain Assembly - Plug, cup strainer, crossbars, jam nuts, washers, couplings, stopper, etc., shall be copper alloy or stainless steel.

P-8 SERVICE SINK (Floor mounted janitor' sink):

Enameled cast iron ASME A112.19.1M, copper alloy or stainless steel ASME A112.19.3M corner, floor mounted 711.2 mm (28 inches) square, 171.5 mm (6-3/4 inches) deep.

Faucet and Spout - Cast or wrought copper alloy, with top or bottom brace, with backflow preventer. Faucets shall have replaceable seat and the washer shall rotate onto the seat. Handles shall be lever type. Strainers shall have internal threads.

Drain Assembly - Plug, cup strainer, crossbars, jam nuts, washers, couplings, stopper, etc., shall be copper alloy or stainless steel.

Trap - Cast iron, minimum 7.5 cm diameter.

P-9 COMBINATION SINK AND LAUNDRY TRAY (Barracks building):

Elkay model WNSF8236LR Weldbilt Stainless Steel Scullery Sink, or equal. Single compartment 14 gauge, type 304, stainless steel scullery sink, overall dimensions are 84inches long x 27.5 inches wide, compartment is 36inches long x 24inches wide x 14 inches deep, left and right drainboards that are each 24inches wide, sink supported on four Elkay model LK251 or equal, 16gauge stainless steel 1 5/8inch diameter legs with adjustable feet, 8inch high full length backsplash.

Faucet and Spout - Cast or wrought copper alloy, with top or bottom brace, with backflow preventer. Faucets shall have replaceable seat and the washer shall rotate onto the seat. Strainers shall have internal threads. Combination faucets with two valves and spouts shall be provided.

Handles - Cast or wrought copper alloy. Lever type.

P-10 KITCHEN SINK (Barracks Buildings):

Barracks building; Elkay model LR1517 or approved equal. Self rim with holes for faucet and handles, overall dimensions 17 1/2 inches wide x 15 inches long, single bowl compartment 12 x 12 x 7 1/2 inches deep, seamless 18 gauge 304 stainless steel with full undercoat.

Barracks building; Faucet, Handles, and Spout - Two-wing handle center set type with high arc gooseneck. Faucets shall meet the requirements of NSF 61, Section 9. Spout body, base, dome, and handles are chrome-plated brass. Handles, gooseneck, etc shall be chrome-plated brass. Faucet is protected from back siphonage by combination of two check valves and a vacuum breaker. Flow shall be limited to 0.16 liters per second (2.5gpm) at a flowing water pressure of 549kPa (80psig).

Drain Assembly - Plug, cup strainer, crossbars, jam nuts, washers, couplings, stopper, etc., shall be copper alloy or stainless steel.

P-12 UTILITY SINK (2-COFs & 4-COFs):

Elkay model WNSF8254 Weldbilt Stainless Steel Scullery Sink, or equal.

Double compartment 14 gauge, type 304, stainless steel scullery sink, overall dimensions are 57 inches long x 27.5 inches wide, each compartment is 27inches wide x 24inches long x 14 inches deep, sink supported on four Elkay model LK251 or equal, 16gauge stainless steel 1 5/8inch diameter legs with adjustable feet, 8inch high full length backsplash.

Faucet and Spout - Cast copper alloy, wrought copper alloy, cast iron, or stainless steel, with backflow preventer. Faucets shall have replaceable seat and the stem shall rotate onto the seat. Strainers shall have internal threads. Combination faucets shall be mounted on the tub back. Spouts shall be externally threaded for hose connection.

Handles - Cast copper alloy, wrought copper alloy, or stainless steel, lever type.

Traps - Copper alloy, or cast iron.

P-13 Shower (Battalion Headquarters, 2-COFs, and 4-COFs):

Shower heads, CID A-A-240 shall include a non-removable, tamperproof device to limit water flow to 0.16 liters per second (2.5 gpm) when tested in accordance with ASME A112.18.1M.

Shower head shall be adjustable spray, stainless steel or chromium plated brass with ball joint. Handles shall be chrome-plated die cast zinc alloy.

Control valves shall be copper alloy and have metal integral parts of copper alloy, nickel alloy, or stainless steel. Valves shall be thermostatic mixing type with pressure compensation. Shower head shall be vandalproof with integral back. Mount shower head at 1900mm above finished floor.

Shower Receptors; Florestone Terrazzo Shower Receptor model 200 or equal, tan color, marble chips cast in white Portland cement to produce a compressive strength of over 3000psi and reinforced with 16 gauge galvanized wire. Removeable type strainers are supplied. 1 1/4 inch tiling flange on 3 sides. Center drain.

P-15 WATER COOLER DRINKING FOUNTAINS:

Elkay model LWCE4 or equal. Top mounted push button actuation, stainless steel finish, no lead design. Drinking fountains shall meet the requirements of NSF 61, Section 9. Water cooler drinking fountains shall: be self contained, conform to ARI 1010, use one of the fluorocarbon gases conforming to ARI 700 and ASHRAE 34 which has an Ozone Depletion Potential of less than or equal to 0.05.

P-17 HANDICAPPED WATER COOLER DRINKING FOUNTAINS:

Elkay model EBFSA8 or equal. Front and side push bars, stainless steel finish, ADA compliant, no lead design. Otherwise, same as P-15.

3.9 POSTED INSTRUCTIONS

Framed instructions under glass or in laminated plastic, including wiring and control diagrams showing the complete layout of the entire system, shall be posted where directed. Condensed operating instructions explaining preventive maintenance procedures, methods of checking the system for normal safe operation, and procedures for safely starting and stopping the system shall be prepared in typed form, framed as specified above for the wiring and control diagrams and posted beside the diagrams. The framed instructions shall be posted before acceptance testing of the systems.

3.10 PERFORMANCE OF WATER HEATING EQUIPMENT

Standard rating condition terms are as follows:

EF = Energy factor, overall efficiency.

ET = Thermal efficiency with 21 degrees C delta T.

EC = Combustion efficiency, 100 percent - flue loss when smoke = 0 (trace is permitted).

SL = Standby loss in W/0.093 sq. m. based on 27 degrees C delta T, or in percent per hour based on nominal 38 degrees C delta T.

HL = Heat loss of tank surface area.

V = Storage volume in liters

3.10.1 Storage Water Heaters

3.10.1.1 Gas

- a. Storage capacity of 379 liters or less, and input rating of 21980 W or less: minimum EF shall be $0.62 - 0.0019V$ per 10 CFR 430.
- b. Storage capacity of more than 379 liters - or input rating more than 21980 W: Et shall be 77 percent; maximum SL shall be $1.3 + 38/V$, per ANSI Z21.10.3.

3.11 TABLES

TABLE I
PIPE AND FITTING MATERIALS FOR
DRAINAGE, WASTE, AND VENT PIPING SYSTEMS

Item #	Pipe and Fitting Materials	SERVICE					
		A	B	C	D	E	F
1	Cast iron soil pipe and fittings, hub and spigot, ASTM A 74 with compression gaskets	X	X	X	X	X	
2	Cast iron soil pipe and fittings hubless, CISPI 301 and ASTM A 888		X	X	X		
11	Seamless red brass pipe, ASTM B 43		X	X			
12	Bronzed flanged fittings, ASME B16.24 for use with Items 11 and 14				X	X	
13	Cast copper alloy solder joint pressure fittings, ASME B16.18 for use with Item 14				X	X	
14	Seamless copper pipe, ASTM B 42				X		
15	Cast bronze threaded fittings, ASME B16.15				X	X	
16	Copper drainage tube, (DWV), ASTM B 306	X*	X	X*	X	X	
17	Wrought copper and wrought alloy solder-joint drainage fittings. ASME B16.29	X	X	X	X	X	
18	Cast copper alloy solder joint drainage fittings, DWV, ASME B16.23	X	X	X	X	X	
19	Acrylonitrile-Butadiene-Styrene (ABS) plastic drain, waste, and vent pipe and fittings ASTM D 2661, ASTM F 628	X	X	X	X	X	X
20	Polyvinyl Chloride plastic drain, waste and vent pipe and fittings, ASTM D 2665, ASTM F 891, (Sch 40)	X	X	X	X	X	X

TABLE I
PIPE AND FITTING MATERIALS FOR
DRAINAGE, WASTE, AND VENT PIPING SYSTEMS

		SERVICE					
Item #	Pipe and Fitting Materials	A	B	C	D	E	F
	ASTM F 1760						

SERVICE:

- A - Underground Building Soil, Waste and Storm Drain
- B - Aboveground Soil, Waste, Drain In Buildings
- C - Underground Vent
- D - Aboveground Vent
- E - Interior Rainwater Conductors Aboveground
- F - Corrosive Waste And Vent Above And Belowground
- * - Hard Temper

TABLE II
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

Item No.	Pipe and Fitting Materials	SERVICE			
		A	B	C	D
5	Seamless red brass pipe, ASTM B 43	X	X		X
6	Bronze flanged fittings, ASME B16.24 for use with Items 5 and 7	X	X		X
7	Seamless copper pipe, ASTM B 42	X	X		X
8	Seamless copper water tube, ASTM B 88, ASTM B 88M	X**	X**	X**	X***
9	Cast bronze threaded fittings, ASME B16.15 for use with Items 5 and 7	X	X		X
10	Wrought copper and bronze solder-joint pressure fittings, ASME B16.22 for use with Items 5 and 7	X	X	X	X
11	Cast copper alloy solder-joint pressure fittings, ASME B16.18 for use with Items 8 and 9	X	X	X	X

A - Cold Water Aboveground

B - Hot Water 82 degree C Maximum Aboveground

C - Compressed Air Lubricated

D - Cold Water Service Belowground

Indicated types are minimum wall thicknesses.

** - Type L - Hard

*** - Type K - Hard temper with brazed joints only or type K-soft temper
without joints in or under floors

**** - In or under slab floors only brazed joints

TABLE III
STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING
EQUIPMENT

A. STORAGE WATER HEATERS

FUEL	STORAGE CAPACITY LITERS		INPUT RATING	TEST PROCEDURE	REQUIRED
					PERFORMANCE
Elect.	454 max.		12 kW max.	10 CFR 430	EF = 0.95-0.00132V minimum
Elect.	454 min.	OR	12 kW min.	ASHRAE 90.1 (Addenda B)	SL = 1.9 W/0.09 sq. m. maximum
Gas	380 max.		22 kW max.	10 CFR 430	EF = 0.62-0.0019V minimum
Gas	380 min.	OR	22 kW min.	ANSI Z21.10.3	ET= 77 percent; SL = 1.3+38/V max.

TERMS:

EF = Energy factor, overall efficiency.

ET = Thermal efficiency with 21 degrees C delta T.

EC = Combustion efficiency, 100 percent - flue loss when smoke = 0
(trace is permitted).SL = Standby loss in W/0.09 sq. m. based on 27 degrees C delta T, or in
percent per hour based on nominal 32 degrees C delta T.

HL = Heat loss of tank surface area

V = Storage volume in gallons

-- End of Section --

SECTION 15895A

AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEM

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

ARI 350	(1986) Sound Rating of Non-Ducted Indoor Air-Conditioning Equipment
ARI 410	(1991) Forced-Circulation Air-Cooling and Air-Heating Coils
ARI 430	(1989) Central-Station Air-Handling Units
ARI 440	(1998) Room Fan-Coil and Unit Ventilator
ARI 880	(1998) Air Terminals
ARI Guideline D	(1996) Application and Installation of Central Station Air-Handling Units

AIR MOVEMENT AND CONTROL ASSOCIATION (AMCA)

AMCA 210	(1999) Laboratory Methods of Testing Fans for Rating
AMCA 300	(1996) Reverberant Room Method for Sound Testing of Fans

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)

AFBMA Std 9	(1990) Load Ratings and Fatigue Life for Ball Bearings
AFBMA Std 11	(1990; R 1999) Load Ratings and Fatigue Life for Roller Bearings

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 123/A 123M	(2001) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A 53/A 53M	(2001) Pipe, Steel, Black and Hot-Dipped,

Zinc-Coated, Welded and Seamless

ASTM A 924/A 924M	(1999) General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM B 117	(1997) Operating Salt Spray (Fog) Apparatus
ASTM C 1071	(1998) Thermal and Acoustical Insulation (Glass Fiber, Duct Lining Material)
ASTM D 1654	(1992) Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments
ASTM D 3359	(1997) Measuring Adhesion by Tape Test
ASTM D 520	(2000) Zinc Dust Pigment
ASTM E 437	(1992; R 1997) Industrial Wire Cloth and Screens (Square Opening Series)

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 52.1	(1992) Gravimetric and Dust-Spot Procedures for Testing Air-Cleaning Devices Used in General Ventilation for Removing Particulate Matter
ASHRAE 68	(1986) Laboratory Method of Testing In-Duct Sound Power Measurement Procedures for Fans
ASHRAE 70	(1991) Method of Testing for Rating the Performance of Air Outlets and Inlets

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1	(1998) Motors and Generators
-----------	------------------------------

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A	(1999) Installation of Air Conditioning and Ventilating Systems
----------	---

SHEET METAL & AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA HVAC Duct Const Stds	(1995; Addenda Nov 1997) HVAC Duct Construction Standards - Metal and Flexible
SMACNA Install Fire Damp HVAC	(1992) Fire, Smoke and Radiation Damper Installation Guide for HVAC Systems

SMACNA Leakage Test Mnl (1985) HVAC Air Duct Leakage Test Manual

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1419 (Rev D; Canc. Notice 1) Filter Element,
Air Conditioning (Viscous-Impingement and
Dry Types, Replaceable)

UNDERWRITERS LABORATORIES (UL)

UL 181 (1996; Rev Dec 1998) Factory-Made Air
Ducts and Air Connectors

UL 1995 (1995; Rev thru Aug 1999) Heating and
Cooling Equipment

UL 214 (1997) Tests for Flame-Propagation of
Fabrics and Films

UL 555 (1999) Fire Dampers

UL 586 (1996; Rev thru Aug 1999) High-Efficiency,
Particulate, Air Filter Units

UL 705 (1994; Rev thru Feb 1999) Power Ventilators

UL 900 (1994; Rev thru Nov 1999) Test Performance
of Air Filter Units

UL Bld Mat Dir (1999) Building Materials Directory

UL Elec Const Dir (1999) Electrical Construction Equipment
Directory

UL Fire Resist Dir (1999) Fire Resistance Directory (2 Vol.)

1.2 COORDINATION OF TRADES

Ductwork, piping offsets, fittings, and accessories shall be furnished as required to provide a complete installation and to eliminate interference with other construction.

1.3 DELIVERY AND STORAGE

Equipment delivered and placed in storage shall be stored with protection from the weather, humidity and temperature variations, dirt and dust, or other contaminants.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

All items designated with a G, EC including product literature, calculations, component data, certificates, diagrams and drawings, shall be submitted concurrently in one complete system submittal. Omission of any required submittal item from the package shall be sufficient cause for disapproval of the entire submittal. Unless otherwise indicated in the submittal review commentary, disapproval of any item within the package shall require a re-submittal of the entire system package, in which all deficiencies shall be corrected.

SD-02 Shop Drawings

Drawings; G, EC

Installation; G, EC

Drawings shall consist of equipment layout including assembly and installation details and electrical connection diagrams; ductwork layout showing the location of all supports and hangers, typical hanger details, gauge reinforcement, reinforcement spacing rigidity classification, and static pressure and seal classifications; and piping layout showing the location of all guides and anchors, the load imposed on each support or anchor, and typical support details. Drawings shall include any information required to demonstrate that the system has been coordinated and will properly function as a unit and shall show equipment relationship to other parts of the work, including clearances required for operation and maintenance.

Test Procedures

Proposed test procedures for piping hydrostatic test, ductwork leak test, and performance tests of systems, at least 2 weeks prior to the start of related testing.

Welding Procedures

A copy of qualified welding procedures, at least 2 weeks prior to the start of welding operations.

System Diagrams; G, RE

Proposed diagrams, at least 2 weeks prior to start of related testing. System diagrams that show the layout of equipment, piping, and ductwork, and typed condensed operation manuals explaining preventative maintenance procedures, methods of checking the system for normal, safe operation, and procedures for safely starting and stopping the system shall be framed under glass or laminated plastic. After approval, these items shall be posted where directed.

Similar Services

Statement demonstrating successful completion of similar

services on at least 5 projects of similar size and scope, at least 2 weeks prior to submittal of other items required by this section.

Welding Joints

A list of names and identification symbols of qualified welders and welding operators, at least 2 weeks prior to the start of welding operations.

SD-03 Product Data

Air Handling Units; G, EC.
 Ductwork and Fittings; G, EC.
 Dampers; G, EC.
 Exhaust Fans; G, EC.
 Diffusers, Registers and Grilles; G, EC.
 Louvers; G, EC.
 VAV Boxes; G, EC.
 Fan Coil Units; G, EC.
 Wall Mounted Humidifier; G, EC
 Blower Coils; G, EC

Complete product literature and supporting data to demonstrate compliance with the contract requirements. Data shall indicate specific item and model proposed. Performance and material specifications shall be clearly identified.

SD-06 Test Reports

Performance Tests; ,

Test reports for the piping hydrostatic test, ductwork leak test, and performance tests in booklet form, upon completion of testing. Reports shall document phases of tests performed including initial test summary, repairs/adjustments made, and final test results.

SD-07 Certificates

Bolts; ,

Written certification from the bolt manufacturer that the bolts furnished comply with the requirements of this specification. The certification shall include illustrations of product markings, and the number of each type of bolt to be furnished.

SD-10 Operation and Maintenance Data

Operating and Maintenance Instructions; G, RE

Six manuals listing step-by-step procedures required for system startup, operation, shutdown, and routine maintenance, at least 2 weeks prior to field training. The manuals shall include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance including the name of a local supplier, simplified wiring and controls diagrams, troubleshooting guide, and recommended service organization (including address and telephone

number) for each item of equipment. Each service organization submitted shall be capable of providing 4 hour onsite response to a service call on an emergency basis.

1.5 BATTALION HEADQUARTERS

For Battalion Headquarters, extend exhaust register and associated ductwork shown on sheet CM5.1 at about 4 meters plan South (true East) of Janitors Closet Room 106 in Womens Room 116, to serve Janitor's Closet 106. Install Return Grille RG-1 in ceiling of Janitor's Closet Room 106. Delete Note 11 from sheet CM5.1 concerning holding ductwork close to underside of structure. Extend supply registers shown on sheet CM5.1 serving Lobby room 102 to soffit shown on sheet CA2.1 with bottom of diffuser at about 2800mm above finished floor. Disregard sheet CM8.1 portion which incorrectly shows outside ventilation air for air handling unit AHU-1C and blower coil BC-1C being supplied through mechanical room outside wall. Runouts to diffusers, grilles, and registers for all supply and exhaust shall contain manual balancing dampers. The round louver shown on sheet CM5.3 is a relief and exhaust louver and not an intake louver as stated in note. Coordinate move ceiling diffusers, registers, and grilles where interference is present with lights. Add 300mm x 300mm transfer opening in wall above ceiling, and return grille RG-1 in ceiling, for Women room 116 and Men room 119. Add return grille in ceilings for Vestibule 101, 143, and 103.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Components and equipment shall be standard products of a manufacturer regularly engaged in the manufacturing of products that are of a similar material, design and workmanship. The standard products shall have been in satisfactory commercial or industrial use for 2 years before bid opening. The 2-year experience shall include applications of components and equipment under similar circumstances and of similar size. The 2 years must be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures. Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown. The equipment items shall be supported by a service organization.

2.2 ASBESTOS PROHIBITION

Asbestos and asbestos-containing products shall not be used.

2.3 NAMEPLATES

Equipment shall have a nameplate that identifies the manufacturer's name, address, type or style, model or serial number, and catalog number.

2.4 EQUIPMENT GUARDS AND ACCESS

Belts, pulleys, chains, gears, couplings, projecting setscrews, keys, and other rotating parts exposed to personnel contact shall be fully enclosed or guarded according to OSHA requirements. High temperature equipment and piping exposed to contact by personnel or where it creates a potential fire hazard shall be properly guarded or covered with insulation of a type specified. Catwalks, shall be provided where shown and shall be constructed according to Section 05500A MISCELLANEOUS METAL.

2.5 ELECTRICAL WORK

Electrical motor-driven equipment specified shall be provided complete with motor, motor starter, and controls. Unless otherwise specified, electric equipment, including wiring and motor efficiencies, shall be according to Section 16415A ELECTRICAL WORK, INTERIOR. Electrical characteristics and enclosure type shall be as shown. Unless otherwise indicated, motors of 745 W and above shall be high efficiency type. Motor starters shall be provided complete with thermal overload protection and other appurtenances necessary. Each motor shall be according to NEMA MG 1 and shall be of sufficient size to drive the equipment at the specified capacity without exceeding the nameplate rating of the motor. Manual or automatic control and protective or signal devices required for the operation specified, and any control wiring required for controls and devices, but not shown, shall be provided. Where two-speed or variable-speed motors are indicated, solid-state variable-speed controller may be provided to accomplish the same function. Solid-state variable-speed controllers shall be utilized for motors rated 7.45 kW (10 hp) or less. Adjustable frequency drives shall be used for larger motors.

2.6 CONTROLS

Controls shall be provided as specified in Section 15951A HEATING, VENTILATING AND AIR CONDITIONING (HVAC) CONTROL SYSTEMS.

2.7 DUCTWORK COMPONENTS

2.7.1 Metal Ductwork

All aspects of metal ductwork construction, including all fittings and components, shall comply with SMACNA HVAC Duct Const Stds unless otherwise specified. Elbows shall be radius type with a centerline radius of 1-1/2 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes may be used. All ductwork shall meet the requirements of Seal Class A. Sealants shall conform to fire hazard classification specified in Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS. Pressure sensitive tape shall not be used as a sealant. Spiral lock seam duct, and flat oval shall be made with duct sealant and locked with not less than 3 equally spaced drive screws or other approved methods indicated in SMACNA HVAC Duct Const Stds. The sealant shall be applied to the exposed male part of the fitting collar so that the sealer will be on the inside of the joint and fully protected by the metal of the duct fitting. One brush coat of the sealant shall be applied over the outside of the joint to at least 50 mm band width covering all screw heads and joint gap. Dents in the male portion of the

slip fitting collar will not be acceptable. Outdoor air intake ducts and plenums shall be fabricated with watertight soldered or brazed joints and seams.

2.7.1.1 Transitions

Diverging air flow transitions shall be made with each side pitched out a maximum of 15 degrees, for an included angle of 30 degrees. Transitions for converging air flow shall be made with each side pitched in a maximum of 30 degrees, for an included angle of 60 degrees, or shall be as indicated. Factory-fabricated reducing fittings for systems using round duct sections when formed to the shape of the ASME short flow nozzle, need not comply with the maximum angles specified.

2.7.1.2 Insulated Nonmetallic Flexible Duct Runouts

Flexible duct runouts shall be used only where indicated. Runout length shall be as shown on the drawings, but shall in no case exceed 3 m. Runouts shall be preinsulated, factory fabricated, and shall comply with NFPA 90A and UL 181. Either field or factory applied vapor barrier shall be provided. Where coil induction or high velocity units are supplied with vertical air inlets, a streamlined and vaned and mitered elbow transition piece shall be provided for connection to the flexible duct or hose. The last elbow to these units, other than the vertical air inlet type, shall be a die-stamped elbow and not a flexible connector. Insulated flexible connectors may be used as runouts. The insulated material and vapor barrier shall conform to the requirements of Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS. The insulation material surface shall not be exposed to the air stream.

2.7.1.3 General Service Duct Connectors

A flexible duct connector approximately 150 mm in width shall be provided where sheet metal connections are made to fans or where ducts of dissimilar metals are connected. For round/oval ducts, the flexible material shall be secured by stainless steel or zinc-coated, iron clinch-type draw bands. For rectangular ducts, the flexible material locked to metal collars shall be installed using normal duct construction methods. The composite connector system shall comply with UL 214 and be classified as "flame-retarded fabrics" in UL Bld Mat Dir.

2.7.2 Ductwork Accessories

2.7.2.1 Duct Access Doors

Access doors shall be provided in ductwork and plenums where indicated and at all air flow measuring primaries, automatic dampers, fire dampers, coils, thermostats, and other apparatus requiring service and inspection in the duct system, and unless otherwise shown, shall conform to SMACNA HVAC Duct Const Stds. Access doors shall be provided upstream and downstream of air flow measuring primaries and heating and cooling coils. Doors shall be minimum 375 x 450 mm, unless otherwise shown. Where duct size will not accommodate this size door, the doors shall be made as large as practicable. Doors 600 x 600 mm or larger shall be provided with

fasteners operable from both sides. Doors in insulated ducts shall be the insulated type.

2.7.2.2 Fire Dampers

Fire dampers shall be 1-1/2 hour fire rated unless otherwise indicated. Fire dampers shall conform to the requirements of NFPA 90A and UL 555. A positive pressure relief door shall be provided upstream of fire dampers which are provided in the supply air and exhaust ducts. A negative pressure relief door shall be provided downstream of fire dampers which are provided in the return air ducts. The size and pressure relief rating of the relief doors shall be in accordance with the manufacturer's recommendations. The pressure relief door may be a combined pressure relief and access door unit if it is specifically listed by the manufacturer as such. A pressure relief door shall be provided upstream of the fire damper. If the ductwork connected to the fire damper is to be insulated then this pressure relief damper shall be factory insulated. Fire dampers shall be automatic operating type and shall have a dynamic rating suitable for the maximum air velocity and pressure differential to which it will be subjected. Fire dampers shall be approved for the specific application, and shall be installed according to their listing. Fire dampers shall be equipped with a steel sleeve or adequately sized frame installed in such a manner that disruption of the attached ductwork, if any, will not impair the operation of the damper. Sleeves or frames shall be equipped with perimeter mounting angles attached on both sides of the wall or floor opening. Ductwork in fire-rated floor-ceiling or roof-ceiling assembly systems with air ducts that pierce the ceiling of the assemblies shall be constructed in conformance with UL Fire Resist Dir. Fire dampers shall be curtain type with damper blades. Dampers shall not reduce the duct or the air transfer opening cross-sectional area. Dampers shall be installed so that the centerline of the damper depth or thickness is located in the centerline of the wall, partition or floor slab depth or thickness. Unless otherwise indicated, the installation details given in SMACNA Install Fire Damp HVAC and in manufacturer's instructions for fire dampers shall be followed.

2.7.2.3 Splitters and Manual Balancing Dampers

Splitters and manual balancing dampers shall be furnished with accessible operating mechanisms. Where operators occur in finished portions of the building, operators shall be chromium plated with all exposed edges rounded. Splitters shall be operated by quadrant operators or 5 mm (3/16 inch) rod brought through the side of the duct with locking setscrew and bushing. Two rods are required on splitters over 200 mm (8 inches). Manual volume control dampers shall be operated by locking-type quadrant operators. Dampers and splitters shall be 2 gauges heavier than the duct in which installed. Unless otherwise indicated, multileaf dampers shall be opposed blade type with maximum blade width of 300 mm. Access doors or panels shall be provided for all concealed damper operators and locking setscrews. Unless otherwise indicated, the locking-type quadrant operators for dampers, when installed on ducts to be thermally insulated, shall be provided with stand-off mounting brackets, bases, or adapters to provide clearance between the duct surface and the operator not less than the thickness of the insulation. Stand-off mounting items shall be integral

with the operator or standard accessory of the damper manufacturer. Volume dampers shall be provided where indicated and where required for balancing.

2.7.2.4 Air Deflectors and Branch Connections

Air deflectors shall be provided at duct mounted supply outlets, at takeoff or extension collars to supply outlets, at duct branch takeoff connections, and at 90 degree elbows, as well as at locations as indicated on the drawings or otherwise specified. Conical branch connections or 45 degree entry connections may be used in lieu of deflectors or extractors for branch connections. All air deflectors, except those installed in 90 degree elbows, shall be provided with an approved means of adjustment. Adjustment shall be made from easily accessible means inside the duct or from an adjustment with sturdy lock on the face of the duct. When installed on ducts to be thermally insulated, external adjustments shall be provided with stand-off mounting brackets, integral with the adjustment device, to provide clearance between the duct surface and the adjustment device not less than the thickness of the thermal insulation. Air deflectors shall be factory-fabricated units consisting of curved turning vanes or louver blades designed to provide uniform air distribution and change of direction with minimum turbulence or pressure loss. Air deflectors shall be factory or field assembled. Blade air deflectors, also called blade air extractors, shall be approved factory fabricated units consisting of equalizing grid and adjustable blade and lock. Adjustment shall be easily made from the face of the diffuser or by position adjustment and lock external to the duct. Stand-off brackets shall be provided on insulated ducts and are described herein. Fixed air deflectors, also called turning vanes, shall be provided in 90 degree elbows.

2.7.3 Duct Sleeves, Framed Prepared Openings, Closure Collars

2.7.3.1 Duct Sleeves

Duct sleeves shall be provided for round ducts 375 mm in diameter or less passing through floors, walls, ceilings, or roof, and installed during construction of the floor, wall, ceiling, or roof. Round ducts larger than 375 mm in diameter and square, rectangular, and oval ducts passing through floors, walls, ceilings, or roof shall be installed through framed prepared openings. The Contractor shall be responsible for the proper size and location of sleeves and prepared openings. Sleeves and framed openings are also required where grilles, registers, and diffusers are installed at the openings. Framed prepared openings shall be fabricated from 1.0 mm (20 gauge) galvanized steel, unless otherwise indicated. Where sleeves are installed in bearing walls or partitions, black steel pipe, ASTM A 53/A 53M, Schedule 20 shall be used. Sleeve shall provide 25 mm clearance between the duct and the sleeve or 25 mm clearance between the insulation and the sleeve for insulated ducts.

2.7.3.2 Framed Prepared Openings

Openings shall have 25 mm clearance between the duct and the opening or 25 mm clearance between the insulation and the opening for insulated ducts.

2.7.3.3 Closure Collars

Collars shall be fabricated of galvanized sheet metal not less than 100 mm wide, unless otherwise indicated, and shall be installed on exposed ducts on each side of walls or floors where sleeves or prepared openings are provided. Collars shall be installed tight against surfaces. Collars shall fit snugly around the duct or insulation. Sharp edges of the collar around insulated duct shall be ground smooth to preclude tearing or puncturing the insulation covering or vapor barrier. Collars for round ducts 375 mm in diameter or less shall be fabricated from 1.0 mm (20 gauge) galvanized steel. Collars for round ducts larger than 375 mm and square, and rectangular ducts shall be fabricated from 1.3 mm (18 gauge) galvanized steel. Collars shall be installed with fasteners on maximum 150 mm centers, except that not less than 4 fasteners shall be used.

2.7.4 Diffusers, Registers, and Grilles

Units shall be factory-fabricated of stainless steel or aluminum and shall distribute the specified quantity of air evenly over space intended without causing noticeable drafts, air movement faster than 0.25 m/s (50 fpm) in occupied zone, or dead spots anywhere in the conditioned area. Outlets for diffusion, spread, throw, and noise level shall be as required for specified performance. Performance shall be certified according to ASHRAE 70. Inlets and outlets shall be sound rated and certified according to ASHRAE 70. Sound power level shall be as indicated. Diffusers and registers shall be provided with volume damper with accessible operator, unless otherwise indicated; or if standard with the manufacturer, an automatically controlled device will be acceptable. Volume dampers shall be opposed blade type for all diffusers and registers, except linear slot diffusers. Linear slot diffusers shall be provided with round or elliptical balancing dampers. Where the inlet and outlet openings are located less than 2 m above the floor, they shall be protected by a grille or screen according to NFPA 90A.

2.7.4.1 Diffusers

Diffuser types shall be as indicated. Ceiling mounted units shall be furnished with anti-smudge devices, unless the diffuser unit minimizes ceiling smudging through design features. Diffusers shall be provided with air deflectors of the type indicated. Air handling troffers or combination light and ceiling diffusers shall conform to the requirements of UL Elec Const Dir for the interchangeable use as cooled or heated air supply diffusers or return air units. Ceiling mounted units shall be installed with rims tight against ceiling. Sponge rubber gaskets shall be provided between ceiling and surface mounted diffusers for air leakage control. Suitable trim shall be provided for flush mounted diffusers. Duct collar connecting the duct to diffuser shall be airtight and shall not interfere with volume controller. Return or exhaust units shall be similar to supply diffusers.

2.7.4.2 Registers and Grilles

Units shall be four-way directional-control type, except that return and exhaust registers may be fixed horizontal or vertical louver type similar

in appearance to the supply register face. Registers shall be provided with sponge-rubber gasket between flanges and wall or ceiling. Wall supply registers shall be installed at least 150 mm below the ceiling unless otherwise indicated. Return and exhaust registers shall be located 150 mm above the floor unless otherwise indicated. Four-way directional control may be achieved by a grille face which can be rotated in 4 positions or by adjustment of horizontal and vertical vanes. Grilles shall be as specified for registers, without volume control damper.

2.7.5 Louvers

Louvers for installation in exterior walls which are associated with the air supply and distribution system shall be as specified in Section 07600A SHEET METALWORK, GENERAL.

2.7.6 Air Vents, Penthouses, and Goosenecks

Air vents, penthouses, and goosenecks shall be fabricated from galvanized steel or aluminum sheets with galvanized or aluminum structural shapes. Sheet metal thickness, reinforcement, and fabrication shall conform to SMACNA HVAC Duct Const Stds. Louver blades shall be accurately fitted and secured to frames. Edges of louver blades shall be folded or beaded for rigidity and baffled to exclude driving rain. Air vents, penthouses, and goosenecks shall be provided with bird screen.

2.7.7 Bird Screens and Frames

Bird screens shall conform to ASTM E 437, No. 2 mesh, aluminum or stainless steel. Aluminum screens shall be rated "medium-light". Stainless steel screens shall be rated "light". Frames shall be removable type, or stainless steel or extruded aluminum.

2.8 AIR SYSTEMS EQUIPMENT

2.8.1 Fans

Fans shall be tested and rated according to AMCA 210. Fans may be connected to the motors either directly or indirectly with V-belt drive. V-belt drives shall be designed for not less than 150 percent of the connected driving capacity. Motor sheaves shall be variable pitch for 11 kW (15 hp) and below and fixed pitch as defined by ARI Guideline D. Variable pitch sheaves shall be selected to drive the fan at a speed which will produce the specified capacity when set at the approximate midpoint of the sheave adjustment. When fixed pitch sheaves are furnished, a replaceable sheave shall be provided when needed to achieve system air balance. Motors for V-belt drives shall be provided with adjustable rails or bases. Removable metal guards shall be provided for all exposed V-belt drives, and speed-test openings shall be provided at the center of all rotating shafts. Fans shall be provided with personnel screens or guards on both suction and supply ends, except that the screens need not be provided, unless otherwise indicated, where ducts are connected to the fan.

Fan and motor assemblies shall be provided with vibration-isolation supports. Vibration-isolation units shall be standard products with published loading ratings. Each fan shall be selected to produce the

capacity required at the fan static pressure indicated. Sound power level shall be as indicated. The sound power level values shall be obtained according to AMCA 300. Standard AMCA arrangement, rotation, and discharge shall be as indicated.

2.8.1.1 In-Line Centrifugal Fans

In-line fans shall have centrifugal backward inclined blades, stationary discharge conversion vanes, internal and external belt guards, and adjustable motor mounts. Fans shall be mounted in a welded tubular casing.

Air shall enter and leave the fan axially. Inlets shall be streamlined with conversion vanes to eliminate turbulence and provide smooth discharge air flow. Fan bearings and drive shafts shall be enclosed and isolated from the air stream. Fan bearings shall be sealed against dust and dirt and shall be permanently lubricated, and shall be precision self aligning ball or roller type. Bearing life shall be L50 rated at not less than 200,000 hours as defined by AFBMA Std 9 and AFBMA Std 11.

2.8.1.2 Panel Type Power Wall Ventilators

Fans shall be propeller type, assembled on a reinforced metal panel with venturi opening spun into panel. Fans with wheels less than 600 mm (24 inches) diameter shall be direct or V-belt driven and fans with wheels 600 mm (24 inches) diameter and larger shall be V-belt drive type. Fans shall be furnished with wall mounting collar. Lubricated bearings shall be provided. Fans shall be fitted with wheel and motor side metal or wire guards which have a corrosion-resistant finish. Motor enclosure shall be dripproof type. Motor operated or pneumatic-operated dampers shall be provided as shown.

2.8.1.3 Centrifugal Type Power Wall Ventilators

Fans shall be V-belt driven centrifugal type with backward inclined, non-overloading wheel. Motor housing shall be removable and weatherproof. Unit housing shall be designed for sealing to building surface and for discharge and condensate drippage away from building surface. Housing shall be constructed of heavy gauge aluminum. Unit shall be fitted with an manufacturer's standard motor-operated damper, an airtight and liquid-tight metallic wall sleeve. Motor enclosure shall be totally enclosed fan cooled type. Lubricated bearings shall be provided.

2.8.1.4 Centrifugal Type Power Roof Ventilators

Fans shall be direct driven with backward inclined, non-overloading wheel. Motor compartment housing shall be hinged or removable and weatherproof, constructed of heavy gauge aluminum. Fans shall be provided with birdscreen, disconnect switch, motorized dampers, sound curb, roof curb, and extended base. Motors enclosure shall be dripproof type. Grease-laden kitchen exhaust fans shall be centrifugal type according to UL 705 and fitted with V-belt drive, round hood, and windband upblast discharge configuration, integral residue trough and collection device, motor and power transmission components located in outside positively air ventilated compartment. Lubricated bearings shall be provided.

2.8.1.5 Ceiling Exhaust Fans

Suspended cabinet-type ceiling exhaust fans shall be centrifugal type, direct-driven. Fans shall have acoustically insulated housing. Integral backdraft damper shall be chatter-proof. The integral face grille shall be of egg-crate design or louver design. Fan motors shall be mounted on vibration isolators. Unit shall be provided with mounting flange for hanging unit from above. Fans shall be U.L. listed.

2.8.2 Coils

Coils shall be fin-and-tube type constructed of seamless copper tubes and aluminum fins mechanically bonded or soldered to the tubes. Copper tube wall thickness shall be a minimum of 0.508 mm. Casing and tube support sheets shall be not lighter than 1.6 mm (16 gauge) galvanized steel, formed to provide structural strength. When required, multiple tube supports shall be provided to prevent tube sag. Each coil shall be tested at the factory under water at not less than 2.76 MPa (400 psi) air pressure and shall be suitable for 1.38 MPa (200 psi) working pressure. Coils shall be mounted for counterflow service. Coils shall be rated and certified according to ARI 410.

2.8.2.1 Water Coils

Water coils shall be installed with a pitch of not less than 10 mm per meter of the tube length toward the drain end. Headers shall be constructed of cast iron, welded steel or copper. Each coil shall be provided with a plugged vent and drain connection extending through the unit casing.

2.8.3 Air Filters

Air filters shall be listed according to requirements of UL 900, except high efficiency particulate air filters of 99.97 percent efficiency by the DOP Test method shall be as listed under the Label Service and shall meet the requirements of UL 586.

2.8.3.1 Extended Surface Pleated Panel Filters

Filters shall be 50 mm (2 inch) depth, sectional, disposable type of the size indicated and shall have an average efficiency of 25 to 30 percent when tested according to ASHRAE 52.1. Initial resistance at 2.54 m/s (500 feet per minute) shall not exceed 9 mm water gauge. Filters shall be UL Class 2. Media shall be nonwoven cotton and synthetic fiber mat. A wire support grid bonded to the media shall be attached to a moisture resistant fiberboard frame. All four edges of the filter media shall be bonded to the inside of the frame to prevent air bypass and increase rigidity.

2.9 AIR HANDLING UNITS

2.9.1 Factory-Fabricated Air Handling Units

Units shall be as indicated. Units shall include fans, coils, airtight insulated casing, adjustable V-belt drives, belt guards for externally

mounted motors, access sections where indicated, mixing box combination sectional filter-mixing box, vibration-isolators, and appurtenances required for specified operation. Vibration isolators shall be as indicated. Each air handling unit shall have physical dimensions suitable to fit space allotted to the unit and shall have the capacity indicated. Air handling unit shall have published ratings based on tests performed according to ARI 430.

2.9.1.1 Casings

Casing sections shall be 2 inch double wall type constructed of a minimum 18 gauge galvanized steel, or 18 gauge steel outer casing protected with a corrosion resistant paint finish according to paragraph FACTORY PAINTING. Inner casing of double-wall units shall be minimum 1.0 mm (20 gauge) solid galvanized steel. Casing shall be designed and constructed with an integral structural steel frame such that exterior panels are non-load bearing. Exterior panels shall be individually removable. Removal shall not affect the structural integrity of the unit. Casings shall be provided with inspection doors, access sections, and access doors. Inspection and access doors shall be insulated, fully gasketed, double-wall type, of a minimum 1.3 mm (18 gauge) outer and 1.0 mm (20 gauge) inner panels. Doors shall be rigid and provided with heavy duty hinges and latches. Inspection doors shall be a minimum 300 mm wide by 300 mm high. Access doors shall be minimum 600 mm wide and shall be the full height of the unit casing or a minimum of 1800 mm, whichever is less. A minimum 200 mm by 200 mm sealed glass window suitable for the intended application shall be installed in all access doors. Access Sections shall be according to paragraph AIR HANDLING UNITS. Drain pan shall be double-bottom type constructed of 16 gauge galvanized steel, pitched to the drain connection. Drain pans shall be constructed water tight, treated to prevent corrosion, and designed for positive condensate drainage. When 2 or more cooling coils are used, with one stacked above the other, condensate from the upper coils shall not flow across the face of lower coils. Intermediate drain pans or condensate collection channels and downspouts shall be provided, as required to carry condensate to the unit drain pan out of the air stream and without moisture carryover. Each casing section handling conditioned air shall be insulated with not less than 25 mm (1 inch) thick, 24 kg per cubic meter (1-1/2 pound density) coated fibrous glass material having a thermal conductivity not greater than 0.033 W/m-K (0.23 Btu/hr-sf-F). Factory applied fibrous glass insulation shall conform to ASTM C 1071, except that the minimum thickness and density requirements do not apply, and shall meet the requirements of NFPA 90A. Foam-type insulation is not acceptable. Foil-faced insulation shall not be an acceptable substitute for use on double-wall access doors and inspections doors and casing sections. Duct liner material, coating, and adhesive shall conform to fire-hazard requirements specified in Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS. Exposed insulation edges and joints where insulation panels are butted together shall be protected with a metal nosing strip or shall be coated to conform to meet erosion resistance requirements of ASTM C 1071. A latched and hinged inspection door, shall be provided in the fan and coil sections. Additional inspection doors, access doors and access sections shall be provided where indicated.

2.9.1.2 Heating and Cooling Coils

Coils shall be provided as specified in paragraph AIR SYSTEMS EQUIPMENT, for types indicated.

2.9.1.3 Air Filters

Air filters shall be as specified in paragraph AIR SYSTEMS EQUIPMENT for types and thickness indicated.

2.9.1.4 Fans

Fans shall be double-inlet, centrifugal type with each fan in a separate scroll. Fans and shafts shall be dynamically balanced prior to installation into air handling unit, then the entire fan assembly shall be statically and dynamically balanced at the factory after it has been installed in the air handling unit. Fans shall be mounted on steel shafts accurately ground and finished. Fan bearings shall be sealed against dust and dirt and shall be precision self-aligning ball or roller type. Bearing life shall be L50 rated at not less than 200,000 hours as defined by AFBMA Std 9 and AFBMA Std 11. Bearings shall be permanently lubricated or lubricated type with lubrication fittings readily accessible at the drive side of the unit. Bearings shall be supported by structural shapes, or die formed sheet structural members, or support plates securely attached to the unit casing. Bearings may not be fastened directly to the unit sheet metal casing. Fans and scrolls shall be furnished with coating indicated. Fans shall be driven by a unit-mounted or a floor-mounted motor connected to fans by V-belt drive complete with belt guard for externally mounted motors. Belt guards shall be the three sided enclosed type with solid or expanded metal face. Belt drives shall be designed for not less than a 1.3 service factor based on motor nameplate rating. Motor sheaves shall be variable pitch for 20 kW and below and fixed pitch above 20 kW as defined by ARI Guideline D. Where fixed sheaves are required, variable pitch sheaves may be used during air balance, but shall be replaced with an appropriate fixed sheave after air balance is completed. Variable pitch sheaves shall be selected to drive the fan at a speed that will produce the specified capacity when set at the approximate midpoint of the sheave adjustment. Motors for V-belt drives shall be provided with adjustable bases. Fan motors shall have open enclosures. Unit fan or fans shall be selected to produce the required capacity at the fan static pressure. Sound power level shall be as indicated. The sound power level values shall be obtained according to AMCA 300 or ASHRAE 68.

2.9.1.5 Access Sections and Filter/Mixing Boxes

Access sections shall be provided where indicated and shall be furnished with access doors. Access sections and filter/mixing boxes shall be constructed in a manner identical to the remainder of the unit casing and shall be equipped with access doors. Mixing boxes shall be designed to minimize air stratification and to promote thorough mixing of the air streams.

2.9.1.6 Dampers

Dampers shall be as specified in paragraph CONTROLS.

2.10 TERMINAL UNITS

2.10.1 Room Fan-Coil Units

Base units shall include galvanized coil casing, coil assembly drain pan air filter, fans, motor, fan drive, and motor switch, plus an enclosure for cabinet models and casing for concealed models. Leveling devices integral with the unit shall be provided for vertical type units. Sound power levels shall be as indicated. Sound power level data or values for these units shall be obtained according to test procedures based on ARI 350. Sound power values apply to units provided with factory fabricated cabinet enclosures and standard grilles. Values obtained for the standard cabinet models will be acceptable for concealed models without separate test provided there is no variation between models as to the coil configuration, blowers, motor speeds, or relative arrangement of parts. Automatic valves and controls shall be provided as specified in paragraph CONTROLS. Each unit shall be fastened securely to the building structure. Capacity of the units shall be as indicated. Room fan-coil units shall be certified as complying with ARI 440, and shall meet the requirements of UL 1995.

2.10.1.1 Enclosures

Enclosures shall be fabricated of not lighter than 1.3 mm (18 gauge) steel, reinforced and braced. Front panels of enclosures shall be removable and provided with 13 mm (1/2 inch) thick dual density fibrous glass insulation. The exposed side shall be high density, erosion-proof material suitable for use in air streams with velocities up to 23 m/s (4,500 fpm). Ferrous metal surfaces shall be galvanized or factory finished with corrosion resistant enamel. Access doors or removable panels shall be provided for piping and control compartments. Duct discharge collar shall be provided for concealed models. Enclosures shall have easy access for filter replacement.

2.10.1.2 Fans

Fans shall be galvanized steel or aluminum, multiblade, centrifugal type. In lieu of metal, fans and scrolls may be non-metallic materials of suitably reinforced compounds. Fans shall be dynamically and statically balanced. Surfaces shall be smooth. Assemblies shall be accessible for maintenance. Disassembly and re-assembly shall be by means of mechanical fastening devices and not by epoxies or cements.

2.10.1.3 Coils

Coils shall be constructed of not less than 10 mm (3/8 inch) outside diameter seamless copper tubing, with copper or aluminum fins mechanically bonded or soldered to the tubes. Coils shall be provided with not less than 12 mm (1/2 inch) outside diameter flare or sweat connectors, accessory piping package with thermal connections suitable for connection to the type of control valve supplied, and manual air vent. Coils shall be tested hydrostatically at 2000 kPa (300 psi) or under water at 1700 kPa (250 psi) air pressure and suitable for 1400 kPa (200 psi) working pressure. Provisions shall be made for coil removal.

2.10.1.4 Drain Pans

Drain and drip pans shall be sized and located to collect all water condensed on and dripping from any item within the unit enclosure or casing. Drain pans shall be constructed of not lighter than 0.9 mm (21 gauge) steel, galvanized after fabrication, thermally insulated to prevent condensation. Insulation shall have a flame spread rating not over 25 without evidence of continued progressive combustion, a smoke developed rating no higher than 50, and shall be of a waterproof type or coated with a waterproofing material. In lieu of the above, drain pans may be constructed of die-formed 0.85 mm (22 gauge) steel, formed from a single sheet, galvanized after fabrication, insulated and coated as specified for the 0.9 mm (21 gauge) material or of die-formed 0.9 mm (21 gauge) type 304 stainless steel, insulated as specified above. Drain pans shall be pitched to drain. Minimum 20 mm (3/4 inch) NPT or 15 mm (5/8 inch) OD drain connection shall be provided in drain pan. Auxiliary drain pans to catch drips from control and piping packages, eliminating insulation of the packages, may be plastic; if metal, the auxiliary pans shall comply with the requirements specified above. Insulation at control and piping connections thereto shall extend 25 mm minimum over the auxiliary drain pan.

2.10.1.5 Manually Operated Outside Air Dampers

Manually operated outside air dampers shall be provided according to the arrangement indicated. Dampers shall be parallel airfoil type and of galvanized construction. Blades shall rotate on stainless steel or nylon sleeve bearings.

2.10.1.6 Filters

Filters shall be of the fiberglass disposable type, 25 mm (1 inch) thick, conforming to CID A-A-1419. Filters in each unit shall be removable without the use of tools.

2.10.1.7 Motors

Motors shall be of the permanent split-capacitor type with built-in thermal overload protection, directly connected to unit fans. Motor switch shall be two or three speeds and off, manually operated, and shall be mounted on an identified plate adjacent to the room thermostat. In lieu of the above fan speed control, a solid-state variable-speed controller having a minimum speed reduction of 50 percent may be provided. Motors shall have permanently-lubricated or oilable sleeve-type or combination ball and sleeve-type bearings with vibration isolating mountings suitable for continuous duty. Motor power consumption, shown in watts, at the fan operating speed selected to meet the specified capacity shall not exceed the following values:

Free Discharge Motors

Unit Capacity (LS)	Maximum Power Consumption (Watts)		
	115V	230V	277V
94	70	110	90
142	100	110	110
189	170	150	150
283	180	210	220
378	240	240	230
472	310	250	270
566	440	400	440

High Static Motors

Unit Capacity (L/S)	Maximum Power Consumption (Watts)
94	145
142	145
189	210
283	320
378	320
472	530
566	530

2.10.1.8 Sound Considerations

Unit fan motors shall not exceed 1520 rpm when operating at high speed.

2.10.2 Variable Air Volume (VAV)

VAV terminal units shall be the type, size, and capacity shown and shall be mounted in the ceiling or wall cavity and shall be suitable for single duct system applications. Volume damper, damper actuators and controls shall not be installed in the unit. Unit enclosures shall be constructed of galvanized steel not lighter than 0.85 mm (22 gauge) or aluminum sheet not lighter than 1.3 mm (18 gauge). Reheat coils shall be provided as indicated. Acoustical lining shall be according to NFPA 90A.

2.10.2.1 Variable Volume, Parallel Fan Powered

Unit fan shall be centrifugal, direct-driven, double-inlet type with forward curved blades. Fan motor shall be either single speed with speed controller or three-speed, permanently lubricated, permanent split-capacitor type. Fan/motor assembly shall be isolated from the casing to minimize vibration transmission. Fan control shall be factory furnished.

2.11 FACTORY PAINTING

Units which are not of galvanized construction according to ASTM A 123/A 123M or ASTM A 924/A 924M shall be factory painted with a corrosion

resisting paint finish. Internal and external ferrous metal surfaces shall be cleaned, phosphatized and coated with a paint finish which has been tested according to ASTM B 117, ASTM D 1654, and ASTM D 3359. Evidence of satisfactory paint performance for a minimum of 125 hours for units to be installed indoors and 500 hours for units to be installed outdoors shall be submitted. Rating of failure at the scribe mark shall be not less than 6, average creepage not greater than 3 mm. Rating of the inscribed area shall not be less than 10, no failure. On units constructed of galvanized steel which have been welded, exterior surfaces of welds or welds that have burned through from the interior shall receive a final shop docket of zinc-rich protective paint according to ASTM D 520 Type I.

PART 3 EXECUTION

3.1 INSTALLATION

Work shall be installed as shown and according to the manufacturer's diagrams and recommendations.

3.1.1 Condensate Drain Lines

Water seals shall be provided in the condensate drain from all units except room fan-coil units. The depth of each seal shall be 50 mm plus 0.1 mm for each Pa, of the total static pressure rating of the unit to which the drain is connected. Water seals shall be constructed of 2 tees and an appropriate U-bend with the open end of each tee plugged. Pipe cap or plug cleanouts shall be provided where indicated. Drains indicated to connect to the sanitary waste system shall be connected by an indirect waste fitting. Air conditioner drain lines shall be insulated as specified in Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS.

3.1.2 Equipment and Installation

Frames and supports shall be provided for tanks, compressors, pumps, valves, air handling units, fans, coils, dampers, and other similar items requiring supports. Air handling units shall be floor mounted or ceiling hung, as indicated. The method of anchoring and fastening shall be as detailed. Floor-mounted equipment, unless otherwise indicated, shall be set on not less than 150 mm (6 inch) concrete pads or curbs doweled in place. Concrete foundations for circulating pumps shall be heavy enough to minimize the intensity of the vibrations transmitted to the piping and the surrounding structure, as recommended in writing by the pump manufacturer. In lieu of a concrete pad foundation, a concrete pedestal block with isolators placed between the pedestal block and the floor may be provided. The concrete foundation or concrete pedestal block shall be of a mass not less than three times the weight of the components to be supported. Lines connected to the pump mounted on pedestal blocks shall be provided with flexible connectors. Foundation drawings, bolt-setting information, and foundation bolts shall be furnished prior to concrete foundation construction for all equipment indicated or required to have concrete foundations. Concrete for foundations shall be as specified in Section 03300 CAST-IN-PLACE STRUCTURAL CONCRETE.

3.1.3 Access Panels

Access panels shall be provided for concealed valves, vents, controls, dampers, and items requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced and maintained or completely removed and replaced. Access panels shall be as specified in Section 05500A MISCELLANEOUS METAL.

3.1.4 Flexible Connectors

Pre-insulated flexible connectors and flexible duct shall be attached to other components in accordance with the latest printed instructions of the manufacturer to ensure a vapor tight joint. Hangers, when required to suspend the connectors, shall be of the type recommended by the connector or duct manufacturer and shall be provided at the intervals recommended.

3.1.5 Sleeved and Framed Openings

Space between the sleeved or framed opening and the duct or the duct insulation shall be packed as specified in Section 07840A FIRESTOPPING for fire rated penetrations. For non-fire rated penetrations, the space shall be packed as specified in Section 07900A JOINT SEALING.

3.1.6 Metal Ductwork

Installation shall be according to SMACNA HVAC Duct Const Stds unless otherwise indicated. Duct supports for sheet metal ductwork shall be according to SMACNA HVAC Duct Const Stds, unless otherwise specified. Friction beam clamps indicated in SMACNA HVAC Duct Const Stds shall not be used. Risers on high velocity ducts shall be anchored in the center of the vertical run to allow ends of riser to move due to thermal expansion. Supports on the risers shall allow free vertical movement of the duct. Supports shall be attached only to structural framing members and concrete slabs. Supports shall not be anchored to metal decking unless a means is provided and approved for preventing the anchor from puncturing the metal decking. Where supports are required between structural framing members, suitable intermediate metal framing shall be provided. Where C-clamps are used, retainer clips shall be provided.

3.1.7 Dust Control

To prevent the accumulation of dust, debris and foreign material during construction, temporary dust control protection shall be provided. The distribution system (supply and return) shall be protected with temporary seal-offs at all inlets and outlets at the end of each day's work. Temporary protection shall remain in place until system is ready for startup.

3.1.8 Insulation

Thickness and application of insulation materials for ductwork, piping, and equipment shall be according to Section 15080A THERMAL INSULATION FOR MECHANICAL SYSTEMS. Outdoor air intake ducts and plenums shall be externally insulated up to the point where the outdoor air reaches the conditioning unit.

3.1.9 Duct Test Holes

Holes with closures or threaded holes with plugs shall be provided in ducts and plenums as indicated or where necessary for the use of pitot tube in balancing the air system. Extensions, complete with cap or plug, shall be provided where the ducts are insulated.

3.1.10 Power Transmission Components Adjustment

V-belts and sheaves shall be tested for proper alignment and tension prior to operation and after 72 hours of operation at final speed. Belts on drive side shall be uniformly loaded, not bouncing. Alignment of direct driven couplings shall be to within 50 percent of manufacturer's maximum allowable range of misalignment.

3.2 FIELD PAINTING AND COLOR CODE MARKING

Finish painting of items only primed at the factory, surfaces not specifically noted otherwise, and color code marking for piping shall be as specified in Section 09900 PAINTS AND COATINGS.

3.3 DUCTWORK LEAK TEST

Ductwork leak test shall be performed for the entire air distribution and exhaust system, including fans, coils, filters, etc. designated as static pressure Class 750 Pa (3 inch water gauge) through Class 2500 Pa (10 inch water gauge). Test procedure, apparatus, and report shall conform to SMACNA Leakage Test Mnl. The maximum allowable leakage rate is 3 l/s per 10 square meters of duct surface. Ductwork leak test shall be completed with satisfactory results prior to applying insulation to ductwork exterior.

3.4 CLEANING AND ADJUSTING

Pipes shall be cleaned free of scale and thoroughly flushed of foreign matter. A temporary bypass shall be provided for water coils to prevent flushing water from passing through coils. Strainers and valves shall be thoroughly cleaned. Prior to testing and balancing, air shall be removed from water systems by operating the air vents. Temporary measures, such as piping the overflow from vents to a collecting vessel shall be taken to avoid water damage during the venting process. Air vents shall be plugged or capped after the system has been vented. Inside of room fan-coil units air terminal units, ducts, plenums, and casing shall be thoroughly cleaned of debris and blown free of small particles of rubbish and dust and then shall be vacuum cleaned before installing outlet faces. Equipment shall be wiped clean, with traces of oil, dust, dirt, or paint spots removed. Temporary filters shall be provided prior to startup of all fans that are operated during construction, and new filters shall be installed after all construction dirt has been removed from the building, and the ducts, plenums, casings, and other items specified have been vacuum cleaned. System shall be maintained in this clean condition until final acceptance. Bearings shall be properly lubricated with oil or grease as recommended by the manufacturer. Belts shall be tightened to proper tension. Control valves and other miscellaneous equipment requiring adjustment shall be

adjusted to setting indicated or directed. Fans shall be adjusted to the speed indicated by the manufacturer to meet specified conditions.

3.5 TESTING, ADJUSTING, AND BALANCING

Testing, adjusting, and balancing shall be as specified in Section 15990A TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS. Testing, adjusting, and balancing shall begin only when the air supply and distribution, including controls, has been completed, with the exception of performance tests.

3.6 PERFORMANCE TESTS

After testing, adjusting, and balancing has been completed as specified, each system shall be tested as a whole to see that all items perform as integral parts of the system and temperatures and conditions are evenly controlled throughout the building. Corrections and adjustments shall be made as necessary to produce the conditions indicated or specified. Capacity tests and general operating tests shall be conducted by an experienced engineer. Tests shall cover a period of not less than 5 days for each system and shall demonstrate that the entire system is functioning according to the specifications. Coincidental chart recordings shall be made at points indicated on the drawings for the duration of the time period and shall record the temperature at space thermostats or space sensors, the humidity at space humidistats or space sensors and the ambient temperature and humidity in a shaded and weather protected area.

3.7 FIELD TRAINING

The Contractor shall conduct a training course for operating and maintenance personnel as designated by the Contracting Officer. Training shall be provided for a period of 40 hours of normal working time and shall start after the system is functionally complete but prior to the performance tests. The field instruction shall cover all of the items contained in the approved Operating and Maintenance Instructions.

-- End of Section --

SECTION 15951A

DIRECT DIGITAL CONTROL FOR HVAC

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION (AMCA)

AMCA 500 (11989; Rev994) Test Methods for Louvers, Dampers and Shutters

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C12.1 (1995) Code for Electricity Metering

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 269 (1996) Seamless and Welded Austenitic Stainless Steel Tubing for General Service

ASTM B 88 (1996) Seamless Copper Water Tube

ASTM B 88M (1996) Seamless Copper Water Tube (Metric)

ASTM D 1693 (1997a) Environmental Stress-Cracking of Ethylene Plastics

ASTM D 635 (1997) Rate of Burning and/or Extent and Time of Burning of Self-Supporting Plastics in a Horizontal Position

ASME INTERNATIONAL (ASME)

ASME B40.1 (1991) Gauges - Pressure Indicating Dial Type - Elastic Element

ASME BPVC SEC VIII D1 (1998) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels Division 1 - Basic Coverage

ELECTRONIC INDUSTRIES ALLIANCE (EIA)

EIA ANSI/EIA/TIA-232-F (1991) Interface Between Data Technical Equipment and Data Circuit-Terminating Equipment Employing Serial Binary Data

Interchange

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41	(1991; R 1995) Surge Voltages in Low-Voltage AC Power Circuits
IEEE Std 142	(1991) IEEE Recommended Practice for Grounding of Industrial and Commercial Power Systems

INSTRUMENT SOCIETY OF AMERICA (ISA)

ISA S7.0.01	(1996) Quality Standard for Instrument Air
-------------	--

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(1991) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ICS 1	(1993) Industrial Control and Systems
NEMA ST 1	(1988) Specialty Transformers (Except General-Purpose Type)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A	(1996) Installation of Air Conditioning and Ventilating Systems
----------	--

UNDERWRITERS LABORATORIES (UL)

UL 268A	(1998) Smoke Detectors for Duct Application
UL 508	(1993; Rev thru Oct 1997) Industrial Control Equipment
UL 94	(1996; Rev thru Jul 1998) Tests for Flammability of Plastic Materials for Parts in Devices and Appliances

1.2 GENERAL REQUIREMENTS

The direct digital control (DDC) shall be a complete system suitable for the heating, ventilating and air-conditioning (HVAC) system. The DDC system shall be a complete control system consisting of a building automation system and an automatic temperature control system suitable for the HVAC system. The direct digital control system shall be connected to the existing Johnson Controls Metasys System (EMCS) at Fort Riley that has been accepted as an approved interface by the Contracting Officer. The direct digital controls shall be Johnson Controls Metasys. All controls added under this project shall be connected to a global network control unit located as shown, and shall communicate to the basewide EMCS via the

LAN serving the base. The contractor shall supply all materials required and software generation necessary to enable the DDC to communicate with the Fort Riley EMCS engineering control station located in building 364. Fort Riley will supply the necessary LAN drops and IP addresses. The Contractor shall generate all software and install all hardware required to connect the new facilities to the existing EMCS. The Contractor shall update all EMCS workstation networks with all the new 7002 area buildings.

1.2.1 Dynamic Color Graphic Displays

Color graphic floor plan displays, and system schematics for each piece of mechanical equipment, including air handling units, chilled water systems and hot water boiler systems, shall be generated to optimize system performance analysis and speed alarm recognition. the existing operator interface workstation located in Building 364 shall be utilized for operator interface.

1.2.1 Nameplates, Lens Caps, and Tags

Nameplates and lens caps bearing legends and tags bearing device-unique identifiers as shown shall have engraved or stamped characters. A plastic or metal tag shall be mechanically attached directly to each device or attached by a metal chain or wire. Each airflow measurement station shall have a tag showing flow rate range for signal output range, duct size, and identifier as shown.

1.2.2 Verification of Dimensions

After becoming familiar with all details of the work, the Contractor shall verify all dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing any work.

1.2.3 Drawings

Because of the small scale of the drawings, it is not possible to indicate all offsets, fittings, and accessories that may be required. The Contractor shall carefully investigate the mechanical, electrical, and finish conditions that could affect the work to be performed, shall arrange such work accordingly, and shall furnish all work necessary to meet such conditions.

1.2.4 Power-Line Surge Protection

Equipment connected to ac circuits shall be protected from power-line surges. Equipment protection shall meet the requirements of IEEE C62.41. Fuses shall not be used for surge protection.

1.2.5 Surge Protection for Transmitter and Control Wiring

DDC system control-panel equipment shall be protected against surges induced on control and transmitter wiring installed outside. The equipment protection shall be tested in the normal mode and in the common mode, using the following two waveforms:

a. A 10-microsecond by 1,000-microsecond waveform with a peak voltage of 1,500 volts and a peak current of 60 amperes.

b. An eight microsecond by 20-microsecond waveform with a peak voltage of 1,000 volts and a peak current of 500 amperes.

1.2.6 System Overall Reliability Requirement

The system shall be configured and installed to yield a mean time between failure (MTBF) of at least 40,000 hours. Each DDC controller shall be designed, configured, installed and programmed to provide for stand alone operation with minimal performance degradation on failure of other system components to which it is connected or with which it communicates.

1.2.7 DDC System Network Accessibility

Where the systems to be controlled by the DDC system are located in multiple mechanical rooms, each mechanical room shall have at least one communication port for the portable workstation/tester. DDC controllers shall be located in the same room as the equipment being controlled or in an adjacent space which has direct access to the equipment room.

1.2.8 System Accuracy and Display

The system shall maintain an end-to-end accuracy for one year from sensor to operator's console display for the applications specified and shall display the value as specified. Each temperature shall be displayed and printed to nearest 0.05 degree C.

1.2.8.1 Space Temperature

Space temperature with a range of 10 to 30 degrees C plus or minus 0.5 degrees C for conditioned space; minus 1 to plus 55 degrees C plus or minus 0.5 degrees C for unconditioned space.

1.2.8.2 Duct Temperature

Duct temperature with a range of 5 to 60 degrees C plus or minus 1 degree C.

1.2.8.3 Outside Air Temperature

Outside air (OA) temperature with a range of minus 35 to plus 55 degrees C plus or minus 1 degree C; with a subrange of minus 1 to plus 40 degrees C plus or minus 0.5 degree C.

1.2.8.4 Water Temperature

Water temperature with a range of minus 1 to plus 40 degrees C plus or minus 0.5 degree C; the range of 40 to 120 degrees C plus or minus 1 degree C; and water temperatures for the purpose of performing energy calculations using differential temperatures to plus or minus 0.5 degree C using matched sensors.

1.2.8.5 High Temperature

High temperature with a range of 100 to 260 degrees C plus or minus 1 degree C.

1.2.8.6 Relative Humidity

Relative humidity, within a range of 20 to 80 percent, plus or minus 6.0 percent of range (display and print to nearest 1.0 percent).

1.2.8.7 Pressure

Pressure with a range for the specific application plus or minus 2.0 percent of range (display and print to nearest kPa.)

1.2.8.8 Flow

Flow with a range for the specific application plus or minus 3.0 percent of range, and flows for the purpose of thermal calculations to plus or minus 2.0 percent of actual flow (display and print to nearest unit, such as liters per second.

1.2.8.9 KWh and kW Demand

KWh and kW demand with a range for the specific application plus or minus 1.0 percent of reading (display and print to nearest kWh or kW).

1.2.8.10 Analog Value Input

An analog value input to the system's equipment via an AI with a maximum error of 0.50 percent of range, not including the sensor or transmitter error. This accuracy shall be maintained over the specified environmental conditions.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. All items designated with a G, EC, including product literature, calculations, component data, certificates, diagrams and drawings, shall be submitted concurrently in one complete system submittal. Omission of any required submittal item from the package shall be sufficient cause for disapproval of the entire submittal. Unless otherwise indicated in the submittal review commentary, disapproval of any item within the package shall require a re-submittal of the entire system package, in which all deficiencies shall be corrected. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

HVAC Control System; G, EC

Drawings shall be on A1 (841 by 594 mm) sheets in the form and arrangement shown. The drawings shall use the same abbreviations, symbols, nomenclature and identifiers shown. Each control system element on a drawing shall have a unique identifier as shown. The HVAC Control System Drawings shall be delivered together as a complete submittal. Deviations must be approved by the Contracting Officer. Drawings shall be submitted along with Submittal SD-01, Data.

a. HVAC Control System Drawings shall include the following:

Sheet One: Drawing Index, HVAC Control System Legend.
 Sheet Two: Valve Schedule, Damper Schedule.
 Sheet Three: Compressed Air Station Schematic.
 Sheet Four: Control System Schematic and Equipment Schedule.
 Sheet Five: Sequence of Operation and Data Terminal Strip Layout.
 Sheet Six: Control Loop Wiring Diagrams.
 Sheet Seven: Motor Starter and Relay Wiring Diagram.
 Sheet Eight: Communication Network and Block Diagram.
 Sheet Nine: DDC Panel Installation and Block Diagram.

(Repeat Sheets Four through Seven for each AHU System.)

b. The HVAC Control System Drawing Index shall show the name and number of the building, military site, State or other similar designation, and Country. The Drawing Index shall list HVAC Control System Drawings, including the drawing number, sheet number, drawing title, and computer filename when used. The HVAC Control System Legend shall show generic symbols and the name of devices shown on the HVAC Control System Drawings.

c. The valve schedule shall include each valve's unique identifier, size, flow coefficient Kv, pressure drop at specified flow rate, spring range, positive positioner range, actuator size, close-off pressure data, dimensions, and access and clearance requirements data. Valve schedules may be submitted in advance but shall be included in the complete submittal.

d. The damper schedule shall contain each damper's and each actuator's identifier, nominal and actual sizes, orientation of axis and frame, direction of blade rotation, spring ranges, operation rate, positive positioner ranges, locations of actuators and damper end switches, arrangement of sections in multi-section dampers, and methods of connecting dampers, actuators, and linkages. The Damper Schedule shall include the maximum leakage rate at the operating static-pressure differential. The Damper Schedule shall contain actuator selection data supported by calculations of the torque required to move and seal the dampers, access and clearance requirements. Damper schedules may be submitted in advance but shall be included in the complete submittal.

e. The compressed air station schematic diagram shall show all

equipment, including: compressor with motor horsepower and voltage; starter; isolators; manual bypasses; tubing sizes; drain piping and drain traps; reducing valves; dryer; and data on manufacturer's names and model numbers, mounting, access, and clearance requirements. Air Compressor and air dryer data shall include calculations of the air consumption of all current-to-pneumatic transducers and of any other control system devices to be connected to the compressed air station, and the compressed air supply dewpoint temperature at 140 kPa . Compressed air station schematic drawings shall be submitted for each compressed air station.

f. The HVAC control system schematics shall be in the form shown, and shall show all control and mechanical devices associated with the HVAC system. A system schematic drawing shall be submitted for each HVAC system.

g. The HVAC control system equipment Schedule shall be in the form shown. All devices shown on the drawings having unique identifiers shall be referenced in the equipment schedule. Information to be included in the equipment schedule shall be the control loop, device unique identifier, device function, setpoint, input range, and additional important parameters (i.e., output range). An equipment schedule shall be submitted for each HVAC system.

h. The HVAC control system sequence of operation shall reflect the language and format of this specification, and shall refer to the devices by their unique identifiers as shown. No operational deviations from specified sequences will be permitted without prior written approval of the Contracting Officer. Sequences of operation shall be submitted for each HVAC control system including each type of terminal unit control system.

i. The HVAC control system wiring diagrams shall be functional wiring diagrams which show the interconnection of conductors and cables to HVAC control panel terminal blocks and to the identified terminals of devices, starters and package equipment. The wiring diagrams shall show necessary jumpers and ground connections. The wiring diagrams shall show the labels of all conductors. Sources of power required for HVAC control systems and for packaged equipment control systems shall be identified back to the panel board circuit breaker number, HVAC system control panel, magnetic starter, or packaged equipment control circuit. Each power supply and transformer not integral to a controller, starter, or packaged equipment shall be shown. The connected volt-ampere load and the power supply volt-ampere rating shall be shown. Wiring diagrams shall be submitted for each HVAC control system.

SD-03 Product Data

Surge Protection;G, EC
Regulated Power Supplies;G, EC
Power Line Conditioners;G, EC

Wiring;G, EC
 Valve Actuators and positive positioners;G, EC
 Damper Actuators and positive positioners;G, EC
 Control Valves;G, EC
 Control Dampers;G, EC
 Temperature Switches;G, EC
 Temperature and Pressure Instruments;G, EC
 Thermostats;G, EC
 Thermometers and Gauges;G, EC
 DDC Control Panels and Accessories;G, EC
 Relays;G, EC
 Tubing;G, EC
 Compressed Air Station;G, EC
 Compressed Air Station Specialities;G, EC
 IP Transducers;G, EC
 Manual Switches;G,EC
 Equipment Compliance Booklet; G, EC
 Dynamic Color Graphic Display Layout Proposals; G, EC
 Input Output (I/O) Summary Tables; G, EC

The HVAC Control System Equipment Compliance Booklet (ECB) shall be in booklet form and indexed, with numbered tabs separating the information on each device. It shall consist of, but not be limited to, data sheets and catalog cuts which document compliance of all devices and components with the specifications. The ECB shall be indexed in alphabetical order by the unique identifiers. Devices and components which do not have unique identifiers shall follow the devices and components with unique identifiers and shall be indexed in alphabetical order according to their functional name. The ECB shall include a Bill of Materials for each HVAC Control System. The Bill of Materials shall function as the Table of Contents for the ECB and shall include the device's unique identifier, device function, manufacturer, model/part/catalog number used for ordering, and tab number where the device information is located in the ECB. The ECB shall be submitted along with Submittal SD-04, Drawings.

Service Organizations; G, RE
 Six copies of a list of service organizations qualified to service the HVAC control system. The list shall include the service organization name, address, technical point of contact and telephone number, and contractual point of contact and telephone number.

Commissioning Procedures; G, EC

Six copies of the HVAC control system commissioning procedures, in booklet form and indexed, 60 days prior to the scheduled start of commissioning. Commissioning procedures shall be provided for each HVAC control system, and for each type of terminal unit control system. The Commissioning procedures shall reflect the format and language of this specification, and refer to devices by their unique identifiers as shown. The Commissioning procedures shall be specific for each HVAC system, and shall give detailed step-by-step procedures for commissioning of the system.

a. The Commissioning procedures shall include detailed, product specific set-up procedures, configuration procedures, adjustment procedures, and calibration procedures for each device. Where the detailed product specific commissioning procedures are included in manufacturer supplied manuals, reference may be made in the HVAC control system commissioning procedures to the manuals.

b. An HVAC control system commissioning procedures equipment list shall be included that lists the equipment to be used to accomplish commissioning. The list shall include manufacturer name, model number, equipment function, the date of the latest calibration, and the results of the latest calibration.

Performance Verification Test Procedures; G, RE

Six copies of the HVAC Control System Performance Verification Test Procedures, in booklet form and indexed, 60 days before the Contractor's scheduled test dates. The performance verification test procedures shall refer to the devices by their unique identifiers as shown, shall explain, step-by-step, the actions and expected results that will demonstrate that the HVAC control system performs in accordance with the sequences of operation, and other contract documents. An HVAC control system performance verification test equipment list shall be included that lists the equipment to be used during performance verification testing. The list shall include manufacturer name, model number, equipment function, the date of the latest calibration, and the results of the latest calibration.

Training; G, RE

An outline for the HVAC control system training course with a proposed time schedule. Approval of the planned training schedule shall be obtained from the Government at least 60 days prior to the start of the training. Six copies of HVAC control system training course material 30 days prior to the scheduled start of the training course. The training course material shall include the operation manual, maintenance and repair manual, and paper copies of overheads used in the course.

SD-06 Test Reports

Commissioning Report; G, EC,

Six copies of the HVAC Control System Commissioning Report, in booklet form and indexed, within 30 days after completion of the system commissioning. The commissioning report shall include data collected during the HVAC control system commissioning procedures and shall follow the format of the commissioning procedures. The commissioning report shall include all configuration checksheets with final values listed for all parameters, setpoints, P, I, D setting constants, calibration data for all devices, results of adjustments, and results of testing.

Performance Verification Test; G, RE

Six copies of the HVAC Control System Performance Verification Test Report, in booklet form and indexed, within 30 days after completion of the test. The HVAC control system performance verification test report shall include data collected during the HVAC control system performance verification test. The original copies of all data gathered during the performance verification test shall be turned over to the Government after Government approval of the test results.

SD-07 Certificates

Air Storage Tank; G, RE

An ASME Air Storage Tank Certificate for each storage tank.

SD-10 Operation and Maintenance Data

Operation Manual; G, RE

Maintenance and Repair Manual; G, RE

Six copies of the HVAC Control System Operation Manual and HVAC Control System Maintenance and Repair Manual, for each HVAC control system, 30 days before the date scheduled for the training course.

1.4 DELIVERY AND STORAGE

Products shall be stored with protection from the weather, humidity and temperature variations, dirt and dust, and other contaminants, within the storage condition limits published by the equipment manufacturer. Dampers shall be stored so that seal integrity, blade alignment and frame alignment are maintained.

1.4 OPERATION MANUAL

An HVAC control system operation manual in indexed booklet form shall be provided for each HVAC control system. The operation manual shall include the HVAC control system sequence of operation, and procedures for the HVAC system start-up, operation and shut-down. The operation manual shall include as-built HVAC control system detail drawings. The operation manual shall include the as-built configuration checksheets, the procedures for changing HVAC control system setpoints, and the procedures for placing HVAC system controllers in the manual control mode.

a. The procedures for changing HVAC control system setpoints shall describe the step-by-step procedures required to change the process variable setpoints, the alarm setpoints, the bias settings, and setpoint reset schedules.

b. The procedures for placing HVAC system controllers in the manual control mode shall describe step-by-step procedures required to obtain manual control of each controlled device and to manually adjust their positions.

1.5 MAINTENANCE AND REPAIR MANUAL

An HVAC control system maintenance and repair manual in indexed booklet form in hardback binders shall be provided for each HVAC control system. The maintenance and repair manual shall include the routine maintenance checklist, a recommended repair methods list, a list of recommended maintenance and repair tools, the qualified service organization list, the as-built commissioning procedures and report, the as-built performance verification test procedures and report, and the as-built equipment data booklet.

a. The routine maintenance checklist shall be arranged in a columnar format. The first column shall list all devices listed in the equipment compliance booklet, the second column shall state the maintenance activity or state no maintenance required, the third column shall state the frequency of the maintenance activity, and the fourth column for additional comments or reference.

b. The recommended repair methods list shall be arranged in a columnar format and shall list all devices in the equipment data compliance booklet and state the guidance on recommended repair methods, either field repair, factory repair, or whole-item replacement.

c. The as-built equipment data booklet shall include the equipment compliance booklet and manufacturer supplied user manuals and information.

d. If the operation manual and the maintenance and repair manual are provided in a common volume, they shall be clearly differentiated and separately indexed.

1.6 MAINTENANCE AND SERVICE

Services, materials and equipment shall be provided as necessary to maintain the entire system in an operational state as specified for a period of one year after successful completion and acceptance of the Performance Verification Test. Impacts on facility operations shall be minimized.

1.6.1 Description of Work

The adjustment and repair of the system shall include the manufacturer's required adjustments of computer equipment, software updates, transmission equipment and instrumentation and control devices.

1.6.2 Personnel

Service personnel shall be qualified to accomplish work promptly and satisfactorily. The Government shall be advised in writing of the name of the designated service representative, and of any changes in personnel.

1.6.3 Scheduled Inspections

Two inspections shall be performed at six-month intervals and all work required shall be performed. Inspections shall be scheduled in June and

December. These inspections shall include:

- a. Visual checks and operational tests of equipment.
- b. Fan checks and filter changes for control system equipment.
- c. Clean control system equipment including interior and exterior surfaces.
- d. Check and calibrate each field device. Check and calibrate 50 percent of the total analog points during the first inspection. Check and calibrate the remaining 50 percent of the analog points during the second major inspection. Certify analog test instrumentation accuracy to be twice that of the device being calibrated. Randomly check at least 25 percent of all digital points for proper operation during the first inspection. Randomly check at least 25 percent of the remaining digital points during the second inspection.
- e. Run system software diagnostics and correct diagnosed problems.
- f. Resolve any previous outstanding problems.

1.6.4 Scheduled Work

This work shall be performed during regular working hours, Monday through Friday, excluding legal holidays.

1.6.5 Emergency Service

The Government will initiate service calls when the system is not functioning properly. Qualified personnel shall be available to provide service to the system. A telephone number where the service supervisor can be reached at all times shall be provided. Service personnel shall be at the site within 4 hours after receiving a request for service. The control system shall be restored to proper operating condition within 1 calendar day or 8 hours.

1.6.6 Operation

Scheduled adjustments and repairs shall include verification of the control system operation as demonstrated by the applicable tests of the performance verification test.

1.6.7 Records and Logs

Dated records and logs shall be kept of each task, with cumulative records for each major component, and for the complete system chronologically. A continuous log shall be maintained for all devices. The log shall contain initial analog span and zero calibration values and digital points. Complete logs shall be kept and shall be available for inspection onsite, demonstrating that planned and systematic adjustments and repairs have been accomplished for the control system.

1.6.8 Work Requests

Each service call request shall be recorded as received and shall include the serial number identifying the component involved, its location, date and time the call was received, nature of trouble, names of the service personnel assigned to the task, instructions describing what has to be done, the amount and nature of the materials to be used, the time and date work started, and the time and date of completion. A record of the work performed shall be submitted within 5 days after work is accomplished.

1.6.9 System Modifications

Recommendations for system modification shall be submitted in writing. No system modifications, including operating parameters and control settings, shall be made without prior approval of the Government. Any modifications made to the system shall be incorporated into the operations and maintenance manuals, and other documentation affected.

1.6.10 Software

Updates to the software shall be provided for system, operating and application software, and operation in the system shall be verified. Updates shall be incorporated into operations and maintenance manuals, and software documentation. There shall be at least one scheduled update near the end of the first year's warranty period, at which time the latest released version of the Contractor's software shall be installed and validated.

1.7 FACTORY TESTING

The Contractor shall assemble the factory test DDC system as specified and shall perform test to demonstrate that the performance of the system satisfies the requirements of this specification. Model numbers of equipment tested shall be identical to those to be delivered to the site. Original copies of data produced, including results of each test procedure during factory testing shall be delivered to the Government at the conclusion of testing, prior to Government approval of the test. The test results documentation shall be arranged so that commands, responses, and data acquired are correlated in a manner which will allow for logical interpretation of the data.

1.7.1 Factory Test Setup

The factory test setup shall include the following:

- a. Central workstation/tester.
- b. Printer.
- c. DDC test set.
- d. Portable workstation/tester.
- e. Communication links of each type and speed including MODEMs.

f. Dial-up MODEM.

g. Software.

PART 2 PRODUCTS

2.1 GENERAL EQUIPMENT REQUIREMENTS

Units of the same type of equipment shall be products of a single manufacturer. Each major component of equipment shall have the manufacturer's name and address, and the model and serial number in a conspicuous place. Materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacturing of such products, which are of a similar material, design and workmanship. The standard products shall have been in a satisfactory commercial or industrial use for two years prior to use on this project. The two years' use shall include applications of equipment and materials under similar circumstances and of similar size. The two years' experience shall be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures. Products having less than a two-year field service record will be acceptable if a certified record of satisfactory field operation, for not less than 6,000 hours exclusive of the manufacturer's factory tests, can be shown. The equipment items shall be supported by a service organization. Items of the same type and purpose shall be identical, including equipment, assemblies, parts and components. Automatic temperature controls shall be direct digital controls that will provide the required sequence of operation.

2.1.1 Electrical and Electronic Devices

Electrical, electronic, and electropneumatic devices not located within a DDC panel shall have a NEMA ICS 1 enclosure in accordance with NEMA 250 unless otherwise shown.

2.1.2 Standard Signals

The output of all analog transmitters and the analog input and output of all DDC controllers shall manufacturer's standard signals (voltage or current).

2.1.3 Ambient Temperature Limits

DDC panels shall have ambient condition ratings of 1.7 to 49 degrees C and 10 to 95 percent relative humidity, noncondensing. Devices installed outdoors shall operate within limit ratings of minus 37 to plus 66 degrees C. Instrumentation and control elements shall be rated for continuous operation under the ambient environmental temperature, pressure, humidity, and vibration conditions specified or normally encountered for the installed location.

2.1.4 Year 2000 Compliance

All equipment and software shall be Year 2000 compliant and shall be able

to accurately process date/time data (including, but not limited to, calculating, comparing, and sequencing) from, into, and between the twentieth and twenty-first centuries, including leap year calculations, when used in accordance with the product documentation provided by the contractor, provided that all products (e.g. hardware, software, firmware) used in combination with other information technology, shall accurately process date/time data if other information technology properly exchanges date/time data with it.

2.2 TUBING

2.2.1 Copper

Copper tubing shall conform to ASTM B 88, ASTM B 88M and shall have sweat fittings and valves.

2.2.2 Stainless Steel

Stainless steel tubing shall conform to ASTM A 269 and shall have stainless steel compression fittings.

2.2.3 Plastic

Plastic tubing shall have barbed fittings and valves. Plastic tubing shall have the burning characteristics of linear low-density polyethylene tubing, shall be self-extinguishing when tested in accordance with ASTM D 635, shall have UL 94 V-2 flammability classification, and shall withstand stress cracking when tested in accordance with ASTM D 1693. Plastic-tubing bundles shall be provided with Mylar barrier and flame-retardant polyethylene jacket.

2.3 WIRING

2.3.1 Terminal Blocks

Terminal blocks shall be insulated, modular, feed-through, clamp style with recessed captive screw-type clamping mechanism, shall be suitable for rail mounting, and shall have end plates and partition plates for separation or shall have enclosed sides.

2.3.2 Control Wiring for 24-Volt Circuits

Control wiring for 24-volt circuits shall be 18 AWG minimum, stranded copper and shall be rated for 300-volt service.

2.3.3 Wiring for 120-Volt Circuits

Wiring for 120-volt circuits shall be 18 AWG minimum, stranded copper and shall be rated for 600-volt service.

2.3.4 Instrumentation Cable

Instrumentation cable shall be 18 AWG, stranded copper, single- or multiple-twisted, minimum 50 mm lay of twist, 100 percent shielded pairs,

and shall have a 300-volt insulation. Each pair shall have a 20 AWG tinned-copper drain wire and individual overall pair insulation. Cables shall have an overall aluminum-polyester or tinned-copper cable-shield tape, overall 20 AWG tinned-copper cable drain wire, and overall cable insulation.

2.3.5 Transformers

Step down transformers shall be utilized where control equipment operates at lower than line circuit voltage. Transformers, other than transformers in bridge circuits, shall have primaries wound for the voltage available and secondaries wound for the correct control circuit voltage. Transformer shall be sized so that the connected load is 80 percent of the rated capacity or less. Transformers shall conform to UL 508 and NEMA ST 1.

2.4 ACTUATORS

Actuators shall be pneumatic for air handling unit control valves, zone dampers and control dampers (OA, RA, and MA). Electric actuators may be utilized for VAV terminal unit valves, exhaust fan dampers, and for fan coil units valves. Electric damper actuators shall directly mount on the damper shaft without linkages and shall have sufficient torque for the application. Actuators shall be provided with mounting and connecting hardware. Actuators shall fail to their spring-return positions on signal or power failure, except that VAV terminal unit volume damper actuators may be of the floating type. The actuator stroke shall be limited in the direction of power stroke by an adjustable stop. Actuators shall have a visible position indicator. Actuators shall smoothly open or close the devices to which they are applied and shall have a full stroke response time of 90 seconds or less. Electric actuators shall have an oil-immersed gear train. Electric or electronic actuators operating in series shall have an auxiliary actuator driver. Electric or electronic actuators used in sequencing applications shall have an adjustable operating range and start point. Pneumatic actuators shall be rated for 172 kPa operating pressure except for high-pressure cylinder-type actuators.

2.4.1 Valve Actuators

Valve actuators shall be selected to provide a minimum of 125 percent of the motive power necessary to operate the valve over its full range of operation.

2.4.2 Positive Positioners

Positive positioners are required for pneumatic actuators except for multizone zone control dampers. Each positive positioner shall be a pneumatic relay with a mechanical feedback mechanism and an adjustable operating range and starting point.

2.5 AUTOMATIC CONTROL VALVES

Valves shall have stainless-steel stems and stuffing boxes with extended necks to clear the piping insulation. Unless otherwise stated, valves shall have globe style bodies. Valve bodies shall be designed for not less

than 862 kPa working pressure or 150 percent of the system operating pressure, whichever is greater. Valve leakage rating shall be 0.01 percent of rated Kv . Unless otherwise specified, bodies for valves 40 mm and smaller shall be brass or bronze, with threaded or union ends; bodies for 50 mm valves shall have threaded ends; and bodies for valves 50 to 80 mm shall be of brass, bronze or iron. Bodies for valves 65 mm and larger shall be provided with flanged-end connections. Valve Kv shall be within 100 to 125 percent of the Kv shown.

2.5.1 Butterfly Valve Assembly

Butterfly valves shall be threaded lug type suitable for dead-end service and modulation to the fully-closed position, with carbon-steel bodies and noncorrosive discs, stainless steel shafts supported by bearings, and EPDM seats suitable for temperatures from minus 29 to plus 121 degrees C. Valves shall have a manual means of operation independent of the actuator. The rated Kv for butterfly valves shall be the value Kv at 70% open (60 degrees open).

2.5.2 Two-Way Valves

Two-way modulating valves shall have equal-percentage characteristics.

2.5.3 Three-Way Valves

Three-way valves shall provide linear flow control with constant total flow throughout full plug travel.

2.5.4 Duct-Coil and Terminal-Unit-Coil Valves

Control valves with either flare-type or solder-type ends shall be provided for duct or terminal-unit coils. Flare nuts shall be furnished for each flare-type end valve.

2.5.5 Valves for Chilled-Water Service

Internal valve trim shall be bronze except that valve stems may be type 316 stainless steel. Valve Kv shall be within 100 to 125 percent of the Kv shown. Valves 100 mm and larger shall be butterfly.

2.5.6 Valves for Hot-Water Service

For hot water service below 122 degrees C and dual-temperature service, internal trim (including seats, seat rings, modulating plugs, and springs) of valves controlling water hotter than 99 degrees C shall be Type 316 stainless steel. Internal trim for valves controlling water 99 degrees C or less shall be brass or bronze. Nonmetallic parts of hot-water control valves shall be suitable for a minimum continuous operating temperature of 121 degrees C or 28 degrees C above the system design temperature, whichever is higher. Valves 100 mm and larger shall be butterfly valves.

2.6 DAMPERS

2.6.1 Damper Assembly

A single damper section shall have blades no longer than 1.2 meters and shall be no higher than 1.8 meters. Maximum damper blade width shall be 203 mm. Larger sizes shall be made from a combination of sections. Dampers shall be steel, or other materials where shown. Flat blades shall be made rigid by folding the edges. Blade-operating linkages shall be within the frame so that blade-connecting devices within the same damper section shall not be located directly in the air stream. Damper axles shall be 13 mm minimum, plated steel rods supported in the damper frame by stainless steel or bronze bearings. Blades mounted vertically shall be supported by thrust bearings. Pressure drop through dampers shall not exceed 10 Pa at 5.1 m/s in the wide-open position. Frames shall not be less than 50 mm in width. Dampers shall be tested in accordance with AMCA 500.

2.6.2 Operating Links

Operating links external to dampers, such as crankarms, connecting rods, and line shafting for transmitting motion from damper actuators to dampers, shall withstand a load equal to at least twice the maximum required damper-operating force. Rod lengths shall be adjustable. Links shall be brass, bronze, zinc-coated steel, or stainless steel. Working parts of joints and clevises shall be brass, bronze, or stainless steel. Adjustments of crankarms shall control the open and closed positions of dampers.

2.6.3 Damper Types

Dampers shall be parallel-blade type.

2.6.3.1 Outside Air, Return Air, and Relief Air Dampers

Outside air, return air and relief air dampers shall be provided where shown. Blades shall have an airfoil shape with interlocking edges and shall be provided with compressible seals at points of contact. The channel frames of the dampers shall be provided with jamb seals to minimize air leakage. Dampers shall not leak in excess of 36 L/s per square meter at 1000 Pa static pressure when closed. Seals shall be suitable for an operating temperature range of minus 40 to plus 94 degrees C. Dampers shall be rated at not less than 10 m/s air velocity.

2.6.3.2 Mechanical and Electrical Space Ventilation Dampers

Mechanical and electrical space ventilation dampers shall be as shown. Dampers shall not leak in excess of 102 L/s per square meter at 1000 Pa static pressure when closed. Dampers shall be rated at not less than 7.6 m/s air velocity.

2.6.4 Damper End Switches

Each end switch shall be a hermetically sealed switch with a trip lever and over-travel mechanism. The switch enclosure shall be suitable for mounting on the duct exterior and shall permit setting the position of the trip lever that actuates the switch. The trip lever shall be aligned with the

damper blade.

2.7 SMOKE DETECTORS

Duct smoke detectors shall be provided in supply and return air ducts in accordance with NFPA 90A. Duct smoke detectors shall conform to the requirements of UL 268A. Duct smoke detectors shall have perforated sampling tubes extended into the air duct. Detector circuitry shall be mounted in a metallic enclosure exterior to the duct. Detectors shall have manual reset. Detectors shall be rated for air velocities that include air flows between 2.5 and 20 m/s. Detectors shall be powered from the fire alarm control panel (FACP). Detectors shall have two sets of normally open alarm contacts and two sets of normally closed alarm contacts. Detectors shall be connected to the building fire alarm panel for alarm initiation. A remote annunciation lamp and accessible remote reset switch shall be provided for duct detectors that are mounted eight feet or more above the finished floor and for detectors that are not readily visible. Remote lamps and switches as well as the affected fan units shall be properly identified in etched rigid plastic placards.

2.8 INSTRUMENTATION

2.8.1 Measurements

Transmitters shall be calibrated to provide the following measurements, over the indicated ranges, for an output of 4 to 20 mAdc:

- a. Conditioned space temperature, from 10 to 30 degrees C .
- b. Duct temperature, from 5 to 60 degrees C .
- c. High-temperature hot-water temperature, from 94 to 260 degrees C .
- d. Chilled-water temperature, from minus 1 to plus 38 degrees C .
- e. Dual-temperature water, from minus 1 to plus 116 degrees C .
- f. Heating hot-water temperature, from 10 to 121 degrees C .
- g. Condenser-water temperature, from minus 1 to plus 55 degrees C .
- h. Outside-air temperature, from minus 35 to plus 55 degrees C .
- i. Relative humidity, 0 to 100 percent for space and duct high-limit applications.
- j. Differential pressure for VAV supply-duct static pressure from 0 to 500 Pa .
- k. Pitot-tube air-flow measurement station and transmitter, from 0 to 25 Pa for flow velocities of 3.5 to 6 m/s , 0 to 60 Pa for velocities of 3.5 to 9 m/s , or 0 to 125 Pa for velocities of 3.5 to 13 m/s .
- l. Electronic air-flow measurement station and transmitter, from 0.6

to 13 m/s .

2.8.2 Temperature Instruments

2.8.2.1 Resistance Temperature Detectors (RTD)

Temperature sensors shall be 1000 ohms 2-wire RTD. Each RTD shall be platinum with a tolerance of 0.30 degrees C at 0 degrees C and shall be encapsulated in epoxy, series 300 stainless steel, anodized aluminum, or copper.

2.8.2.2 Continuous Averaging RTD

Continuous averaging RTDs shall have a tolerance of plus or minus 0.5 degrees C at the reference temperature, and shall be of sufficient length to ensure that the resistance represents an average over the cross section in which it is installed. The sensing element shall have a bendable copper sheath. Each averaging RTD shall be furnished with an RTD transmitter to match the resistance range of the averaging RTD.

2.8.3 Electronic Airflow Measurement Stations and Transmitters

2.8.3.1 Stations

Each station shall consist of an array of velocity sensing elements and an air-flow straightener. Air-flow straightener shall be contained in a flanged sheet metal or aluminum casing. The velocity sensing elements shall be of the RTD or thermistor type, producing a temperature compensated output. The sensing elements shall be distributed across the duct cross section in the quantity and pattern specified by the published application data of the station manufacturer. The resistance to air flow through the airflow measurement station shall not exceed 20 Pa at an airflow of 10 m/s. Station construction shall be suitable for operation at airflows of up to 25 m/s over a temperature range of 4 to 49 degrees C, and accuracy shall be plus or minus three percent over a range of 0.6 to 12.5 m/s. In outside air measurement or in low-temperature air delivery applications, the station shall be certified by the manufacturer to be accurate as specified over a temperature range of minus 29 to plus 49 degrees C. In outside air measurement applications, the air flow straightener shall be constructed of 3 mm aluminum honeycomb and the depth of the straightener shall not be less than 40 mm.

2.8.4 Differential Pressure Instruments

The instrument shall be a pressure transmitter with an integral sensing element. The instrument over pressure rating shall be 300 percent of the operating pressure. The sensor/transmitter assembly accuracy shall be plus or minus two percent of full scale. The transmitter shall be a two-wire, loop-powered device. The transmitter shall produce a linear 4-to-20 mAdc output corresponding to the required pressure measurement.

2.8.5 Thermowells

Thermowells shall be Series 300 stainless steel with threaded brass plug

and chain, 50 mm lagging neck and extension type well. Inside diameter and insertion length shall be as required for the application.

2.8.6 Sunshields

Sunshields for outside air temperature sensing elements shall prevent the sun from directly striking the temperature sensing elements. The sunshields shall be provided with adequate ventilation so that the sensing element responds to the ambient temperature of the surroundings. The top of each sunshield shall have a galvanized metal rainshield projecting over the face of the sunshield. The sunshields shall be painted white.

2.9 THERMOSTATS

Thermostat ranges shall be selected so that the setpoint is adjustable without tools between plus or minus 5 degrees C of the setpoint shown. Thermostats shall be electronic or electric.

2.9.1 Nonmodulating Room Thermostats

Contacts shall be single-pole double-throw (SPDT), hermetically sealed, and wired to identified terminals. Maximum differential shall be 3 degrees C.

Room thermostats shall be enclosed with separate locking covers (guards).

2.9.2 Temperature Switches

Temperature switches shall have a repetitive accuracy of plus or minus 1 percent of the operating ranges shown. Switch actuation shall be adjustable over the operating temperature range. The switch shall have a snap-action Form C contact rated for the application.

2.9.3 Nonmodulating Capillary Aquastats

Each aquastat shall have a capillary length of at least 1500 mm, shall have adjustable direct-reading scales for both setpoint and differential, and shall have a differential adjustable from 3 to 9 degrees C. Aquastats shall be of the strap on type, with 5 degrees C fixed differential.

2.9.4 Freezestats

Freezestats shall be automatic reset, low temperature safety thermostats, with NO and NC contacts and a 6000 mm element which shall respond to the coldest 450 mm segment.

2.9.5 Fan-Coil Unit Room Thermostats

Fan-coil unit thermostats in personnel living spaces shall be of the low voltage type with locking covers. Electrical rating shall not exceed 2.5 amperes at 30 volts ac. Housing shall be corrosion resisting metal or molded plastic. Transformer and fan relay shall be provided for the proper operation of each thermostatic control system as necessary to suit the design of the control system using the thermostats specified below. Either separate heating thermostats and separate cooling thermostats or dual element heating cooling thermostats may be provided. Motor speed switches

shall be provided for three-speed fan control.

2.9.5.1 Combination Thermostat

Fan coil unit combination heating-cooling thermostats shall be provided with separate temperature sensing elements for each system, and shall have a single-pole, single-throw (SPST) switch, hermetically sealed and actuated by a bimetallic or bellows type element. Each element shall operate switches to provide single stage control for heating and cooling. Scales and ranges shall be as specified for individual thermostats. Thermostats shall contain, or a subbase shall be provided which contains, selector switches for Heat-Off-Cool. A changeover controller providing automatic summer-winter changeover for thermostats by sensing the supplied fluid temperature shall be provided. A limited range heating-cooling dead band thermostat shall control cooling when temperature is above the upper setpoint and heating when temperature is below the lower setpoint and shall have a dead band, with no heating or cooling, when temperature is between the setpoints. Setpoint adjustment shall be concealed.

2.10 PRESSURE SWITCHES AND SOLENOID VALVES

2.10.1 Pressure Switches

Each switch shall have an adjustable setpoint with visible setpoint scale. Range shall be as shown. Differential adjustment shall span 20 to 40 percent of the range of the device.

2.10.2 Differential-Pressure Switches

Each switch shall be an adjustable diaphragm-operated device with two SPDT contacts, with taps for sensing lines to be connected to duct pressure fittings designed to sense air pressure. These fittings shall be of the angled-tip type with tips pointing into the air stream. The setpoint shall not be in the upper or lower quarters of the range and the range shall not be more than three times the setpoint. Differential shall be a maximum of 35 Pa at the low end of the range and 85 Pa at the high end of the range.

2.10.3 Pneumatic Electric (PE) Switches

Each switch shall have an adjustable setpoint range of 20 to 140 kPa with a switching differential adjustable from 15 to 35 kPa. The switch action shall be SPDT.

2.10.4 Solenoid-Operated Pneumatic (EP) Valves

Each valve shall have three-port operation: common, normally open, and normally closed. Each valve shall have an outer cast aluminum body and internal parts of brass, bronze, or stainless steel. The air connection shall be a 10 mm NPT threaded connection. Valves shall be rated for 345 kPa when used in a control system that operates at 172 kPa or less, or 1035 kPa when used in a control system that operates in the range of 172 to 690 kPa.

2.11 INDICATING DEVICES

2.11.1 Thermometers

Mercury shall not be used in thermometers.

2.11.1.1 System Thermometers

Thermometers shall have brass, malleable iron or aluminum alloy case and frame, clear protective face, permanently stabilized glass tube with indicating-fluid column, white face, black numbers, and a 230 mm scale. Thermometers for piping systems shall have rigid stems with straight, angular, or inclined pattern.

2.11.1.2 Thermometer Stems

Thermometer stems shall have expansion heads as required to prevent breakage at extreme temperatures. On rigid-stem thermometers, the space between bulb and stem shall be filled with a heat-transfer medium.

2.11.1.3 Air-Duct Thermometers

Non-averaging air-duct thermometers shall have perforated stem guards. Thermometers shall have 45-degree adjustable duct flanges with locking mechanism.

2.11.1.4 Accuracy

Thermometers shall have an accuracy of plus or minus one percent of scale range. Thermometers shall have a range suitable for the application.

2.11.2 Pressure Gauges

Gauges shall be 50 mm (nominal) size, back connected, suitable for field or panel mounting as required, shall have black legend on white background, and shall have a pointer traveling through a 270-degree arc. Accuracy shall be plus or minus three percent of scale range. Gauges shall meet requirements of ASME B40.1.

2.11.2.1 Pneumatic Actuator Gauges

Gauges for indicating signal output to pneumatic actuators shall have an outer scale of 21 to 103 kPa in 7 kPa graduations.

2.11.2.2 Air Storage Tank and Filter and Dryer Gauge

Gauges for air storage tanks or for use before and after dirt and oil filters or dryers, shall have a scale of 0 to 1100 kPa with 20 kPa graduations.

2.11.2.3 Hydronic System Gauges

Gauges for hydronic system applications shall have ranges suitable for the application.

2.11.3 Low Differential Pressure Gauges

Gauges for low differential pressure measurements shall be a minimum of 90 mm (nominal) size with two sets of pressure taps, and shall have a diaphragm-actuated pointer, white dial with black figures, and pointer zero adjustment. Gauges shall have ranges and graduations as shown. Accuracy shall be plus or minus two percent of scale range.

2.12 CONTROL DEVICES AND ACCESSORIES

2.12.1 Relays

Control relay contacts shall have utilization category and ratings selected for the application, with a minimum of two sets of contacts (two normally open, two normally closed) enclosed in a dustproof enclosure. Relays shall be rated for a minimum life of one million operations. Operating time shall be 20 milliseconds or less. Relays shall be equipped with coil transient suppression devices to limit transients to 150 percent of rated coil voltage. Time delay relays shall be 2PDT with eight-pin connectors, dust cover, and a matching rail-mounted socket. Adjustable timing range shall be 0 to 5 minutes. Power consumption shall not be greater than three watts.

2.12.2 Current to Pneumatic (IP) Transducers

The transducers shall be two-wire current-to-pressure transmitters that convert a 4-to-20 mA_{dc} input signal to a 21 to 103 kPa (3 to 15 psig) , or a 103 to 21 kPa (15 to 3 psig) , pneumatic output, with a conversion accuracy of plus or minus two percent of full scale, including linearity and hysteresis. Input impedance shall not exceed 250 ohms. Air consumption shall not be greater than 0.12 L/s.

2.12.3 Joule or Watthour Meters

Joule meters shall be in accordance with ANSI C12.1 and have pulse initiators for remote monitoring of Joule consumption. Pulse initiator shall consist of form C contacts with a current rating not to exceed two amperes and voltage not to exceed 500 V, with combinations of VA not to exceed 100 VA, and a life rating of one billion operations. Meter sockets shall be in accordance with ANSI C12.1.

2.12.4 Current Sensing Relays (Current Switches)

Current sensing relays shall provide a normally-open contact rated at a minimum of 50 volts peak and 1/2 ampere or 25 VA, noninductive. There shall be a single hole for passage of current carrying conductors. The devices shall be sized for operation at 50 percent rated current based on the connected load. Voltage isolation shall be a minimum of 600 volts.

2.12.5 Power-Line Conditioners (PLC)

Power line conditioners shall be furnished for each DDC panel. The PLCs shall provide both voltage regulation and noise rejection. The PLCs shall be of the ferro-resonant design, with no moving parts and no tap switching,

while electrically isolating the secondary from the power-line side. The PLCs shall be sized for 125 percent of the actual connected kVA load. Characteristics of the PLC shall be as follows:

a. At 85 percent load, the output voltage shall not deviate by more than plus or minus one percent of nominal when the input voltage fluctuates between minus 20 percent to plus 10 percent of nominal.

b. During load changes of zero to full load, the output voltage shall not deviate by more than plus or minus three percent of nominal voltage. Full correction of load switching disturbances shall be accomplished within five cycles, and 95 percent correction shall be accomplished within two cycles of the onset of the disturbance.

c. Total harmonic distortion shall not exceed 3-1/2 percent at full load.

2.13 COMPRESSED AIR STATIONS

2.13.1 Air Compressor Assembly

The air compressor shall be a high pressure compressing unit with electric motor. The compressor shall be equipped with a motor with totally enclosed belt guard, an operating-pressure switch, safety relief valves, gauges, intake filter and intake silencer, and combination type magnetic starter with undervoltage protection and thermal-overload protection for each phase, and shall be supported by a steel base mounted on an air storage tank. The air compressor shall provide the compressed air required for control operation while operating not more than one-third of the time. The air storage tank shall be fabricated for a working pressure of not less than 1380 kPa, and constructed and certified in accordance with ASME BPVC SEC VIII D1. The tank shall be of sufficient volume so that no more than six compressor starts per hour are required with the starting pressure switch differential set at 140 kPa. The tank shall be provided with an automatic condensate drain trap with manual override feature. A second (duplex arrangement) compressor of capacity equal to the primary compressor shall be provided, with interlocked control to provide automatic changeover upon malfunction or failure of either compressor. A manual selector switch shall be provided to index the lead compressor including the automatic changeover.

2.13.2 Compressed Air Station Specialties

2.13.2.1 Refrigerated Dryer, Filters and, Pressure Regulator

A refrigerated dryer shall be provided in the air outlet line of the air storage tank. The dryer shall be of the size required for the full delivery capacity of the compressor. The air shall be dried at a pressure of not less than 483 kPa to a temperature not greater than 2 degrees C. The dryer shall be provided with an automatic condensate drain trap with manual override feature. The refrigerant used in the dryer shall be one of the fluorocarbon gases and have an Ozone Depletion Potential of not more than 0.05. A five micron prefilter and coalescing-type 0.03 micron oil removal filter with shut-off valves shall be provided in the dryer

discharge. Each filter bowl shall be rated for 1034 kPa maximum working pressure. A pressure regulator, with high side and low side pressure gauges, and a safety valve shall be provided downstream of the filter. Pressure regulators of the relieving type shall not be used.

2.13.2.2 Flexible Pipe Connections

The flexible pipe connectors shall be designed for 1034 kPa and 120 degree C service, and shall be constructed of rubber, tetrafluoroethylene resin, or braided corrosion-resistant steel, bronze, monel, or galvanized steel. The connectors shall be suitable for the service intended and may have threaded or soldered ends. The length of the connectors shall be as recommended by the manufacturer for the service intended.

2.13.2.3 Vibration Isolation Units

The vibration isolation units shall be standard products with published loading ratings, and shall be single rubber-in-shear, double rubber-in-shear, or spring type.

2.13.2.4 Compressed Air Piping

Control air delivered to the system shall conform to ISA S7.0.01. Air lines for pneumatic controls shall be seamless copper tubing. Air lines shall be concealed except in mechanical rooms and other areas where other tubing and piping is exposed. Air lines in exposed and concealed locations, free standing or enclosed in the conduit or other protective coverings, shall be run parallel to the building lines and shall be adequately supported from the building structure, at least every 2 m horizontally and every 2.5 m vertically. Copper tubing shall be hard-drawn in exposed areas and either hard-drawn or annealed in concealed areas. Only tool-made bends shall be used. Fittings for copper tubing shall be brass or copper solder joint type except at connections to apparatus, where fittings shall be brass compression type. Nonmetallic tubing shall be compounded from polyethylene, meeting the stress crack test of ASTM D 1693. Nonmetallic individual tube polyethylene or multitube instrument tubing bundle shall be classified as flame retardant under UL 94.

The polyethylene material shall be rated as self-extinguishing when tested in accordance with ASTM D 635. Air lines concealed in walls shall be hard-drawn copper tubing or nonmetallic tubing in rigid conduit. Terminal single lines shall be hard-drawn copper tubing, except when the run is less than 300 mm in length, flexible polyethylene may be used. Air lines shall be tested periodically for leaks during installation. Air lines shall be purged of dirt, impurities and moisture before connecting to the control equipment. Fittings for nonmetallic tubing shall be for instrument service and may be brass or acetal resin of the compression or barbed push-on type.

Air lines shall be number coded or color coded and keyed to the submittal drawings for future identification and servicing the control system.

2.14 DIRECT DIGITAL CONTROL (DDC) HARDWARE

All functions, constraints, data base parameters, operator developed programs and any other data shall be downloadable from a portable workstation/tester or the central workstation/tester to network control

panels, RIU's, universal programmable controllers, and unitary controllers.

Download shall be accomplished through both the primary network and the local DDC portable workstation/tester port.

2.14.1 Network Control Panel

Network control panels shall be microcomputer-based with sufficient memory provided to perform all specified and shown network control panel functions and operations, including spare capacity for all spares and its I/O functions specified. Each network control panel and remote I/O units (RIU) shall have a minimum of 10% of its I/O functions as spare capacity but not less than 2 of each type used in each. The type of spares shall be in the same proportion as the implemented I/O functions on the panel, but in no case shall there be less than two spare points of each type. The panel I/O functions shall be furnished complete, with no changes or additions necessary to support implementation of spare functions. Output relays associated with digital signals shall be considered part of the I/O function, whether physically mounted in the enclosure or separately mounted. Implementation of spare points shall necessitate only providing the additional field sensor or control device, field wiring including connection to the system, and point definition assignment by the operator using the central workstation/tester or portable workstation/tester. The panel shall contain all necessary I/O functions to connect to field sensors and control panels. I/O function operation shall be fully supervised to detect I/O function failures. Network control panels shall operate in an independent stand-alone mode, which is defined as all network control panel operations performed by the network control panel without any continuing input from other Direct digital controls or portable workstation/tester. The network control panel shall be capable of controlling a mix of at least 32 RIUs, unitary controllers, and universal programmable controllers.

2.14.1.1 Integral Features

The network control panel shall include:

- a. Main power switch.
- b. Power on indicator.
- c. Portable workstation/tester port, connector, and if necessary power supply.
- d. Manufacturers control network port.
- e. On-Off-Auto switches for each DO which controls a device. These switches shall be mounted in the field panel, with the exception of motors, for which the switch shall be mounted at the motor control center. On-Off-Auto switches are not required for DO associated with a status or alarm such as pilot lights. The status of these switches shall be available to the panel for further processing.
- f. Minimum-Maximum-Auto switches, or Auto-Manual switches with manual output override, for each AO. The status of these shall be available to the panel for further processing.

- g. An intrusion detection device, connected as an alarm.

2.14.1.2 Communication Interfaces

The following communication capabilities shall function simultaneously.

- a. Manufacturers Control Network. Manufacturers control network communications interfaces for each data transmission systems (DTS) circuit between network control panels and RIUs, unitary controllers, and universal programmable controllers, shall be provided. Communication interfaces shall be provided between each network control panel and associated I/O functions. The DTS will provide for transmission speeds necessary to comply with performance requirements specified. DTS equipment shall be installed in the network control panel enclosure.

- b. Portable Workstation/Tester Port. A communications port for interfacing to a portable workstation/tester shall be provided. Network control panel workstation/tester port other than RS-232, shall be converted to RS-232, including cabling and power supply, and shall be permanently installed in the panel.

- c. Primary Network Port. The network control panel shall either have a built in primary network Port or be capable of accepting a primary network port expansion card for future networking to a base wide utility monitoring and control system (UMCS). The primary network port expansion card shall be either Ethernet (IEEE802.3) or ARCNET.

2.14.1.3 Memory and Real Time Clock (RTC) Backup

The network control panel memory and real time clock functions shall continue to operate for a minimum of 72 hours in the event of a power failure. If rechargeable batteries are provided, automatic charging of batteries shall be provided. Whenever a either a permanent workstation/tester or portable workstation/tester is monitoring the network control panel, a low battery alarm message shall be sent to it.

2.14.1.4 Duplex Outlet

A single phase, 120 Vac electrical service outlet for use with test equipment shall be furnished either inside or within 2 meters of the network control panel enclosure.

2.14.1.5 Locking Enclosures

Locking type mounting cabinets with common keying shall be furnished for each network control panel.

2.14.1.6 Failure Mode

Upon failure of the network control panel, either due to failure of the network control panel hardware or of the manufacturers control network, the network control panel shall revert to the failure mode as shown.

a. Manufacturers Control Network Failure: Upon failure of the manufacturers control network, the network control panel shall operate in an independent stand-alone mode.

b. Network Control Panel Hardware Failure: Upon failure of the network control panel hardware, the network control panel shall cease operation and stop communications with other network control panels, RIUs, unitary controllers and universal programmable controllers connected to the affected network control panel. The affected network control panel shall respond to this failure as specified and shown.

2.14.2 RIU

The RIU shall be functionally a part of the network control panel as specified, but may be remotely located from the network control panel and communicate over a dedicated communication circuit. When remotely located, the I/O functions shall be subject to the same requirements as for the network control panel hardware. RIUs shall be used to connect remote inputs and outputs to a network control panel and shall contain all necessary I/O functions to connect to field sensors and control devices. RIU operation shall be fully supervised by the network control panel to detect failures. Each RIU shall have a minimum of 10 % of its I/O functions as spare capacity. The type of spares shall be in the same proportion as the implemented I/O functions on the RIU, but in no case shall there be less than two spare points of each type. The RIU shall be furnished complete, with no changes or additions necessary to support implementation of spare functions. Output relays associated with digital signals shall be considered part of the I/O function, whether physically mounted in the enclosure or separately mounted. Implementation of spare points by others shall require only providing the additional field sensor or control device, field wiring including connection to the system, and point definition assignment by the operator. The RIU shall either report the status of all connected points on each scan, or report the status of all points which have changed state or value since the previous scan.

2.14.2.1 Integral Features

The RIU shall include:

- a. Main power switch.
- b. Power on indicator.
- c. Portable workstation/tester port, connector, and if necessary power supply.
- d. Manufacturers control network port.
- e. On-Off-Auto switches for each DO which controls a device. These switches shall be mounted in the RIU, with the exception of motors, for which the switch shall be mounted at the motor control center. On-Off-Auto switches are not required for DO associated with a status or alarm such as pilot lights. The status of these switches shall be available to the RIU for further processing.

f. Minimum-Maximum-Auto switches, or Auto-Manual switches with manual output override, for each AO. The status of these shall be available to the panel for further processing.

g. An intrusion detection device, connected as an alarm.

2.14.2.2 Duplex Outlet

A single phase, 120 Vac electrical service outlet for use with test equipment shall be furnished either inside or within 2 meters of the RIU.

2.14.2.3 Locking Enclosures

Locking type mounting cabinets with common keying shall be furnished for each RIU.

2.14.2.4 Failure Mode

Upon failure of the RIU, either due to failure of the RIU hardware or of the DTS, the RIU shall revert to the failure mode shown.

2.14.3 Universal Programmable Controller (UPC)

The universal programmable controller shall be a microprocessor based controller designed and programmed to control and monitor systems as shown.

Resident programs shall be contained in reprogrammable nonvolatile memory. Each universal programmable controller shall contain necessary power supplies, transformers, memory, I/O functions and communications interfaces necessary to perform its required functions and to provide control and monitoring of connected equipment and devices. It shall contain all necessary I/O functions to connect to field sensors and controls. I/O operation shall be fully supervised to detect I/O function failures. It shall provide for operation as a device connected to the system via the manufacturers control network.

2.14.3.1 Integral Features

The universal programmable controller shall include as a minimum:

- a. Main power switch.
- b. Power on indicator.
- c. Portable workstation/tester port, connector, and if necessary power supply.
- d. Manufacturers control network port.
- e. I/O functions
 - (1) 8 DI
 - (2) 4 DO

(3) 8 AI

(4) 4 AO

(5) 1 PA

f. On-Off-Auto switches for each DO which controls a device. These switches shall be mounted in the universal programmable controller, with the exception of motors, for which the switch shall be mounted at the motor control center. On-Off-Auto switches are not required for DO associated with a status or alarm such as pilot lights. The status of these switches shall be available to the panel for further processing.

g. Minimum-Maximum-Auto switches, or Auto-Manual switches with manual output override, for each AO. The status of these shall be available to the panel for further processing.

2.14.3.2 Communication Interfaces

The UPC shall have the following communication capabilities which shall function simultaneously.

a. Manufacturers Control Network. The manufacturers control network communications interface for a data transmission systems (DTS) circuit between the UPC and a network control panels shall be provided. The DTS will provide for transmission speeds necessary to comply with performance requirements specified. DTS equipment shall be installed in the UPC Panel enclosure.

b. Portable Workstation/Tester Port. A communications port for interfacing to a portable workstation/tester shall be provided. A UPC workstation/tester port other than RS-232, shall be converted to RS-232, including cabling and power supply, and shall be permanently installed in the panel.

2.14.3.3 Memory and RTC Backup

The UPC memory and real time clock functions shall continue to operate for a minimum of 72 hours in the event of a power failure. If rechargeable batteries are provided, automatic charging of batteries shall be provided. Whenever a either a permanent workstation/tester or portable workstation/tester is monitoring the network control panel, a low battery alarm message shall be sent to it.

2.14.3.4 Specific Requirements

Each universal programmable controller shall be accessible for purposes of application selection, control parameters, set point adjustment, and monitoring from any DDC controller connected to the same manufacturers control network as the universal programmable controller. This shall be done using a portable workstation/tester connected to a portable workstation/tester port either directly or via modem.

2.14.3.5 Locking Enclosures

Locking type mounting cabinets with common keying shall be furnished for each enclosure.

2.14.3.6 Failure Mode

Upon failure of the universal programmable controller, it shall revert to the failure mode of operation as shown.

2.14.4 Unitary Controller

The unitary controller shall be a microprocessor based, stand-alone, dedicated purpose controller, communicating with the network control panel, designed and programmed to control air distribution system mixing boxes, terminal units, heat pumps, fan coil units, self-contained DX units or VAV boxes. Each unitary controller shall contain resident programs in nonvolatile memory for each specific application implemented. Each unitary controller shall contain necessary power supplies, transformers, memory, I/O functions and communications interfaces necessary to perform its required functions and to provide control and monitoring of connected equipment and devices. It shall contain all necessary I/O functions to connect to field sensors and controls. I/O operation shall be fully supervised to detect I/O function failures and shall provide for operation as a device connected to the network control panel via the manufacturers control network.

2.14.4.1 Integral Features

The unitary controller shall include:

- a. Main power switch.
- b. Power on indicator.
- c. Portable workstation/tester port, connector, and power supply.
- d. Manufacturers control network port.
- e. All I/O functions required to implement the requirements as shown.

f. On-Off-Auto switches for each DO which controls a device. These switches shall be mounted in the field panel, with the exception of motors, for which the switch shall be mounted at the motor control center. On-Off-Auto switches are not required for DO associated with a status or alarm such as pilot lights. The status of these switches shall be available to the panel for further processing.

g. Minimum-Maximum-Auto switches, or Auto-Manual switches with manual output override, for each AO. The status of these shall be available to the panel for further processing.

2.14.4.2 Communication Interfaces

The unitary controller shall have the following communication capabilities which shall function simultaneously.

a. Manufacturers Control Network. The manufacturers control network communications interface for a data transmission systems (DTS) circuit between the unitary controller and a network control panel shall be provided. The DTS will provide for transmission speeds necessary to comply with performance requirements specified. DTS equipment shall be installed in the unitary control panel enclosure.

b. Portable Workstation/Tester Port. A communications port for interfacing to a portable workstation/tester shall be provided. A unitary controller workstation/tester port other than RS-232, shall be converted to RS-232, including cabling and power supply, and shall be permanently installed in the panel. For unitary controller applications where the controller is not mounted in an enclosure, such as for fan-coil units or VAV terminal units, a portable conversion device for an RS-232 connection to the portable workstation/tester may be provided.

2.14.4.3 Specific Requirements

Unitary controller components for new air distribution terminal units shall be furnished to the air distribution terminal unit manufacturer for factory mounting and calibration. Existing air distribution terminal units shall be controlled by field installed unitary controllers.

a. Accessibility and Interfaces: Each unitary controller shall be accessible for purposes of application selection, control parameters, set point adjustment, and monitoring using a portable workstation/tester connected to the manufacturers control network. They shall also be accessible with a portable workstation/tester connected to the unitary controller portable workstation/tester port.

b. Air Distribution Terminal Unit Controls - Pressure Independent: Controls shall consist of a transducer for connection to the velocity-sensing device provided by the terminal unit supplier in the primary air entering the terminal unit, a room temperature sensor, a damper actuator, and an adjustable microprocessor-based controller. The room temperature sensor shall have occupant setpoint adjustment and temperature display, timed override of unoccupied mode, and a communication port. The controller shall operate the damper for cooling and heating and provide control outputs for duct heating coil if applicable. This controller capability shall allow the sequencing of the damper and the heating coil to maintain conditions in the space.

c. Air Distribution Terminal Unit Controls - Pressure Independent with Recirculating Fan: Controls for pressure-independent boxes with recirculating fans shall consist of a transducer for connection to the velocity-sensing device provided by the terminal unit supplier in the primary air entering the terminal unit, a room temperature sensing element, a damper actuator, an adjustable microprocessor-based terminal unit controller, and a switch to operate the recirculation fan, provided by the terminal unit supplier. The room temperature sensor shall have occupant setpoint adjustment and temperature display, timed override of unoccupied

mode, and a communication port. The controller shall operate the damper for cooling and shall provide outputs for controlling the recirculation fan and duct heating coil in sequence for heating.

d. Air Distribution Terminal Unit Damper Actuator: Air distribution terminal unit damper actuator shall open or close the device to which it is connected within 60 seconds.

2.14.4.4 Failure Mode

Upon failure of the unitary controller, it shall revert to the failure mode of operation as shown.

2.14.5 Chiller Control Panel

Chiller control panel shall be microprocessor-based and shall provide, both locally and through the Manufacturers Control Network, the control, monitoring, and safety equipment functions provided by the chiller manufacturer's control panel(s) (two communications ports total). The chiller control panel instrumentation and control ranges and accuracies shall match those of the chiller manufacturer's control devices. The chiller panel shall have a communication port for interface to a Portable Workstation/Tester through either the Manufacturers Control Network or modem for chiller(s) start/stop, chilled water temperature reset, and monitoring of chiller operating status, alarms, and power consumption.

2.14.6 Boiler Control Panel

Boiler control panel shall be microprocessor-based and shall provide, both locally and through the Manufacturers Control Network, the control, monitoring, and safety equipment functions provided by the boiler manufacturer's control panel(s) (two communications ports total). The boiler control panel instrumentation and controls ranges and accuracies shall match those of the boiler manufacturer's control devices. The boiler panel shall have a communication port for interface to a Portable Workstation/Tester through either the Manufacturers Control Network or modem for boiler(s) and start/stop, boiler water temperature reset, and monitoring of boiler operating status, alarms.

2.14.7 I/O Functions

2.14.7.1 DDC Hardware I/O Functions

I/O Functions shall be provided as part of the DDC system and shall be in accordance with the following:

a. The analog input (AI) function shall monitor each analog input, perform A-to-D conversion, and hold the digital value in a buffer for interrogation. The A-to-D conversion shall have a minimum resolution of 10 bits plus sign. Signal conditioning shall be provided for each analog input. Analog inputs shall be individually calibrated for zero and span, in hardware or in software. The AI shall incorporate common mode noise rejection of 50 dB from 0 to 100 Hz for differential inputs, and normal mode noise rejection of 20 dB at 60 Hz from a source impedance of 10,000

ohms. Input ranges shall be within the range of 4-to-20 mAdc.

b. The analog output (AO) function shall accept digital data, perform D-to-A conversion, and output a signal within the range of 4-to-20 mAdc. D-to-A conversion shall have a minimum resolution of eight bits plus sign. Analog outputs shall be individually calibrated for zero and span. Short circuit protection on voltage outputs and open circuit protection on current outputs shall be provided. An individual gradual switch for manual override of each analog output and means of physically securing access to these switches shall be provided. Each AO shall have a three-position switch for selection of the DDC control signal, no control, or a locally generated control signal for connection to the controlled device. Feedback shall be provided to the system as to the status of the output (manual control or automatic). Switches for pneumatic control outputs shall provide a connection for an externally generated pneumatic signal. All switches shall be either of a key operated design with the same keying system used for other outputs or otherwise suitably protected from unauthorized access .

c. The digital input (DI) function shall accept on-off, open-close, or other change of state (two state data) indications. Isolation and protection against an applied steady-state voltage up to 180 Vac peak shall be provided.

d. The digital output (DO) function shall provide contact closures for momentary and maintained operation of output devices. Closures shall have a minimum duration of 0.1 second. DO relays shall have an initial breakdown voltage between contacts and coil of at least 500 V peak. Electromagnetic interference suppression shall be furnished on all output lines to limit transients to nondamaging levels. Protection against an applied steady-state voltage up to 180 Vac peak shall be provided. Minimum contact rating shall be one ampere at 24 Vac. Key locked HOA switches shall be provided for manual override of each digital output. Feedback shall be provided to the system as to the status of the output (manual control or automatic). Switches shall be common keyed .

e. The pulse accumulator function shall have the same characteristics as the DI. In addition, a buffer shall be provided to totalize pulses and allow for interrogation by the DDC system. The pulse accumulator shall accept rates up to 20 pulses per second. The totalized value shall be reset to zero upon operator's command.

f. Signal conditioning for sensors shall be provided as specified.

g. The binary coded decimal (BCD) function: The BCD function shall have the same characteristics as the DI, except that, in addition, a buffer shall be provided to totalize inputs and allow for interrogation by the network control panel. The BCD function shall have 16-channel optically isolated buffered inputs to read four digit numbers. The BCD function shall accumulate inputs at rates up to 10 inputs per second.

2.14.7.2 Failure Mode

Upon failure of the I/O function, including data transmission failure,

logic power supply failure, DDC processor malfunction, software failure, interposing relay power failure, or any other failure which prevents stand alone operation of any DDC normally capable of stand alone operation, connected outputs shall be forced to the failure mode shown.

2.14.8 Portable Workstation/Tester

A portable workstation/tester shall be provided and shall be able to connect to any DDC hardware. The portable workstation/tester shall consist of a portable computer with a nominal 15-inch TFT active matrix XGA display, capable of displaying at a minimum resolution of 1600 X 1200 pixels, 64 MB DDR video memory utilizing 4X AGP interface, Pentium 4 microprocessor operating at a minimum of 2.0 GHZ, 256 MB DDR system memory.

The portable workstation/tester shall have, as a minimum, a 60 GB hard drive, integral pointing device, serial and parallel ports, color VGA video port for an external color monitor, 3.5 inch floppy disk drive, v.92, 56K modem, Ethernet 10/100 network adaptor, CD-RW/DVD-Rom combo optical disk drive, integral sound card with speakers, rechargeable battery, battery charger and 120 Vac power supply, type III card connector, and Windows XP operating system. It shall include carrying case, extra battery, charger and a compatible network adapter. The workstation/tester shall:

- a. Run DDC diagnostics.
- b. Load all DDC memory resident programs and information, including parameters and constraints.
- c. Display any AI, DI, AO, DO, or PA point in engineering units for analog points or status for digital points.
- d. Control any AO or DO.
- e. Provide an operator interface, contingent on password level, allowing the operator to use full English language words and acronyms, or an object oriented graphical user interface.
- f. Display database parameters.
- g. Modify database parameters.
- h. Accept DDC software and information for subsequent loading into a specific DDC. Provide all necessary software and hardware required to support this function, including an EIA ANSI/EIA/TIA-232-F port.
- i. Disable/enable each DDC.
- j. Perform all workstation functions as specified.

2.14.9 Central Workstation/Tester

The existing central workstation located in building 364 shall be utilized.

2.15 DDC SOFTWARE

All DDC software described in this specification shall be furnished as part of the complete DDC System.

2.15.1 Operating System

Each DDC shall contain an operating system that controls and schedules that DDC's activities in real time. The DDC shall maintain a point database in its memory that includes all parameters, constraints, and the latest value or status of all points connected to that DDC. The execution of DDC application programs shall utilize the data in memory resident files. The operating system shall include a real time clock function that maintains the seconds, minutes, hours, date and month, including day of the week. Each DDC real time clock shall be automatically synchronized with the network control panel real time clock at least once per day to plus or minus 10 seconds. When the network control panel is connected to a central workstation/tester, the network control panel RTC shall be updated by the central workstation/tester RTC. The time synchronization shall be accomplished without operator intervention and without requiring system shutdown. The operating system shall allow loading of software, data files data entry, and diagnostics from the central workstation/tester both locally through the central workstation/tester port and remotely through a network control panel and the manufacturers control network.

2.15.1.1 Startup

The DDC shall have startup software that causes automatic commencement of operation without human intervention, including startup of all connected I/O functions. A DDC restart program based on detection of power failure at the DDC shall be included in the DDC software. Upon restoration of power to the DDC, the program shall restart equipment and restore loads to the state at time of power failure, or to the state as commanded by time programs or other overriding programs. The restart program shall include start time delays between successive commands to prevent demand surges or overload trips. The startup software shall initiate operation of self-test diagnostic routines. Upon failure of the DDC, if the database and application software are no longer resident or if the clock cannot be read, the DDC shall not restart and systems shall remain in the failure mode indicated until the necessary repairs are made. If the database and application programs are resident, the DDC shall resume operation after an adjustable time delay of from 0 to 600 seconds. The startup sequence for each DDC shall include a unique time delay setting for each control output when system operation is initiated.

2.15.1.2 Operating Mode

Each DDC shall control and monitor functions as specified, independent of communications with other DDC. This software shall perform all DDC functions and DDC resident application programs as specified using data obtained from I/O functions and based upon the DDC real time clock function. When communications circuits between the DDC are operable, the DDC shall obtain real time clock updates and any required global data values transmitted from other network control panels. The DDC software shall execute commands after performing constraints checks in the DDC. Status and analog values, including alarms and other data shall be

transmitted from other network control panels when communications circuits are operable. If communications are not available, each DDC shall function in stand-alone mode and operational data, including the latest status and value of each point and results of calculations, normally transmitted from other network control panels shall be stored for later transmission to the network control panel. Storage for the latest 256 values shall be provided at each network control panel. Each DDC shall accept software downloaded from the network control panel. Constraints shall reside at the DDC.

2.15.1.3 Failure Mode

Upon failure for any reason, each DDC shall perform an orderly shutdown and force all DDC outputs to a predetermined (failure mode) state, consistent with the failure modes shown and the associated control device.

2.15.2 Functions

The Contractor shall provide software necessary to accomplish the following functions, as appropriate, fully implemented and operational, within each network control panel, RIU, unitary controller and universal programmable controller.

- a. Scanning of inputs.
- b. Control of outputs.
- c. Reporting of analog changes outside a selectable differential.
- d. Reporting of unauthorized digital status.
- e. Reporting of alarms automatically to network control panel.
- f. Reporting of I/O status to network control panel upon request.
- g. Maintenance of real time, updated by the network control panel at least once a day.
- h. Communication with the network control panel.
- i. Execution of DDC resident application programs.
- j. Averaging or filtering of AIs.
- k. Constraints checks (prior to command issuance).
- l. Diagnostics.
- m. Portable workstation/tester operation as specified.
- n. Reset of PA by operator based on time and value.

2.15.2.1 Analog Monitoring

The system shall measure and transmit analog values including calculated

analog points. An analog change in value is defined as a change exceeding a preset differential value as specified. The record transmitted for each analog value shall include a readily identifiable flag which indicates the abnormal status of the value when it deviates from operator selectable upper and lower analog limits. Analog values shall be expressed in proper engineering units with sign. Engineering units conversions shall be provided for each measurement. Each engineering units conversion set shall include range, span, and conversion equation. A vocabulary of engineering unit descriptors shall be provided, using at least three alphanumeric characters to identify information in the system. The system shall support 255 different engineering units.

2.15.2.2 Logic (Virtual) Points

Logic (virtual) points shall be software points entered in the point database which are not directly associated with a physical I/O function. Logic (virtual) points shall be analog or digital points created by calculation from any combination of digital and analog points, or other data having the properties of real points, including alarms, without the associated hardware. Logic (virtual) points shall be defined or calculated and entered into the database by the Contractor. The calculated analog point shall have point identification in the same format as any other analog point. The calculated point shall be used in any program where the real value is not obtainable directly. Constants used in calculations shall be changeable on-line by the operator. Calculated point values shall be current for use by the system within 10 seconds of the time of any input changes.

2.15.2.3 State Variables

If an analog point represents more than two (up to eight) specific states, each state shall be nameable. For example, a level sensor shall be displayed at its measured engineering units plus a state variable with named states usable in programs or for display such as low alarm/low/normal/high/high alarm.

2.15.2.4 Analog Totalization

Any analog point shall be operator assignable to the totalization program. Up to eight analog values shall be totalized within a selectable time period. At the end of the period, the totals shall be stored. Totalization shall then restart from zero for the next time period. The program shall keep track of the peak and total value measured during the current period and for the previous period. The operator shall be able to set or reset each totalized value individually. The time period shall be able to be operator defined, modified or deleted on-line.

2.15.2.5 Energy Totalization

The system shall calculate the heat energy in Btus, for each energy source consumed by the mechanical systems specified, totalize the calculated Btus, the instantaneous rate in Btus per hour, and store totals in thousands of Btus (MBtu). The Btus calculated shall be totalized for an adjustable time period. The time period shall be defined uniquely for each Btu

totalization. Software shall be capable of generating monthly energy savings reports. These reports shall include each HVAC system with the associates savings printed out in actual dollars and cents saved. The savings would be generated by utilizing energy saving routines included in the software.

2.15.2.6 Trending

Any analog or calculated point shall be operator assignable to the trend program. Up to eight points shall be sampled at individually assigned intervals, selectable between one minute and two hours. A minimum of the most recent 128 samples of each trended point shall be stored. The sample intervals shall be able to be defined, modified, or deleted on-line.

2.15.3 I/O Point Database/Parameter Definition

Each I/O point shall be defined in a database residing in the DDC. The definition shall include all physical parameters associated with each point. Each point shall be defined and entered into the database by the Contractor, including as applicable:

- a. Name.
- b. Device or sensor type (i.e., sensor, control relay, motors).
- c. Point identification number.
- d. Unit.
- e. Building number.
- f. Area.
- g. Island.
- h. DDC number and channel address.
- i. KW (running).
- j. KW (starting).
- k. Sensor range.
- l. Controller range.
- m. Sensor span.
- n. Controller span.
- o. Engineering units conversion (scale factor).
- p. Setpoint (analog).
- q. High reasonableness value (analog).

- r. Low reasonableness value (analog).
- s. High alarm limit differential (return to normal).
- t. Low alarm limit differential (return to normal).
- u. High alarm limit (analog).
- v. Low alarm limit (analog).
- w. Alarm disable time period upon startup or change of setpoint.
- x. Analog change differential (for reporting).
- y. Alarm class and associated primary message text.
- z. High accumulator limit (pulse).
- aa. Status description.
- bb. Run time target.
- cc. Failure mode as specified and shown.
- dd. Constraints as specified.

2.15.4 Alarm Processing

Each DDC shall have alarm processing software for AI, DI, and PA alarms for all real and virtual points connected to that DDC.

2.15.4.1 Digital Alarms Definition

Digital alarms are those abnormal conditions indicated by DIs as specified and shown.

2.15.4.2 Analog Alarms Definition

Analog alarms are those conditions higher or lower than a defined value, as measured by an AI. Analog readings shall be compared to predefined high and low limits, and alarmed each time a value enters or returns from a limit condition. Unique high and low limits shall be assigned to each analog point in the system. Analog alarm limits shall be stored in the DDC database. Each analog alarm limit shall have an associated unique limit differential specifying the amount by which a variable must return into the proper operating range before being annunciated as a return-to-normal-state. All limits and differentials shall be entered on-line by the operator in limits of the measured variable, without interruption or loss of monitoring of the point concerned. The program shall automatically change the high or low limits or both, of any analog point, based on time scheduled operations as specified, allowing for a time interval before the alarm limit becomes effective. In CPA applications, key the limit to a finite deviation traveling with the setpoint. The

system shall automatically suppress analog alarm reporting associated with a digital point when that digital point is turned off.

2.15.4.3 Pulse Accumulator Alarms Definition

Pulse accumulator alarms are those conditions calculated from totalized values of accumulator inputs or PA input rates that are outside defined limits as specified and shown. PA totalized values shall be compared to predefined limits and alarmed each time a value enters a limit condition. Unique limits shall be assigned to each PA point in the system. Limits shall be stored in the DDC database.

2.15.5 Constraints

2.15.5.1 Equipment Constraints Definitions

Each control point in the database shall have DDC resident constraints defined and entered by the Contractor, including as applicable:

- a. Maximum starts (cycles) per hour.
- b. Minimum off time.
- c. Minimum on time.
- d. High limit (value in engineering units).
- e. Low limit (value in engineering units).

2.15.5.2 Constraints Checks

Control devices connected to the system shall have the DDC memory resident constraints checked before each command is issued to insure that no equipment damage will result from improper operation. Each command shall be executed by the DDC only after all constraints checks have been passed. Each command point shall have unique constraints assigned. High and low "reasonableness" values or one differential "rate-of-change" value shall be assigned to each AI. Values outside the reasonableness limits shall be rejected and an alarm message sent to the network control panel or portable workstation/tester. Status changes and analog point values shall be reported to the workstation upon operator request, such as for reports, alphanumeric displays, graphic displays, and application programs. Each individual point shall be capable of being selectively disabled by the operator from a workstation/tester. Disabling a point shall prohibit monitoring and automatic control of that point.

2.15.6 Diagnostics

Each DDC shall have self-test diagnostic routines implemented in firmware. The tests shall include routines that exercise memory. Diagnostic software shall be usable in conjunction with the central workstation/tester and portable workstation/tester. The software shall display messages in English to inform the tester's operator of diagnosed problems.

2.15.7 Summer-Winter Operation Monitoring

The system shall provide software to automatically change the operating parameters, monitoring of alarm limits, and start-stop schedules for each mechanical system from summer to winter and vice-versa. The software shall provide automatic commands to applications programs to coordinate proper summer or winter operation. Change over setpoints shall be operator selectable and settable.

2.15.8 Control Sequences and Control Loops

Sufficient memory shall be provided to implement the requirements specified and shown for each DDC. Specific functions to be implemented are defined in individual system control sequences and database tables shown in the drawings, and shall include, as applicable, the following:

- a. PI Control: This function shall provide proportional control and proportional plus integral control.
- b. Two Position Control: This function shall provide control for a two state device by comparing a set point against a process variable and an established deadband.
- c. Floating Point Control: This function shall exercise control when an error signal exceeds a selected deadband, and shall maintain control until the error is within the deadband limits.
- d. Signal Selection: This function shall allow the selection of the highest or lowest analog value from a group of analog values as the basis of control. The function shall include the ability to cascade analog values so that large numbers of inputs can be reduced to one or two outputs.
- e. Signal Averaging: This function shall allow the mathematical calculation of the average analog value from a group of analog values as the basis of control. The function shall include the ability to "weight" the individual analog values so that the function output can be biased as necessary to achieve proper control.
- f. Reset Function: This function shall develop an AO based on up to two AIs and one operator specified reset schedule.
- g. Cooling/Heating Operation Program: Software shall be provided to change, either automatically or on operator command, the operating parameters, monitoring of alarm limits, and start-stop schedules for each mechanical system where such a change from cooling to heating and vice versa is meaningful. The software shall provide commands to application programs to coordinate cooling or heating mode operation. Software shall automatically switch facilities from cooling to heating, and vice versa, based on schedules or temperatures. All HVAC equipment and systems shall be assigned to the program.

2.15.9 Command Priorities

A scheme of priority levels shall be provided to prevent interaction of a

command of low priority with a command of higher priority. The system shall require the latest highest priority command addressed to a single point to be stored for a period of time longer than the longest time constraint in the on and off states, insuring that the correct command shall be issued when the time constraint is no longer in effect or report the rejected command. Override commands entered by the operator shall have higher priority than those emanating from applications programs.

2.15.10 Resident Application Software

The Contractor shall provide resident applications programs to achieve the sequences of operation, parameters, constraints, and interlocks necessary to provide control of the systems connected to the DDC system. Application programs shall be resident and shall execute in the DDC, and shall coordinate with each other, to insure that no conflicts or contentions remain unresolved. The Contractor shall coordinate the application programs specified with the equipment and controls operation, and other specified requirements. A scheme of priority levels shall be provided to prevent interaction of a command of low priority with a command of higher priority. The system shall require the latest highest priority command addressed to a single point to be stored for a period of time longer than the longest time constraint in the ON and OFF states, insuring that the correct command shall be issued when the time constraint is no longer in effect or the rejected command shall be reported. Override commands entered by the operator shall have higher priority than those emanating from application programs.

2.15.10.1 Program Inputs and Outputs

The Contractor shall select the appropriate program inputs listed for each application program to calculate the required program outputs. Where the specific program inputs are not available, a "default" value or virtual point appropriate for the equipment being controlled and the proposed sequence of operation shall be provided to replace the missing input, thus allowing the application program to operate. AIs to application programs shall have an operator adjustable deadband to preclude short cycling or hunting. Program outputs shall be real analog or digital outputs or logic (virtual) points as required to provide the specified functions. The Contractor shall select the appropriate input and output signals to satisfy the requirements for control of systems as shown.

2.15.10.2 DDC General Conditions

The Contractor shall provide software required to achieve the sequences of operation, parameters, constraints, and interlocks shown. Application software shall be resident in the DDC in addition to any other required software. In the event of a DDC failure, the controlled equipment shall continue to function in the failure mode shown.

2.15.10.3 Scheduled Start/Stop Program

This program shall start and stop equipment based on a time of day schedule for each day of the week, and on a holiday schedule. To eliminate power surges, an operator adjustable time delay shall be provided between

consecutive start commands.

a. Program Inputs:

- (1) Day of week/holiday.
- (2) Time of day.
- (3) Cooling and heating high-low alarm limits.
- (4) Cooling and heating start-stop schedules.
- (5) Cooling or heating mode of operation.
- (6) Equipment status.
- (7) Equipment constraints.
- (8) Consecutive start time delay.

b. Program Outputs: Start/stop signal.

2.15.10.4 Optimum Start/Stop Program

This program shall start and stop equipment as specified for the scheduled start/stop program, but shall include a sliding schedule based on indoor and outdoor air conditions. The program shall take into account the thermal characteristics of the structure, and indoor and outdoor air conditions, using prediction software to determine the minimum time of HVAC system operation needed to satisfy space environmental requirements at the start of the occupied cycle, and determine the earliest time for stopping equipment at the day's end without exceeding space environmental requirements. An adaptive control algorithm shall be utilized to automatically adjust the constants used in the program.

a. Program Inputs:

- (1) Day of week/holiday.
- (2) Time of day.
- (3) Cooling or heating mode of operation.
- (4) Equipment status.
- (5) Cooling and heating building occupancy schedules.
- (6) Space temperature.
- (7) Building heating constant (operator adjustable and automatically optimized).
- (8) Building cooling constant (operator adjustable and automatically optimized).

- (9) OA temperature.
- (10) Required space temperature at occupancy (heating).
- (11) Required space temperature at occupancy (cooling).
- (12) Equipment constraints.
- (13) Cooling and heating high-low alarm limits.

b. Program Outputs: Start/stop signal.

2.15.10.5 Day-Night Setback Program

The software shall limit the rise or drop of space temperature (or specified fluid temperature) during unoccupied hours. Whenever the space temperature (or specified fluid temperature) is above (or below for heating) the operator assigned temperature limit, the system shall be turned on until the temperature is within the assigned temperature limit.

a. Program Inputs:

- (1) Day of week.
- (2) Time of day.
- (3) Cooling or heating mode of operation.
- (4) Cooling and heating occupancy schedules.
- (5) Equipment status.
- (6) Space temperature (or specified fluid temperature).
- (7) Minimum space temperature (or specified fluid temperature) during unoccupied periods.
- (8) Maximum space temperature (or specified fluid temperature) during unoccupied periods.
- (9) Equipment constraints.

b. Program Outputs: Start/stop signal.

2.15.10.6 Economizer Program I

The software shall reduce the HVAC system cooling requirements when the OA dry bulb temperature is less than the return air temperature. When the OA dry bulb temperature is above the return air temperature or changeover setpoint, the OA dampers, return air dampers, and relief air dampers shall be positioned to provide minimum required OA. When the OA dry bulb temperature is below a changeover setpoint temperature, the OA dampers, return air dampers, and exhaust air dampers shall be positioned to maintain

the required mixed air temperature.

a. Program Input:

- (1) Changeover conditions.
- (2) OA dry bulb temperature.
- (3) RA dry bulb temperature.
- (4) Mixed air dry bulb temperature.
- (5) Equipment constraints.

b. Program Output: Damper actuator/cooling control signal.

2.15.10.7 Ventilation/Recirculation and Flush Programs

The software shall reduce the HVAC system thermal load for two modes of operation and provide for flushing of the building as follows:

a. Ventilation mode: In this mode, the system shall precool the space prior to building occupancy. When the outside air temperature is lower than the space temperature, the outside air damper and exhaust air damper shall open to their maximum positions and the return air damper shall close to its minimum position.

b. Recirculation mode: In this mode, the system shall preheat the space prior to building occupancy. When the outside air temperature is lower than the space temperature, the outside air damper and the exhaust air damper shall close to their minimum positions and the return air damper shall open to its maximum position.

c. Flush mode: The software shall use the HVAC supply system to provide 100% outside air for ventilation purpose and flush building spaces.

The network control panel shall modulate the control valves to maintain the air supply temperature setpoints while the flush program is in effect. The flush mode shall be manually initiated and have the highest priority (it shall override all other programs). The outside air damper and the exhaust air damper shall be closed at other times during unoccupied periods, except for economizer operation during day/night setback periods. For systems without mechanical cooling, this program shall, in addition to the above requirements, act as an economizer. The outside, return, and exhaust air dampers shall be modulated to maintain the required mixed air temperature setpoint. When this program is released, the outside and exhaust air dampers shall return to their minimum positions, and the return air damper shall return to its maximum position.

d. Program Inputs:

- (1) Day of week.
- (2) Time of day.

- (3) Cooling or heating mode of operation.
- (4) Equipment status.
- (5) Cooling and heating occupancy schedules.
- (6) OA dry bulb temperature.
- (7) Space temperature.
- (8) Equipment constraints.

e. Program Output: Damper actuator control signal.

2.15.10.8 Hot Deck/Cold Deck Temperature Reset Program

The software shall use space, mixed air, and deck temperatures to calculate the hot deck/cold deck temperature setpoints in dual duct and multizone HVAC systems. The program shall select the zones with the greatest heating and cooling requirements; establish the HVAC minimum hot and cold deck temperature differentials required to meet the zone temperatures; modulate valves to maintain deck temperature setpoints; and modulate zone dampers to maintain space temperature setpoints, without exceeding space humidity limits (where shown).

a. Program Inputs:

- (1) Space temperature setpoint.
- (2) Space humidity limit (where shown).
- (3) Mixing box damper position or proportional signal from primary element.
- (4) Hot deck temperature.
- (5) Cold deck temperature.
- (6) Zone temperatures (where shown).
- (7) Space RH (where shown).
- (8) Minimum space temperature during occupied periods.
- (9) Maximum space temperature during occupied periods.
- (10) Equipment constraints.

b. Program Outputs:

- (1) Hot deck valve actuator control signal.
- (2) Cold deck valve actuator control signal.

- (3) Zone damper or mixing box actuator control output signal.

2.15.10.9 Reheat Coil Reset Program

The software shall select the zone with the least amount of heat required. The program shall reset the cold deck discharge temperature upward until it satisfies the zone with the lowest demand, or until the zone humidity control requirements cannot be met.

a. Program Inputs:

- (1) Zone RH high limit.
- (2) Zone temperature (where shown).
- (3) Zone RH (where shown).
- (4) Cold deck temperature.
- (5) Reheat coil valve positions or proportional signals from primary elements.
- (6) Minimum space temperature during occupied periods.
- (7) Maximum space temperature during occupied periods.
- (8) Equipment constraints.

b. Program Output: Cold deck valve actuator control signal.

2.15.10.10 Heating and Ventilating Unit Program

The software shall control hot water/steam coil valve position to maintain space/supply air temperatures for heating and ventilating units. This program shall be coordinated with the ventilation-recirculation program for damper control and the scheduled or optimum start-stop program for fan control.

a. Program Inputs

- (1) Space temperature.
- (2) Space temperature setpoint.
- (3) Supply air temperature.
- (4) Supply air temperature setpoint.

b. Program Outputs

- (1) Heating or steam coil valve actuator control signal.
- (2) Damper actuator control signal.

2.15.10.11 Air Volume Control Program

The software shall monitor supply and return/exhaust air flow volumes and modulate fan controls to maintain required air flow volumes and/or ratio or

fixed differential of supply to return air flows. This program shall be coordinated with the ventilation-recirculation program and the economizer program for damper control and with static pressure control requirements for fan control.

a. Program Inputs

- (1) Supply air flow.
- (2) Return/exhaust air flow.
- (3) Required supply air flow - high and low limits.
- (4) Required return/exhaust air flow - high and low limits.
- (5) Volume offset or ratio, as appropriate.

b. Program Outputs

- (1) Supply fan volume control.
- (2) Return/exhaust fan volume control.

2.15.10.12 Air Distribution Unitary Controller Software

Software shall be provided for the management and control of the air distribution terminal units. Software shall allow for operator definition of multiple air distribution terminal units as functional groups which may be treated as a single entity; monitoring, alarming and reporting of terminal unit parameters on an individual or group basis; and remote setpoint adjustment on an individual or group basis.

a. Functions:

- (1) Volume control in response to temperature.
- (2) Volume flow limits, minimum and maximum.
- (3) Occupied and unoccupied operation with associated temperature and volume limits.
- (4) Temperature setpoint override.

b. Program Inputs

- (1) Space temperature.
- (2) Space temperature setpoint.
- (3) Space temperature setpoint limits.
- (4) Supply airflow volume.
- (5) Supply airflow volume high and low limits.

c. Program Outputs

- (1) Supply volume control signal.
- (2) Auxiliary fan start/stop signal.
- (3) Supplemental heat control signal.

2.15.10.13 Chiller Selection Program

Chiller program shall be used for chiller selection as well as control and monitoring of chillers. The software shall select the most efficient chiller or combination of chillers based on chiller operating data to

satisfy the cooling load. Based on chiller operating data, energy input vs chilled water output, the chiller with the highest efficiency shall be selected to satisfy the cooling load calculated by prediction software. The program shall calculate equipment electrical energy input based on percent full load, current, or other inputs provided, and equipment nameplate data. The program shall prevent the chiller from going to full load for a predetermined period to allow the system to stabilize, in order to determine the actual cooling load. The program shall follow the chiller manufacturer's startup and shutdown sequence requirements. Interlocks between chilled water pumps, condenser water pumps, and chiller shall be in accordance with the chiller manufacturer's requirements.

a. Program Inputs

- (1) Efficiency curves.
- (2) Chiller water supply temperatures.
- (3) Chiller water return temperatures.
- (4) Chiller water flows.
- (5) Entering condenser water temperatures.
- (6) Leaving condenser water temperatures.
- (7) Condenser water flows.
- (8) Instantaneous KW to chillers.
- (9) Instantaneous KW to chilled water pumps (if variable).
- (10) Instantaneous KW to condenser water pumps (if variable).
- (11) Instantaneous KW to cooling tower fans (if variable).
- (12) Common chilled water supply temperatures.
- (13) Common chilled water return temperatures.
- (14) Total chilled water flow.
- (15) Chilled water pumps status.
- (16) Refrigerant pressure, suction and discharge.
- (17) Equipment constraints.
- (18) Steam flow.

b. Program Outputs

- (1) Start/stop signals for chillers (manual or automatic to control panel).
- (2) Start/stop signals for chilled water pumps (manual or automatic to control panel).
- (3) Start/stop signals for condenser water pumps (manual or automatic to control panel).
- (4) Start/stop signals for cooling tower fans (manual or automatic to control panel).
- (5) Chilled water supply temperature setpoint control signal.
- (6) Chiller efficiency.

2.15.10.14 Chilled Water Temperature Reset Program

The software shall reset the chilled water temperature supplied by a water chiller. The program shall reset the chilled water temperature upward or downward to meet the required space temperature or humidity setpoints. The program shall monitor the positions of the chilled water control valves (percent of opening) and space temperatures.

a. Program Input:

- (1) Chilled water valve position.
- (2) High limit for space dry bulb temperature.
- (3) Chiller supply water temperature.
- (4) High chilled water operating temperature.
- (5) Low chilled water operating temperature.
- (6) High limit for space RH.
- (7) Equipment constraints.

b. Program Output: Chilled water supply temperature setpoint control signal.

2.15.10.15 Condenser Water Temperature Reset Program

The software shall reset the condenser water temperature from a fixed temperature downward when the OA wet bulb temperature will produce lower condenser water temperature. Program shall be coordinated with the chiller control loop algorithms for chiller supply, return water temperatures and safety interlocks.

a. Program Inputs:

- (1) Maximum condenser water operating temperature.
- (2) Minimum condenser water operating temperature.
- (3) Condenser water supply temperature.
- (4) OA dry bulb temperature.
- (5) OA RH.
- (6) Condenser water cooling equipment thermal approach characteristics.
- (7) Equipment constraints.

b. Program Output: Condenser water supply temperature setpoint control signal.

2.15.10.16 Chiller Demand Limit Program

The software shall limit maximum available chiller cooling capacity in fixed steps as shown to limit electrical demand. Each fixed step shall be considered as one point in the demand limiting program. Each chiller demand control step shall be assigned an equipment priority level.

a. Program Inputs:

- (1) Chiller percent capacity.
- (2) Minimum cooling capacity.
- (3) Equipment priority schedules.
- (4) Equipment constraints.

b. Program Output

- (1) Calculated percent load point.
- (2) Control signal to chiller controller/panel, new setpoint (manual or automatic as shown).

2.15.10.17 Hot Water OA Reset Program

The software shall reset the hot water temperature supplied by the boiler or converter in accordance with the OA temperature or other specified independent- dent variable. The hot water supply temperature shall be reset downward or upward from a fixed temperature proportionally, as a function of OA temperature or other specified independent variable.

a. Program Inputs

- (1) Reset schedule.
- (2) OA dry bulb temperature or other specified independent variable.
- (3) Hot water supply temperature.
- (4) Maximum hot water supply temperature.
- (5) Minimum hot water supply temperature.
- (6) Equipment constraints.

b. Program Output: Valve actuator control signal.

2.15.10.18 Boiler Monitoring and Control

The software shall remotely monitor and control boiler operation based on boiler operational data. The program shall monitor inputs and discontinue boiler operation if any monitored point exceeds a predetermined value or changes status incorrectly. The operator shall be able to add or delete individual program input points from the list of points that will discontinue boiler operation.

a. Program Inputs

- (1) Fuel flow.
- (2) Fuel pressure (natural gas).
- (3) Fuel temperature (heated fuel oil).
- (4) Flame status.
- (5) Flue gas oxygen.
- (6) Flue gas temperature.
- (7) Make-up or feed water flow.
- (8) Furnace draft.
- (9) Flue gas carbon monoxide (for boilers over 20 million BTUs).
- (10) Hot water flow.
- (11) Hot water pressure.
- (12) Hot water supply temperature.
- (13) Hot water return temperature.
- (14) Hot water BTUs.
- (15) Steam flow.
- (16) Steam pressure.
- (17) Steam temperature.
- (18) Steam BTUs.
- (19) Feedwater temperature.
- (20) Boiler drum level.

b. Program Outputs

- (1) Boiler enable/disable control signal.
- (2) Boiler enable/disable permission to boiler operator for manual control.
- (3) Boiler efficiency.

2.15.10.19 Hot Water Distribution Program

The software shall control the hot water distribution temperature to individual building zones. The zone hot water distribution temperature shall be reset downward or upward from a fixed temperature proportionally as a function of OA temperature or other specified independent variable by modulating the respective zone mixing valve. The zone pump shall be stopped when the OA temperature exceeds the specified setpoint. When parallel pumps are used, the software shall alternate pump operation and shall start the standby pump (after a time delay) upon failure of the operating pump.

a. Program Inputs

- (1) Zone hot water distribution temperature.
- (2) Reset schedule.
- (3) OA dry bulb temperature or other specified independent variable.
- (4) Maximum zone hot water distribution temperature.
- (5) Zone pump status.
- (6) Equipment constraints.

b. Program Outputs

- (1) Zone mixing valve control.
- (2) Zone pump start/stop signal(s).

2.15.10.20 Domestic Hot Water Generator Program

The software shall control the domestic hot water temperature by adjusting the hot water heating control valve.

a. Program Inputs

- (1) Domestic hot water temperature.
- (2) Domestic hot water temperature setpoint.

b. Program Output: Hot water heating control valve actuator control signal.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION CRITERIA

3.1.1 HVAC Control System

The HVAC control system shall be completely installed and ready for operation. Dielectric isolation shall be provided where dissimilar metals

are used for connection and support. Penetrations through and mounting holes in the building exterior shall be made watertight. The HVAC control system installation shall provide clearance for control system maintenance by maintaining access space between coils, access space to mixed-air plenums, and other access space required to calibrate, remove, repair, or replace control system devices. The control system installation shall not interfere with the clearance requirements for mechanical and electrical system maintenance.

3.1.2 Software Installation

Software shall be loaded for an operational system, including databases for all points, operational parameters, and system, command, and application software. The Contractor shall provide original and backup copies of source, excluding the general purpose operating systems and utility programs furnished by computer manufacturers and the non-job-specific proprietary code furnished by the system manufacturer, and object modules for software on each type of media utilized, within 30 days of formal Government acceptance. In addition, a copy of individual floppy disks of software for each DDC panel shall be provided.

3.1.3 Device Mounting Criteria

Devices mounted in or on piping or ductwork, on building surfaces, in mechanical/electrical spaces, or in occupied space ceilings shall be installed in accordance with manufacturer's recommendations and as shown. Control devices to be installed in piping and ductwork shall be provided with required gaskets, flanges, thermal compounds, insulation, piping, fittings, and manual valves for shutoff, equalization, purging, and calibration. Strap-on temperature sensing elements shall not be used except as specified.

3.1.4 Wiring Criteria

Wiring external to control panels, including low-voltage wiring, shall be installed in metallic raceways. Wiring shall be installed without splices between control devices and DDC panels. Instrumentation grounding shall be installed as necessary to prevent ground loops, noise, and surges from adversely affecting operation of the system. Ground rods installed by the contractor shall be tested as specified in IEEE Std 142. Cables and conductor wires shall be tagged at both ends, with the identifier shown on the shop drawings. Electrical work shall be as specified in Section 16415A ELECTRICAL WORK, INTERIOR and as shown.

3.2 CONTROL SYSTEM INSTALLATION

3.2.1 Damper Actuators

Actuators shall not be mounted in the air stream. Multiple actuators operating a common damper shall be connected to a common drive shaft. Actuators shall be installed so that their action shall seal the damper to the extent required to maintain leakage at or below the specified rate and shall move the blades smoothly.

3.2.2 Local Gauges for Actuators

Pneumatic actuators shall have an accessible and visible receiver gauge installed in the tubing lines at the actuator as shown.

3.2.3 Room Instrument Mounting

Room instruments , such as wall mounted thermostats, shall be mounted 1.5 m above the floor unless otherwise shown. Temperature setpoint devices shall be recess mounted.

3.2.4 Freezestats

For each 2 square meters of coil face area, or fraction thereof, a freezestat shall be provided to sense the temperature at the location shown. Manual reset freezestats shall be installed in approved, accessible locations where they can be reset easily. The freezestat sensing element shall be installed in a serpentine pattern.

3.2.5 Averaging Temperature Sensing Elements

Sensing elements shall have a total element minimum length equal to 3 m per square meter of duct cross-sectional area.

3.2.6 Foundations and Housekeeping Pads

Foundations and housekeeping pads shall be provided for the HVAC control system air compressors.

3.2.7 Compressed Air Stations

The air compressor assembly shall be mounted on vibration eliminators, in accordance with ASME BPVC SEC VIII D1 for tank clearance. The air line shall be connected to the tank with a flexible pipe connector. Compressed air station specialties shall be installed with required tubing, including condensate tubing to a floor drain.

3.2.8 Duct Static Pressure Sensing Elements and Transmitters

The duct static pressure sensing element and transmitter sensing point shall be located at 75% to 100% of the distance between the first and last air terminal units.

3.2.9 Indication Devices Installed in Piping and Liquid Systems

Gauges in piping systems subject to pulsation shall have snubbers. Gauges for steam service shall have pigtail fittings with cock. Thermometers and temperature sensing elements installed in liquid systems shall be installed in thermowells.

3.2.10 Tubing

3.2.10.1 Control System Installation

The control system shall be installed so that pneumatic lines are not exposed to outside air temperatures. All tubes and tube bundles exposed to view shall be installed neatly in lines parallel to the lines of the building. Tubing between panels and actuators in mechanical/electrical spaces shall be routed so that the lines are easily traceable.

3.2.10.2 Pneumatic Lines In Mechanical/Electrical Spaces

In mechanical/electrical spaces, pneumatic lines shall be copper tubing. Horizontal and vertical runs of soft copper tubes shall be installed in raceways dedicated to tubing. Dedicated raceways and tubing not installed in raceways shall be supported every 2 m for horizontal runs and every 2.5 m for vertical runs.

3.2.10.3 Pneumatic Lines External To Mechanical/Electrical Spaces

Tubing external to mechanical/electrical spaces shall be soft copper with sweat fittings.

3.2.10.4 Connection to Liquid and Steam Lines

Tubing for connection of sensing elements and transmitters to liquid and steam lines shall be copper with brass compression fittings.

3.2.10.5 Connection to Ductwork

Tubing for connection of sensing elements and transmitters to ductwork shall be plastic tubing.

3.2.10.6 Final Connection to Actuators

Final connections to actuators shall be plastic tubing 300 mm long and unsupported at the actuator.

3.3 COMMISSIONING PROCEDURES

3.3.1 Evaluations

The Contractor shall make the observations, adjustments, calibrations, measurements, and tests of the control systems, set the time schedule, and make any necessary control system corrections to ensure that the systems function as described in the sequence of operation.

3.3.1.1 Item Check

Signal levels shall be recorded for the extreme positions of each controlled device. An item-by-item check of the sequence of operation requirements shall be performed using Steps 1 through 4 in the specified control system commissioning procedures. Steps 1, 2, and 3 shall be performed with the HVAC system shut down; Step 4 shall be performed after the HVAC systems have been started. External input signals to the DDC system (such as starter auxiliary contacts, and external systems) may be simulated in steps 1, 2, and 3. With each operational mode signal change, DDC system output relay contacts shall be observed to ensure that they

function.

3.3.1.2 Weather Dependent Test Procedures

The cooling system shall be commissioned when the outside air temperature is greater than 80 degrees F. The heating system shall be commissioned when the outside air temperature is less than 32 degrees F. All air handling systems shall be commissioned twice, once when outside air temperature is less than 32 degrees F, and also when outside air temperature is greater than 80 degrees F.

3.3.1.3 Two-Point Accuracy Check

A two-point accuracy check of the calibration of each HVAC control system sensing element and transmitter shall be performed by comparing the DDC system readout to the actual value of the variable measured at the sensing element and transmitter or airflow measurement station location. Digital indicating test instruments shall be used, such as digital thermometers, motor-driven psychrometers, and tachometers. The test instruments shall be at least twice as accurate as the specified sensing element-to-DDC system readout accuracy. The calibration of the test instruments shall be traceable to National Institute Of Standards And Technology standards. The first check point shall be with the HVAC system in the shutdown condition, and the second check point shall be with the HVAC system in an operational condition. Calibration checks shall verify that the sensing element-to-DDC system readout accuracies at two points are within the specified product accuracy tolerances. If not, the device shall be recalibrated or replaced and the calibration check repeated.

3.3.1.4 Insertion and Immersion Temperatures

Insertion temperature and immersion temperature sensing elements and transmitter-to-DDC system readout calibration accuracy shall be checked at one physical location along the axis of the sensing element.

3.3.1.5 Averaging Temperature

Averaging temperature sensing element and transmitter-to-DDC system readout calibration accuracy shall be checked every 600 mm along the axis of the sensing element in the proximity of the sensing element, for a maximum of 10 readings. These readings shall then be averaged.

3.3.2 Space Temperature Controlled Perimeter Radiation

The heating medium shall be turned on, and the thermostat temperature setpoint shall be raised. The valve shall open. The thermostat temperature shall be lowered and the valve shall close. The thermostat shall be set at the setpoint shown.

3.3.3 Unit Heater and Cabinet Unit Heater

The "OFF/AUTO" switch shall be placed in the "OFF" position. Each space thermostat temperature setting shall be turned up so that it makes contact to turn on the unit heater fans. The unit heater fans shall not start.

The "OFF/AUTO" switch shall be placed in the "AUTO" position. It shall be ensured that the unit heater fans start. Each space thermostat temperature setting shall be turned down, and the unit heater fans shall stop. The thermostats shall be set at their temperature setpoints. The results of testing of one of each type of unit shall be logged.

3.3.4 Fan Coil Unit

The dual-temperature hydronic system shall be set to heating. Each space thermostat temperature setting shall be turned up so that it makes contact and turns the fan coil unit on. It shall be ensured that the fan coil unit fan starts and the valves open to flow through the coils. Each space thermostat temperature setting shall be turned down and it shall be ensured that the fan coil unit fans stop. It shall be ensured that the valves close to flow through the coils. The dual-temperature hydronic system shall be switched to cooling. Each space thermostat temperature setting shall be turned up and it shall be ensured that contact is broken and the fan coil unit fans stop. It shall be ensured that the valves close to flow through the coil. Each space thermostat temperature setting shall be turned down. It shall be ensured that the fan coil unit fans start and the valves open to flow through the coils. The thermostats shall be set at their temperature setpoints. The results of testing of one of each type of unit shall be logged.

3.3.5 Single Building Hydronic Heating with Hot Water Boiler

Steps for installation shall be as follows:

a. Step 1 - System Inspection: The HVAC system shall be observed in its shutdown condition. It shall be verified that power and main air are available where required.

b. Step 2 - Calibration Accuracy Check with HVAC System Shutdown: Readings shall be taken with a digital thermometer at each temperature sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system readings logged. The calibration accuracy of the sensing element-to-DDC system readout for outside air temperature and system supply temperature shall be checked.

c. Step 3 - Actuator Range Adjustments: N/A.

d. Step 4 - Control System Commissioning:

(1) The two-point calibration sensing element-to-DDC system readout accuracy check for the outside air temperature shall be performed. Any necessary software adjustments to setpoints or parameters shall be made to achieve the outside air temperature schedule.

(2) The outside air temperature shall be simulated through an operator entered value to be above the setpoint. It shall be verified that pumps and boilers stop. A value shall be entered to simulate that the outside air temperature is below the setpoint as shown. It shall be verified that pumps start and boilers are

fired in sequence. It shall be verified that each boiler recirculation pump starts when its respective boiler is firing. Each current switch reading shall be verified at the operator's console.

(3) The two-point calibration accuracy check of the sensing element-to-DDC system readout for the hydronic system supply temperature shall be performed. The supply temperature setpoint shall be set for the temperature schedule as shown. Signals at two points sent to the DDC system from the outside air temperature sensor, to verify that the supply temperature setpoint changes to the appropriate values.

3.3.6 Single Building Cooling System

Steps for installation shall be as follows:

a. Step 1 - System Inspection: The HVAC system shall be observed in its shutdown condition. It shall be verified that power and main air are available where required.

b. Step 2 - Calibration Accuracy Check with HVAC System Shutdown: Readings shall be taken with a digital thermometer at each temperature sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system readings logged. The calibration accuracy of the sensing element-to-DDC system readout for outside air temperature and system supply temperature shall be checked.

c. Step 3 - Actuator Range Adjustments: N/A.

d. Step 4 - Control System Commissioning:

(1) The two-point calibration sensing element-to-DDC system readout accuracy check for the outside air temperature shall be performed. Any necessary software adjustments to setpoints or parameters shall be made to achieve the outside air temperature schedule.

(2) The outside air temperature shall be simulated through an operator entered value to be below the setpoint. It shall be verified that pumps stop. A value shall be entered to simulate that the outside air temperature is above the setpoint as shown. It shall be verified that pumps start. Each current switch reading shall be verified at the operator's console.

(3) The two-point calibration accuracy check of the sensing element-to-DDC system readout for the hydronic system supply temperature shall be performed. The supply temperature setpoint shall be set for the temperature schedule as shown. Signals at two points sent to the DDC system from the outside air temperature sensor, to verify that the supply temperature setpoint changes to the appropriate values.

3.3.7 Heating and Ventilating Unit

Steps for installation are as follows:

a. Step 1 - System Inspection: The HVAC system shall be observed in its shutdown condition. The system shall be checked to see that power and main air are available where required, the outside air damper and relief air damper are closed, and the return air damper is open.

b. Step 2 - Calibration Accuracy Check with HVAC System Shutdown: Readings shall be taken with a digital thermometer at each temperature sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system readings logged. The calibration accuracy of the sensing element-to-DDC system readout for space temperature shall be checked.

c. Step 3 - Actuator Range Adjustments: A signal shall be applied to the actuator through an operator entered value to the DDC system. The proper operation of the actuators and positioners for all dampers and valves shall be verified. The signal shall be varied from live zero to full range, and that the actuators travel from zero stroke to full stroke within the signal range shall be verified. It shall be verified that all sequenced and parallel-operated actuators move from zero stroke to full stroke in the proper direction, and move the connected device in the proper direction from one extreme position to the other.

d. Step 4 - Control System Commissioning:

(1) With the fan ready to start, the system shall be placed in the ventilation delay mode and in the occupied mode through operator entered values. It shall be verified that supply fan starts. It shall be verified that the outside air and relief air dampers are closed, the return air damper is open, and the heating coil valve is under control, by artificially changing the space temperature through operator entered values. The system shall be placed out of the ventilation delay mode, and it shall be verified that the outside air, return air, and relief air dampers come under control by simulating a change in space temperature.

(2) The control system shall be placed in the minimum outside air mode. It shall be verified that the outside air damper opens to minimum position.

(3) The calibration accuracy check of sensing element-to-DDC system readout for the space temperature shall be performed. The space temperature setpoint shall be set as shown.

(4) The control system shall be placed in the unoccupied mode, and it shall be verified that the HVAC system shuts down, and the control system assumes the specified shutdown conditions. The space temperature shall be artificially changed to below the night setback setpoint, and it shall be verified that the HVAC system starts; the space temperature shall be artificially changed to above the night setback setpoint, and it shall be verified that the HVAC system stops. The night setback temperature setpoint

shall be set as shown.

(5) With the HVAC system running, a filter differential pressure switch input signal shall be simulated, at the device. It shall be verified that the filter alarm is initiated. The differential pressure switch shall be set at the setpoint as shown.

(6) With the HVAC system running, a signal shall be applied to simulate an outdoor-air temperature of 38 degrees F. It shall be verified that the cooling coil recirculation pump starts and runs continuously. A signal shall be applied to simulate a unit leaving air temperature of 34 degrees F. It shall be verified that a low temperature alarm is initiated at the operator's console and the unit shuts down. The HVAC system shall be restarted by manual restart and it shall be verified that the alarm returns to normal.

(7) With the HVAC system running, a smoke detector trip input signal shall be simulated at each detector, and verification of control device actions and interlock functions as described in the Sequence of Operation shall be made. Simulation shall be performed without false-alarms any Life Safety systems. It shall be verified that the HVAC system shuts down and that the smoke detector alarm is initiated. The detectors shall be reset. The HVAC system shall be restarted by manual reset, and it shall be verified that the alarm signal is changed to a return-to-normal signal.

(8) With the HVAC system running, an emergency shutdown switch signal shall be simulated. It shall be verified that the HVAC system shuts down and that the shutdown alarm is initiated at the operator's console.

(9) With the HVAC system running, the fan status current switches shall be verified at the operator's console.

3.3.8 Multizone Control System without Return Fan

Steps for installation shall be as follows:

a. Step 1 - System Inspection: The HVAC system shall be observed in its shutdown condition. The system shall be checked to see that power and main air are available where required; that the outside air damper, and relief air damper are closed; and that the return air damper is open.

b. Step 2 - Calibration Accuracy Check with HVAC System Shutdown: Readings shall be taken with a digital thermometer at each temperature-sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system readings logged. The calibration accuracy of the sensing element-to-DDC system readout for outside air, return air, mixed air, cold-deck, and hot-deck temperatures shall be checked.

c. Step 3 - Actuator Range Adjustments: A signal shall be applied to

the actuator through an operator entered value to the DDC system. The proper operation of the actuators and positioners for all dampers and valves shall be verified. The signal shall be varied from live zero to full range, and it shall be verified that the actuators travel from zero stroke to full stroke within the signal range. It shall be verified that all sequenced and parallel-operated actuators move from zero stroke to full stroke in the proper direction, and move the connected device in the proper direction from one extreme position to the other.

d. Step 4 - Control System Commissioning:

(1) With the fans ready to start, the system shall be placed in the ventilation delay mode (COF only) and in the occupied mode, and it shall be verified that supply fan starts. It shall be verified that the outside air and relief air dampers are closed, and the return air damper is open, by artificially changing the mixed air temperature through operator entered values. The system shall be placed in the occupied mode and it shall be verified that the outside air, return air, and relief air dampers come under control, by artificially changing the mixed air temperature.

(2) The control system shall be placed in the minimum outside air mode. It shall be verified that the outside air damper opens to minimum position.

(3) The economizer mode shall be simulated by a change in the outside air temperature and the return air temperature through operator entered values and it shall be verified that the system goes into the economizer mode. The mixed air temperature shall be artificially changed through operator entered values to slightly open the outside air damper and the second point of the two-point calibration accuracy check of sensing element-to-DDC system readout for outside air, return air, and mixed air temperatures shall be performed. The temperature setpoint shall be set as shown.

(4) The two-point calibration sensing element-to-DDC system readout accuracy check for the outside air temperature shall be performed. Any necessary software adjustments shall be made to setpoints or parameters to achieve the outside air temperature schedule as shown.

(5) The system shall be placed in economizer mode. The two-point calibration accuracy check of sensing element-to-DDC system readout for mixed-air temperatures shall be performed. The outside air temperature shall be artificially changed through operator entered values. Three values shall be entered simulating outside air temperature changes. The values shall be selected at midrange, lower 1/3 range, and upper 1/3 range of the temperature schedule. It shall be verified that the setpoint tracks the schedule.

(8) The control system shall be placed in the unoccupied mode, and it shall be verified that the HVAC system shuts down, and the

control system assumes the specified shutdown conditions. Where night setback is required, the space temperature shall be artificially changed to below the night setback setpoint and it shall be verified that the HVAC system starts; the space temperature shall be artificially changed to above the night setback setpoint, and it shall be verified that the HVAC system stops. The night setback temperature setpoint shall be set as shown.

(9) With the HVAC system running, a filter differential pressure switch input signal shall be simulated at the device. It shall be verified that the filter alarm is initiated. The differential pressure switch shall be set at the setpoint.

(10) With the HVAC system running, a freezestat trip input signal shall be simulated at the device. It shall be verified that the cooling coil recirculation pump starts and runs. It shall be verified that the outdoor air and return air dampers are modulated to raise the mixed air temperature until the freezestat resets. It shall be verified that a low temperature warning is initiated at the operator's console. A signal shall be applied to simulate a unit leaving air temperature of 34 degrees F. It shall be verified that a low temperature alarm is initiated at the operator's console and the unit shuts down. The HVAC system shall be restarted by manual restart and it shall be verified that the alarm returns to normal.

(11) With the HVAC system running, a smoke detector trip input signal shall be simulated at each detector, and control device actions and interlock functions as described in the Sequence of Operation shall be verified. Simulation shall be performed without false-alarms any Life Safety systems. It shall be verified that the HVAC system shuts down and that the smoke detector alarm is initiated. The detectors shall be reset. HVAC system shall be restarted by manual reset, and it shall be verified that the alarm signal is changed to a return-to-normal signal.

(12) The temperature setpoint of each zone thermostat shall be raised and it shall be verified that the zone damper closes to the cold-deck and opens to the hot-deck. Each zone thermostat shall be calibrated and set at its setpoint as shown.

(13) With the HVAC system running, an emergency shutdown switch signal shall be simulated. It shall be verified that the HVAC system shuts down and that the shutdown alarm is initiated at the operator's console.

(14) With the HVAC system running, the fan status current switches shall be verified at the operator's console.

3.3.9 Variable Air Volume Makeup Air Unit (Barracks AHU-1)

Steps for installation shall be as follows:

a. Step 1 - System Inspection: The HVAC system shall be observed in its shutdown condition. The system shall be checked to see that power and main air are available where required, the outside air and relief air dampers are closed, the return air damper is open, and the supply fan is off and coil valves are closed.

b. Step 2 - Calibration Accuracy Check with HVAC System in Shutdown: Readings shall be taken with a digital thermometer at each temperature sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system display readings logged. The calibration accuracy of the sensing element-to-DDC system readout for AHU supply and laundry room temperature shall be checked.

c. Step 3 - Actuator Range Adjustments: A signal shall be applied to the actuators through an operator entered value to the DDC system. The proper operation of the actuators and positioners for all dampers and valves shall be visually verified. The signal shall be varied from live zero to full range, and it shall be verified that the actuators travel from zero stroke to full stroke within the signal range. It shall be verified that all sequenced and parallel operated actuators move from zero stroke to full stroke in the proper direction, and move the connected device in the proper direction from one extreme position to the other.

d. Step 4 - Control System Commissioning:

(1) With the fan ready to start, the control system shall be placed in the the enabled mode through operator entered values. It shall be verified that supply fan starts. It shall be verified that the outside air damper is open, and the cooling coil valve, heating coil valve and fan speed are under control, by simulating a change in the fan discharge temperature.

(2) The two-point calibration accuracy check for sensing element-to-DDC system readout for the static pressure in the supply duct shall be performed.

(3) The two-point calibration accuracy check of sensing element-to-DDC system readout for the fan discharge temperature shall be performed. The setpoint for the fan discharge temperature shall be set as shown. A change shall be simulated in the discharge air temperature through an operator entered value and it shall be verified that the control valves are modulated.

(4) The control system shall be placed in the unoccupied mode and it shall be verified that the HVAC system shuts down and the control system assumes the specified shutdown conditions.

(5) With the HVAC system enabled and all clothes dryer current switches closed, it shall be verified that the air handler fan is stopped. Clothier dryer current switches for all dryers shall be closed to simulate operating dryers. It shall be verified that the fan starts and drives to full speed (60 HZ). One by one, the current switches shall be opened. For each opened switch, it

shall be verified that the fan speed is reduced by 6.25% until only a single switch is left. It shall be verified that the fan operates at a speed corresponding to 5 HZ.

(6) The space temperature shall be simulated to be below the heating setpoint and it shall be verified that the VAV box fan starts. The space temp signal shall be simulated above the heating setpoint and it shall be verified that the fan stops.

(7) With the HVAC system running, a filter differential pressure switch input signal shall be simulated at the device. It shall be verified that the filter alarm is initiated at the operator's console. The differential pressure switch shall be set at the setpoint. This shall be performed for each filter.

(8) With the HVAC system running, a signal shall be applied to simulate an outdoor-air temperature of 38 degrees F. It shall be verified that the cooling coil recirculation pump starts and runs continuously. A signal shall be applied to simulate a unit leaving air temperature of 34 degrees F. It shall be verified that a low temperature alarm is initiated at the operator's console and the unit shuts down. The HVAC system shall be restarted by manual restart and it shall be verified that the alarm returns to normal.

(10) With the HVAC system running, a smoke detector trip input signal shall be simulated at each detector, and control device actions and interlock functions as described in the Sequence of Operation shall be verified. Simulation shall be performed without false-alarms any Life Safety systems. It shall be verified that the HVAC system shuts down and the smoke detector alarm is initiated. The detectors shall be reset. The HVAC system shall be restarted by manual reset, and it shall be verified that the alarm returns to normal.

(11) With the HVAC system running, an emergency shutdown switch signal shall be simulated. It shall be verified that the HVAC system shuts down and that the shutdown alarm is initiated at the operator's console.

(12) With the HVAC system running, the fan status current switches shall be verified at the operator's console.

3.3.10 Blower Coil Make-up Air Units

Steps for installation shall be as follows:

a. Step 1 - System Inspection: The HVAC system shall be verified in its shutdown condition. The system shall be checked to see that power and main air are available where required, that the outside air damper is closed.

b. Step 2 - Calibration Accuracy Check with HVAC System Shutdown:

Readings shall be taken with a digital thermometer at each temperature sensing element location. Each temperature shall be read at the DDC controller, and the thermometer and DDC system display readings logged. The calibration accuracy of the sensing element-to-DDC system readout for outside air, return air, and space temperatures shall be checked.

c. Step 3 - Actuator Range Adjustments: A signal shall be applied to the actuator through an operator entered value to the DDC system. The proper operation of the actuators and positioners for all dampers and valves shall be visually verified. The signal shall be varied from live zero to full range, and the actuator travel from zero stroke to full stroke within the signal range shall be verified. It shall be verified that all sequenced and parallel-operated actuators move from zero stroke to full stroke in the proper direction, and move the connected device in the proper direction from one extreme position to the other.

d. Step 4 - Control System Commissioning:

(1) With the fan ready to start, the control system shall be placed in the occupied (or enabled), and it shall be verified that supply fan starts. It shall be verified that the outside air damper opens, and the heating coil and cooling coil valves are under control, by simulating a change in the space temperature through an operator entered value.

(4) An unoccupied (disabled) mode signal shall be applied, and it shall be verified that the HVAC system shuts down, and the control system assumes the specified shutdown conditions.

(5) With the HVAC system running, a filter differential pressure switch input signal shall be simulated, at the device. It shall be verified that the filter alarm is initiated. The differential pressure switch shall be set at the setpoint as shown.

(6) With the HVAC system running, a signal shall be applied to simulate an outdoor-air temperature of 38 degrees F. It shall be verified that the cooling coil recirculation pump starts and runs continuously. A signal shall be applied to simulate a unit leaving air temperature of 34 degrees F. It shall be verified that a low temperature alarm is initiated at the operator's console and the unit shuts down. The HVAC system shall be restarted by manual restart and it shall be verified that the alarm returns to normal.

(7) With the HVAC system running, a smoke detector trip input signal shall be simulated at each detector, and verification of control device actions and interlock functions as described in the Sequence of Operation shall be made. Simulation shall be performed without false-alarms any Life Safety systems. It shall be verified that the HVAC system shuts down and that the smoke detector alarm is initiated. The detectors shall be reset. The HVAC system shall be restarted by manual reset, and it shall be verified that the alarm signal is changed to a return-to-normal signal.

(8) With the HVAC system running, an emergency shutdown switch signal shall be simulated. It shall be verified that the HVAC system shuts down and that the shutdown alarm is initiated at the operator's console.

(9) With the HVAC system running, the fan status current switches shall be verified at the operator's console.

3.4 BALANCING, COMMISSIONING, AND TESTING

3.4.1 Coordination with HVAC System Balancing

Commissioning of the control system, except for tuning of controllers, shall be performed prior to or simultaneous with HVAC system balancing. The contractor shall tune the HVAC control system after all air system and hydronic system balancing has been completed, minimum damper positions set and a report has been issued.

3.4.2 Control System Calibration, Adjustments, and Commissioning

Control system commissioning shall be performed for each HVAC system, using test plans and procedures previously approved by the Government. The Contractor shall provide all personnel, equipment, instrumentation, and supplies necessary to perform commissioning and testing of the HVAC control system. All instrumentation and controls shall be calibrated and the specified accuracy shall be verified using test equipment with calibration traceable to NIST standards. Wiring shall be tested for continuity and for ground, open, and short circuits. Tubing systems shall be tested for leaks. Mechanical control devices shall be adjusted to operate as specified. HVAC control panels shall be pretested off-site as a functioning assembly ready for field connections, calibration, adjustment, and commissioning of the operational HVAC control system. Control parameters and logic (virtual) points including control loop setpoints, gain constants, and integral constraints, shall be adjusted before the system is placed on line. Communications requirements shall be as indicated. Written notification of any planned commissioning or testing of the HVAC Control systems shall be given to the Government at least 14 calendar days in advance.

3.4.3 Performance Verification Test

The Contractor shall demonstrate compliance of the HVAC control system with the contract documents. Using test plans and procedures previously approved by the Government, the Contractor shall demonstrate all physical and functional requirements of the project. The performance verification test shall show, step-by-step, the actions and results demonstrating that the control systems perform in accordance with the sequences of operation. The performance verification test shall not be started until after receipt by the Contractor of written permission by the Government, based on Government approval of the Commissioning Report and completion of balancing. The tests shall not be conducted during scheduled seasonal off periods of base heating and cooling systems.

3.4.4 Endurance Test

The endurance test shall be used to demonstrate the specified overall system reliability requirement of the completed system. The endurance test shall not be started until the Government notifies the Contractor in writing that the performance verification test is satisfactorily completed.

The Government may terminate the testing at any time when the system fails to perform as specified. Upon termination of testing by the Government or by the Contractor, the Contractor shall commence an assessment period as described for Phase II. Upon successful completion of the endurance test, the Contractor shall deliver test reports and other documentation as specified to the Government prior to acceptance of the system.

a. Phase I (Testing). The test shall be conducted 24 hours per day, 7 days per week, for 15 consecutive calendar days, including holidays, and the system shall operate as specified. The Contractor shall make no repairs during this phase of testing unless authorized by the Government in writing.

b. Phase II (Assessment). After the conclusion of Phase I, the Contractor shall identify failures, determine causes of failures, repair failures, and deliver a written report to the Government. The report shall explain in detail the nature of each failure, corrective action taken, results of tests performed, and shall recommend the point at which testing should be resumed. After delivering the written report, the Contractor shall convene a test review meeting at the jobsite to present the results and recommendations to the Government. As a part of this test review meeting, the Contractor shall demonstrate that all failures have been corrected by performing appropriate portions of the performance verification test. Based on the Contractor's report and test review meeting, the Government may require that the Phase I test be totally or partially rerun. After the conclusion of any retesting which the Government may require, the Phase II assessment shall be repeated as if Phase I had just been completed.

3.4.5 Posted and Panel Instructions

Posted and Panel Instructions, showing the final installed conditions, shall be provided for each system. The posted instructions shall consist of laminated half-size drawings and shall include the control system schematic, equipment schedule, sequence of operation, wiring diagram, communication network diagram, and valve and damper schedules. The posted instructions shall be permanently affixed, by mechanical means, to a wall near the control panel. Panel instructions shall consist of laminated letter-size sheets and shall include a Routine Maintenance Checklist and as-built configuration check sheets. Panel instructions and one copy of the Operation and Maintenance Manuals, previously described herein, shall be placed inside each control panel or permanently affixed, by mechanical means, to a wall near the panel.

3.5 TRAINING

3.5.1 Training Course Requirements

A training course shall be conducted for 5 operating staff members designated by the Contracting Officer in the maintenance and operation of the system, including specified hardware and software. The training period, for a total of 32 hours of normal working time, shall be conducted within 30 days after successful completion of the performance verification test. The training course shall be conducted at the project site. Audiovisual equipment and 5 sets of all other training materials and supplies shall be provided. A training day is defined as 8 hours of classroom instruction, including two 15 minute breaks and excluding lunchtime, Monday through Friday, during the daytime shift in effect at the training facility.

3.5.2 Training Course Content

For guidance in planning the required instruction, the Contractor shall assume that attendees will have a high school education or equivalent, and are familiar with HVAC systems. The training course shall cover all of the material contained in the Operating and Maintenance Instructions, the layout and location of each HVAC control panel, the layout of one of each type of unitary equipment and the locations of each, the location of each control device external to the panels, the location of the compressed air station, preventive maintenance, troubleshooting, diagnostics, calibration, adjustment, commissioning, tuning, and repair procedures. Typical systems and similar systems may be treated as a group, with instruction on the physical layout of one such system. The results of the performance verification test and the calibration, adjustment and commissioning report shall be presented as benchmarks of HVAC control system performance by which to measure operation and maintenance effectiveness.

-- End of Section --

SECTION 16415A

ELECTRICAL WORK, INTERIOR
11/01

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C12.1	(1995) Code for Electricity Metering
ANSI C12.10	(1997) Electromechanical Watthour Meters
ANSI C12.11	(1987; R 1993) Instrument Transformers for Revenue Metering, 10 kV BIL through 350 kV BIL (0.6 kV NSV through 69 kV NSV)
ANSI C12.4	(1984; R 1996) Mechanical Demand Registers
ANSI C135.30	(1988) Zinc-Coated Ferrous Ground Rods for Overhead or Underground Line Construction
ANSI C37.16	(2000) Low-Voltage Power Circuit Breakers and AC Power Circuit Protectors - Preferred Ratings, Related Requirements, and Application Recommendations
ANSI C39.1	(1981; R 1992) Requirements for Electrical Analog Indicating Instruments
ANSI C57.12.10	(1988) Safety Requirements for Transformers 230 kV and Below 833/958 Through 8333/10417 kVA, Single-Phase, and 750/862 Through 60 000/80 000/ 100 000 kVA, Three-Phase Without Load Tap Charging; and 3750/4687 Through 60 000/80 000/100/000 kVA With Load Tap Charging
ANSI C57.12.13	(1982) Conformance Requirements for Liquid-Filled Transformers Used in Unit Installations, Including Unit Substations
ANSI C57.12.27	(1982) Conformance Requirements for Liquid-Filled Distribution Transformers Used in Pad-Mounted Installations, Including Unit Substations

ANSI C57.12.50	(1981; R 1989) Ventilated Dry-Type Distribution Transformers 1 to 500 kVA, Single-Phase; and 15 to 500 kVA, Three-Phase with High-Voltage 601 to 34 500 Volts, Low-Voltage 120 to 600 Volts
ANSI C57.12.51	(1981; R 1989) Ventilated Dry-Type Power Transformers, 501 kVA and Larger, Three-Phase, with High-Voltage 601 to 34 500 Volts, Low-Voltage 208Y/120 to 4160 Volts
ANSI C57.12.52	(1981; R 1989) Sealed Dry-Type Power Transformers, 501 kVA and Larger, Three-Phase with High-Voltage 601 to 34 500 Volts, Low-Voltage 208Y/120 to 4160 Volts
ANSI C57.12.70	(1978; R 1993) Terminal Markings and Connections for Distribution and Power Transformers
ANSI C78.1	(1991; C78.1a; R 1996) Fluorescent Lamps - Rapid-Start Types - Dimensional and Electrical Characteristics
ANSI C78.1350	(1990) Electric Lamps - 400-Watt, 100-Volt, S51 Single-Ended High-Pressure Sodium Lamps
ANSI C78.1351	(1989) Electric Lamps - 250-Watt, 100-Volt S50 Single-Ended High-Pressure Sodium Lamps
ANSI C78.1352	(1990) Electric Lamps - 1000-Watt, 250-Volt, S52 Single-Ended High-Pressure Sodium Lamps
ANSI C78.1355	(1989) Electric Lamps - 150-Watt, 55-Volt S55 High-Pressure Sodium Lamps
ANSI C78.1375	(1996) 400-Watt, M59 Single-Ended Metal-Halide Lamps
ANSI C78.1376	(1996) 1000-Watt, M47 Metal-Halide Lamps
ANSI C78.20	(1995) Electric Lamps - Characteristics of Incandescent Lamps A, G, PS, and Similar Shapes with E26 Medium Screw Bases
ANSI C78.21	(1995) Physical and Electrical Characteristics - Incandescent Lamps - PAR and R Shapes

ANSI C78.2A	(1991) 18 & 26- Watt, Compact Fluorescent Quad Tube Lamps
ANSI C78.2B	(1992) 9 & 13-Watt, Compact Fluorescent Quad Tube Lamps
ANSI C80.5	(1995) Rigid Aluminum Conduit
ANSI C82.1	(1997) Specifications for Fluorescent Lamp Ballasts
ANSI C82.4	(1992) Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type)

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM B 1	(1995) Hard-Drawn Copper Wire
ASTM B 8	(1999) Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D 4059	(1996) Analysis of Polychlorinated Biphenyls in Insulating Liquids by Gas Chromatography
ASTM D 709	(2000) Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(1997) National Electrical Safety Code
IEEE C37.13	(1990; R 1995) Low-Voltage AC Power Circuit Breakers Used in Enclosures
IEEE C37.20.1	(1993) Metal-Enclosed Low-Voltage Power Circuit-Breaker Switchgear
IEEE C57.100	(1999) Test Procedure for Thermal Evaluation of Oil-Immersed Distribution Transformers \savail only as part of Distribution, Power, and Regulating Transformers Stds Collection
IEEE C57.12.00	(1993) Standard General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers
IEEE C57.12.80	(1996) Terminology for Power and Distribution Transformers \savail only as part of Distribution, Power, and Regulating Transformer Stds Collection
IEEE C57.12.90	1999) Test Code for Liquid-Immersed

Distribution, Power, and Regulating
Transformers and Guide for Short-Circuit
Testing of Distribution and Power
Transformers \ \$avail only as part of
Distribution, Power, and Regulating
Transformers Stds Collection

IEEE C57.13	(1993) Instrument Transformers
IEEE C57.98	(1993) Guide for Transformer Impulse Tests \ \$avail only as part of Distribution, Power, and Regulating Transformers Stds Collection
IEEE C62.41	(1991; R 1995) Surge Voltages in Low-Voltage AC Power Circuits
IEEE Std 242	(1986; R 1991) Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems
IEEE Std 399	(1997) Recommended Practice for Industrial and Commercial Power Systems Analysis
IEEE Std 81	(1983) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System (Part 1)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(1997) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA AB 1	(1993) Molded Case Circuit Breakers and Molded Case Switches
NEMA BU 1	(1994) Busways
NEMA FU 1	(1986) Low Voltage Cartridge Fuses
NEMA ICS 1	(1993) Industrial Control and Systems
NEMA ICS 2	(1993) Industrial Controls and Systems Controllers, Contactors, and Overload Relays Rated Not More Than 2,000 Volts AC or 750 Volts DC
NEMA ICS 3	(1993) Industrial Control and Systems Factory Built Assemblies
NEMA ICS 6	(1993) Industrial Control and Systems, Enclosures

NEMA LE 4	(1987) Recessed Luminaires, Ceiling Compatibility
NEMA MG 1	(1998) Motors and Generators
NEMA MG 10	(1994) Energy Management Guide for Selection and Use of Polyphase Motors
NEMA OS 1	(1996) Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports
NEMA OS 2	(1998) Nonmetallic Outlet Boxes, Device Boxes, Covers and Box Supports
NEMA PB 1	(1995) Panelboards
NEMA PB 2	(1995) Deadfront Distribution Switchboards
NEMA PE 5	(1996) Utility Type Battery Chargers
NEMA RN 1	(1998) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA SG 3	(1995) Power Switching Equipment
NEMA ST 20	(1992) Dry-Type Transformers for General Applications
NEMA TC 13	(1993) Electrical Nonmetallic Tubing (ENT)
NEMA TC 2	(1998) Electrical Polyvinyl Chloride (PVC) Tubing (EPT) and Conduit (EPC-40 and EPC-80)
NEMA VE 1	(1996) Metal Cable Tray Systems
NEMA WD 1	(1999) General Requirements for Wiring Devices
NEMA WD 6	(1997) Wiring Devices - Dimensional Requirements

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2000) Life Safety Code
NFPA 70	(1999) National Electrical Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

47 CFR 18	Industrial, Scientific, and Medical Equipment
-----------	---

UNDERWRITERS LABORATORIES (UL)

UL 1	(2000) Flexible Metal Conduit
UL 1004	(1994; Rev thru Nov 1999) Electric Motors
UL 1010	(1995; Rev thru Mar 1999) Receptical-Plug Combinations for Use in Hazardous (Classified) Locations
UL 1022	(1998) Line Isolation Monitors
UL 1029	(1994; Rev thru Dec 1997) High-Intensity-Discharge Lamp Ballasts
UL 1047	(1995; Rev Jul 1998) Isolated Power Systems Equipment
UL 1236	(1994; Rev thru Mar 1999) Battery Chargers for Charging Engine-Starter Batteries
UL 1242	(1996; Rev Mar 1998) Intermediate Metal Conduit
UL 1449	(1996; Rev thru Dec 1999) Transient Voltage Surge Suppressors
UL 1564	(1993; R Sep 1998) Industrial Battery Chargers
UL 1569	(1999; Rev thru Jan 2000) Metal-Clad Cables
UL 1570	(1995; Rev thru Nov 1999) Fluorescent Lighting Fixtures
UL 1571	(1995; Rev thru Nov 1999) Incandescent Lighting Fixtures
UL 1572	(1995; Rev thru Nov 1999) High Intensity Discharge Lighting Fixtures
UL 1660	(2000) Liquid-Tight Flexible Nonmetallic Conduit
UL 198B	(1995) Class H Fuses
UL 198C	(1986; Rev thru Feb 1998) High-Interrupting-Capacity Fuses, Current-Limiting Types
UL 198D	(1995) Class K Fuses
UL 198E	(1988; Rev Jul 1988) Class R Fuses

UL 198G	(1988; Rev May 1988) Fuses for Supplementary Overcurrent Protection
UL 198H	(1988; Rev thru Nov 1993) Class T Fuses
UL 198L	(1995; Rev May 1995) D-C Fuses for Industrial Use
UL 20	(1995; Rev thru Oct 1998) General-Use Snap Switches
UL 360	(1996; Rev thru Oct 1997) Liquid-Tight Flexible Steel Conduit
UL 4	(1996) Armored Cable
UL 44	(1999) Thermoset-Insulated Wires and Cables
UL 467	(1993; Rev thru Apr 1999) Grounding and Bonding Equipment
UL 486A	(1997; Rev thru Dec 1998) Wire Connectors and Soldering Lugs for Use with Copper Conductors
UL 486B	(1997; Rev Jun 1997) Wire Connectors for Use with Aluminum Conductors
UL 486C	(1997; Rev thru Aug 1998) Splicing Wire Connectors
UL 486E	(1994; Rev thru Feb 1997) Equipment Wiring Terminals for Use with Aluminum and/or Copper Conductors
UL 489	(1996; Rev thru Dec 1998) Molded-Case Circuit Breakers, Molded-Case Switches, and Circuit-Breaker Enclosures
UL 498	(1996; Rev thru Jan 1999) Attachment Plugs and Receptacles
UL 5	(1996) Surface Metal Raceways and Fittings
UL 50	(1995; Rev thru Nov 1999) Enclosures for Electrical Equipment
UL 506	(1994; R Oct 1997) Specialty Transformers
UL 508	(1999) Industrial Control Equipment
UL 510	(1994; Rev thru Apr 1998) Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape

UL 512	(1993; Rev thru Mar 1999) Fuseholders
UL 514A	(1996; Rev Dec 1999) Metallic Outlet Boxes
UL 514B	(1997; Rev Oct 1998) Fittings for Cable and Conduit
UL 514C	(1996; Rev thru Dec 1999) Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 542	(1999) Lampholders, Starters, and Starter Holders for Fluorescent Lamps
UL 6	(1997) Rigid Metal Conduit
UL 651	(1995; Rev thru Oct 1998) Schedule 40 and 80 Rigid PVC Conduit
UL 651A	(1995; Rev thru Apr 1998) Type EB and A Rigid PVC Conduit and HDPE Conduit
UL 67	(1993; Rev thru Oct 1999) Panelboards
UL 674	(1994; Rev thru Oct 1998) Electric Motors and Generators for Use in Division 1 Hazardous (Classified) Locations
UL 698	(1995; Rev thru Mar 1999) Industrial Control Equipment for Use in Hazardous (Classified) Locations
UL 719	(1996; Rev Jul 1999) Nonmetallic-Sheathed Cables
UL 797	(1993; Rev thru Mar 1997) Electrical Metallic Tubing
UL 817	(1994; Rev thru May 1999) Cord Sets and Power-
UL 83	(1998; Rev thru Sep 1999) Thermoplastic-Insulated Wires and Cables
UL 844	(1995; Rev thru Mar 1999) Electric Lighting Fixtures for Use in Hazardous (Classified) Locations
UL 845	(1995; Rev thru Nov 1999) Motor Control Centers
UL 854	(1996; Rev Oct 1999) Service-Entrance Cables

UL 857	(1994; Rev thru Dec 1999) Busways and Associated Fittings
UL 869A	(1998) Reference Standard for Service Equipment
UL 877	(1993; Rev thru Nov 1999) Circuit Breakers and Circuit-Breaker Enclosures for Use in Hazardous (Classified) Locations
UL 886	(1994; Rev thru Apr 1999) Outlet Boxes and Fittings for Use in Hazardous (Classified) Locations
UL 891	(1994; Rev thru Jan 1995) Dead-Front Switchboards
UL 916	(1998) Energy Management Equipment
UL 924	(1995; Rev thru Oct 97) Emergency Lighting and Power Equipment
UL 935	(1995; Rev thru Oct 1998) Fluorescent-Lamp Ballasts
UL 943	(1993; Rev thru May 1998) Ground-Fault Circuit-Interrupters
UL 98	(1994; Rev thru Jun 1998) Enclosed and Dead-Front Switches
UL Elec Const Dir	(1999) Electrical Construction Equipment Directory

1.2 GENERAL

1.2.1 Rules

The installation shall conform to the requirements of NFPA 70 and NFPA 101, unless more stringent requirements are indicated or shown.

1.2.2 Coordination

The drawings indicate the extent and the general location and arrangement of equipment, conduit, and wiring. The Contractor shall become familiar with all details of the work and verify all dimensions in the field so that the outlets and equipment shall be properly located and readily accessible.

Lighting fixtures, outlets, and other equipment and materials shall be carefully coordinated with mechanical or structural features prior to installation and positioned according to architectural reflected ceiling plans; otherwise, lighting fixtures shall be symmetrically located according to the room arrangement when uniform illumination is required, or asymmetrically located to suit conditions fixed by design and shown.

Raceways, junction and outlet boxes, and lighting fixtures shall not be supported from sheet metal roof decks. If any conflicts occur necessitating departures from the drawings, details of and reasons for departures shall be submitted and approved prior to implementing any change. The Contractor shall coordinate the electrical requirements of the mechanical work and provide all power related circuits, wiring, hardware and structural support, even if not shown on the drawings.

1.2.3 Special Environments

Wiring, Fixtures, and equipment in designated locations shall conform to NFPA 70 requirements for installation in damp or wet locations.

1.2.4 Hazardous Locations

Wiring and equipment in locations indicated shall be of the classes, groups, divisions, and suitable for the operating temperature; as indicated.

1.2.5 Ducts, Plenums and Other Air-Handling Spaces

Wiring and equipment in ducts, plenums and other air-handling spaces shall be installed using materials and methods in conformance with NFPA 70 unless more stringent requirements are indicated in this specification or on the contract drawings.

1.3 Standard Products

Material and equipment shall be a standard product of a manufacturer regularly engaged in the manufacture of the product and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening.

1.4 Nameplates

1.4.1 Identification Nameplates

Major items of electrical equipment and major components shall be permanently marked with an identification name to identify the equipment by type or function and specific unit number as indicated. Designation of motors shall coincide with their designation in the motor control center or panel. Unless otherwise specified, identification nameplates shall be made of laminated plastic in accordance with ASTM D 709 with black outer layers and a white core. Edges shall be chamfered. Plates shall be fastened with black-finished round-head drive screws, except motors, or approved nonadhesive metal fasteners. When the nameplate is to be installed on an irregular-shaped object, the Contractor shall devise an approved support suitable for the application and ensure the proper installation of the supports and nameplates. In all instances, the nameplate shall be installed in a conspicuous location. At the option of the Contractor, the equipment manufacturer's standard embossed nameplate material with black paint-filled letters may be furnished in lieu of laminated plastic. The front of each panelboard, motor control center, switchgear, and switchboard shall have a nameplate to indicate the phase letter, corresponding color and arrangement of the phase conductors. The following equipment, as a

minimum, shall be provided with identification nameplates:

Minimum 6.4 mm High Letters	Minimum 3.2 mm High Letters
Panelboards	Control Power Transformers
Starters	Control Devices
Safety Switches	Instrument Transformers
Motor Control Centers	
Transformers	
Equipment Enclosures	
Switchgear	
Switchboards	
Motors	

Each panel, section, or unit in motor control centers, switchgear or similar assemblies shall be provided with a nameplate in addition to nameplates listed above, which shall be provided for individual compartments in the respective assembly, including nameplates which identify "future," "spare," and "dedicated" or "equipped spaces."

1.5 As-Built Drawings

Following the project completion or turnover, within 30 days the Contractor shall furnish 2 sets of as-built drawings to the Contracting Officer.

1.6 Recessed Light Fixtures (RLF) Option

The Contractor has the option to substitute inch-pound (I-P) RLF to metric RLF. This option shall be coordinated with Section 09510 ACOUSTICAL CEILINGS.

1.7 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Interior Electrical Equipment; G, RE.

Detail drawings consisting of equipment drawings, illustrations, schedules, instructions, diagrams, and other information necessary to define the installation. Detail drawings shall show the rating of items and systems and how the components of an item and system are assembled, function together, and how they will be installed on the project. Data and drawings for component parts of an item or system shall be coordinated and submitted as a unit. Data and drawings shall be coordinated and included in a single submission.

Multiple submissions for the same equipment or system are not acceptable except where prior approval has been obtained from the Contracting Officer. In such cases, a list of data to be submitted later shall be included with the first submission. Detail drawings shall show physical arrangement, construction details, connections, finishes, materials used in fabrication, provisions for conduit or busway entrance, access requirements for installation and maintenance, physical size, electrical characteristics, foundation and support details, and equipment weight. Drawings shall be drawn to scale and/or dimensioned. Optional items shall be clearly identified as included or excluded. Detail drawings shall as a minimum include:

- a. Transformers.
- b. Switchgear.
- c. Battery system including calculations for the battery and charger.
- d. Voltage regulators.
- e. Grounding resistors.
- f. Motors and rotating machinery.
- g. Motor control centers.
- h. Busway systems.
- i. Single line electrical diagrams including primary, metering, sensing and relaying, control wiring, and control logic.
- j. Sway bracing for suspended luminaires.

Structural drawings showing the structural or physical features of major equipment items, components, assemblies, and structures, including foundations or other types of supports for equipment and conductors. These drawings shall include accurately scaled or dimensioned outline and arrangement or layout drawings to show the physical size of equipment and components and the relative arrangement and physical connection of related components. Weights of equipment, components and assemblies shall be provided when required to verify the adequacy of design and proposed construction of foundations or other types of supports. Dynamic forces shall be stated for switching devices when such forces must be considered in the design of support structures. The appropriate detail drawings shall show the provisions for leveling, anchoring, and connecting all items during installation, and shall include any recommendations made by the manufacturer.

Electrical drawings including single-line and three-line diagrams, and schematics or elementary diagrams of each electrical system; internal wiring and field connection diagrams of each

electrical device when published by the manufacturer; wiring diagrams of cabinets, panels, units, or separate mountings; interconnection diagrams that show the wiring between separate components of assemblies; field connection diagrams that show the termination of wiring routed between separate items of equipment; internal wiring diagrams of equipment showing wiring as actually provided for this project. Field wiring connections shall be clearly identified.

If departures from the contract drawings are deemed necessary by the Contractor, complete details of such departures, including changes in related portions of the project and the reasons why, shall be submitted with the detail drawings. Approved departures shall be made at no additional cost to the Government.

SD-03 Product Data

Manufacturer's Catalog; G, RE.

Data composed of catalog cuts, brochures, circulars, specifications, product data, and printed information in sufficient detail and scope to verify compliance with the requirements of the contract documents.

Material, Equipment, and Fixture Lists; G, RE.

A complete itemized listing of equipment and materials proposed for incorporation into the work. Each entry shall include an item number, the quantity of items proposed, and the name of the manufacturer of each item.

Installation Procedures; G, RE.

Installation procedures for rotating equipment, transformers, switchgear, battery systems, voltage regulators, and grounding resistors. Procedures shall include diagrams, instructions, and precautions required to install, adjust, calibrate, and test devices and equipment.

As-Built Drawings; G, RE.

The as-built drawings shall be a record of the construction as installed. The drawings shall include all the information shown on the contract drawings, deviations, modifications, and changes from the contract drawings, however minor. The as-built drawings shall be kept at the job site and updated daily. The as-built drawings shall be a full-sized set of prints marked to reflect all deviations, changes, and modifications. The as-built drawings shall be complete and show the location, size, dimensions, part identification, and other information. Additional sheets may be added. The as-built drawings shall be jointly inspected for accuracy and completeness by the Contractor's quality control

representative and by the Contracting Officer prior to the submission of each monthly pay estimate. Upon completion of the work, the Contractor shall submit three full sized sets of the marked prints to the Contracting Officer for approval. If upon review, the as-built drawings are found to contain errors and/or omissions, they will be returned to the Contractor for correction.

The Contractor shall correct and return the as-built drawings to the Contracting Officer for approval within ten calendar days from the time the drawings are returned to the Contractor.

Onsite Tests; G, G.

A detailed description of the Contractor's proposed procedures for on-site tests.

SD-06 Test Reports

Factory Test Reports; G, RE.

Six copies of the information described below in 216 x 280 mm binders having a minimum of 5 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs.

- a. A list of equipment used, with calibration certifications.
- b. A copy of measurements taken.
- c. The dates of testing.
- d. The equipment and values to be verified.
- e. The conditions specified for the test.
- f. The test results, signed and dated.
- g. A description of adjustments made.

Field Test Plan; G, RE.

A detailed description of the Contractor's proposed procedures for onsite test submitted 30 days prior to testing the installed system. No field test will be performed until the test plan is approved. The test plan shall consist of complete field test procedures including tests to be performed, test equipment required, and tolerance limits.

Field Test Reports; G, RE.

Six copies of the information described below in 216 x 280 mm binders having a minimum of 5 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers

with tabs.

- a. A list of equipment used, with calibration certifications.
- b. A copy of measurements taken.
- c. The dates of testing.
- d. The equipment and values to be verified.
- e. The conditions specified for the test.
- f. The test results, signed and dated.
- g. A description of adjustments made.
- h. Final position of controls and device settings.

SD-07 Certificates

Materials and Equipment; G, RE.

The label or listing of the Underwriters Laboratories, Inc., will be accepted as evidence that the materials or equipment conform to the applicable standards of that agency. In lieu of this label or listing, a statement from a nationally recognized, adequately equipped testing agency indicating that the items have been tested in accordance with required procedures and that the materials and equipment comply with all contract requirements will be accepted. However, materials and equipment installed in hazardous locations must bear the UL label unless the data submitted from other testing agency is specifically approved in writing by the Contracting Officer. Items which are required to be listed and labeled in accordance with Underwriters Laboratories must be affixed with a UL label that states that it is UL listed. No exceptions or waivers will be granted to this requirement. Materials and equipment will be approved based on the manufacturer's published data.

For other than equipment and materials specified to conform to UL publications, a manufacturer's statement indicating complete compliance with the applicable standard of the American Society for Testing and Materials, National Electrical Manufacturers Association, or other commercial standard, is acceptable.

1.8 WORKMANSHIP

Materials and equipment shall be installed in accordance with NFPA 70, recommendations of the manufacturer, and as shown.

1.9 SEISMIC REQUIREMENTS

Seismic details shall conform to Sections 13080 SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT and 16070 SEISMIC PROTECTION FOR ELECTRICAL

EQUIPMENT

PART 2 PRODUCTS

Products shall conform to the respective publications and other requirements specified below. Materials and equipment not listed below shall be as specified elsewhere in this section. Items of the same classification shall be identical including equipment, assemblies, parts, and components.

2.1 CABLES AND WIRES

Conductors No. 8 AWG and larger diameter shall be stranded. Conductors No. 10 AWG and smaller diameter shall be solid, except that conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3, shall be stranded unless specifically indicated otherwise. Conductor sizes and ampacities shown are based on copper, unless indicated otherwise. All conductors shall be copper.

2.1.1 Equipment Manufacturer Requirements

When manufacturer's equipment requires copper conductors at the terminations or requires copper conductors to be provided between components of equipment, provide copper conductors or splices, splice boxes, and other work required to meet manufacturer's requirements.

2.1.2 Aluminum Conductors

Aluminum conductors shall not be used.

2.1.3 Insulation

Unless indicated otherwise, or required by NFPA 70, power and lighting wires shall be 600-volt, Type THWN, THHN, or THW conforming to UL 83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits shall be Type TW, THW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.1.4 Bonding Conductors

ASTM B 1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B 8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

2.1.5 Service Entrance Cables

Service entrance (SE) and underground service entrance (USE) cables, UL 854.

2.1.6 Non-metallic Sheathed Cable

UL 719, type NM or NMC.

2.1.7 Metal-Clad Cable

UL 1569; NFPA 70, Type MC cable.

2.1.8 Armored Cable

UL 4; NFPA 70, Type AC cable.

2.1.9 Mineral-Insulated, Metal-Sheathed Cable

UL listed NFPA 70, type MI cable. Sheathing containing asbestos fibers shall not be used.

2.1.10 Flat Conductor Cable

UL listed NFPA 70, type FCC.

2.1.11 Tray Cable or Power Limited Tray Cable

UL listed; Type TC or PLTC.

2.1.12 Cord Sets and Power-Supply Cords

UL 817.

2.2 CABLE TRAYS

NEMA VE 1 cable trays shall form a wireway system, and shall be as indicated in the drawings. Cable trays shall be constructed of zinc-coated steel. Trays shall include splice and end plates, dropouts, and miscellaneous hardware. Edges, fittings, and hardware shall be finished free from burrs and sharp edges. Fittings shall have not less than the load-carrying ability of straight tray sections and shall have manufacturer's minimum standard radius. Radius of bends shall be 610 mm.

2.2.1 Wire Basket

Wire basket size shall be as indicated on the drawings. Wire basket system shall be made of high strength steel wires and formed into a standard 51mm x 102mm wire mesh pattern with intersecting wires welded together. All wire ends along systems sides shall be rounded during manufacturing for safety of cables and installers.

2.2.2 Ladder

Ladder-type cable trays shall be of nominal 300 mm width. Rung spacing shall be on 230 mm maximum centers. Ladder type tray will only be used in communications rooms where cable rack is indicated.

2.3 TRANSIENT VOLTAGE SURGE PROTECTION

Transient voltage surge suppressors shall be provided in the main switchboard or panelboard of each facility. Transient voltage surge

suppressor shall be connected directly to the bus or be connected via a branch breaker. All installation methods must insure compliance with the peak let through voltages indicated below. Surge suppressors shall meet the requirements of IEEE C62.41 and be UL listed and labeled as having been tested in accordance with UL 1449. Surge suppressor ratings shall be 480 OR 208 volts rms, operating voltage; 60 Hz; 3-phase; 4 wire with ground; transient suppression voltage (peak let-through voltage) of 400 volts for IEEE Category C1, 470 volts for IEEE Category C3 and 150 volts for IEEE Cat B3 waves. Fuses shall not be used as surge suppression.

2.4 CIRCUIT BREAKERS

2.4.1 MOLDED-CASE CIRCUIT BREAKERS

Molded-case circuit breakers shall conform to NEMA AB 1 and UL 489 and UL 877 for circuit breakers and circuit breaker enclosures located in hazardous (classified) locations. Circuit breakers may be installed in panelboards, switchboards, enclosures, motor control centers, or combination motor controllers.

2.4.1.1 Construction

Circuit breakers shall be suitable for mounting and operating in any position. Lug shall be listed for copper conductors only in accordance with UL 486E. Single-pole circuit breakers shall be full module size with not more than one pole per module. Multi-pole circuit breakers shall be of the common-trip type having a single operating handle such that an overload or short circuit on any one pole will result in all poles opening simultaneously. Sizes of 100 amperes or less may consist of single-pole breakers permanently factory assembled into a multi-pole unit having an internal, mechanical, nontamperable common-trip mechanism and external handle ties. All circuit breakers shall have a quick-make, quick-break overcenter toggle-type mechanism, and the handle mechanism shall be trip-free to prevent holding the contacts closed against a short-circuit or sustained overload. All circuit breaker handles shall assume a position between "ON" and "OFF" when tripped automatically. All ratings shall be clearly visible.

2.4.1.2 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. The interrupting rating of the circuit breakers shall be at least equal to the available short-circuit current at the line terminals of the circuit breaker and correspond to the UL listed integrated short-circuit current rating specified for the panelboards and switchboards. Molded-case circuit breakers shall have nominal voltage ratings, maximum continuous-current ratings, and maximum short-circuit interrupting ratings in accordance with NEMA AB 1. Ratings shall be coordinated with system X/R ratio.

2.4.1.3 Thermal-Magnetic Trip Elements

Thermal magnetic circuit breakers shall be provided as shown. Automatic operation shall be obtained by means of thermal-magnetic tripping devices

located in each pole providing inverse time delay and instantaneous circuit protection. The instantaneous magnetic trip shall be adjustable and accessible from the front of all circuit breakers on frame sizes above 150 amperes.

2.4.2 Solid-State Trip Elements

Solid-state circuit breakers shall be provided for all switchboard main breakers and any feeder breakers 400 amps or larger. All electronics shall be self-contained and require no external relaying, power supply, or accessories. Printed circuit cards shall be treated to resist moisture absorption, fungus growth, and signal leakage. All electronics shall be housed in an enclosure which provides protection against arcs, magnetic interference, dust, and other contaminants. Solid-state sensing shall measure true RMS current with error less than one percent on systems with distortions through the 13th harmonic. Peak or average actuating devices are not acceptable. Current sensors shall be torodial construction, encased in a plastic housing filled with epoxy to protect against damage and moisture and shall be integrally mounted on the breaker. Where indicated on the drawings, circuit breaker frames shall be rated for 100 percent continuous duty. Circuit breakers shall have tripping features as shown on the drawings and as described below:

- a. Long-time current pick-up, adjustable from 50 percent to 100 percent of continuous current rating.
- b. Adjustable long-time delay.
- c. Short-time current pick-up, adjustable from 1.5 to 9 times long-time current setting.
- d. Adjustable short-time delay.
- e. Short-time $I^2 t$ switch.
- f. Instantaneous current pick-up, adjustable from 1.5 to 9 times long-time current setting.
- j. Overload and short-time trip indicators shall be provided.

2.4.3 Arc Fault Circuit Interrupters

Breakers equipped with arc fault circuit interrupters shall be provided as indicated.

2.4.4 SWD Circuit Breakers

Circuit breakers rated 15 amperes and intended to switch 277 volts or less fluorescent lighting loads shall be marked "SWD."

2.4.5 HACR Circuit Breakers

Circuit breakers 60 amperes or below, 240 volts, 1-pole or 2-pole, intended to protect multi-motor and combination-load installations involved in heating, air conditioning, and refrigerating equipment shall be marked "Listed HACR Type."

2.4.6 Ground Fault Circuit Interrupters

UL 943. Breakers equipped with ground fault circuit interrupters shall have ground fault class, interrupting capacity, and voltage and current ratings as indicated.

2.5 CONDUIT AND TUBING

2.5.1 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797

2.5.2 Electrical Nonmetallic Tubing (ENT)

NEMA TC 13.

2.5.3 Electrical Plastic Tubing and Conduit

NEMA TC 2.

2.5.4 Flexible Conduit, Steel and Plastic

General-purpose type, UL 1; liquid tight, UL 360, and UL 1660.

2.5.5 Intermediate Metal Conduit

UL 1242.

2.5.6 PVC Coated Rigid Steel Conduit

NEMA RN 1.

2.5.7 Rigid Aluminum Conduit

ANSI C80.5 and UL 6.

2.5.8 Rigid Metal Conduit

UL 6.

2.5.9 Rigid Plastic Conduit

NEMA TC 2, UL 651 and UL 651A.

2.5.10 Surface Metal Electrical Raceways and Fittings

UL 5.

2.6 CONDUIT AND DEVICE BOXES AND FITTINGS

2.6.1 Boxes, Metallic Outlet

NEMA OS 1 and UL 514A.

2.6.2 Boxes, Nonmetallic, Outlet and Flush-Device Boxes and Covers

NEMA OS 2 and UL 514C.

2.6.3 Boxes, Switch (Enclosed), Surface-Mounted

UL 98.

2.6.4 Fittings for Conduit and Outlet Boxes

UL 514B.

2.6.5 Fittings, PVC, for Use with Rigid PVC Conduit and Tubing

UL 514B.

2.7 CONDUIT COATINGS PLASTIC RESIN SYSTEM

NEMA RN 1, Type A-40.

2.8 CONNECTORS, WIRE PRESSURE

2.8.1 For Use With Copper Conductors

UL 486A.

2.9 ELECTRICAL GROUNDING AND BONDING EQUIPMENT

UL 467.

2.9.1 Ground Rods

Ground rods shall be of copper-clad steel conforming to UL 467 not less than 15.9 mm in diameter by 3.1 meter in length of the sectional type driven full length into the earth.

2.9.2 Ground Bus

The ground bus shall be bare conductor or flat copper in one piece, if practicable.

2.10 ENCLOSURES

NEMA ICS 6 or NEMA 250 unless otherwise specified.

2.10.1 Cabinets and Boxes

Cabinets and boxes with volume greater than 0.0164 cubic meters shall be in accordance with UL 50, hot-dip, zinc-coated, if sheet steel.

2.10.2 Circuit Breaker Enclosures

UL 489.

2.11 LIGHTING FIXTURES, LAMPS, BALLASTS, EMERGENCY EQUIPMENT, CONTROLS AND ACCESSORIES

The following specifications are supported and supplemented by information and details on the drawings. Additional fixtures, if shown, shall conform to this specification. Lamps, lampholders, ballasts, transformers, electronic circuitry and other lighting system components shall be constructed according to industry standards. Equipment shall be tested and listed by a recognized independent testing laboratory for the expected installation conditions. Equipment shall conform to the standards listed below.

2.11.1 Lamps

Lamps shall be constructed to operate in the specified fixture, and shall function without derating life or output as listed in published data. Lamps shall meet the requirements of the Energy Policy Act of 1992.

- a. Incandescent and tungsten halogen lamps shall be designed for 125 volt operation (except for low voltage lamps), shall be rated for minimum life of 2,000 hours, and shall have color temperature between 2,800 and 3,200 degrees Kelvin. Tungsten halogen lamps shall incorporate quartz capsule construction. Lamps shall comply with ANSI C78.20 and sections 238 and 270 of ANSI C78.21.
- b. Fluorescent lamps shall be designed to operate with the ballasts and circuitry of the fixtures in which they will be used. Fluorescent lamps, including spares, shall be manufactured by one manufacturer to provide for color and performance consistency. Fluorescent lamps shall comply with ANSI C78.1. Fluorescent tube lamp efficiencies shall meet or exceed the following requirements.

T8, 32 watts	(4' lamp)	2800 lumens
T12,34 watts	(4' lamp)	2800 lumens
T8,59 watts	(8' lamp)	5700 lumens
T12,60 watts	(8' lamp)	5600 lumens
T8/U,31-32 watts	(U-tube)	2600 lumens
T12/U,34 watts	(U-tube)	2700 lumens

(1) Linear fluorescent lamps, unless otherwise indicated, shall be 1219 mm long 32 watt T8, 265 mA, with minimum CRI of 75. Lamps of other lengths or types shall be used only where specified or shown. Lamps shall deliver rated life when operated on rapid

start ballasts .

2.11.2 Ballasts and Transformers

Ballasts or transformers shall be designed to operate the designated lamps within their optimum specifications, without derating the lamps. Lamp and ballast combinations shall be certified as acceptable by the lamp manufacturer.

- b. Fluorescent ballasts shall comply with ANSI C82.1 and shall be mounted integrally within fluorescent fixture housing unless otherwise shown. Ballasts shall have maximum current crest factor of 1.7; high power factor; Class A sound rating; maximum operating case temperature of 25 degrees C above ambient; and shall be rated Class P. Unless otherwise indicated, the minimum number of ballasts shall be used to serve each individual fixture. A single ballast may be used to serve multiple fixtures if they are continuously mounted, identically controlled and factory manufactured for that installation with an integral wireway.

(2) Electronic fluorescent ballasts shall comply with 47 CFR 18 for electromagnetic interference. Ballasts shall withstand line transients per IEEE C62.41, Category A. Ballasts shall have total harmonic distortion between 10 and 20%; minimum frequency of 20,000Hz; filament voltage between 2.5 and 4.5 volts; maximum starting inrush current of 20 amperes; and shall comply with the minimum Ballast Efficacy Factors shown in the table below. Minimum starting temperature shall be 10 degrees C . Ballasts shall carry a manufacturer's full warranty of three years, including a minimum \$10 labor allowance per ballast.

ELECTRONIC FLUORESCENT BALLAST EFFICACY FACTORS

LAMP TYPE	TYPE OF STARTER & LAMP	NOMINAL OPERATIONAL VOLTAGE	NUMBER OF LAMPS	MINIMUM BALLAST EFFICACY FACTOR
32W T8	rapid	120 or 277 V	1	2.54
	start		2	1.44
	linear &		3	0.93
	U-tubes		4	0.73
34W T12	rapid	120 or 277 V	1	2.64
	start		2	1.41
	linear & U-tubes		3	0.93

ELECTRONIC FLUORESCENT BALLAST EFFICACY FACTORS

59W T8	rapid start linear	120 or 277 V	2	0.80
60W T12	rapid start linear	120 or 277 V	2	0.80

2.11.3 Fixtures

Fixtures shall be in accordance with the size, shape, appearance, finish, and performance shown. Unless otherwise indicated, lighting fixtures shall be provided with housings, junction boxes, wiring, lampholders, mounting supports, trim, hardware and accessories for a complete and operable installation. Recessed housings shall be minimum 20 gauge cold rolled or galvanized steel as shown. Extruded aluminum fixtures shall have minimum wall thickness of 3 mm . Plastic lenses shall be 100% virgin acrylic or as shown. Glass lenses shall be tempered. Heat resistant glass shall be borosilicate type. Conoid recessed reflector cones shall be Alzak with clear specular low iridescent finish.

- a. Incandescent fixtures shall comply with UL 1571. Incandescent fixture specular reflector cone trims shall be integral to the cone and shall be finished to match. Painted trim finishes shall be white with minimum reflectance of 88%.
- b. Fluorescent fixtures shall comply with UL 1570. Recessed ceiling fixtures shall comply with NEMA LE 4. Fixtures shall be plainly marked for proper lamp and ballast type to identify lamp diameter, wattage, color and start type. Marking shall be readily visible to service personnel, but not visible from normal viewing angles. Fluorescent fixture lens frames on recessed and surface mounted troffers shall be one assembly with mitered corners. Parabolic louvers shall have a low iridescent finish and 45 degree cut-off. Louver intersection joints shall be hairline type and shall conceal mounting tabs or other assembly methods. Louvers shall be free from blemishes, lines or defects which distort the visual surface. Integral ballast and wireway compartments shall be easily accessible without the use of special tools. Housings shall be constructed to include grounding necessary to start the lamps. Open fixtures shall be equipped with a sleeve, wire guard, or other positive means to prevent lamps from falling. Medium bi-pin lampholders shall be twist-in type with positive locking position.
- d. Emergency lighting fixtures and accessories shall be constructed and independently tested to meet the requirements of applicable codes. Batteries shall be Nicad or equal with no required maintenance, and shall have a minimum life expectancy of five

years and warranty period of three years.

e. Exit Signs

Exit signs shall be ENERGY STAR compliant, thereby meeting the following requirements. Input power shall be less than 5 watts per face. Letter size and spacing shall adhere to NFPA 101. Luminance contrast shall be greater than 0.8. Average luminance shall be greater than 15 cd/m^2 measured at normal (0 degree) and 45 degree viewing angles. Minimum luminance shall be greater than 8.6 cd/m^2 measured at normal and 45 degree viewing angles. Maximum to minimum luminance shall be less than 20:1 measured at normal and 45 degree viewing angles. The manufacturer warranty for defective parts shall be at least 5 years. Exit signs shall flash when a general evacuation alarm is initiated by the fire alarm system.

2.11.4 Lampholders, Starters, and Starter Holders

UL 542

2.11.5 Ultrasonic, and Passive Infrared Occupancy Sensors

Sensors shall be as specied on the drawings and listed in accordance with UL 916

2.12 INSTRUMENTS, ELECTRICAL INDICATING

ANSI C39.1.

2.13 MOTORS, AC, FRACTIONAL AND INTEGRAL

Motors, ac, fractional and integral kilowatt, 373.0 kW and smaller shall conform to NEMA MG 1 and UL 1004 for motors; NEMA MG 10 for energy management selection of polyphase motors; and UL 674 for use of motors in hazardous (classified) locations. In addition to the standards listed above, motors shall be provided with efficiencies as specified in the table "MINIMUM NOMINAL EFFICIENCIES" below. Motors with power supplied by Variable Frequency Drives shall be a definite purpose inverter fed type in accordance with Part 31, NEMA MG-1.

2.13.1 Rating

The kilowatt rating of motors should be limited to no more than 125 percent of the maximum load being served unless a NEMA standard size does not fall within this range. In this case, the next larger NEMA standard motor size should be used.

2.13.2 Motor Efficiencies

All permanently wired polyphase motors of 746 W or more shall meet the minimum full-load efficiencies as indicated in the following table, and as specified in this specification. Motors of 746 W or more with open, drip

proof or totally enclosed fan cooled enclosures shall be high efficiency type, unless otherwise indicated. Motor efficiencies indicated in the tables apply to general-purpose, single-speed, polyphase induction motors. Applications which require definite purpose, special purpose, special frame, or special mounted polyphase induction motors are excluded from these efficiency requirements. Motors provided as an integral part of motor driven equipment are excluded from this requirement if a minimum seasonal or overall efficiency requirement is indicated for that equipment by the provisions of another section.

MINIMUM NOMINAL MOTOR EFFICIENCIES
OPEN DRIP PROOF MOTORS

<u>kW</u>	<u>1200 RPM</u>	<u>1800 RPM</u>	<u>3600 RPM</u>
0.746	82.5	85.5	80.0
1.12	86.5	86.5	85.5
1.49	87.5	86.5	86.5
2.24	89.5	89.5	86.5
3.73	89.5	89.5	89.5
5.60	91.7	91.0	89.5
7.46	91.7	91.7	90.2
11.2	92.4	93.0	91.0
14.9	92.4	93.0	92.4
18.7	93.0	93.6	93.0
22.4	93.6	93.6	93.0
29.8	94.1	94.1	93.6
37.3	94.1	94.5	93.6
44.8	95.0	95.0	94.1
56.9	95.0	95.0	94.5
74.6	95.0	95.4	94.5
93.3	95.4	95.4	95.0
112.0	95.8	95.8	95.4
149.0	95.4	95.8	95.4
187.0	95.4	96.2	95.8
224.0	95.4	95.0	95.4
261.0	94.5	95.4	95.0
298.0	94.1	95.8	95.0
336.0	94.5	95.4	95.4
373.0	94.5	94.5	94.5

TOTALLY ENCLOSED FAN-COOLED MOTORS

<u>kW</u>	<u>1200 RPM</u>	<u>1800 RPM</u>	<u>3600 RPM</u>
0.746	82.5	85.5	78.5
1.12	87.5	86.5	85.5
1.49	88.5	86.5	86.5
2.24	89.5	89.5	88.5
3.73	89.5	89.5	89.5
5.60	91.7	91.7	91.0
7.46	91.7	91.7	91.7
11.2	92.4	92.4	91.7
14.9	92.4	93.0	92.4

TOTALLY ENCLOSED FAN-COOLED MOTORS

18.7	93.0	93.6	93.0
22.4	93.6	93.6	93.0
29.8	94.1	94.1	93.6
37.3	94.1	94.5	94.1
44.8	94.5	95.0	94.1
56.9	95.0	95.4	94.5
74.6	95.4	95.4	95.0
93.3	95.4	95.4	95.4
112.0	95.8	95.8	95.4
149.0	95.8	96.2	95.8
187.0	95.6	96.2	95.9
224.0	95.4	96.1	95.8
261.0	94.5	96.2	94.8
298.0	94.5	95.8	94.5
336.0	94.5	94.5	94.5
373.0	94.5	94.5	94.5

MINIMUM NOMINAL MOTOR EFFICIENCIES
OPEN DRIP PROOF MOTORS

<u>HP</u>	<u>1200 RPM</u>	<u>1800 RPM</u>	<u>3600 RPM</u>
1	82.5	85.5	80.0
1.5	86.5	86.5	85.5
2	87.5	86.5	86.5
3	89.5	89.5	86.5
5	89.5	89.5	89.5
7.5	91.7	91.0	89.5
10	91.7	91.7	90.2
15	92.4	93.0	91.0
20	92.4	93.0	92.4
25	93.0	93.6	93.0
30	93.6	93.6	93.0
40	94.1	94.1	93.6
50	94.1	94.5	93.6
60	95.0	95.0	94.1
75	95.0	95.0	94.5
100	95.0	95.4	94.5
125	95.4	95.4	95.0
150	95.8	95.8	95.4
200	95.4	95.8	95.4
250	95.4	96.2	95.8
300	95.4	95.0	95.4
350	94.5	95.4	95.0
400	94.1	95.8	95.0
450	94.5	95.4	95.4
500	94.5	94.5	94.5

TOTALLY ENCLOSED FAN-COOLED MOTORS

<u>HP</u>	<u>1200 RPM</u>	<u>1800 RPM</u>	<u>3600 RPM</u>
1	82.5	85.5	78.5

TOTALLY ENCLOSED FAN-COOLED MOTORS

1.5	87.5	86.5	85.5
2	88.5	86.5	86.5
3	89.5	89.5	88.5
5	89.5	89.5	89.5
7.5	91.7	91.7	91.0
10	91.7	91.7	91.7
15	92.4	92.4	91.7
20	92.4	93.0	92.4
25	93.0	93.6	93.0
30	93.6	93.6	93.0
40	94.1	94.1	93.6
50	94.1	94.5	94.1
60	94.5	95.0	94.1
75	95.0	95.4	94.5
100	95.4	95.4	95.0
125	95.4	95.4	95.4
150	95.8	95.8	95.4
200	95.8	96.2	95.8
250	95.6	96.2	95.9
300	95.4	96.1	95.8
350	94.5	96.2	94.8
400	94.5	95.8	94.5
450	94.5	94.5	94.5
500	94.5	94.5	94.5

2.14 MOTOR CONTROLS AND MOTOR CONTROL CENTERS

2.14.1 General

NEMA ICS 1, NEMA ICS 2, NEMA ICS 3 and NEMA ICS 6, and UL 508 and UL 845. Panelboards supplying non-linear loads shall have neutrals sized for 200 percent of rated current.

2.14.2 Motor Starters

Combination starters shall be provided with circuit breakers, .

2.14.3 Thermal-Overload Protection

Each motor of 93 W (1/8 hp) or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller, or shall be mounted in a separate enclosure. Unless otherwise specified, the protective device shall be of the manually reset type. Single or double pole tumbler switches specifically designed for alternating-current operation only may be used as manual controllers for single-phase motors having a current rating not in excess of 80 percent of the switch rating.

2.14.4 Low-Voltage Motor Overload Relays

2.14.4.1 General

Thermal overload relays shall conform to NEMA ICS 2 and UL 508. Overload protection shall be provided either integral with the motor or motor controller, and shall be rated in accordance with the requirements of NFPA 70. Standard units shall be used for motor starting times up to 7 seconds.

2.14.4.2 Construction

Manual reset type thermal relay shall be bimetallic construction. Automatic reset type thermal relays shall be bimetallic construction. Magnetic current relays shall consist of a contact mechanism and a dash pot mounted on a common frame.

2.14.4.3 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. Trip current ratings shall be established by selection of the replaceable overload device and shall not be adjustable. Where the controller is remotely-located or difficult to reach, an automatic reset, non-compensated overload relay shall be provided. Manual reset overload relays shall be provided otherwise, and at all locations where automatic starting is provided. Where the motor is located in a constant ambient temperature, and the thermal device is located in an ambient temperature that regularly varies by more than minus 10 degrees C, an ambient temperature-compensated overload relay shall be provided.

2.14.5 Automatic Control Devices

2.14.5.1 Direct Control

Automatic control devices (such as thermostats, float or pressure switches) which control the starting and stopping of motors directly shall be designed for that purpose and have an adequate kilowatt rating.

2.14.5.2 Pilot-Relay Control

Where the automatic-control device does not have such a rating, a magnetic starter shall be used, with the automatic-control device actuating the pilot-control circuit.

2.14.5.3 Manual/Automatic Selection

- a. Where combination manual and automatic control is specified and the automatic-control device operates the motor directly, a double-throw, three-position tumbler or rotary switch (marked MANUAL-OFF-AUTOMATIC) shall be provided for the manual control.
- b. Where combination manual and automatic control is specified and the automatic-control device actuates the pilot control circuit of a magnetic starter, the magnetic starter shall be provided with a three-position selector switch marked MANUAL-OFF-AUTOMATIC.
- c. Connections to the selector switch shall be such that; only the normal automatic regulatory control devices will be bypassed when the switch is in the Manual position; all safety control devices,

such as low-or high-pressure cutouts, high-temperature cutouts, and motor-overload protective devices, shall be connected in the motor-control circuit in both the Manual and the Automatic positions of the selector switch. Control circuit connections to any MANUAL-OFF-AUTOMATIC switch or to more than one automatic regulatory control device shall be made in accordance with wiring diagram approved by the Contracting Officer unless such diagram is included on the drawings. All controls shall be 120 volts or less unless otherwise indicated.

2.14.6 Variable Speed Drive

a Solid State Drive

Drive shall be solid state with adjustable frequency and voltage, and 3 phase output capable of driving standard NEMA class B induction motors to their full rated output. The drives shall use diode bridge rectifying circuitry for AC to DC conversion and pulse width modulation for DC to AC conversion. The drives shall be designed to be used on variable torque loads and shall be capable of providing sufficient torque to allow the motor to break away from rest upon application of power. The drive shall convert the input voltage to an adjustable frequency output of suitable capacity and waveform to provide stepless speed control of the motor supplied.

b Voltage

Drive shall be capable of converting the supplied nominal voltage in a range of +10% to ?15% at a nominal frequency of 60Hz plus 2Hz to minus 2Hz.

c Circuitry

Drive shall have current limiting circuitry adjustable to 150% of motor full load current to provide soft start, acceleration and running without exceeding motor rated current.

d Power Circuit Design

The power circuit design shall be such that the following conditions can occur without damage to the power circuit components:

- A. Short circuit or ground fault at the drive output terminals.
- B. Commutation failure.
- C. Opening of drive contactor or circuit breaker during drive operation.

e Protective Features

The drive protective features which will cause an orderly shutdown of the drive shall include overcurrent trip, overvoltage trip, undervoltage trip, overspeed protection, overtemperature protection, loss of line

fuse, and improper phase sequence detection.

f Other Features

Drive features shall include isolated power for control circuits, manually resettable motor overload protection for each phase, independent acceleration and deceleration time adjustments adjustable from 2 to 30 seconds, 4-20mA current follower circuitry for interface with HVAC temperature control systems, hand/off/auto selector switch, and manual speed control.

g Housing

Drive unit shall be housed in a NEMA 12 enclosure.

h Efficiency

Drive efficiency shall exceed 90% at 100% rated motor speed. Input power factor of the drive shall be 95% at 100% rated motor speed.

i Switches

Drive shall include a door interlocked circuit breaker switch which will disconnect all input power.

2.15 PANELBOARDS

Dead-front construction, NEMA PB 1 and UL 67.

2.16 RECEPTACLES

UL 498.

2.17 Standard Grade

UL 498.

2.18 Ground Fault Interrupters

UL 943, Class A or B.

2.19 NEMA Standard Receptacle Configurations

NEMA WD 6.

a. Single and Duplex, 15-Ampere and 20-Ampere, 125 Volt

15-ampere, non-locking: NEMA type 5-15R, locking: NEMA type L5-15R,
20-ampere, non-locking: NEMA type 5-20R, locking: NEMA type L5-20R.

b. 15-Ampere, 250 Volt

Two-pole, 3-wire grounding, non-locking: NEMA type 6-15R, locking: NEMA type L6-15R. Three-pole, 4-wire grounding, non-locking: NEMA type 15-15R, locking: NEMA type L15-15R.

c. 20-Ampere, 250 Volt

Two-pole, 3-wire grounding, non-locking: NEMA type 6-20R, locking: NEMA type L6-20R. Three-pole, 4-wire grounding, non-locking: NEMA type 15-20R, locking: NEMA type L15-20R.

d. 30-Ampere, 125/250 Volt

Three-pole, 3-wire, non-locking: NEMA type 10-30R, locking: NEMA type L10-30R. Three-pole, 4-wire grounding, non-locking: NEMA type 14-30R, locking: NEMA type L14-30R.

e. 30-Ampere, 250 Volt

Two-pole, 3-wire grounding, non-locking: NEMA type 6-30R, locking: NEMA type L6-30R. Three-pole, 4-wire grounding, non-locking: NEMA type 15-30R, locking: NEMA type L15-30R.

f. 50-Ampere, 125/250 Volt

Three-pole, 3-wire: NEMA type 10-50R. Three-pole, 4-wire grounding: NEMA type 14-50R.

g. 50-Ampere, 250 Volt

Two-pole, 3-wire grounding: NEMA type 6-50R. Three-pole, 4-wire grounding: NEMA type 15-50R.

2.20 Service Entrance Equipment

UL 869A.

2.21 SPLICE, CONDUCTOR

UL 486C.

2.22 POWER-SWITCHGEAR ASSEMBLIES INCLUDING SWITCHBOARDS

Assemblies shall be metal-enclosed, freestanding general-purpose type in accordance with NEMA PB 2, UL 891, and IEEE C37.20.1 and shall be installed to provide front and rear access. Busses shall be copper. Assembly shall be approximately 2.3 meters high; arrangement of circuit breakers and other items specified shall be as indicated. The withstand rating and

interrupting capacity of the switchboards and circuit breakers shall be based on the maximum fault current available.

2.22.1 Circuit Breakers

Circuit breakers shall be molded-case circuit breakers .

2.22.2 Auxiliary Equipment

2.22.2.1 Instruments

Instruments shall be long scale, 173 mm minimum, semiflush rectangular, indicating or digital switchboard type, mounted at eye level.

- a. Ammeter, range 0 to 100 % of switchboard circuit breaker rating of each building switchboard. a Complete with selector switch having off position and positions to read each phase current.
- b. Voltmeter, range 0 to System voltage of respective building , complete with selector switch having off position and positions to read each phase to phase and phase to neutral voltage.

2.22.2.2 Control Switch

2.23 SNAP SWITCHES

UL 20.

2.24 Dimmers

Incandescent NEMA WD-1; Dimmer switches shall be constructed such that the on-off function is independent of the brightness setting; shall be semiconductor phase control type; and shall have voltage and wattage ratings suitable for the intended application. Dimmer switch shall be slide type.

2.25 Occupancy Sensors

Occupancy sensors shall meet the requirements of UL 916 and include both ultrasonic and infrared type sensors. The technical requirements of the sensors are indicated on the drawings. Sensor quantities and locations will vary by manufacture. As part of submittal for occupancy sensors, the contractor shall provide a sensor layout provided by the sensor manufacturer. The layout shall indicate the location of the sensors and the coverage area in the room.

2.26 TAPES

2.26.1 Plastic Tape

UL 510.

2.26.2 Rubber Tape

UL 510.

2.27 TRANSFORMERS

Single- and three-phase transformers shall have two windings per phase. Full-capacity standard NEMA taps shall be provided in the primary windings of transformers unless otherwise indicated. Three-phase transformers shall be configured with delta-wye windings, except as indicated. "T" connections may be used for transformers rated 15 kVA or below. T

2.27.1 Transformers, Dry-Type

Transformers shall have 220 degrees C insulation system for transformers 15 kVA and greater, and shall have 180 degrees C insulation system for transformers rated 10 kVA and less, with temperature rise not exceeding 150 degrees C under full-rated load in maximum ambient temperature of 40 degrees C. Transformer of 150 degrees C temperature rise shall be capable of carrying continuously 100 percent of nameplate kVA without exceeding insulation rating. Transformers shall meet the energy efficiency standards of NEMA TP-1 and the DOE 'ENERGY STAR' label. Transformer losses shall conform to NEMA TP-1.

a. 600 Volt or Less Primary:

NEMA ST 20, UL 506, general purpose, dry-type, self-cooled, ventilated. Transformers shall be provided in NEMA 1 enclosure. Transformers shall be quiet type with maximum sound level at least 3 decibels less than NEMA standard level for transformer ratings indicated.

2.27.2 Average Sound Level

The average sound level in decibels (dB) of transformers shall not exceed the following dB level at 300 mm for the applicable kVA rating range listed unless otherwise indicated:

kVA Range	dB Sound Level
1-50	50
51-150	55
151-300	58
301-500	60
501-700	62
701-1000	64
1001-1500	65
1501 & above	70

2.28 ISOLATED POWER SYSTEM EQUIPMENT

UL 1047, with monitor UL 1022.

2.29 WATTHOUR METERS, UTILITY REVENUE

Watthour Meters shall conform to ANSI C12.1. Watthour demand meters shall have factory installed electronic pulse initiators meeting the requirements of ANSI C12.1. Pulse initiators shall be solid state devices incorporating light emitting diodes, phototransistors, and power transistors, except that mercury wetted contacts are acceptable. Initiators shall be totally contained within the watthour demand meter enclosure; shall be capable of operating at speeds up to 500 pulses per minute with no false pulses; and shall require no field adjustments. Initiators shall be calibrated for a pulse rate output of one pulse per 1/4 disc revolution of the associated meter and shall be compatible with the indicated equipment.

2.29.1 Solid State Type

2.1.31.2 Solid State Type Solid state watthour meters shall conform to ANSI C12.16, except that numbered terminal wiring sequence and case size shall be the manufacturer's standard. Watthour meters shall be of the panel mounted, switchboard type having a 15 minute cumulative form demand register. Assemblies shall be suitable for use in an environment ranging from -20 degrees celsius to 70 degrees celsius. The meter shall have a self check function. Three phase units shall be provided with not less than 3 current and voltage sensing elements. Solid state meters shall not require batteries to maintain the setup information for the watthour, demand and pulse initiation functions during a power outage or during normal usage. Solid state meters shall have integral surge withstand capability per ANSI C37.90.1 or supplemental surge suppression shall be provided per ANSI C62.41. Surge suppression shall be designed to attenuate both line-to-neutral and neutral-to-ground transients.

2.30 INSTRUMENT TRANSFORMERS

2.30.1 General

Instrument transformers shall comply with ANSI C12.11 and IEEE C57.13. Instrument transformers shall be configured for mounting in/on the device to which they are applied. Polarity marks on instrument transformers shall be visually evident and shown on drawings.

2.30.2 Current Transformers

Unless otherwise indicated, bar, wound, or window-type transformers are acceptable; and except for window-type units installed over insulated buses, transformers shall have a BIL rating consistent with the rated BIL of the associated switchgear or electric power apparatus bushings, buses or conductors. Other thermal and mechanical ratings of current transformer and their primary leads shall be coordinated with the design of the circuit breaker and shall be not less than the momentary rating of the associated

circuit breaker. Circuit protectors shall be provided across secondary leads of the current transformers to prevent the accidental open-circuiting of the transformers while energized. Each terminal of each current transformer shall be connected to a short-circuiting terminal block in the circuit interrupting mechanism cabinet, power transformer terminal cabinet, and in the associated instrument and relay cabinets.

2.30.2.1 Voltage Transformers

Voltage transformers shall have indicated ratios. Voltage transformers shall be of the drawout type having current-limiting fuses in both primary and secondary circuits. Mechanical interlocks shall prevent removal of fuses, unless the associated voltage transformer is in a drawout position. Voltage transformer compartments shall have hinged doors.

2.31 WIRING DEVICES

NEMA WD 1 for wiring devices, and NEMA WD 6 for dimensional requirements of wiring devices.

PART 3 EXECUTION

3.1 GROUNDING

Grounding shall be in conformance with NFPA 70, the contract drawings, and the following specifications.

3.1.1 Ground Rods

The resistance to ground shall be measured using the fall-of-potential method described in IEEE Std 81. The maximum resistance of a driven ground shall not exceed 25 ohms under normally dry conditions. If this resistance cannot be obtained with a single rod, additional rods not less than 1.8 meters on centers shall be used. In high-ground-resistance, UL listed chemically charged ground rods may be used. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, the Contracting Officer shall be notified immediately. Connections below grade shall be fusion welded. Connections above grade shall be fusion welded or shall use UL 467 approved connectors.

3.1.2 Ground Bus

Ground bus shall be provided in the electrical equipment rooms. Noncurrent-carrying metal parts of transformer neutrals and other electrical equipment shall be effectively grounded by bonding to the ground bus. The ground bus shall be bonded to both the entrance ground, and to a ground rod or rods as specified above having the upper ends terminating approximately 100 mm above the floor. Connections and splices shall be of the brazed, welded, bolted, or pressure-connector type, except that pressure connectors or bolted connections shall be used for connections to removable equipment. Connections shall be bolted type in lieu of thermoweld, so they can be changed as required by additions and/or

alterations.

3.1.3 Grounding Conductors

A green equipment grounding conductor, sized in accordance with NFPA 70 shall be provided, regardless of the type of conduit. Equipment grounding bars shall be provided in all panelboards. The equipment grounding conductor shall be carried back to the service entrance grounding connection or separately derived grounding connection. All equipment grounding conductors, including metallic raceway systems used as such, shall be bonded or joined together in each wiring box or equipment enclosure. Metallic raceways and grounding conductors shall be checked to assure that they are wired or bonded into a common junction. Metallic boxes and enclosures, if used, shall also be bonded to these grounding conductors by an approved means per NFPA 70. When switches, or other utilization devices are installed, any designated grounding terminal on these devices shall also be bonded to the equipment grounding conductor junction with a short jumper.

3.2 WIRING METHODS

Wiring shall conform to NFPA 70, the contract drawings, and the following specifications. Unless otherwise indicated, wiring shall consist of insulated conductors installed in rigid zinc-coated steel conduit, electrical metallic tubing, electrical nonmetallic tubing, and intermediate metal conduit. Nonmetallic-sheathed cables or metallic-armored cables may be installed in areas permitted by NFPA 70. Wire fill in conduits shall be based on NFPA 70 for the type of conduit and wire insulations specified. Wire fill in conduits located in Class I or II hazardous areas shall be limited to 25 percent of the cross sectional area of the conduit.

3.2.1 Conduit and Tubing Systems

Conduit and tubing systems shall be installed as indicated. Conduit sizes shown are based on use of copper conductors with insulation types as described in paragraph WIRING METHODS. Minimum size of raceways shall be 15 mm. Only metal conduits will be permitted when conduits are required for shielding or other special purposes indicated, or when required by conformance to NFPA 70. Nonmetallic conduit and tubing may be used in damp, wet or corrosive locations when permitted by NFPA 70 and the conduit or tubing system is provided with appropriate boxes, covers, clamps, screws or other appropriate type of fittings. Electrical metallic tubing (EMT) may be installed only within buildings. EMT may be installed in concrete and grout in dry locations. EMT installed in concrete or grout shall be provided with concrete tight fittings. EMT shall not be installed in damp or wet locations, or the air space of exterior masonry cavity walls. Bushings, manufactured fittings or boxes providing equivalent means of protection shall be installed on the ends of all conduits and shall be of the insulating type, where required by NFPA 70. Only UL listed adapters shall be used to connect EMT to rigid metal conduit, cast boxes, and conduit bodies. Penetrations of above grade floor slabs, time-rated partitions and fire walls shall be firestopped in accordance with Section 07840 FIRESTOPPING. Except as otherwise specified, IMC may be used as an option for rigid steel conduit in areas as permitted by NFPA 70. Raceways

shall not be installed under the firepits of boilers and furnaces and shall be kept 150 mm away from parallel runs of flues, steam pipes and hot-water pipes. Raceways shall be concealed within finished walls, ceilings, and floors unless otherwise shown. Raceways crossing structural expansion joints or seismic joints shall be provided with suitable expansion fittings or other suitable means to compensate for the building expansion and contraction and to provide for continuity of grounding. Conductors routed through expansion fittings shall have a suitable amount of conductor coiled in the nearest junction box or termination point on both sides of the expansion fitting to allow slack when the expansion, contraction, or differential movement occurs. Wiring installed in underfloor duct system shall be suitable for installation in wet locations.

3.2.1.1 Pull Wires

A pull wire shall be inserted in each empty raceway in which wiring is to be installed if the raceway is more than 15 meters in length and contains more than the equivalent of two 90-degree bends, or where the raceway is more than 45 meters in length. The pull wire shall be of No. 14 AWG zinc-coated steel, or of plastic having not less than 1.4 MPa (200 psi) tensile strength. Not less than 254 mm of slack shall be left at each end of the pull wire.

3.2.1.2 Conduit Stub-Ups

Where conduits are to be stubbed up through concrete floors, a short elbow shall be installed below grade to transition from the horizontal run of conduit to a vertical run. A conduit coupling fitting, threaded on the inside shall be installed, to allow terminating the conduit flush with the finished floor. Wiring shall be extended in rigid threaded conduit to equipment, except that where required, flexible conduit may be used 150 mm above the floor. Empty or spare conduit stub-ups shall be plugged flush with the finished floor with a threaded, recessed plug.

3.2.1.3 Below Slab-on-Grade or in the Ground

Electrical wiring below slab-on-grade shall be protected by a conduit system. Conduit passing vertically through slabs-on-grade shall be rigid steel or IMC. Rigid steel or IMC conduits installed below slab-on-grade or in the earth shall be field wrapped with 0.254 mm thick pipe-wrapping plastic tape applied with a 50 percent overlay, or shall have a factory-applied polyvinyl chloride, plastic resin, or epoxy coating system.

3.2.1.4 Installing in Slabs Including Slabs on Grade

Conduit installed in slabs-on-grade shall be rigid steel or IMC. Conduits shall be installed as close to the middle of concrete slabs as practicable without disturbing the reinforcement. Outside diameter shall not exceed 1/3 of the slab thickness and conduits shall be spaced not closer than 3 diameters on centers except at cabinet locations where the slab thickness shall be increased as approved by the Contracting Officer. Where conduit is run parallel to reinforcing steel, the conduit shall be spaced a minimum of one conduit diameter away but not less than 25.4 mm from the reinforcing steel.

3.2.1.5 Changes in Direction of Runs

Changes in direction of runs shall be made with symmetrical bends or cast-metal fittings. Field-made bends and offsets shall be made with an approved hickey or conduit-bending machine. Crushed or deformed raceways shall not be installed. Trapped raceways in damp and wet locations shall be avoided where possible. Lodgment of plaster, dirt, or trash in raceways, boxes, fittings and equipment shall be prevented during the course of construction. Clogged raceways shall be cleared of obstructions or shall be replaced.

3.2.1.6 Supports

Metallic conduits and tubing, and the support system to which they are attached, shall be securely and rigidly fastened in place to prevent vertical and horizontal movement at intervals of not more than 3 meters and within 900 mm of boxes, cabinets, and fittings, with approved pipe straps, wall brackets, conduit clamps, conduit hangers, threaded C-clamps, beam clamps, or ceiling trapeze. Loads and supports shall be coordinated with supporting structure to prevent damage or deformation to the structure. Loads shall not be applied to joist bridging. Attachment shall be by wood screws or screw-type nails to wood; by toggle bolts on hollow masonry units; by expansion bolts on concrete or brick; by machine screws, welded threaded studs, heat-treated or spring-steel-tension clamps on steel work. Nail-type nylon anchors or threaded studs driven in by a powder charge and provided with lock washers and nuts may be used in lieu of expansion bolts or machine screws. Raceways or pipe straps shall not be welded to steel structures. Cutting the main reinforcing bars in reinforced concrete beams or joists shall be avoided when drilling holes for support anchors. Holes drilled for support anchors, but not used, shall be filled. In partitions of light steel construction, sheet-metal screws may be used. Raceways shall not be supported using wire or nylon ties. Raceways shall be independently supported from the structure. Upper raceways shall not be used as a means of support for lower raceways. Supporting means shall not be shared between electrical raceways and mechanical piping or ducts. Cables and raceways shall not be supported by ceiling grids. Except where permitted by NFPA 70, wiring shall not be supported by ceiling support systems. Conduits shall be fastened to sheet-metal boxes and cabinets with two locknuts where required by NFPA 70, where insulating bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, a single locknut and bushing may be used. Threadless fittings for electrical metallic tubing shall be of a type approved for the conditions encountered. Additional support for horizontal runs is not required when EMT rests on steel stud cutouts.

3.2.1.7 Exposed Raceways

Exposed raceways shall be installed parallel or perpendicular to walls, structural members, or intersections of vertical planes and ceilings. Raceways under raised floors and above accessible ceilings shall be

considered as exposed installations in accordance with NFPA 70 definitions.

3.2.1.8 Exposed Risers

Exposed risers in wire shafts of multistory buildings shall be supported by U-clamp hangers at each floor level, and at intervals not to exceed 3 meters.

3.2.1.9 Communications Raceways

Communications raceways indicated shall be installed in accordance with the previous requirements for conduit and tubing and with the additional requirement that the minimum conduit size shall be 26mm and shall not contain more than two 90-degree bends or the equivalent. Additional pull or junction boxes shall be installed to comply with these limitations whether or not indicated. Inside radii of bends in conduits of 26 mm (1 inch) size or larger shall not be less than ten times the nominal diameter.

3.2.2 Cable Trays

Cable trays shall be supported in accordance with the recommendations of the manufacturer but at no more than 1.8 meter intervals. Contact surfaces of aluminum connections shall be coated with an antioxidant compound prior to assembly. Adjacent cable tray sections shall be bonded together by connector plates of an identical type as the cable tray sections. The Contractor shall submit the manufacturer's certification that the cable tray system meets all requirements of Article 318 of NFPA 70.

The cable tray shall be installed and grounded in accordance with the provisions of Article 318 of NFPA 70. Data submitted by the Contractor shall demonstrate that the completed cable tray systems will comply with the specified requirements. Cable trays shall terminate 250 mm from both sides of smoke and fire partitions. Conductors run through smoke and fire partitions shall be installed in 103 mm (4 inch) rigid steel conduits with grounding bushings, extending 300 mm beyond each side of the partitions. The installation shall be sealed to preserve the smoke and fire rating of the partitions. Penetrations shall be firestopped in accordance with Section 07840 FIRESTOPPING.

3.2.3 Cables and Conductors

Installation shall conform to the requirements of NFPA 70. Covered, bare or insulated conductors of circuits rated over 600 volts shall not occupy the same equipment wiring enclosure, cable, or raceway with conductors of circuits rated 600 volts or less.

3.2.3.1 Sizing

Unless otherwise noted, all sizes are based on copper conductors and the insulation types indicated. Sizes shall be not less than indicated. Branch-circuit conductors shall be not smaller than No. 12 AWG. Conductors for branch circuits of 120 volts more than 30 meters long and of 277 volts

more than 70 meters long, from panel to load center, shall be no smaller than No. 10 AWG. Class 1 remote control and signal circuit conductors shall be not less than No. 14 AWG. Class 2 remote control and signal circuit conductors shall be not less than No. 16 AWG. Class 3 low-energy, remote-control and signal circuits shall be not less than No. 22 AWG.

3.2.3.2 Use of Aluminum Conductors in Lieu of Copper

Aluminum conductors shall not be used.

3.2.3.3 Cable Systems

Cable systems shall be installed where indicated. Cables shall be installed concealed behind ceiling or wall finish where practicable. Cables shall be threaded through holes bored on the approximate centerline of wood members; notching of surfaces will not be permitted. Sleeves shall be provided through bond beams of masonry-block walls for threading cables through hollow spaces. Exposed cables shall be installed parallel or at right angles to walls or structural members. In rooms or areas not provided with ceiling or wall finish, cables and outlets shall be installed so that a room finish may be applied in the future without disturbing the cables or resetting the boxes. Exposed nonmetallic-sheathed cables less than 1.2 meters above floors shall be protected from mechanical injury by installation in conduit or tubing.

3.2.3.4 Cable Splicing

Splices shall be made in an accessible location. Crimping tools and dies shall be approved by the connector manufacturer for use with the type of connector and conductor.

- a. Copper Conductors, 600 Volt and Under: Splices in conductors No. 10 AWG and smaller diameter shall be made with an insulated, pressure-type connector. Splices in conductors No. 8 AWG and larger diameter shall be made with a solderless connector and insulated with tape or heat-shrink type insulating material equivalent to the conductor insulation.

3.2.3.5 Conductor Identification and Tagging

Power, control, and signal circuit conductor identification shall be provided within each enclosure where a tap, splice, or termination is made.

Where several feeders pass through a common pull box, the feeders shall be tagged to indicate clearly the electrical characteristics, circuit number, and panel designation. Phase conductors of low voltage power circuits shall be identified by color coding. Phase identification by a particular color shall be maintained continuously for the length of a circuit, including junctions.

- a. Color coding shall be provided for service, feeder, branch, and ground conductors. Color shall be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in the same raceway or box, other neutral shall be white with colored (not green) stripe. The color coding for 3-phase and single-phase low voltage systems shall be as follows:

120/208-volt, 3-phase: Black(A), red(B), and blue(C).
 277/480-volt, 3-phase: Brown(A), orange(B), and yellow(C).
 120/240-volt, 1-phase: Black and red.

- b. Conductor phase and voltage identification shall be made by color-coded insulation for all conductors smaller than No. 6 AWG. For conductors No. 6 AWG and larger, identification shall be made by color-coded insulation, or conductors with black insulation may be furnished and identified by the use of half-lapped bands of colored electrical tape wrapped around the insulation for a minimum of 75 mm of length near the end, or other method as submitted by the Contractor and approved by the Contracting Officer.
- c. Control and signal circuit conductor identification shall be made by color-coded insulated conductors, plastic-coated self-sticking printed markers, permanently attached stamped metal foil markers, or equivalent means as approved. Control circuit terminals of equipment shall be properly identified. Terminal and conductor identification shall match that shown on approved detail drawings. Hand lettering or marking is not acceptable.

3.3 BOXES AND SUPPORTS

Boxes shall be provided in the wiring or raceway systems where required by NFPA 70 for pulling of wires, making connections, and mounting of devices or fixtures. Pull boxes shall be furnished with screw-fastened covers. Indicated elevations are approximate, except where minimum mounting heights for hazardous areas are required by NFPA 70. Unless otherwise indicated, boxes for wall switches shall be mounted 1.2 meters above finished floors.

Switch and outlet boxes located on opposite sides of fire rated walls shall be separated by a minimum horizontal distance of 600 mm. The total combined area of all box openings in fire rated walls shall not exceed 0.0645 square meters per 9.3 square meters. Maximum box areas for individual boxes in fire rated walls vary with the manufacturer and shall not exceed the maximum specified for that box in UL Elec Const Dir. Only boxes listed in UL Elec Const Dir shall be used in fire rated walls.

3.3.1 Box Applications

Each box shall have not less than the volume required by NFPA 70 for number of conductors enclosed in box. Boxes for metallic raceways shall be listed

for the intended use when located in normally wet locations, when flush or surface mounted on outside of exterior surfaces, or when located in hazardous areas. Boxes installed in wet locations and boxes installed flush with the outside of exterior surfaces shall be gasketed. Boxes for mounting lighting fixtures shall be not less than 102 mm square, or octagonal, except smaller boxes may be installed as required by fixture configuration, as approved. Cast-metal boxes with 2.4 mm wall thickness are acceptable. Large size boxes shall be NEMA 1 or as shown. Boxes in other locations shall be sheet steel except that aluminum boxes may be used with aluminum conduit, and nonmetallic boxes may be used with nonmetallic conduit and tubing or nonmetallic sheathed cable system, when permitted by NFPA 70. Boxes for use in masonry-block or tile walls shall be square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers.

3.3.2 Brackets and Fasteners

Boxes and supports shall be fastened to wood with wood screws or screw-type nails of equal holding strength, with bolts and metal expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screw or welded studs on steel work. Threaded studs driven in by powder charge and provided with lockwashers and nuts, or nail-type nylon anchors may be used in lieu of expansion shields, or machine screws. Penetration of more than 38.1 mm (1-1/2 inches) into reinforced-concrete beams or more than 19.1 mm (3/4 inch) into reinforced-concrete joists shall avoid cutting any main reinforcing steel. The use of brackets which depend on gypsum wallboard or plasterboard for primary support will not be permitted. In partitions of light steel construction, bar hangers with 25 mm long studs, mounted between metal wall studs or metal box mounting brackets shall be used to secure boxes to the building structure. When metal box mounting brackets are used, additional box support shall be provided on the side of the box opposite the brackets. This additional box support shall consist of a minimum 300 mm long section of wall stud, bracketed to the opposite side of the box and secured by two screws through the wallboard on each side of the stud. Metal screws may be used in lieu of the metal box mounting brackets.

3.3.3 Mounting in Walls, Ceilings, or Recessed Locations

In walls or ceilings of concrete, tile, or other non-combustible material, boxes shall be installed so that the edge of the box is not recessed more than 6 mm from the finished surface. Boxes mounted in combustible walls or ceiling material shall be mounted flush with the finished surface. The use of gypsum or plasterboard as a means of supporting boxes will not be permitted. Boxes installed for concealed wiring shall be provided with suitable extension rings or plaster covers, as required. The bottom of boxes installed in masonry-block walls for concealed wiring shall be mounted flush with the top of a block to minimize cutting of the blocks, and boxes shall be located horizontally to avoid cutting webs of block. Separate boxes shall be provided for flush or recessed fixtures when required by the fixture terminal operating temperature, and fixtures shall be readily removable for access to the boxes unless ceiling access panels are provided.

3.3.4 Installation in Overhead Spaces

In open overhead spaces, cast-metal boxes threaded to raceways need not be separately supported except where used for fixture support; cast-metal boxes having threadless connectors and sheet metal boxes shall be supported directly from the building structure or by bar hangers. Hangers shall not be fastened to or supported from joist bridging. Where bar hangers are used, the bar shall be attached to raceways on opposite sides of the box and the raceway shall be supported with an approved type fastener not more than 600 mm from the box.

3.4 DEVICE PLATES

One-piece type device plates shall be provided for all outlets and fittings. Plates on unfinished walls and on fittings shall be of zinc-coated sheet steel, cast-metal, or impact resistant plastic having rounded or beveled edges. Plates on finished walls shall be of steel with baked enamel finish or impact-resistant plastic and shall be ivory. Screws shall be of metal with countersunk heads, in a color to match the finish of the plate. Plates shall be installed with all four edges in continuous contact with finished wall surfaces without the use of mats or similar devices. Plaster fillings will not be permitted. Plates shall be installed with an alignment tolerance of 1.6 mm. The use of sectional-type device plates will not be permitted. Plates installed in wet locations shall be gasketed and provided with a hinged, gasketed cover, unless otherwise specified.

3.5 RECEPTACLES

3.5.1 Single and Duplex, 15 or 20-ampere, 125 volt

Single and duplex receptacles shall be rated 20 amperes, 125 volts, two-pole, three-wire, grounding type with polarized parallel slots. Bodies shall be of ivory to match color of switch handles in the same room or to harmonize with the color of the respective wall, and supported by mounting strap having plaster ears. Contact arrangement shall be such that contact is made on two sides of an inserted blade. Receptacle shall be side- or back-wired with two screws per terminal. The third grounding pole shall be connected to the metal mounting yoke. Switched receptacles shall be the same as other receptacles specified except that the ungrounded pole of each suitable receptacle shall be provided with a separate terminal. Only the top receptacle of a duplex receptacle shall be wired for switching application. Receptacles with ground fault circuit interrupters shall have the current rating as indicated, and shall be UL Class A type unless otherwise shown. Ground fault circuit protection shall be provided as required by NFPA 70 and as indicated on the drawings.

3.5.2 Weatherproof Applications

Weatherproof receptacles shall be suitable for the environment, damp or wet as applicable, and the housings shall be labeled to identify the allowable use. Receptacles shall be marked in accordance with UL 514A for the type

of use indicated; "Damp locations", "Wet Locations", "Wet Location Only When Cover Closed". Assemblies shall be installed in accordance with the manufacturer's recommendations.

3.5.2.1 Damp Locations

Receptacles in damp locations shall be mounted in an outlet box with a gasketed, weatherproof, cast-metal cover plate (device plate, box cover) and a gasketed cap (hood, receptacle cover) over each receptacle opening. The cap shall be either a screw-on type permanently attached to the cover plate by a short length of bead chain or shall be a flap type attached to the cover with a spring loaded hinge.

3.5.2.2 Wet Locations

Receptacles in wet locations shall be installed in an assembly rated for such use whether the plug is inserted or withdrawn, unless otherwise indicated. In a duplex installation, the receptacle cover shall be configured to shield the connections whether one or both receptacles are in use. .

3.5.3 Receptacles, 15-Ampere, 250-Volt

Receptacles, 15-ampere, 250-volt, shall be as indicated with bodies of ivory phenolic compound supported by mounting yoke having plaster ears. The third grounding pole shall be connected to the metal yoke. Each receptacle shall be provided with a mating cord-grip plug.

3.5.4 Receptacles, 20-Ampere, 250-Volt

Receptacles, single, 20-ampere, 250-volt, shall be ivory molded plastic, two-pole, three-wire or three-pole, four-wire, grounding type complete with appropriate mating cord-grip plug.

3.6 WALL SWITCHES

Wall switches shall be of the totally enclosed tumbler type. The wall switch handle and switch plate color shall be ivory. Wiring terminals shall be of the screw type or of the solderless pressure type having suitable conductor-release arrangement. Not more than one switch shall be installed in a single-gang position. Switches shall be rated 20-ampere 120-volt for use on alternating current only. Dimming switches shall be solid-state flush mounted, sized for the loads.

3.7 SERVICE AND METERING EQUIPMENT

Service Provisions Service-disconnecting means shall be of the enclosed molded-case circuit breaker type as indicated with external handle for manual operation. When service disconnecting means is a part of an assembly, the assembly shall be listed as suitable for service entrance equipment. Enclosures shall be sheet metal with hinged cover for surface mounting unless otherwise indicated. 3.7.1 Metering Equipment

Tex3.7.2 Metering Equipment watt-hour meters shall be installed where indicated. Current transformers and voltage transformers conforming to ANSI C12.11 and IEEE C57.13 shall be included with ratios appropriate for use on a 480 or 208 volt, 3 phase, 4 wire system with an amperage equal to the main protective device. Meters shall have demand registers and pulse initiators suitable for connection to a monitoring or automation system. The pulse rate shall be identified by a label or other marking on each initiator.

3.8 PANELBOARDS AND LOADCENTERS

Circuit breakers and switches used as a motor disconnecting means shall be capable of being locked in the open position. Door locks shall be keyed alike. Nameplates shall be as approved. Directories shall be typed to indicate loads served by each circuit and mounted in a holder behind a clear protective covering. Busses shall be aluminum.

3.8.1 Loadcenters

Loadcenters shall be circuit breaker equipped.

3.8.2 Panelboards

Panelboards shall be circuit breaker equipped as indicated on the drawings.

3.8.3 Motor Control Centers

Control centers shall conform to the requirements of NEMA ICS 1, NEMA ICS 2, NEMA ICS 3 and NEMA ICS6, and UL 508 and UL 845. Control centers shall be indoor type and shall contain combination starters and other equipment as indicated. Control centers shall be NEMA ICS 2, Class 1, Type B. Each control center shall be mounted on mounting channels. Each circuit shall have a suitable metal or laminated plastic nameplate with white cut letters. Motor control center shall be provided with a full-length ground bar.

3.9 UNDERGROUND SERVICE

Unless otherwise indicated, interior conduit systems shall be stubbed out 1.5 m beyond the building wall and 600 mm below finished grade, for interface with the exterior service lateral conduits and exterior communications conduits. Outside conduit ends shall be bushed when used for direct burial service lateral conductors. Outside conduit ends shall be capped or plugged until connected to exterior conduit systems. Underground service lateral conductors will be extended to building service entrance and terminated in accordance with the requirements of Section 16375 ELECTRICAL DISTRIBUTION SYSTEM, UNDERGROUND and NFPA 70.

3.10 MOTORS

Each motor shall conform to the kW and voltage ratings indicated, and

shall have a service factor and other characteristics that are essential to the proper application and performance of the motors under conditions shown or specified. Three-phase motors for use on 3-phase 208-volt systems shall have a nameplate rating of 200 volts. Unless otherwise specified, all motors shall have open frames, and continuous-duty classification based on a 40 degree C ambient temperature reference. Polyphase motors shall be squirrel-cage type, having normal-starting-torque and low-starting-current characteristics, unless other characteristics are specified in other sections of these specifications or shown on contract drawings. The Contractor shall be responsible for selecting the actual kilowatt (horsepower) ratings and other motor requirements necessary for the applications indicated. When electrically driven equipment furnished under other sections of these specifications materially differs from the design, the Contractor shall make the necessary adjustments to the wiring, disconnect devices and branch-circuit protection to accommodate the equipment actually installed.

3.11 MOTOR CONTROL

Each motor or group of motors requiring a single control and not controlled from a motor-control center shall be provided under other sections of these specifications with a suitable controller and devices that will perform the functions as specified for the respective motors. Each motor of 93 W (1/8 hp) or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller, or shall be mounted in a separate enclosure. Unless otherwise specified, the protective device shall be of the manually reset type. Single or double pole tumbler switches specifically designed for alternating-current operation only may be used as manual controllers for single-phase motors having a current rating not in excess of 80 percent of the switch rating. Automatic control devices such as thermostats, float or pressure switches may control the starting and stopping of motors directly, provided the devices used are designed for that purpose and have an adequate kilowatt rating. When the automatic-control device does not have such a rating, a magnetic starter shall be used, with the automatic-control device actuating the pilot-control circuit. When combination manual and automatic control is specified and the automatic-control device operates the motor directly, a double-throw, three-position tumbler or rotary switch shall be provided for the manual control; when the automatic-control device actuates the pilot control circuit of a magnetic starter, the latter shall be provided with a three-position selector switch marked MANUAL-OFF-AUTOMATIC. Connections to the selector switch shall be such that only the normal automatic regulatory control devices will be bypassed when the switch is in the Manual position; all safety control devices, such as low- or high-pressure cutouts, high-temperature cutouts, and motor-overload protective devices, shall be connected in the motor-control circuit in both the Manual and the Automatic positions of the selector switch. Control circuit connections to any MANUAL-OFF-AUTOMATIC switch or to more than one automatic regulatory control device shall be made in accordance with wiring diagram approved by the Contracting Officer unless such diagram is included on the drawings. All controls shall be 120 volts or less unless otherwise indicated. All 3-phase motors shall be equipped with phase failure and undervoltage

protection relays. Relays shall have automatic reset feature. The undervoltage relay shall be adjustable from 80% to 100% of nominal voltage. The output contact shall be form C, SPDT, rated 5A and 240V. The output contact shall be connected in the motor starter circuit with the motor starter selector switch (H-O-A) in the hand and automatic positions. The relay shall be connected to the motor circuit at the motor terminals. Motor starters, control panels and disconnect switches shall not be mounted on equipment or equipment housings unless provided as an integral part of the equipment from the manufacturer. When not mounted in a Motor Control Center and where no suitable walls exist on which to mount control panels, disconnect switches and starters the contractor shall fabricate suitable supports near the controlled equipment from galvanized steel channels or galvanized angled steel. Supports inside shall be securely bolted to the floor and supports outside shall be bolted to concrete footings. Control equipment shall be mounted in NEMA 3R enclosures when located outside or in areas designated as wet locations. Motor starters shall be provided with auxiliary contacts as required to achieve the control shown on the control diagrams or specified; plus two spare auxiliary contacts shall be provided. Disconnect switches shall be heavy duty type.

3.11.1 Contacts

Unless otherwise indicated, contacts in miscellaneous control devices such as float switches, pressure switches, and auxiliary relays shall have current and voltage ratings in accordance with NEMA ICS 2 for rating designation B300.

3.11.2 Safety Controls

Safety controls for boilers shall be connected to a 2-wire, 120 volt grounded circuit supplied from the associated boiler-equipment circuit. Where the boiler circuit is more than 120 volts to ground, safety controls shall be energized through a two-winding transformer having its 120 volt secondary winding grounded. Overcurrent protection shall be provided in the ungrounded secondary conductor and shall be sized for the load encountered.

3.11.3 Motor 3-Phase Failure Relay

All 3-phase motors 1.5 horsepower and above shall be equipped with phase failure and undervoltage protection relays. Relays shall have automatic reset feature. The undervoltage relay shall be adjustable from 80% to 100% of nominal voltage. The output contact shall be from C, SPDT, rated 5A and 240V. The output contact shall be connected in the motor starter circuit with the motor starter selector switch (H-O-A) in the hand and automatic positions. The relay shall be connected to the motor circuit at the motor terminals.

3.12 MOTOR-DISCONNECT MEANS

Each motor shall be provided with a disconnecting means when required by NFPA 70 even though not indicated. For single-phase motors, a single or

double pole toggle switch, rated only for alternating current, will be acceptable for capacities less than 30 amperes, provided the ampere rating of the switch is at least 125 percent of the motor rating. Disconnect switches for three phase motors shall be non-fused heavy duty type. Switches shall disconnect all ungrounded conductors.

3.13 TRANSFORMER INSTALLATION

Three-phase transformers shall be connected only in a delta-wye or wye-delta configuration as indicated. "T" connections may be used for transformers rated at 15 kVA or below. Dry-type transformers shown located within 1.5 meters of the exterior wall shall be provided in a weatherproof enclosure. Transformers to be located within the building may be provided in the manufacturer's standard, ventilated indoor enclosure designed for use in 40 degrees C ambient temperature, unless otherwise indicated.

3.14 LIGHTING FIXTURES, LAMPS AND BALLASTS

This paragraph shall cover the installation of lamps, lighting fixtures and ballasts in interior or building mounted applications.

3.14.1 Lamps

Lamps of the type, wattage, and voltage rating indicated shall be delivered to the project in the original cartons and installed just prior to project completion. Lamps installed and used for working light during construction shall be replaced prior to turnover to the Government if more than 15% of their rated life has been used. Lamps shall be tested for proper operation prior to turn-over and shall be replaced if necessary with new lamps from the original manufacturer. 10% spare lamps of each type, from the original manufacturer, shall be provided.

3.14.2 Lighting Fixtures

Fixtures shall be as shown and shall conform to the following specifications and shall be as detailed on the drawings. Illustrations shown on the drawings are indicative of the general type desired and are not intended to restrict selection to fixtures of any particular manufacturer. Fixtures of similar designs and equivalent energy efficiency, light distribution and brightness characteristics, and of equal finish and quality will be acceptable if approved. In suspended acoustical ceilings with fluorescent fixtures, the fluorescent emergency light fixtures shall be furnished with self-contained battery packs.

3.14.2.1 Accessories

Accessories such as straps, mounting plates, nipples, or brackets shall be provided for proper installation.

3.14.2.2 Ceiling Fixtures

Ceiling fixtures shall be coordinated with and suitable for installation in, on or from the ceiling as shown. Installation and support of fixtures shall be in accordance with NFPA 70 and manufacturer's recommendations.

Where seismic requirements are specified herein, fixtures shall be supported as shown or specified. Recessed fixtures shall have adjustable fittings to permit alignment with ceiling panels. Recessed fixtures installed in fire-resistive ceiling construction shall have the same fire rating as the ceiling or shall be provided with fireproofing boxes having materials of the same fire rating as the ceiling, in conformance with UL Elec Const Dir. Surface-mounted fixtures shall be suitable for fastening to the ceiling panel structural supports.

3.14.2.3 Fixtures for Installation in Grid Type Ceilings

Fixtures for installation in grid type ceilings which are smaller than a full tile shall be centered in the tile. 305 by 1219 mm fixtures shall be mounted along the grid rail as shown. Work above the ceiling shall be coordinated among the trades to provide the lighting layout shown. Fixtures mounted to the grid shall have trim exactly compatible with the grid. Contractor shall coordinate trims with ceiling trades prior to ordering fixtures. Metric fixtures shall be designed to fit the metric grid specified. Fixtures in continuous rows shall be coordinated between trades prior to ordering. Fixtures shall be mounted using independent supports capable of supporting the entire weight of the fixture. No fixture shall rest solely on the ceiling grid. Recessed fixtures installed in seismic areas should be installed utilizing specially designed seismic clips. Junction boxes shall be supported at four points.

3.14.2.4 Suspended Fixtures

Suspended fixtures shall be provided with swivel hangers or hand-straightens so that they hang plumb. Pendants, rods, or chains 1.2 meters or longer excluding fixture shall be braced to prevent swaying using three cables at 120 degrees of separation. Suspended fixtures in continuous rows shall have internal wireway systems for end to end wiring and shall be properly aligned to provide a straight and continuous row without bends, gaps, light leaks or filler pieces. Aligning splines shall be used on extruded aluminum fixtures to assure hairline joints. Steel fixtures shall be supported to prevent "oil-canning" effects. Fixture finishes shall be free of scratches, nicks, dents, and warps, and shall match the color and gloss specified. Pendants shall be finished to match fixtures. Aircraft cable shall be stainless steel. Canopies shall be finished to match the ceiling and shall be low profile unless otherwise shown. Maximum distance between suspension points shall be 3.1 meters or as recommended by the manufacturer, whichever is less.

Suspended fixtures installed in seismic areas shall have 45% swivel hangers and shall be located with no obstructions within the 45% range in all directions. The stem, canopy and fixture shall be capable of 45% swing.

3.14.3 Ballasts

Remote type ballasts or transformers, where indicated, shall be mounted in a well ventilated, easily accessible location, within the maximum operating distance from the lamp as designated by the manufacturer.

3.14.4 Emergency Light Sets

Emergency light sets shall conform to UL 924 with the number of heads as indicated. Sets shall be permanently connected to the wiring system by conductors installed in short lengths of flexible conduit.

3.15 EQUIPMENT CONNECTIONS

Wiring not furnished and installed under other sections of the specifications for the connection of electrical equipment as indicated on the drawings shall be furnished and installed under this section of the specifications. Connections shall comply with the applicable requirements of paragraph WIRING METHODS. Flexible conduits 2 m or less in length shall be provided to all electrical equipment subject to periodic removal, vibration, or movement and for all motors. All motors shall be provided with separate grounding conductors. Liquid-tight conduits shall be used in damp or wet locations.

3.15.1 Motors and Motor Control

Motors, motor controls, and motor control centers shall be installed in accordance with NFPA 70, the manufacturer's recommendations, and as indicated. Wiring shall be extended to motors, motor controls, and motor control centers and terminated.

3.15.2 Installation of Government-Furnished Equipment

Wiring shall be extended to the equipment and terminated.

3.16 CIRCUIT PROTECTIVE DEVICES

The Contractor shall calibrate, adjust, set and test each new adjustable circuit protective device to ensure that they will function properly prior to the initial energization of the new power system under actual operating conditions.

3.17 PAINTING AND FINISHING

Field-applied paint on exposed surfaces shall be provided under Section 09900 PAINTING, GENERAL.

3.18 REPAIR OF EXISTING WORK

The work shall be carefully laid out in advance, and where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceiling, or other surfaces is necessary for the proper installation, support, or anchorage of the conduit, raceways, or other electrical work, this work shall be carefully done, and any damage to building, piping, or equipment shall be repaired by skilled mechanics of the trades involved at no additional cost to the Government.

3.19 FIELD TESTING

Field testing shall be performed in the presence of the Contracting Officer. The Contractor shall notify the Contracting Officer 30 days prior to conducting tests. The Contractor shall furnish all materials, labor, and equipment necessary to conduct field tests. The Contractor shall perform all tests and inspection recommended by the manufacturer unless specifically waived by the Contracting Officer. The Contractor shall maintain a written record of all tests which includes date, test performed, personnel involved, devices tested, serial number and name of test equipment, and test results. All field test reports will be signed and dated by the Contractor.

3.19.1 Safety

The Contractor shall provide and use safety devices such as rubber gloves, protective barriers, and danger signs to protect and warn personnel in the test vicinity. The Contractor shall replace any devices or equipment which are damaged due to improper test procedures or handling.

3.19.2 Ground-Resistance Tests

The resistance of each grounding electrode system shall be measured using the fall-of-potential method defined in IEEE Std 81. Soil resistivity in the area of the grid shall be measured concurrently with the grid measurements. Ground resistance measurements shall be made before the electrical distribution system is energized and shall be made in normally dry conditions not less than 48 hours after the last rainfall. Resistance measurements of separate grounding electrode systems shall be made before the systems are bonded together below grade. The combined resistance of separate systems may be used to meet the required resistance, but the specified number of electrodes must still be provided.

- a. Single rod electrode - 25 ohms .

3.19.3 Ground-Grid Connection Inspection

3.19.4 Cable Tests

The Contractor shall be responsible for identifying all equipment and devices that could be damaged by application of the test voltage and ensuring that they have been properly disconnected prior to performing insulation resistance testing. An insulation resistance test shall be performed on all low and medium voltage cables after the cables are installed in their final configuration and prior to energization. The test voltage shall be 500 volts DC applied for one minute between each conductor and ground and between all possible combinations of conductors. The minimum value of resistance shall be:

$$R \text{ in megohms} = (\text{rated voltage in kV} + 1) \times 304.8 / (\text{length of cable in meters})$$

Each cable failing this test shall be repaired or replaced. The repaired cable system shall then be retested until failures have been eliminated.

3.19.4.1 Medium Voltage Cable Tests

- a. Continuity test.
- b. Insulation resistance test.
- c. DC high-potential test.

3.19.4.2 Low Voltage Cable Tests

- a. Continuity test.
- b. Insulation resistance test.

3.19.5 Metal Enclosed Bus Duct Tests

- a. Insulation Resistance phase-to-phase, all combinations.
- b. Insulation resistance phase-to-ground, each phase.
- c. AC or DC high-potential test.
- d. Phase rotation test.

3.19.6 Motor Tests

- a. Phase rotation test to ensure proper directions.
- b. Operation and sequence of reduced voltage starters.
- c. High potential test on each winding to ground.
- d. Insulation resistance of each winding to ground.
- e. Vibration test.
- f. Dielectric absorption test on motor .

3.19.7 Dry-Type Transformer Tests

The following field tests shall be performed on all dry-type transformers 30 kVA and above.

- a. Insulation resistance test phase-to-ground, each phase.
- b. Turns ratio test.

3.19.8 Circuit Breaker Tests

The following field tests shall be performed on circuit breakers.

3.19.8.1 Circuit Breaker Tests, Medium Voltage

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance tests phase-to-ground, each phase.
- c. Closed breaker contact resistance test.
- d. Power factor test.
- e. High-potential test.
- f. Manual and electrical operation of the breaker.

3.19.8.2 Circuit Breakers, Low Voltage

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance test phase-to-ground, each phase.
- c. Closed breaker contact resistance test.
- d. Manual and electrical operation of the breaker.

3.19.8.3 Circuit Breakers, Molded Case

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance test phase-to-ground, each phase.
- c. Closed breaker contact resistance test.
- d. Manual operation of the breaker.

3.19.9 Motor Control Centers

- a. Insulation resistance test phase-to-phase, all combinations.
- b. Insulation resistance test phase-to-ground, each phase.
- c. Manual and electrical operational tests.

3.20 OPERATING TESTS

After the installation is completed, and at such time as the Contracting Officer may direct, the Contractor shall conduct operating tests for approval. The equipment shall be demonstrated to operate in accordance with the specified requirements. An operating test report shall be submitted in accordance with paragraph FIELD TEST REPORTS.

3.21 FIELD SERVICE

3.21.1 Onsite Training

The Contractor shall conduct a training course for the operating staff as designated by the Contracting Officer. The training period shall consist of a total of 8 hours of normal working time and shall start after the system is functionally completed but prior to final acceptance tests. The course instruction shall cover pertinent points involved in operating, starting, stopping, servicing the equipment, as well as all major elements of the operation and maintenance manuals. Additionally, the course instructions shall demonstrate all routine maintenance operations. A VHS format video tape of the entire training shall be submitted.

3.21.2 Installation Engineer

After delivery of the equipment, the Contractor shall furnish one or more field engineers, regularly employed by the equipment manufacturer to supervise the installation of equipment, assist in the performance of the onsite tests, oversee initial operations, and instruct personnel as to the operational and maintenance features of the equipment.

3.22 ACCEPTANCE

Final acceptance of the facility will not be given until the Contractor has successfully completed all tests and after all defects in installation, material or operation have been corrected.

-- End of Section --